

2700 Series

2700 Series User's Manual



2722 • 2720 • 2712 • 2702

2700 Series User's Manual

for • SYS-2722 •

and • SYS-2720 •
• SYS-2712 • SYS-2702 •



for version 3.3 control software

Copyright © 2004–2008 Audio Precision, Inc.

All rights reserved.

PN 8211.0183 Revision 4

For AP2700 control software Version 3.3

All content in this manual is owned by Audio Precision and is protected by United States and international copyright laws. Audio Precision allows its customers to make a limited number of copies of this manual, or portions thereof, solely for use in connection with the Audio Precision product covered by this manual. Audio Precision may revoke this permission to make copies at any time. You may not distribute any copies of the manual, apart from a transfer of ownership of the Audio Precision product.

Audio Precision®, System One®, System Two™, System Two Cascade™, System Two Cascade *Plus*™, Cascade™, Cascade *Plus*™, System One + DSP™, System Two + DSP™, Dual Domain®, FASTTEST®, APWIN™, ATS™, ATS-2™, 2700 series™ and AP2700™ are trademarks of Audio Precision, Inc. Windows™ is a trademark of Microsoft Corporation.

Audio Precision instruments equipped with the OPT-2711 Dolby™ Digital Generator are manufactured under license from Dolby Laboratories. Dolby and the double-D symbol are trademarks of Dolby Laboratories. Confidential unpublished works.
© 1992–2004 Dolby Laboratories, Inc. All rights reserved.

Published by:



5750 SW Arctic Drive
Beaverton, Oregon 97005
503-627-0832
1-800-231-7350
fax 503-641-8906
ap.com

Contents

Safety Information	xxv
Safety Symbols	xxvi

Chapter 1

Introduction	1
The 2700 Series: an Overview.	1
2700 Series Components	2
APIB	2
APSI	3
2700 Series Instrument Models	3
About This Manual.	4
Instruments supported.	4
SYS-2722 Capabilities.	5
Architecture of 2700 Series Instruments.	7
Other Documentation for the 2700 series	7
Getting Started with the 2700 series.	8
Online Help	8
The AP Basic Language Manual	8
The AP Basic Extensions Reference for 2700 series	9
Application Notes and Technotes	9

Chapter 2

2700 Series Control Software	11
Overview	11
The User Interface	11
The Workspace.	12
The 2700 series panels.	12
Panel Settings	13
Panel Readings	14
The 2700 series menus	15
The File Menu	15

The Edit Menu	16
The View Menu	17
The Panels Menu	18
The Help Menu.	20
Access to the Audio Precision Web site	21
The Status Bar	21
The Toolbars	21
The Standard Toolbar	22
The Panels Toolbar	23
The Macro Toolbar.	25
The Learn Mode Toolbar.	25
The Quick Launch Toolbar.	25
AP2700 Add-Ins	26
Working with Files and AP2700	26
Test Files.	27
System Two Cascade and Cascade <i>Plus</i> Tests	27
“New Test” files	27
Macro Files.	27
Data Files	28
Waveform Files	28
The Log File	29
Keyboard Shortcuts	29
Function Keys	29
Other Keyboard Shortcuts	31
Chapter 3	
The 2700 Series Hardware	33
2700 Series Interface Bus	33
2700 series Instrument Configurations	33
2700 Series Major Options	34
2700 Series Option Filters	35
Auxiliary Equipment for the 2700 Series	35
The SYS-2722 Front Panel.	37
Main Digital Input and Output	37
The Analog Outputs	38
The Analog Inputs	39
Monitor, sync and trigger connections	39
The 2700 Series Rear Panel	40
Labeling	40
Mains voltages and fusing	40
Power Entry Module	41
The APIB interface connectors.	41
Sync, Reference and Auxiliary Connections	42

Chapter 4

Signal Inputs and Outputs	45
The Analog Outputs	46
Output Impedance	47
The Analog Inputs	48
The Serial Digital Output	49
The Serial Digital Input	49
Electrical vs. Data Characteristics Across Formats	50
Parallel Digital Output and Input	51
Parallel Input	52
Parallel Output	54
Parallel Interface Connector Pin Assignments	56

Chapter 5

Signal Analysis with the 2700 series	57
Test Signal Generation in the 2700 series	57
Two Audio Signal Generators	57
Analog Audio Signals	58
Analog Audio Generation and Output	58
The Analog Analyzer	58
Digital Audio Signals	58
The Serial Digital Interface Signal	58
Digital Audio Generation	59
The Digital Analyzer	59
Real-Time and Batch Mode Measurements	59
The Digital Analyzer Analysis Tools	60
Sweeps and Graphs	61

Chapter 6

The Analog Generator	63
Signals for Analog Measurements	63
Signal generation in analog hardware	64
Signal generation in DSP	64
Performance Extremes versus Specifications	65
The Analog Generator Panel	66
Frequency Units	67
Output ON/OFF and Channel Selection	67
Auto On	67
Channel Invert	68
Amplitude Control and Units	68
Choosing an Analog Generator Waveform	69
Designation of hardware and DSP generation	69
Analog waveforms: speed versus accuracy	69
DSP waveforms: sample rate and bandwidth	70

Sine waveforms	70
Wfm: Sine: Normal.	70
Wfm: Sine: Burst.	71
Wfm: Sine: Normal Burst	71
Wfm: Sine: Gated Burst	72
Wfm: Sine: Trig. Burst	72
Wfm: Sine: EQ Sine	74
Sine waveforms from DSP	75
Wfm: Sine (D/A): Var Phase	75
Wfm: Sine (D/A): Stereo	77
Wfm: Sine (D/A): Dual	78
Wfm: Sine (D/A): Shaped Burst	78
Wfm: Sine (D/A): EQ Sine	79
Square wave waveforms	80
Wfm: Square.	80
Wfm: Square (D/A)	80
Intermodulation Distortion (IMD) waveforms	81
Wfm: IMD: SMPTE/DIN 1:1	81
Wfm: IMD: SMPTE/DIN 4:1	82
Wfm: IMD: CCIF/DFD	82
Wfm: IMD: DIM 30 / DIM 100 / DIM B / DIM B-8K	83
Wfm: IMD (D/A): SMPTE/DIN 1:1	83
Wfm: IMD (D/A): SMPTE/DIN 4:1	84
Wfm: IMD (D/A): CCIF/DFD	84
Wfm: IMD (D/A): DIM 30 / DIM 100 / DIM B	85
Noise Waveforms	85
Random vs. Pseudo-random	86
Noise amplitude calibration	86
Wfm: Noise: Pseudo.	87
Wfm: Noise: Random	88
Variable Bandpass Filter for Pink Noise	89
Wfm: Noise (D/A)	89
Arbitrary Waveforms	90
Wfm: Arb Wfm (D/A).	90
Arbitrary Waveforms and D/A Sample Rate	90
MLS Waveforms	91
Wfm: MLS (D/A)	91
MLS Waveform Sample Rate	91
Special Waveforms.	92
Wfm: Special (D/A): Polarity	92
Wfm: Special (D/A): Pass Thru	92
Setting the D/A Bandwidth	94
Setting the D/A Sample Rate.	94
Configuring the Analog Outputs	95

Analog Generator References	96
dBm Reference	97
dBr Reference	97
Frequency Reference	97
Watts Reference	97

Chapter 7

The Digital Generator	99
Signals for Digital Measurements.	99
The Digital Generator Panel	99
Frequency Units.	100
Output On/Off and Channel Selection.	100
Auto On.	101
Channel Invert.	101
Amplitude Control and Units	101
Choosing a Digital Generator Waveform	102
Sine waveforms	103
Wfm: Sine: Normal	103
Wfm: Sine: Burst	103
Wfm: Sine: Var Phase	104
Wfm: Sine: Stereo	105
Wfm: Sine: Dual	105
Wfm: Sine+Offset.	106
Wfm: Sine: EQ	106
Wfm: Sine: Shaped Burst.	107
Intermodulation Distortion (IMD)	108
Wfm: IMD: SMPTE/DIN 1:1	109
Wfm: IMD: SMPTE/DIN 4:1	109
Wfm: IMD: CCIF/DFD.	109
Wfm: IMD: DIM 30 / DIM 100 / DIM B.	110
Square wave.	111
Wfm: Square	111
Noise	112
Wfm: Noise: White	112
Wfm: Noise: Pink	112
Wfm: Noise: Burst USASI.	113
Special Waveforms	113
Wfm: Special: Monotonicity	113
Wfm: Special: J-Test	114
Wfm: Special: Polarity.	115
Wfm: Special: Walking Ones and Walking Zeros	116
Wfm: Special: Constant Value.	116
Wfm: Special: Random	117
Wfm: Special: Pass Thru	117

MLS Waveforms.	118
Wfm: MLS.	118
MLS Waveform Sample Rate	118
Arbitrary Waveforms.	119
Dither	120
Dither Type	120
Digital Generator References	121
Volts for Full Scale Reference	122
Frequency Reference.	122
dBr Reference	122
Chapter 8	
The Analog Analyzer	123
Overview	123
Analog Analyzer Options	124
The Analog Analyzer Panel	126
Input Selection and Configuration.	126
Source Input Termination	127
DC Coupling of Analog Inputs	127
The Level Meters	128
Level Meter Units	128
The Frequency Meters	129
Input Ranging	129
Autoranging.	130
Fixed Range	130
The Phase Meter	131
Phase Meter Hardware	132
The Function Meter	132
Function Meter Units	132
Function Meter Ranging	133
Function Meter Channel Selection	133
Function Meter Measurement Functions	133
Amplitude	134
Bandpass	135
Bandreject	135
THD+N Ampl	136
THD+N Ratio	137
IMD Measurements: SMPTE/DIN	137
IMD Measurements: CCIF and DFD.	138
CCIF	138
DFD	139
IMD Measurements: DIM (TIM)	139
Wow and Flutter Measurements	140
Ranging Considerations	141

FM discriminator	141
Weighting and Bandpass Filters	141
Detector Selection	142
2-Ch. Ratio	143
Crosstalk	143
Detector Type	144
Detector Reading Rate	146
The Bandwidth and Filter Fields	147
BW: The Highpass Filter	147
BW: The Lowpass Filter	148
The “Fitr” Field	148
Bandpass/Bandreject Filter Tuning	149
References	150

Chapter 9

The Digital I/O Panel	153
Overview	153
The DIO Output Section	154
Connector	155
SR Range	156
Sample Rate (SR)	157
System Sample Rate (SSR)	157
Voltage	158
Output Audio Format	159
Linear	159
μ -Law and A-law Compression	160
IEC 61937 (Dolby Digital)	160
Preemphasis	161
Scale Freq. by	161
Output Impairments	162
The Output Impairment Checkboxes	162
Invert	162
Cable Simulation	162
Changing the Parity bit	163
Sending a high Validity bit	164
Rise/Fall Time	164
Interfering Noise	164
Common Mode Sine	164
Jitter Generation	165
Jitter Type	165
Amplitude	166
Frequency	167
EQ Curve	167
The DIO Input Section	168

Connector	169
Input Impedance	170
Connector I & II Selection	171
Normal Operation	171
Dual Connector Operation	171
Sample Rate-ISR	171
Voltage	172
Input Audio Format	172
Linear	173
μ -Law and A-law Expansion	173
Deemphasis	174
Scale Freq. by	174
Delay from Ref Out	175
Rate Ref	176
Peak Monitors	176
Data Bit Indicators	177
Error Indicators	177
The Confidence Indicator	178
The Lock Indicator	178
The Coding Indicator	178
The Parity Bit Indicator	178
The Validity Bit Indicators	179
Jitter Measurement	179
The Status Bits panel	180
Transmit Status Bits	181
Consumer Format Status Bits	182
Professional Format Status Bits	183
Local Address and Time of Day entry	183
CRC entry	184
Receive Status Bits	184
Hex Control and Display	185
Dual Connector Mode and Status Bits	185
Chapter 10	
The Dolby Digital Generator	187
Overview	187
Connections	188
Using the Dolby Digital Generator	188
Data-type	189
Levels of control	191
Dolby Digital at Normal Level of Control	192
Dolby Digital at Advanced or Expert Levels of Control	193
Channel Routing to the Dolby Digital inputs	193
Normal	194

Follow Switcher	194
Dolby Digital controls	195
Audio Service Configuration	195
frmsizecod	195
fscod mode	196
fscod	196
acmod	197
lfeon	197
bsmod	197
dialnorm	198
dialnorm2	198
Bitstream information	198
cmixlev	199
surmixlev	199
dsurmod	199
copyrightb	200
origbs	200
audprodie	200
mixlevel	200
roomtyp	200
audprodi2e	201
mixlevel2	201
roomtyp2	201
langcode	201
langcod	201
langcod2e	202
langcod2	202
Extended Bitstream information	202
Extended bitstream	202
bsid mode	203
bsid	203
xbsi1e	204
dmixmod	204
lorocmixlev	204
lorosurmixlev	205
ltrcmixlev	205
ltrtsurmixlev	206
xbsi2e	206
dsurexmod	206
dheadphonmod	207
adconvtyp	207
xbsi2	207
encinfo	208
Time Code	208

timecod1e	208
timecod2e	208
Preprocessing	208
Channel Lowpass	208
DC Highpass	209
LFE Lowpass	209
Phase Shift	209
Dynamic Range Compression	209
Line mode compression	209
dynrng	210
RF mode compression	211
compr	211
Impairments	212
crc1	212
crc2	212
syncword	213
syncword mode	213
IEC 61937 bitstream and controls	213
Levels of Control	214
IEC 61937 Idle Data-type (Null data-bursts)	214
Send Null Data-Bursts	215
Null data-burst repetition period	215
Pause Data-type	215
Pause data-burst repetition	216
(Pause) Data-burst repetition mode	217
(Pause) data-burst repetition period	217
gap-length mode and gap-length	217
Preambles controls	218
Data-type mode	218
Data-type (preambles)	219
Data-type code	220
Reserved bits	220
Error flag	220
Data-type-dependent info mode	220
Data-type-dependent info	220
Bitstream number mode	221
Bitstream number	221
Length-code mode	221
Length-code	221
Sweepable parameters	222
Sweep settling and IEC 61937 processing	222
OPT-2711 Required Components	222
APSI: the Audio Precision Streaming Interface	222
OPT-2711 Licensing	223

References	224
----------------------	-----

Chapter 11

The DSP Audio Analyzer	225
Overview	225
Loading the DSP Audio Analyzer	227
Signal Inputs	228
Digital @ISR	228
HiRes A/D & HiBW A/D	228
Converter and Sample Rate Selection	229
Source	230
Coupling.	230
The Level Meters	231
Level Meter Units	231
The Frequency Meters	232
Meter Ranging	233
Autoranging.	233
Fixed Range	233
The Function (Reading) Meters	234
Function Meter Measurement Functions	234
Amplitude Function.	235
2-Channel Ratio Function	237
Crosstalk Function	239
THD+N Ratio and Amplitude Functions	241
Bandpass Function.	243
SMPTE / DIN IMD Function	245
Phase Function.	247
Function Meter Units	248
Function Meter Ranging	249
Detector Type.	249
Detector Reading Rate	251
The Bandwidth and Filter Fields	251
BW: The Highpass Filter	252
BW: The Lowpass Filter	252
The “Filtr” Field	253
Filtr: Weighting Filters.	253
User Filters	255
Bandpass/Bandreject Filter Tuning.	257
Filtr: Selecting Harmonics in Bandpass.	259
References	259
Digital Analyzer References	259
Analog References for the DSP Audio Analyzer	260

Chapter 12

The Spectrum Analyzer	261
--	------------

Introduction	261
Loading the Spectrum Analyzer	262
Signal Inputs	262
Source Selection	263
Digital @ISR Sources.	263
Analog (A/D) Sources.	264
Peak Level Monitors	266
Acquiring, Transforming and Processing	266
The Acquisition Record	267
Acquisition Length.	268
FFT Length	269
FFT Window Selection	269
Hann Window.	271
Blackman-Harris Window.	271
Flat-Top Window	271
Equiripple Window	272
Hamming Window	272
Gaussian Window.	272
Rife-Vincent Windows	272
None (No Window or Rectangular Window)	272
None, move to bin center	273
Quasi-AC Coupling	274
Averaging	275
Synchronous Averaging	276
Signal Alignment for Synchronous Averaging	277
Sync (without re-align)	278
Sync, re-align.	278
Synchronous Averaging for "Move to bin center".	278
Synchronous Averaging and Frequency Domain Views	279
Power (Spectrum) Averaging	280
Display Processing	281
Waveform (time domain) Display Processing.	282
Interpolate	282
Display Samples	283
Peak Values	283
Absolute Values	283
Graphic Aliasing	284
Spectrum (frequency domain) Display Processing	285
Octave Smoothing	285
Peak Picking	285
FFT Start Time	285
Triggering	286
Free Run	286
Auto.	286

Fixed Sensitivity	287
Trig In (Ext)	287
Digital Gen	287
Analog Gen	287
AC Mains	287
Jitter Gen	288
Fixed Level	288
Trigger Delay Time	288
Trigger Slope	289
Triggering with Synchronous Averaging	289
Without Re-alignment	289
With Re-alignment	289
Triggering with Quasi-AC Coupling	290
References	290
The Sweep Spectrum/Waveform Button	290
Acquired Waveform Files	291
Saving Acquired Waveforms	292
Opening Acquired Waveforms	292
Combining two Mono acquisitions to Stereo	293
Compatibility of Acquired Waveform Files	293

Chapter 13

The Digital Interface Analyzer	295
Overview	295
2700 series Digital Interface Analyzer Tools	295
The Digital Interface Analyzer ADC	296
Digital Interface Analyzer Capabilities	296
Loading the Digital Interface Analyzer	296
The Digital Interface Analyzer panel	297
Digital Interface Analyzer Waveform Views	299
Interface Waveform	299
Eye Pattern	300
Jitter Waveform	301
Digital Interface Analyzer Spectrum Views	302
Interface Spectrum	302
Jitter Spectrum	303
Digital Interface Analyzer Histograms	304
Interface Amplitude Histogram	304
Interface Pulse Width Histogram	305
Interface Bit-Rate Histogram	306
Jitter Histogram	307
Quick Launch Digital Interface Tests	308
Digital Interface Analyzer panel settings	309
Amplitude vs Time Displays (Time Domain view only)	309

Interpolate	310
Display Samples	310
Peak Values	311
Eye Pattern	311
Audible Monitoring in the Digital Interface Analyzer.	311
Audio Monitor.	312
Jitter Signal.	312
Jitter Detection	312
Square wave (Converter Clock) Jitter Detection	314
Averages	315
FFT Windows for the Digital Interface Analyzer.	315
Trigger Source	317
Triggering for Square Wave Jitter Detection	320
Trigger Slope	320
Data Acquisition	321
Receive Error Triggers	321
References	321
Saving and Loading Interface Waveforms	322
 Chapter 14	
The Multitone Audio Analyzer	323
Introduction	323
Overview: Multitone Testing	324
Multitone Waveform requirements	324
Sample multitone waveforms.	325
Creating custom multitone waveforms	325
“Inside Information”: Multitone Generator Settings	326
The Multitone Audio Analyzer panel.	327
Signal Inputs	327
Source Selection	328
Digital @ISR Sources.	328
Analog (A/D) Sources.	329
Peak Level Monitors	330
Multitone Measurements	330
Frequency Domain Views by default	330
Spectrum	331
Response	332
Distortion	333
Noise	334
Masking Curve	336
Crosstalk	337
Time Domain View	338
Frequency Resolution.	338
Setting Multitone triggering resolution	338

Setting frequency resolution for rss summing.	339
Multitone FFT Length	339
Processing	340
Triggering	341
Off	341
DGen and AGen	341
Tight, Normal and Loose	341
External	342
Trigger Delay	342
Phase Measurements	342
Channel 1 Phase	342
Channel 2 Phase	343
References	343
Other Considerations	343
Multitone Minimum Duration Requirements.	343
Invalid Multitone Readings	344
Acquired Waveform Files	345
Saving Acquired Waveforms	346
Opening Acquired Waveforms	346
Combining Mono to Stereo	347
Compatibility of Acquired Waveform Files	347
Creating Multitone Waveform Files	348
Multitone Creation Utility opening dialog box	348
Using Existing File Data	350
File Options.	351
Frequencies Menu	352
Editing the Frequency List	352
Sweep Table Definition	354
Creating an MS RIFF (.wav) File	354
Final Options	355

Chapter 15

The MLS Analyzer	357
MLS Overview.	357
Generating an MLS signal.	358
Pink and White MLS Sequences	359
Sequence Variations: 1, 2, 3 or 4?	359
Sequence Lengths	359
Loading the MLS Analyzer	359
The MLS Analyzer panel	360
Signal Inputs	361
Match the Sample Rates!.	361
Source Selection	361
Digital @ISR Sources	362

Analog (A/D) Sources	362
Peak Level Monitors	363
Time Delay	364
Time Domain Display	364
Energy-Time Curve	364
Energy-Time Window	365
Time Window	366
Trigger Source	367
Frequency Domain Display	368
Averages	368
Display processing Methods	369
Interpolate	369
Display Samples	369
Peak Values	369
Smooth	370
Using MLS for Loudspeaker Testing	371
Setting up the Equipment	371
Generator settings	371
Analog Analyzer settings	372
MLS Analyzer settings	372
Using the Spectrum/Waveform Button	372
Measuring the Impulse Response	372
Plotting the Frequency and Phase Spectrum	373
Removing the Propagation Delay	375
Viewing Only the Loudspeaker Response	377
Measuring Delay through an Electronic Device	379
MLS Acquisition Files	380
Chapter 16	
The Digital Data Analyzer	383
Introduction	383
Stimulus Waveform Requirements	384
Stimulus Resolution	384
Bittest Random, Walking Ones and Walking Zeros	384
Constant	385
Sine	385
Recorded or Remote Stimulus	385
Loading the Digital Data Analyzer	385
Input	386
Data and Error Readings	386
Error Display	386
Error Detection Flag	387
Freeze Data on Error	387
Reading Rate	387

Waveform Selection	388
Sine	388
Random	388
Walking-1 and Walking-0	389
Constant	389

Chapter 17

The Harmonic Distortion Analyzer	391
Introduction	391
Loading the Harmonic Distortion Analyzer	393
Signal Inputs	393
Source Selection	394
Digital @ISR Sources	394
Analog (A/D) Sources	394
The Fundamental Amplitude Meters	395
The Fundamental Frequency Meters	395
Harmonic Distortion Product Amplitude	396
Harmonic Order Control	396
Distortion Product Bandwidth Limitations	396
Amplitude Units	398
References	398
Steering Control	398
High Speed/High Accuracy Control	399
Sweeping and Graphing Results	401

Chapter 18

Sweeps and Sweep Settling	403
Introduction: Sweeps and Graphs	403
Batch-Mode “Sweeps”	405
Plan Your Sweep	405
The Sweep Panel	406
Source 1	407
Settings or Readings?	407
Selecting a Sweep Source	407
Start and Stop Values	408
Source 1 Log or Lin Scales	408
Sweep Resolution	409
Linear Scale Steps	409
Logarithmic Scale Steps	409
X-Axis Divisions	409
Data 1	410
Selecting the Data 1 Reading	410
Top and Bottom Values	411
Data 1 Log or Lin Scales	411
Y-Axis Divisions	411

Data Limits	411
Data 2	412
Plotting Data as X-versus-Y	412
Data 3 through Data 6.	413
Sweep Display Mode	414
Go / Stop / Pause	414
Repeat	414
Append	415
Appending a File	415
Stereo Sweeps	416
Single Point Sweeps	416
Nested Sweeps using Source 2.	417
Pre-Sweep Delay	418
Pre-Sweep Delay and Auto On	418
Table Sweeps	418
External Sweeps	419
Background: Internal and External sweeps	419
Performing an External Sweep	420
The External Sweep panel	422
Start, Stop and Start Value	422
Start Tolerance	423
Start Sweep	423
Data Spacing	424
Data Threshold	424
End	424
End Tolerance	425
Stop Sweep.	425
Some Hints for External Sweeps	426
External Stereo Sweep	426
External Single Point Sweeps.	426
Time Sweeps	427
Sweep Settling	427
The Sweep Settling Panel	429
Settling Concepts	430
Settling Delay Time	430
Algorithm Selection	430
Exponential Settling Algorithm	431
Flat Settling Algorithm	432
Average Settling Algorithm	432
Settling Tolerance.	432
Settling Floor	432
Settling Issues for Specific Analysis Tools	433
Timeout	433

Chapter 19

Graphs	435
Graph and Sweep Interaction	435
The Graph Panel	435
Zoom	436
The Graph Options Menu	437
Zoomout	437
Zoomout to Original	438
Optimize	438
Copy to Sweep Panel	439
Display Cursors	439
Scroll Bars	442
Title and Labels	443
Comment	443
New Data	443
Graph Buffer	444
Graph Legend	445
Graph Legend / Data Editor Linkage	446
Trace Colors	447
Color Assignment for a New Test	448
Color Assignment for Multiple-Data-Set Sweeps	448
Color Assignment when Opening a Saved Test	449
Color Cycling in Nested and Appended Sweeps	449
Color Cycling with Appended Files	450
Graph Keyboard Shortcuts	450
Graph Only	450
Re-Transform and Graph	451
Re-Acquire, Re-Transform and Graph	451

Chapter 20

Bar Graphs	453
Creating a Bar Graph	453
Bar Graph Setup	454
Using a Bar Graph for Readings	456
Using a Bar Graph for Settings	456

Chapter 21

Editing Data and Setting Limits	459
The Data Editor	459
The Data Editor Panel	460
Columns	460
Rows	460
Data	461
Editing the Current Data in Memory	461

Saving 2700 Series Data	462
Setting Limits	462
Making a Limit File	463
Attaching a Limit File	464
Using the Attached File Editor	465
Actions Upon Failure	466
More About Using AP Data Files	466
Exporting Data	467
Importing Data	467
The Attached Files Viewer	468
Chapter 22	
Performing Computations on Data	469
The Compute Dialog Boxes	470
Compute: Normalize	472
Compute: Invert	472
Compute: Smooth	473
Compute: Linearity	474
Compute: Center	475
Compute: Delta	476
Compute: 2-Sigma	477
Compute: Average	478
Compute: Minimum	478
Compute: Maximum	479
Compute: Equalize	479
Compute Status	480
Clear All and Reset	481
Computed Results and Original Data	481
Chapter 23	
Printing and Exporting	483
Printing 2700 Series Graphs	483
Page Setup	484
Print Setup	485
Printing a Graph	485
Print Preview	486
Printing Data as a Table	486
Printing to a File	487
Exporting a Graph	488
Copying a Graph to the Clipboard	488
Copying a Panel or Window to the Clipboard	489
Chapter 24	
Monitoring	491
Headphone/Speaker Monitoring	491

Headphone/Speaker panel	491
Stereo / Mono	492
Source	492
The Monitor Outputs	493
Analyzer Signal Monitors	494
Channel A	494
Channel B	494
Reading	494
Digital Signal Monitors	494
Channel 1	494
Channel 2	494
Reading 1	495
Reading 2	495

Chapter 25

Sync/Ref, Trigger and Aux Connections.	497
GENERATOR AUX SIGNALS.	497
SYNC OUTPUT.	497
TRIG/GATE INPUT	498
Auxiliary Digital Signals	498
VIDEO/TTL REF IN.	498
TRIGGER OUT	499
AES/EBU REF IN.	499
AES/EBU REF OUT	499
MASTER CLK OUT.	500
TRANSMIT FRAME SYNC	500
RECEIVE FRAME SYNC.	500
EXT TRIGGER IN	500
AUX OUT	500
PARALLEL OUTPUT and INPUT	501
APSI	501
The Sync/Ref Input/Output panel	501
Reference Input.	502
Source	502
Pass Thru Domain Preference	503
Frame Lock.	503
Input Termination Impedance.	503
Frequency	504
Input Frequency	504
Delay, In from Ref In	504
Out of Range Indicator	505
Sync Output controls	505
Delay, Out from Ref Out	505
Invert Frame Sync	505

Jitter Clock Outputs	506
Chapter 26	
Automating Tests	507
Introduction	507
Learn Mode	507
The Macro Editor	508
AP Basic Documentation	509
Chapter 27	
Regulation	511
The Regulation panel	511
Examples of Regulated Sweeps	514
Chapter 28	
Configuration and the Utilities Menu	517
The Configuration panel.	517
General	518
Configure Filters	521
Log	522
The Log File	522
Graph	524
Other Utilities Menu Commands	525
Restore Hardware	525
Hardware Status	526
Turn All Outputs OFF / ON	526
Clear Log File.	526
View Log File	526
Learn Mode.	526
Multitone Creation	527
Software License Management.	527
Appendix A	
Units of Measurement.	529
Introduction	529
Analog Amplitude Units	530
Digital Amplitude Units	534
Digital Data Units	536
Ratio Units	536
Relative Units	536
Frequency Units.	537
Phase Unit	538
Time Units.	538
DCX-127 Units	539
DCX-127 Amplitude Units.	539
DCX-127 Resistance Units	539

DCX-127 Digital Input and Output Units	539
--	-----

Appendix B

The Digital Audio Signal	541
Introduction	541
The Serial Digital Interface Signal.	542
Bi-phase Mark Encoding	543
The Frame and Subframe	543
Channel Status	544
Serial Interface Measurements	550

Appendix C

FFTs	551
The Fast Fourier Transform	551
Real Time vs. Batch Mode	551
Acquiring Data	552
The FFT Record.	552
FFT Bandwidth	552
FFT Bin Width.	553
FFT Record Looping	554
FFT Windowing	555
Synchronous FFTs	557
Graphing FFTs	558

Appendix D

User Downloadable Filters	559
Creating User Downloadable Filters.	559
User Downloadable Filter Design Constraints:	559
MATLAB Downloadable Filter Support	561
ap_write_filter.	562
Syntax	562
Description	562
Filename	562
Filter Types.	562
Info String	563
Sample Rate	563
Filter Coefficients.	564
Return value	564
Multiple Sample Rates	564
Filter Restrictions.	564
Examples.	564
ap_read_filter.	565
Syntax	565
Description	565
Example	565

Appendix E

AP Waveform File Support	567
Exporting to .WAV	567
Operation	567
Tips and Tricks	568
Importing from .WAV	569
Operation	569
MATLAB support	570
ap_write_wave	570
Syntax	570
Description	570
Example	571
ap_read_wave	571
Syntax	571
Description	571
Example	572
ap_eq_wave	574
Syntax	574
Description	574
Input Signal.	574
Filter	574
Output Signal.	574
Method of Operation	575
Examples.	575

Safety Information

Do NOT service or repair this product unless properly qualified. Servicing should be performed only by a qualified technician or an authorized Audio Precision distributor.

Do NOT defeat the safety ground connection. This product is designed to operate only from a 50/60 Hz AC power source (250 V rms maximum) with an approved three-conductor power cord and safety grounding. Loss of the protective grounding connection can result in electrical shock hazard from the accessible conductive surfaces of this product.

For continued fire hazard protection, fuses should be replaced **ONLY** with the exact value and type indicated on the rear panel of the instrument and discussed on page 8 of the accompanying manual *Getting Started with Your 2700 Series Instrument*. The AC voltage selector also must be set to the same voltage as the nominal power source voltage (100, 120, 230, or 240 V rms) with the appropriate fuses. Different fuses are required depending on the line voltage.

The International Electrotechnical Commission (IEC 1010-1) requires that measuring circuit terminals used for voltage or current measurement be marked to indicate their Measurement Category. The Measurement Category is defined by IEC 664 and is based on the amplitude of transient or impulse voltage that can be expected. This product is classified as Measurement Category I, abbreviated “CAT I” on the instrument front panel. This equipment is rated for a maximum input of 230 Vpk, 160 Vrms and is intended to be used for the measurement of audio signals only. Do NOT use this product for measurements within Categories II, III, or IV.

Do NOT substitute parts or make any modifications without the written approval of Audio Precision. Doing so may create safety hazards.

This product is for indoor use—pollution degree 2.

Safety Symbols

The following symbols may be marked on the panels or covers of equipment or modules, and are used in this manual:



WARNING!—This symbol alerts you to a potentially hazardous condition, such as the presence of dangerous voltage that could pose a risk of electrical shock. Refer to the accompanying Warning Label or Tag, and exercise extreme caution.



ATTENTION!—This symbol alerts you to important operating considerations or a potential operating condition that could damage equipment. If you see this marked on equipment, consult the User's Manual or Operator's Manual for precautionary instructions.



FUNCTIONAL EARTH TERMINAL—This symbol marks a terminal that is electrically connected to a reference point of a measuring circuit or output and is intended to be earthed for any functional purpose other than safety.



PROTECTIVE EARTH TERMINAL—This symbol marks a terminal that is bonded to conductive parts of the instrument. Confirm that this terminal is connected to an external protective earthing system.

Chapter 1

Introduction



Figure 1. An Audio Precision 2700 series audio test and measurement instrument (SYS-2722 shown).

*NOTE: This manual supports the following 2700 series instruments: **SYS-2722**, **SYS-2720**, **SYS-2712** and **SYS-2702**; and also System Two Cascade and Cascade Plus instruments running under AP2700 control software.*

The 2700 Series: an Overview

Audio Precision 2700 series instruments are computer-controlled audio test sets offering broad, high-performance capabilities for testing analog, digital,

and mixed-domain devices. The 2700 series instruments are based on models in the Audio Precision System Two Cascade and Cascade *Plus* lines.

2700 series instruments include both signal generation and analysis capability for audio stimulus-response testing. Virtually all common and many specialized tests (depending on the 2700 series instrument model and configuration) are performed on analog domain and digital domain signals and on the digital interface signal itself.

The versatility of 2700 series instruments can be extended through major options and accessories, such as the OPT-2711 Dolby* Digital Generator, the SWR-2755 audio input or output switchers, the DCX-127 Multifunction Module or the PSIA-2722 Programmable Serial Interface Adapter. These accessories are described in greater detail in the following subsections.

Specifications for 2700 instruments and their options are found in the publication *Getting Started with Your 2700 Series Instrument*.

2700 Series Components

A 2700 series instrument consists of two key components:

- The 2700 series instrument hardware, which provides the physical platform and measurement electronics necessary for proper signal interface and precise signal generation and analysis. The hardware is mounted in a sturdy aluminum and steel chassis that can be installed in a standard 19" wide equipment rack using optional mounting hardware.

With the exception of the mains power switch and the monitor speaker volume control, there are no knobs, dials, controls, readouts, meters or switches on 2700 series instrument hardware. All of the measurement settings and adjustments are made in software on the PC.

- The 2700 series control software, AP2700. AP2700 runs on a personal computer (PC) and provides the control, computation, display, report and automation functions for a 2700 series instrument. (The PC must be purchased separately).

The AP2700 control software will run under Microsoft Windows XP Professional Service Pack 2 or Microsoft Windows Vista Business Edition (32-bit) operating systems.

APIB

The control software communicates with the 2700 series instrument through the Audio Precision Interface Bus (APIB). Several options have been provided for accessing APIB from your PC, including:

- The USB-APIB adapter.

- The APIB PCI card and cable.
- The APIB PCI Express card and cable.
- The APIB PCMCIA card and cable.

APSI

If you have ordered the Dolby Digital Generator option, you will need an additional USB 2.0 port for the Audio Precision Streaming Interface (APSI).

NOTE: The APSI interface is only used with for the OPT-2711 Dolby Digital Generator option, and is only functional with the installation of that option and the licensed activation of the software components. Instructions for use of APSI are included with the OPT-2711 Dolby Digital Generator option.*

2700 Series Instrument Models

The 2700 series includes the following product configurations:



■ SYS-2722

SYS-2722 uses the most advanced Audio Precision hardware platform. It provides analog stimulus and measurement capability, using improved analog circuits for signal generation, filtering, and measurement. SYS-2722 also has a dual-channel DSP (digital signal processing) analyzer and dual-channel DAC signal source. Its enhanced capability includes digital signal generation, high-resolution spectrum analysis via FFT, waveform capture and display, and fast multitone testing. SYS-2722 is a dual domain instrument, with digital audio inputs and outputs in AES3 (AES/EBU), IEC60958 (SPDIF/EIAJ), optical and parallel formats, and complete serial interface analysis per AES3. The AES3 and IEC60958 input and output have sample rate capabilities extended to 192 kHz. These features give the SYS-2722 the capability of providing stimulus and measurement in any combination of digital and analog domains.

* Dolby and the double-D symbol are trademarks of Dolby Laboratories.



■ **SYS-2720**

SYS-2720 has the same digital and DSP signal generation and analysis capabilities as SYS-2722 described above, but no analog capabilities.



■ **SYS-2712**

SYS-2712 has the same analog capabilities as SYS-2722 described above (including DSP signal generation and analysis), but no digital signal input or output capabilities.



■ **SYS-2702**

SYS-2702 has the same analog capabilities as SYS-2712 and SYS-2722 described above, without the DSP signal generation and analysis. Like SYS-2712, SYS-2702 has no digital signal input or output capabilities.

About This Manual

You're reading the *2700 Series User's Manual*. This is the primary operation and reference manual for 2700 Series audio test and measurement instruments. We recommend you begin by reading the separate introductory manual, *Getting Started with Your 2700 Series Instrument*.

Look in the *2700 Series User's Manual* for

- detailed discussions of every 2700 series feature and function; every software panel, control and display;
- reference information on audio test and measurement techniques, sample and utility file listings, and much more.

A copy of the *2700 Series User's Manual* is shipped with every 2700 series instrument. The manual is also published as a PDF on the Audio Precision Resources Disc and on our Web site at ap.com.

Instruments supported

This *2700 Series User's Manual* supports the SYS-2722, SYS-2720, SYS-2712 and SYS-2702 instruments, and System Two Cascade and Cascade

Plus instruments that are running under the 2700 series control software, AP2700. To provide a full explanation of all the features available in the 2700 series, the assumption is made throughout the manual that the instrument under discussion is the 192k SYS-2722.

SYS-2722 Capabilities

The capabilities of the most-capable 2700 series implementation, designated SYS-2722, are listed here:

- SYS-2722 can operate in both the analog and digital domains, providing the best of techniques and performance from both realms.
- SYS-2722 can make amplitude, frequency, THD+N, noise, phase, crosstalk, bandpass, and IMD measurements for analog or digital audio devices, and can perform a detailed analysis of individual harmonic distortion products.
- SYS-2722 can perform measurements on audio signals using fast Fourier transform (FFT) analysis with advanced high-speed FFT techniques available, including multitone recognition and analysis capability, frequency adjustment for bin centering, synchronous FFT processing, and advanced post-FFT analysis. FFT analysis can also provide time-domain, oscilloscope-type waveform display of signals. Non-audio signals such as interface signal jitter components can also be studied with FFT techniques.
- SYS-2722 can examine the data embedded in the digital interface on a bit-by-bit basis, providing powerful analysis of converter behavior.
- SYS-2722 can test acoustical transducers and environments using a sophisticated *maximum length sequence* (MLS) measurement capability.
- SYS-2722 can use a combination of different measurement instruments and parameters to perform complex sweeps, and can display and print the results with a powerful graphing engine. SYS-2722 offers control over instrument regulation and sweep settling parameters. Pass/fail limits or equalization data can be attached to a sweep to constrain a particular measurement. A variety of computations can be performed on the measured data after acquisition. Sweep tests can be saved and recalled, and measurements can be automated by procedures written in the AP Basic programming language.
- SYS-2722 can transmit and receive signals in the AES3 and IEC 60958 formats at a wide range of resolutions and sample rates up to 24-bit at 192 kHz. These signals can be impaired in various ways to test DUT behavior under imperfect conditions.

- SYS-2722 can transmit Dolby Digital-encoded signals with the optional OPT-2711 Dolby Digital Generator.
- SYS-2722 can transmit and receive digital data in a parallel format, and in combination with the ancillary unit PSIA-2722 can transmit and receive serial digital signals for converter testing, providing outputs, inputs and software control of master clock rate, bit rate, number of channels, sub-frame rate, and so on.
- SYS-2722 can examine the digital interface signal and quickly perform elemental analysis of digital communication paths and assure the integrity of digitally transmitted data. A variety of statistics can be extracted from the digital waveform, such as the actual sample rate, the interface waveform voltage, the active and inactive data bits and status bits. Measured jitter can be displayed in real time.
- SYS-2722 also has the capability of transmitting and receiving the full complement of status bits for both the AES3 (professional) and IEC 60958-3 (consumer) digital audio interface signals.
- Using a dedicated 80 MHz ADC and a special DSP analysis program, SYS-2722 can perform detailed FFT measurements on the AES3/IEC 60958 interface signal, providing eye patterns, histograms, waveform display and FFT spectrum analysis of the recovered jitter signal, and triggering from a number of different interface patterns and bits.
- SYS-2722 provides a wide array of synchronization, triggering and monitoring capabilities.

Other models in the 2700 Series have reduced functionality. See **2700 Series Instrument Models** on page 3.

Architecture of 2700 Series Instruments




Figure 2. 2700 series conceptual block diagram, indicating hardware differences between SYS-2702, SYS-2712 and SYS-2722 models.

The functional components implemented in a SYS-2722 instrument include an analog signal generator, an analog signal analyzer, a DSP-implemented audio signal generator, a suite of DSP-implemented audio, data and interface signal analysis capabilities, digital and analog input and output modules, and modules for monitoring, synchronization and APIB communication.

For digital signals, signal generation and analysis is performed in the digital domain. For analog signals, both signal generation and analysis can be performed in the analog domain, the digital domain, or in configurations with components in both domains.

Other Documentation for the 2700 series

Audio Precision publishes material on our hardware and software products, on audio theory, and on specific test and measurement techniques. Here are some important documentation resources:

Getting Started with the 2700 series

We recommend that you read *Getting Started with Your 2700 Series Instrument* before reading any other 2700 series documentation. It is an introductory manual which will help you correctly set up your 2700 series instrument, install the software on your PC and familiarize yourself with the system. Inside *Getting Started with Your 2700 Series Instrument* manual you'll find:

- hardware and software installation instructions;
- an introduction to the 2700 series;
- a look at the key features of the 2700 series control software;
- Quick Guide tutorials, helping you put your instrument to use in simple tests; and
- 2700 series instrument specifications.

A copy of *Getting Started with Your 2700 Series Instrument* is shipped with every 2700 series instrument and is also published in electronic form as a PDF file, available on the Audio Precision Resources Disc and as a download from the Audio Precision Web site at ap.com.

Online Help

While you are running a 2700 series instrument, you will have much of the information contained in the *2700 Series User's Manual* available to you on-screen in the online Help system included as part of the AP2700 control software.

You can access the Help system while you are running the 2700 series control software in two ways:

- On the Menu bar, click **Help**. The Help menu offers commands to search the Help **Contents**, or to select another Help library such as **AP Basic Language** help or **2700 Basic Extensions** help.
- The 2700 series control software also has context-sensitive Help available. The controls and displays on the software panels are each associated with a help topic. To view the topic, click on the field or control, then press the **F1** function key.

The AP Basic Language Manual

You can create simple or complex test and measurement *macros* to automate your 2700 series instrument using AP Basic, the programming language included with the 2700 series. The same AP Basic language is also used to automate other Audio Precision PC-controlled systems and can communicate with other programming languages.

A copy of the *AP Basic Language Manual* is shipped with every 2700 series instrument and is also published in electronic form as a PDF file on the Audio Precision Resources Disc. It is also available as a download from the Audio Precision Web site at ap.com.

You will also find online Help for AP Basic while running the 2700 series control software. Go to **Help > AP Basic Language Help** from the Main menu.

The AP Basic Extensions Reference for 2700 series

The *AP Basic Extensions Reference for 2700 Series Instruments* is a supplementary library of OLE / ActiveX automation commands for use specifically with 2700 series instruments.

A copy of *AP Basic Extensions Reference for 2700 Series Instruments* is shipped with every 2700 series system and is also published in electronic form as a PDF file on the Audio Precision Resources Disc and as a download from the Audio Precision Web site at ap.com.

You will also find online Help for specific Basic Extensions 2700 series commands while running the 2700 series control software. Go to **Help > 2700 Basic Extensions Help** from the Main menu.

Application Notes and Technotes

From time to time Audio Precision publishes technical papers such as AP Application Notes and Technotes, which can help in your understanding of the operation of 2700 series instruments. Many Audio Precision technical publications are available for download from our Web site at ap.com. New technical papers and online solutions are added on a regular basis.

Viewing and Printing PDF files

Audio Precision documentation is provided in Adobe Portable Document Format (PDF) format on the Audio Precision Resources Disc and on our Web site at ap.com.

You can view the PDF files using Adobe Acrobat Reader, a free program that can be downloaded from Adobe at www.adobe.com. You can also print PDF files using Acrobat Reader and a Windows compatible printer.

Chapter 2

2700 Series Control Software

Overview

Most of your interaction with your 2700 series instrument will be through the 2700 control software, AP2700. Once the system is plugged in, turned on and connected to your device under test (or *DUT*), you will be making all your adjustments and taking all your readings from your computer screen.

The 2700 series control software is a powerful and complex program, and most of this book is dedicated to exploring and explaining its many capabilities. In this chapter, we'll look at an overview of the software features and learn the basics of operating the system.

The User Interface

Like many Windows applications, the 2700 series control software has a menu bar, a status bar, toolbars, and a workspace. With these tools you can save test and data files, export and print measurement results, configure both the hardware and software to your needs, access online help, design and launch automated processes and, of course, open and operate the control panels where the core test and measurement work is performed.

The Workspace




Figure 3. The 2700 series workspace.

The 2700 series workspace has 5 pages that you can select by menu commands (**View > Page #**) or by clicking the numbered tabs on the Status Bar. The workspace is like a multi-layered desktop where you can display and organize the control panels you are using for a particular set of tests.

Panels can be placed on any workspace page, and duplicated on more than one page. A control panel that appears on more than one page is simply a redundant display, for your convenience. The settings and results shown on redundant panels are identical, and a change made on one page is reflected on the others.

The 2700 series panels

The real interaction with a 2700 series instrument is done in control and measurement windows called *panels*. These can be thought of rather like the physical control panels found on conventional test and measurement equipment, with range, function and trigger controls, ON and OFF switches, linear adjustment pots and sliders, numerical meter readouts, bar meters, X-Y waveform displays, graphs and so on.

The 2700 series panels are available through menu commands, toolbar icons and keyboard shortcuts.

You can control your 2700 series instrument from just one or two software panels, if that's all your measurement requires. A more typical test might involve four or five panels; a complicated test, perhaps six or seven.

Figure 4. A 2700 series panel.



Although the 2700 series panels can all be placed on one workspace page, most users prefer to organize their workspace by placing panels on several different pages.

You can close a panel without canceling its function or effect; for example, you could set a signal's output voltage and frequency on the Analog Generator panel, turn the generator **ON**, then close the panel window. The signal will continue at the settings you've made until you open the panel again and make changes to the settings.



Many of the 2700 series panels come in two sizes, the smaller having fewer commands and readouts visible, and the larger showing every option. Double-click on the panel title bar to expand or contract it.

Panel Settings

Settings for tests and measurements are made using several different types of controls on the panels:

- *Setting fields*, which come in several versions:
 - The text box, in which you can directly enter a value from the keyboard.

Freq: .997000 kHz



- The drop-down list box, in which you can make a selection from a set of choices.
- The combo box, a combination of a text box with an added drop-down list from which you can choose the units to express your value.

NOTE: Setting fields display dark (black or blue) text or numbers on a white field. 2700 series text boxes and combo boxes, where appropriate, will accept certain letters as shorthand for standard SI multipliers: “n” for nano- (10^{-9}), “u” for μ or micro- (10^{-6}), “m” for milli- (10^{-3}), “k” for kilo- (10^3) and “M” for mega- (10^6). For example, entering either “1001” and “1.001k” in a frequency field will set the frequency to 1.001 kHz.


- *Check boxes*, which allow you to set non-exclusive conditions.
- *Option buttons*, which provide for exclusive conditions.
- *Browser buttons*, which open dialog boxes called *browsers*, which allow you to navigate lists of options, search for a file by browsing through a hierarchy of folders, and so on. Browser buttons are identified by the ellipses mark (...).
- *Custom buttons* that control special functions, such as **GO**, **ON**, **OFF** and so on.
- *Sliders*, with which you can continuously adjust a value. Sliders are found on Bar Graph panels. Sliders can be operated by either the mouse pointer or by using the arrow keys.

Panel Readings

Results of tests or measurements are called *readings*, which the 2700 series control software can display in several ways:


Reading fields, sometimes called *measurement fields* or *meters*. Reading fields come in two variations, with and without a drop-down list to select units.

NOTE: Reading fields always display green text or numbers on a black field.



- *Bar graphs*, which display values as a continuous colored bar like a conventional analog meter.
- *Status indicators*, which show the presence or absence of a condition by a small colored rectangle.

The 2700 series menus




File Edit View Panels Sweep Compute Macro Utilities Window Help

The Menu bar extends across the top of the window and is always visible. In this section we will take a brief tour of the 2700 series menus. Details of menu options, controls and submenus will be explored in the chapters discussing specific 2700 series functions.

The File Menu

The File menu offers commands for opening, saving, appending, importing, exporting and printing 2700 series files, and access to the Quick Launch menu.



Since there are a number of different files types used by the 2700 series, submenus are available (at the small black arrows ► accompanying some menu choices) to choose, for example, whether to **Save As** a **Test** or **Data** or **Macro** file.

The listings at the bottom of the File menu show the last tests opened by the 2700 series, and provide a convenient way to quickly launch a previously used test. Click on the name of the test you would like to open.


The Edit Menu

Edit	
Undo	Ctrl+Z
Cut	Ctrl+X
Copy	Ctrl+C
Paste	Ctrl+V
Copy Panel to Clipboard	
Set Analyzer dBr Ref	F4
Set Analyzer Freq Ref	Ctrl+F4
Set Generator dBr Ref	F3
Set Generator Freq Ref	Ctrl+F3
Reset Bar-graph Max/Min F2	
Insert Row Before	
Insert Row After	
Add Row to the End	
Delete Row	

The Edit Menu provides several groups of commands:

- **Undo** and **Cut**, **Copy**, and **Paste** provide editing functions for 2700 series text entries.
- **Copy Panel to Clipboard** places a bitmap image of the selected 2700 series panel on the Windows clipboard.
- The **Set Analyzer** and **Set Generator** commands provide an easy way to set reference levels and frequencies for the Analyzer and Generator panels for relative measurements. These are discussed in detail in the appropriate chapters.
- **Reset Bar-graph Max/Min** clears the gray minimum/maximum excursion bar from a selected Bar Graph display.
- The four last commands are only active when the Data Editor is open and selected, and provide the means to insert, add and delete data rows. See Chapter 21 for more information about using the Data Editor.

The View Menu



The View menu enables you to choose which workspace page to view, and whether or not the Status bar and any combination of Toolbars are displayed. A checkmark next to a View menu listing indicates that the selection is visible.

You can also open the Attached Files viewer from the View menu. Go to page 468 for more information about the Attached Files viewer.

The Panels Menu

Panels	
Analog Generator	Ctrl+G
Digital Generator	Ctrl+D
Analog Analyzer	Ctrl+A
Digital Analyzer	Ctrl+Y
Digital I/O	Ctrl+I
IEC 61937	▶
Dolby Digital	
Sync/Ref Input/Output	
Status Bits	Ctrl+B
Headphone/Speaker	Ctrl+H
DCX	
Switcher	
PSIA Receiver	Ctrl+R
PSIA Transmitter	Ctrl+T
Sweep	Ctrl+S
Settling	
Regulation	
External Sweep	
Graph	
Data Editor	
Bar Graphs	▶
Macro Editor	

The Panels menu shows all the control panels available in the control software. Click on a Panel name (or on its corresponding Toolbar button) to open a panel on the current workspace page. Panels can be duplicated on more than one page for convenience.


NOTE: Closing a panel does not stop its activity. If a generator panel has been set to output a sine wave, or an analyzer panel to measure a voltage, these activities continue whether or not the panel is visible on any page.

The panel functions are discussed in detail in these chapters:

- Analog Generator panel (Ctrl+G). See Chapter 6.
- Digital Generator panel (Ctrl+D). See Chapter 7.
- Analog Analyzer panel (Ctrl+A). See Chapter 8.
- Digital Analyzer panel (Ctrl+Y). See Chapter 5.

- Digital I/O (Digital Input/Output or DIO) panel (Ctrl+I). See Chapter 9.
- IEC 61937 panel > Dolby Digital. See Chapter 10.
- Sync/Ref Input/Output panel. See Chapter 25.
- Status Bits panel (Ctrl+B). See Chapter 9.
- Headphone/Speaker panel (Ctrl+H). See Chapter 24.
- DCX panel. The DCX-127 is an auxiliary multifunction instrument controlled by the 2700 series software. See the user's manual provided with the DCX-127.
- Switcher panel. The SWR-2755 series are auxiliary switching modules controlled by the 2700 series software. See the user's manual provided with the SWR-2755 switchers.
- PSIA receiver panel (Ctrl+R). The PSIA-2722 is an auxiliary programmable serial interface adapter controlled by the 2700 series software. See the user's manual provided with the PSIA-2722.
- PSIA transmitter panel (Ctrl+T). The PSIA-2722 is an auxiliary programmable serial interface adapter controlled by the 2700 series software. See the user's manual provided with the PSIA-2722.
- Sweep panel (Ctrl+S). See Chapter 18.
- Settling panel. See Chapter 18.
- Regulation panel. See Chapter 27.
- External Sweep panel. See page 422.
- Graph panel. See Chapter 19.
- Data Editor panel. See Chapter 21.
- Bar Graphs panel. See Chapter 20.
- Macro Editor panel. See Chapter 26.

The Help Menu



The Help menu gives you direct access to Online help and other information.

- **Tip of the Day**
opens the next Tip, and allows you to enable or disable the Tips on software launch.
- **2700 series Help**
is the main Help file for the control software. Topics in this Help file can also be accessed as context-sensitive help pushing **F1** while the cursor is in a control or reading field.
- **2700 Basic Extensions Help**
is the Help file that lists every AP Basic ActiveX Automation (OLE) command specific to the 2700 series instruments. Topics in this Help file can also be accessed as context-sensitive help pushing **F1** while the cursor is within command string in the Macro Editor.
- **AP Basic Language Help**
is a listing of the general (non-instrument-specific) command available in AP Basic.
- **Macro Editor Help**
provides topics about the use of the Macro Editor.
- **About AP2700**
provides information about the specific release of AP2700 control software.
- **Release Notes**
is a shortcut to the Readme.doc file.

Access to the Audio Precision Web site



The last line on the Help menu,

- Audio Precision Web... ▶

opens a submenu that lists the Web links currently provided to AP2700. The list will vary from no links to many, depending upon the AP2700 installation and version and whether or not new links have been added or deleted through visits to the Audio Precision Web site at ap.com or other file maintenance.

You will typically have Web links to

- Add-Ins: additional software features for AP2700, downloadable from the Audio Precision Web site. See page 26 for more information about Add-Ins.
- Home: the Audio Precision home page.
- Learning Center: the Tech Support Learning Center area at Audio Precision.
- Samples: the Tech Support Samples area at Audio Precision.

The Status Bar



The Status bar runs across the bottom of the workspace and displays the workspace page tabs and status notes as the control software operates.

The Toolbars

The 2700 series control software has 5 toolbars for quick access to panels and common functions. The toolbars can “float” at any location you place them on the workspace, or they can be “docked” or attached to the Menu bar. Whether docked or floating, the toolbars appear on every workspace page.

The toolbars display command buttons for one-click access to many often used functions.

The Standard Toolbar



The Standard toolbar gives you quick access to 2700 series file, printer and editing operations, as well as Sweep Stop/Start and FFT Time/Frequency domain switching. The buttons on the Standard toolbar are:



New Test resets the 2700 series control software to its defaults and initiates a new test.



New Test (Custom) resets the 2700 series control software to its defaults and initiates a new test, using custom user preferences you can edit and save.



Open Test presents you with a file browser window to select a previously saved test file (.at27 or .at2c) for opening.



Save Test saves the current test as .at27. If the test has not been previously saved, you will be presented with a browser window to choose a file name and location.



Save All saves not only the current test but any other files which are currently open, such as data or procedure files. If any file has not been previously saved, you will be presented with a browser window to choose a file name and location.



Print prints the current graph to your default printer with the current settings.



Print Preview provides a preview window of your graph using the current default printer and the current settings.



Undo allows you to “back up” one step in your text editing.

Cut removes the selected text and places it on the Windows clipboard.



Copy places the selected text on the Windows clipboard.



Paste inserts text from the Windows clipboard at the cursor location.



Go starts a sweep.



Stop ends a sweep.



Toggle FFT Time/Frequency Domain switches the graph between a frequency-domain view (spectrum view) and a time-domain view (waveform view) for the same input signal acquisition. This feature is only available while using the Spectrum Analyzer, the Multitone Audio Analyzer and the Digital Interface Analyzer.



The Panels Toolbar



The Panels toolbar gives you quick access to nineteen 2700 series panels:

This button opens the Analog Generator panel. See Chapter 6.



This button opens the Analog Analyzer panel. See Chapter 8.



This button opens the Digital Generator panel. See Chapter 7.



This button opens the Digital Analyzer panel. See Chapter 5.



This button opens the Digital Input/Output (DIO) panel. See Chapter 9.





This button opens the IEC 61937 / Dolby Digital panel. See Chapter 10.



This button opens the Sync/Ref Input panel. See Chapter 25.



This button opens the Status Bits panel. See Chapter 9.



This button opens the Headphone/Speaker panel. See Chapter 24.



This button opens the DCX panel. See the user's manual for the DCX-127.



This button opens the Switcher panel. See the user's manual for the SWR-2755 switchers.



This button opens the PSIA transmitter panel. See the user's manual for the PSIA-2722.



This button opens the PSIA receiver panel. See the user's manual for the PSIA-2722.



This button opens the Sweep panel. See Chapter 18.



This button opens the Settling panel. See Chapter 18.



This button opens the Graph panel. See Chapter 19.



This button opens the Data Editor panel. See Chapter 21.



This button opens a new Bar Graph panel. See Chapter 20.



This button opens the Regulation panel. See Chapter 27.

This button opens the Macro Editor panel. See Chapter 26.



The Macro Toolbar




The Macro toolbar offers 9 one-click operations for running and editing an AP Basic macro. See Chapter 26, **Automating Tests**, for explanations of functions initiated by Macro toolbar buttons.

The Learn Mode Toolbar



Learn mode logs all your 2700 series operations as you perform them, building a macro or script for automation purposes. The Learn Mode toolbar gives you the ability to turn the macro recording function ON and OFF with a click of the mouse. See Chapter 26, **Automating Tests**, for explanations of Learn Mode toolbar button functions.


The Quick Launch Toolbar



Quick Launch allows you to create and use custom toolbar buttons to open 2700 series tests, run AP Basic macros and even launch other Windows programs.

From the Main menu, choose **File > Quick Launch > Customize Quick Launch** to open the Quick Launch Configuration panel, where you can view or edit the existing Quick Launch commands or to add new commands of your own.

Figure 5.
The Quick Launch
Configuration panel



For each toolbar command, enter (or browse to) a command line with a complete path in the **Command** field. Name the command in the **Menu Text** field, and choose a toolbar button icon using the icon browser to the right. If you would like a macro from the Quick Launch toolbar to run immediately, check **Automatically run when loaded**.

To open the test, macro or program, click the button on the Quick Launch toolbar.

AP2700 Add-Ins

An Add-In is a small software package that adds a specific set of features to AP2700. Add-Ins can be downloaded and installed from the Audio Precision Web site.

An activated Add-In appears as an additional menu item in the appropriate AP2700 menu. If you have an Internet connection, you can browse the available Add-Ins using the Help menu (Help > Audio Precision Web... > Add-Ins) or go to our Web site at ap.com.

Working with Files and AP2700

Part of the power of the 2700 series control software is its capability to create, store, load and run files which contain test setup and measurement data information, similar to the way a word processor or spreadsheet application uses document, template or script files.

Test Files

The key “document” created by AP2700 is the *test*. The measurement settings and readings, control software settings, associated file links and (if you’ve actually used the test on a DUT) the measurement data are all saved in the test file. These files can be opened, re-used, modified and re-saved as you wish.

The filename extension for test files is

- 2700 series test file—.at27

Dozens of sample tests are available on our Web site at ap.com. You can use the test samples as examples or as starting points for your own custom tests.

System Two Cascade and Cascade *Plus* Tests

For your convenience when working with older files, AP2700 will also open and save System Two Cascade and Cascade *Plus* tests created using APWIN control software.

The filename extension for APWIN System Two Cascade and Cascade *Plus* test files is

- Cascade and Cascade *Plus* test file—.at2c

“New Test” files

When you first launch the control software, a default test setup called a *new test* is loaded. A new test not only sets the software to its defaults but also clears any data from memory and resets the instrument hardware, giving you a “clean start” from which to begin designing your own test.

If at some point in designing a test you would like to return to a “clean start” click the **New Test** button or the **New > Test** selection on the File menu. The control software will discard your current settings and data and reload the default setup.

You can also save a custom new test to load as a template using your personal preferences, and use that test as your starting point by clicking the **New Test (Custom)** button or the **New > Test (Custom)** selection on the File menu.

Macro Files

Another important file type is the *macro* file, sometimes called a *procedure* file. As in other programs, a macro is a programming script which can automate program functions. 2700 series macros are written in the programming language AP Basic, which is included with the 2700 series software.

The filename extension for macro files is

- AP Basic macro file—.apb

Data Files

The 2700 series control software stores all data from test results in memory as the test is run. As mentioned before, this information is saved along with panel and sweep setup information in a test file. The data can also be viewed and edited in a panel called the Data Editor, and can be saved as a separate file.

The 2700 series software can open saved data files in order to attach previous data to a current test. There are four different data file types, each of which has a different use.

The filename extensions for data files are

- AP data file—.ada
- AP limit file—.adl
- AP sweep file—.ads
- AP EQ file—.adq

NOTE: The four 2700 series data file types are identical except for their filename extensions. Data saved as .ada, .adl, .ads or .adq files can later be used for any data function. The different extensions serve to help organize data files and to indicate the intended use of the data.

It is also possible to export 2700 series data as an ASCII text file for use in a spreadsheet or text editor program. The extension for an ASCII data file is:

- AP ASCII data file—.adx

Waveform Files

For certain analyzer functions performed in digital signal processing (DSP), including FFT displays and some types of interface analysis, the 2700 series control software acquires a sample of the digital waveform. These samples can be saved as waveform files and later opened for further use.

The filename extensions for waveform files are

- AP stereo waveform file (generator)—.ags
- AP stereo waveform file (analyzer)—.aas
- AP mono waveform file (generator)—.agm
- AP mono waveform file (analyzer)—.aam

- AP digital interface waveform file—.aai

The Log File

The 2700 series software can generate a log file, which can contain error messages, file activity, sweep activity, graph information and pass/fail test results. The log file can be viewed on the screen or printed.

The filename extension for the log file is

- AP log file—.alg

The log file is enabled and set up on the Configuration panel, and is discussed in detail in Chapter 28.

Keyboard Shortcuts

Many of the control software Menu and Toolbar commands are also available as keyboard shortcuts using Function Keys and other key combinations. The Sweep **Start** command, for example, is **F9**; the Analog Generator panel can be brought to the screen with **Ctrl+G**.

Keyboard shortcuts are identified in the chapters which discuss the functions they command, and are shown as alternative commands in the 2700 series menus. They are listed here as well.

Function Keys

- **F1**
Context-sensitive Help—brings the Help topic associated with the currently selected panel feature to the screen.
- **F2**
In a Bar Graph, resets the minimum/maximum value history.
- **F2**
In the Data Editor, enables editing within a data cell.
- **F3**
Sets the Analog Generator dBr reference value to the current Analog Generator amplitude setting.
- **Ctrl-F3**
Sets the Analog Generator frequency reference value to the current Analog Generator frequency setting.
- **F4**
Sets the Analog Analyzer dBr reference value to the current Analog Analyzer amplitude reading.

- **Ctrl-F4**
Sets the Analog Analyzer frequency reference value to the current Analog Analyzer frequency reading.
- **F6** (for FFT-based, batch mode analysis tools: Spectrum Analyzer, Digital Interface Analyzer, Multitone Analyzer, MLS Analyzer).
Performs a new transform on the acquired data and graphs the results.
- **Ctrl-F6** (for FFT-based, batch mode analysis tools: Spectrum Analyzer, Digital Interface Analyzer, Multitone Analyzer, MLS Analyzer).
Graphs the transform results currently in DSP memory without performing a new transform.
- **F7**
Graphs the data currently in computer memory.
- **Alt-F8**
Stores the present trace or traces to the Graph Buffer memory.
- **F8**
Displays the trace or traces currently stored in the Graph Buffer memory.
- **Ctrl-F8**
Deletes any trace or traces in the Graph Buffer memory.
- **F9**
Starts a new Sweep; equivalent of Sweep **Start** or clicking the **Go** button.
- **Ctrl-F9**
Starts a new Sweep while retaining previous data, appending the new sweep to the old; equivalent of clicking **Go** when **Append** box is checked.
- **Alt-F9**
Starts a new Sweep in repeating mode; equivalent of clicking **Go** when **Repeat** box is checked.
- **F10**
The “sweep pause button.” Toggles a sweep from running to paused and back again.
- **F12**
The “panic button.” Turns off all generator outputs.
- **Ctrl-F12**
Turns on any generator outputs previously turned off by the panic button.

Other Keyboard Shortcuts

- **Shift-(Mouse Click)**
For those panels that have a large and a small view, pressing the **Shift** key while clicking on the panel button or the Panels menu command, opens the panel in its large view.
- **Print Scrn**
Copies the entire computer screen to the Windows Clipboard as a bitmap.
- **Alt-Print Scrn**
Copies the active window to the Windows Clipboard as a bitmap.
- **Esc**
Cancels keystrokes if they have not yet been entered; in windows with a **Cancel** button, **Esc** has the same effect as clicking **Cancel**.
- **Ctrl-1**
Displays the Workspace Page One.
- **Ctrl-2**
Displays the Workspace Page Two.
- **Ctrl-3**
Displays the Workspace Page Three.
- **Ctrl-4**
Displays the Workspace Page Four.
- **Ctrl-5**
Displays the Workspace Page Five.
- **Ctrl-A**
Opens the Analog Analyzer panel.
- **Ctrl-B**
Opens the Status Bits panel.
- **Ctrl-C**
Keyboard shortcut for **Edit > Copy**.
- **Ctrl-D**
Opens the Digital Generator panel.
- **Ctrl-G**
Opens the Analog Generator panel.
- **Ctrl-H**
Opens the Headphone/Speaker panel.
- **Ctrl-I**
Opens the Digital Input/Output (DIO) panel.

- **Ctrl-L**
Clears the panel displays from all workspace pages. Panels are still active, but not displayed.
- **Ctrl-N**
Opens a New Test.
- **Ctrl-O**
Opens the Open Test file browser.
- **Ctrl-P**
Opens the Print Dialog.
- **Ctrl-R**
Opens the PSIA Receiver panel.
- **Ctrl-S**
Opens the Sweep panel.
- **Ctrl-T**
Opens the PSIA Transmitter panel.
- **Ctrl-V**
Keyboard shortcut for **Edit > Paste**.
- **Ctrl-X**
Keyboard shortcut for **Edit > Cut**.
- **Ctrl-Y**
Opens the Digital Analyzer panel.
- **Tab**
Within a panel, moves from one control field to the next.
- **Shift-Tab**
Within a panel, moves from one control field to the next in the opposite order of Tab.
- **Ctrl-Tab**
Within the Workspace page, shifts the Windows focus from one panel to another.
- **Ctrl-↑**
Ctrl-↓
For those panels that have a large and a small view, toggles the view.

Chapter 3

The 2700 Series Hardware

There are no measurement control or displays on a 2700 series instrument chassis. Instead, the user interface is through the settings and displays of the control software, running on a personal computer connected to the instrument through the Audio Precision Interface Bus (APIB).

All signal generation and analysis is performed in the 2700 series instrument hardware, including storage of signals acquired for digital signal processing (DSP) waveform display or FFT analysis.

2700 Series Interface Bus

2700 series instruments operate under the 2700 series control software, AP2700, which is included in the purchase. The instruments are connected to the controlling computer by the proprietary Audio Precision Interface Bus (APIB). This manual covers the operation of 2700 series instruments running AP2700 and using APIB exclusively.

2700 series Instrument Configurations

2700 series instruments can be ordered in a number of configurations, enabling you to purchase exactly the features you need for your application. This manual describes the operation of the most-capable 2700 series instrument designated SYS-2722A, which is the APIB model with full features and capabilities, including Dual Domain (operation in both digital and analog domains) and DSP. If you have a 2700 series model equipped with reduced features and capabilities, not all of the discussions in this manual will apply to the operation of your unit.

The 2700 series APIB line includes the following models and capabilities:

Model	Capabilities
SYS-2722A	Dual Domain (DSP included) and 192k
SYS-2720A	Digital Domain Only (DSP included) and 192k
SYS-2712A	Analog Domain Only, with DSP
SYS-2702A	Analog Domain Only

For information on the availability of GPIB versions of 2700 series instruments, please contact your sales representative.

2700 Series Major Options

Several major options are available to add further capabilities to the 2700 series of instruments.

■ S2-IMD

The “IMD” option adds specific intermodulation distortion (IMD) measurement generation and analysis capabilities to the Analog Generator and the Analog Analyzer. This is an analog domain option and cannot be fitted to the SYS-2720 (digital only) instrument.

NOTE: Without the S2-IMD option, 2700 series instruments with DSP can still generate and analyze IMD test signals using digital generation and analysis.

■ S2-W&F

The “W&F” option adds specific wow and flutter (W&F) measurement analysis capabilities to the Analog Analyzer. This is an analog domain option and cannot be fitted to the SYS-2720 (digital only) instrument.

■ S2-BUR

The “BUR” option adds analog generation of both triggered and untriggered tone bursts to the Analog Generator. Also, it adds the capability to generate noise test signals and square wave signals entirely in the analog domain. This is an analog domain option and cannot be fitted to the SYS-2720 (digital only) instruments.

NOTE: Without the S2-BUR option, 2700 series instruments with DSP capabilities can still produce tone bursts and noise and square wave test signals using digital generation.

■ S-AES17

The S-AES17 Option is a set of filters designed to accurately measure signals in the audio passband when in the presence of high-level out-of-band noise, as can occur at the output of oversampled DACs. S-AES17

is different from the 2700 series “option filters” (discussed below) in that much of the filtering occurs *before* the Analyzer circuitry. This option satisfies the AES17-1988 recommendation for a “standard low-pass filter” for such measurements. This is an analog domain option and cannot be fitted to the SYS-2720 (digital only) model.

- **OPT-2020**

The OPT-2020 Pre-Analyzer Filter is similar to the S-AES17 filter described above, but with somewhat different characteristics. For more information on the OPT-2020 Pre-Analyzer Filter, please contact your sales representative.

- **OPT-2711**

The OPT-2711 Dolby Digital Generator can encode into Dolby Digital any of the wide range of digital stimulus signals available from a 2700 series instrument, with both the stimulus generation and the Dolby Digital and IEC 61937 parameters under programmatic control (using AP Basic), if desired. The decoded multichannel outputs of the DUT can be routed through an audio switcher and into the instrument analyzer, once again under programmatic control. The stimulus signals and the integrated control of switching, sweeps, measurement and display can thoroughly and very quickly test DUTs that incorporate Dolby Digital decoder functions.

The options are discussed in more detail in the Analog Generator, Analog Analyzer and Dolby Digital Generator chapters and in documentation included with the options.

2700 Series Option Filters

The Analog Analyzer hardware has seven slots for plug-in option filters. Option filters are specialized high-pass, low-pass, weighting and other filters mounted on small plug-in modules. Once installed in the instrument, option filters can be selected by Analog Analyzer panel software commands.

Use of option filters is discussed in detail in the Analog Analyzer chapter. Filter installation is covered in the documentation accompanying the filter modules.

Auxiliary Equipment for the 2700 Series

Audio Precision manufactures four major products to extend the capabilities of a 2700 series instrument, all under the control of the 2700 control software.

- **PSIA-2722 Programmable Serial Interface Adapter**

The PSIA-2722 enables you to route the digital generator output and digital analyzer input to a custom-designed serial digital interface for con-

verter design and testing, with rates, resolutions and other characteristics not available at the standard AES/IEC60958 input and output. The PSIA-2722 can be synchronized to a variety of external clock signals, and provides both inputs and outputs at master clock, $N \times F_s$, bit clock, sub-frame clock and frame clock rates.

■ **AUX-0025 Switching Amplifier Measurement Filter**

The Switching Amplifier Measurement Filter is a two-channel low-pass filter designed to accurately measure the output signal of switching amplifiers, such as Class D amplifiers. Such amplifiers can produce high-level out-of-band noise and distortion, and the AUX-0025 attenuates these out-of-band signals before they reach the analog analyzer ranging circuits and input amplifiers.

■ **SWR-2755-series Switchers**

SWR-2755 Switchers enable you to route the two-channel 2700 series analog inputs and outputs to multiple device inputs and outputs under software control. Switchers are available as balanced input (SWR-2755F), balanced output (SWR-2755M) and unbalanced input/output (SWR-2755U) models. Each unit is a 12 x 2 routing switcher. Up to 16 switchers can be linked, making a maximum of 192 channels of input and 192 channels of output available.

■ **DCX-127 Multifunction Module**

The DCX-127 Multifunction Module adds these capabilities to a 2700 series instrument: DC voltage measurement, resistance measurement, two software-controlled DC outputs, a 21-bit digital input/output, and three 8-bit programmable utility output ports.

The SYS-2722 Front Panel



Figure 6. SYS-2722 Front Panel.

The main digital and analog input and output connectors are on the SYS-2722 front panel, along with the mains power switch, a lighted “power on” indicator, and the headphone jack and volume control.

The front panel connectors are identified and briefly described in the following sections. See Chapter 4, **Signal Inputs and Outputs** for more information about the SYS-2722 main inputs and outputs and the software panels associated with them. See Chapter 24, **Monitoring** and Chapter 25, **Sync and Auxiliary Connections** for more information about the SYS-2722 monitor, sync and auxiliary inputs and outputs.

Refer to the manual *Getting Started with Your 2700 Series Instrument* for detailed input and output specifications.

Main Digital Input and Output



Figure 7. SYS-2722 main Digital Output and Digital Input.

The main digital output and input are on the lower-left subpanel.

■ THE DIGITAL OUTPUT

The SYS-2722 digital output can be routed to the balanced XLR male “I” connector, the unbalanced “I” BNC connector or the optical connector by software selections. When the dual-connector output configuration

is selected, both the “I” and “II” connectors (either XLR or BNC) are used together.

■ THE DIGITAL INPUT

The SYS-2722 digital input can be routed from the balanced XLR female “I” connector, the unbalanced “I” BNC connector or the optical connector by software selections. When the dual-connector input configuration is selected, both the “I” and “II” connectors (either XLR or BNC) are used together.

The Analog Outputs



Figure 8. SYS-2722 Analog Outputs.

The SYS-2722 analog outputs are on the upper-left subpanel.

The analog outputs for both “A” and “B” channels are available as balanced signals at the XLR male connectors and dual banana jacks, and as unbalanced signals on the BNC connectors.

There is a chassis ground terminal next to each channel output grouping, suitable for bare wire or banana plug connection. This terminal and pin 1 of the XLR are wired to the same chassis ground point. See Chapter 4 for more detail.

The Analog Inputs



Figure 9. SYS-2722 Analog Inputs.

The analog inputs are on the upper-right subpanel.

The XLR female and dual banana balanced connectors and the BNC unbalanced connectors for both “A” and “B” channels are routed to the SYS-2722 analog inputs.

There is a chassis ground terminal next to each channel input grouping, suitable for bare wire or banana plug connection. This terminal and pin 1 of the XLR are wired to the same chassis ground point. See Chapter 4 for more detail.

Monitor, sync and trigger connections



Figure 10. 2700 series Monitor / Aux / Sync connections.

Commonly used monitor, sync and trigger connections are on the lower-right subpanel, which provides BNC outputs that permit monitoring of key generator and analyzer signal points on an external oscilloscope or spectrum analyzer.

On the same panel, the Generator Aux Signals provide a scope sync output and a burst trigger input.

The 2700 Series Rear Panel



Figure 11. 2700 Series Rear Panel.

The 2700 series rear panel provides the mains power and APIB connections and miscellaneous auxiliary, sync and reference inputs and outputs, and the optionally activated APSI interface. The 2700 series mains fuses are mounted within the power entry module, discussed below.

The rear panel connectors are identified and briefly described in the following sections. See Chapter 25, **Sync and Auxiliary Connections** for more information about the 2700 series sync and auxiliary inputs and outputs.

Refer to the manual *Getting Started with Your 2700 Series Instrument* for detailed input and output specifications.

Labeling

The Configuration label is attached in the upper-left area of the 2700 series rear panel. System model number and installed options and option filters are indicated on this label.

The Serial Number label is attached in the upper-right area of the panel, next to the Audio Precision logo.

Mains power requirements are noted on the label in the center of the rear panel, just above the power entry module. Fuse replacement information is noted on the same label.

Mains voltages and fusing

2700 series instruments can be operated with a 50–60 Hz alternating current mains supply, at voltages of 100, 120, 230 or 240 VAC. These voltages must be selected by moving a jumper within the power entry module, as explained in *Getting Started with Your 2700 Series Instrument*. A white plastic tab in the power entry module indicates the currently selected voltage on the outside of the module.

Note that different mains voltages require different fuse values for correct operation; check this label and refer to information in *Getting Started with Your 2700 Series Instrument* for correct fusing when changing mains voltage.

Power Entry Module

The power entry module includes:

- **POWER CORD CONNECTOR**—This is a standard grounded connector for the mains power supply cord.
- **FUSE HOLDER / MAINS SUPPLY VOLTAGE JUMPER**—Open the cover of the fuse holder (see the separate manual *Getting Started with Your 2700 Series Instrument*) for access to the mains power fuse and the mains supply voltage configuration jumper card.
- **MAINS SUPPLY VOLTAGE INDICATOR**—The white tip of the plastic indicator on the voltage configuration jumper card appears in one of four small holes to show the mains voltage selection.

The APIB interface connectors




Figure 12. 2700 series APIB connectors.

The APIB interface connector subpanel is centered in the upper area of the 2700 series rear panel. The APIB interface provides the two-way Audio Precision Interface Bus (APIB) connection between the 2700 series hardware and the PC running the control software.

Other Audio Precision instruments, such as the ancillary units DCX-127 and the SWR-2755 switcher series, also use APIB for communication with the 2700 series control software. A string of APIB instruments can be connected together in a “daisy-chain” pattern, as described in the documentation for the ancillary equipment.

The male 25-pin D-SUB APIB connector on the 2700 series rear panel is normally used for connection to the PC, although the female connector could be used instead. The pins on the male 25-pin D-SUB connector are effectively in parallel with the pins on the female 25-pin D-SUB connector, providing a “loop-through” capability when linking APIB to both the 2700 series instrument and ancillary equipment.

The three LEDs on the panel indicate the status of the APIB. After the 2700 series control software has been launched and has stabilized, the ADDRESSED indicator will remain lit, the RDNG RDY indicator will blink rapidly, and the RESET indicator will be unlit.

Sync, Reference and Auxiliary Connections




Figure 13. 2700 Series Sync, Reference and Auxiliary connectors.

The 2700 series Sync, Reference and Auxiliary subpanel is located in the lower-right rear panel. Various auxiliary digital, sync and trigger connections can be made on this subpanel. The connections available are:

- VIDEO / TTL REF IN—This connector provides an input for a square wave or an NTSC/PAL video signal for sample rate synchronization (“house sync”).
- TRIGGER OUT—This connector provides an output from the DSP module for triggering an external oscilloscope.
- AES/EBU REF IN—This connector provides an input for an external digital audio signal for AES3/IEC 60958 sample and frame rate synchronization (“house sync”) and delay calculations. This connector also serves as the input for the **Pass-Thru** generator function.
- AES/EBU REF OUT—This connector outputs an AES3/IEC 60958 digital reference signal at the current sample rate (SR). This signal is stripped of audio information and interface impairments, and is intended as a synchronization reference (“house sync”) for other equipment.

- **MASTER CLK OUT**—This connector provides a square wave output at the instrument master clock rate.
- **TRANSMIT FRAME SYNC**—This connector provides a square wave output at the current sample rate (SR).
- **RECEIVE FRAME SYNC**—This connector provides a square wave output at the input sample rate (ISR).
- **EXT TRIGGER IN**—This connector provides an input for triggering or initiating DSP acquisitions in certain measurement functions.
- **AUX OUT**—This connector provides a trigger output that is switched high for one sample each time the Digital Data Analyzer detects an error.
- **PARALLEL OUTPUT and PARALLEL INPUT**—These are general-purpose parallel ports, transmitting and receiving the digital audio signal in a multiplexed dual channel, 24-bit 2's complement format. They are intended for connection to parallel-interfaced ADCs and DACs, for direct connection to DSP devices under test, or carry data to and from the PSIA-2722 Serial Interface Adapter.
- **APSI INTERFACE**—This connector provides the two-way Audio Precision Streaming Interface. APSI is only used with for the OPT-2711 Dolby Digital Generator option, and is only functional with the installation of that option and the licensed activation of the software components.

See Chapter 9, the **Digital I/O Panel**, for more information about using the parallel digital input and output.

See Chapter 25, **Sync and Auxiliary Connections** for more information about the 2700 series sync and auxiliary inputs and outputs, and the software panels associated with them.

Chapter 4

Signal Inputs and Outputs

This chapter discusses the hardware aspects of SYS-2722's main analog and digital signal inputs and outputs. Monitor connections are discussed in Chapter 24, while sync, reference and auxiliary connections are examined in Chapter 25.

The analog and serial digital signal input and outputs are located on the SYS-2722 front panel. The parallel digital signal input and output are located on the rear panel.



Figure 14. SYS-2722 Front Panel.

The analog inputs are selected and configured in the 2700 series control software on the Analog Analyzer panel; the analog outputs are controlled from the Analog Generator panel.

Selection and configuration of the serial and parallel digital input and output are accomplished on the Digital Input/Output (DIO) panel.

See **Specifications** in *Getting Started with Your 2700 Series Instrument* for detailed hardware specifications for both the analog and digital inputs and outputs.

The Analog Outputs




Figure 15. Analog Output Circuit Configurations, simplified. One channel shown; both channels are identical.

Output selection and impedance are set on the Analog Generator panel, page 95.

The 2700 series analog outputs can be configured to provide a balanced or unbalanced test signal, either floating or grounded, and a common-mode-test signal. The software output configuration selection affects both Channels A and B.

As shown in Figure 15, the output banana jacks are always hard-wired to the XLR male connector, with the “+” jack to pin 2 and the “-” jack to pin 3. Any signal discussed as appearing at XLR pins 2 and 3 will also appear at the “+” and “-” banana jacks.

The balanced signal is available on the XLR connector, with pin 2 wired to the “high” leg of the signal, pin 3 to the “low,” and pin 1 to chassis ground. In balanced floating configuration, the transformer is connected across pins 2 and

3, and half the selected output impedance is connected in series with each leg. The center pin of the BNC connector is connected to the transformer center tap and may be used to inject a common-mode signal or to provide an AC-coupled ground reference by connecting an external capacitor to ground.

In the balanced grounded configuration, the transformer center tap is grounded through a 5 Ω positive temperature coefficient (PTC) resistor as a protective device. The BNC connector is across this resistor and is essentially shorted; it has no use in this configuration.

When an output is set to unbalanced floating, the signal is available at both the XLR male connector and the BNC connector simultaneously. Only half the output transformer secondary is used, with the signal high connected to the center pin of the BNC and pin 2 of the XLR. The selected output impedance is connected in series with this leg. Signal low is the center tap of the transformer secondary, which is connected to the BNC shell and pin 3 of the XLR. Pin 1 of the XLR is wired to chassis ground. Since only half the transformer secondary is used, the maximum available amplitude is half that (or 6.02 dB less) of the balanced configuration.

In the unbalanced grounded configuration, the signal low (the center tap point) is grounded through the 5 Ω PTC resistor.

The common mode test (CMT) signal is applied to both pins 2 and 3 of the XLR connector, while pin 1 is grounded. The transformer center tap, which is the signal low in this configuration, is grounded through the 5 Ω PTC resistor. The BNC connector is across this resistor and is essentially shorted; it has no use in this configuration. Since only half the transformer secondary is used, the maximum available amplitude is half that (or 6.02 dB less) of the balanced configuration.

Common mode tests measure the ability of a differential input to attenuate common-mode signals; the equal amplitude, in-phase signals (with respect to ground) on pins 2 and 3 in the CMT configuration will be largely rejected by a well designed differential (balanced) input.

Output Impedance

Output impedance can be set to either 40 Ω , 150 Ω or 600 Ω in the balanced configuration (40 Ω , 200 Ω or 600 Ω for the European impedance hardware option EURZ), and to 20 Ω or 600 Ω in the unbalanced configuration.

Changing the output impedance does not change the open-circuit voltage driving the impedance, with the exception noted below. With a finite load impedance, the actual terminal voltage will change as output impedance changes, since the effective voltage-divider ratio between source and load also changes.

The exception is found when **dBm** or **Watts** units are selected. Under these conditions, the 2700 series control software computes the open circuit voltage

necessary to produce the specified power requested in the Amplitude field across the external load value specified in the **Reference dBm** or **Reference Watts** field. Since this open circuit voltage value also depends on generator output impedance, the open circuit voltage will change when the source impedance is changed, to hold power in the load constant. See **Analog Generator Amplitude**, page 68; **Analog Generator References**, page 96; and **Units of Measurement**, Appendix A.

The Analog Inputs




Figure 16. Analog Input Circuit Configurations, simplified.
One channel shown; both channels are identical.

Input source selection is made on the Analog Analyzer panel, page 126.

SYS-2722 will accept a balanced or an unbalanced input signal, with different termination impedances available for the balanced inputs. The software input source and impedance selections are independently set for Channels A and B.

As shown in Figure 16, the input banana jacks are always hard-wired to the XLR female connector, with the “+” jack to pin 2 and the “–” jack to pin 3.

NOTE: Do not connect input cables to both the banana jacks and the XLR connectors of a channel at the same time. Circuit conditions external to the 2700 series instrument could degrade the system performance. However, you may use the banana jack input of one channel and the XLR input of the other channel at the same time.

The input termination impedance at each of the analog inputs can be independently set to 300 Ω , 600 Ω or 100 k Ω .

NOTE: We recommend that you do not leave cables connected to both the balanced and unbalanced analog inputs of either channel simultaneously. Circuit conditions external to the 2700 series instrument could degrade the system performance. However, you may use the balanced input of one channel and the unbalanced input of the other channel at the same time.

The Serial Digital Output

The serial digital output signal is available as a balanced electrical signal at the XLR male connectors, in either single or dual-connector configurations. This output satisfies the electrical requirements of the AES3 professional interface standard. Use the XLR male connector labeled “**I**” for the customary single-connector configuration, and both “**I**” and “**II**” XLRs for the optional dual-connector configuration.

The output signal is also available as an unbalanced electrical signal at the BNC connector. This output satisfies the electrical requirements of both the AES3id professional standard and the IEC 60958-3 standard, which is compatible with the SPDIF consumer digital interface format. Use the BNC connector labeled “**I**” for the customary single-connector configuration, and both “**I**” and “**II**” BNCs for the optional dual-connector configuration.

The XLR and BNC digital outputs are calibrated with the assumption that the signal is terminated in the proper impedance (110 Ω for the balanced output; 75 Ω for the unbalanced). If the signal isn’t properly terminated the actual output voltage will be different from the voltage specified in the DIO panel.

The serial digital output is also provided as an optical signal compatible with the Toslink® interface.

Digital output selection and interface configuration are set on the DIO panel, page 153.

NOTE: We recommend that you do not use the balanced and unbalanced digital outputs simultaneously. Circuit conditions external to the 2700 series instrument could degrade the system performance. However, the optical output can be used simultaneously with either the balanced or unbalanced digital output.

The Serial Digital Input

The serial digital input accommodates the same interface formats as the digital output. The XLR female connectors provide a balanced input for satisfying the electrical requirements of an AES3 professional format digital audio signal

in either single or dual-connector configurations. Use the connector labeled “**I**” for the customary single-connector configuration, and both “**I**” and “**II**” for the optional dual-connector configuration. Input termination can be set on the DIO panel to **HiZ** (approximately 10 k Ω) or to **110 Ω** , the AES3 standard.

The BNC input connector is configured for an unbalanced digital signal satisfying the electrical requirements of both the AES3id professional format and the IEC 60958-3 (SPDIF) consumer interface format. Use the connector labeled “**I**” for the customary single-connector configuration, and both “**I**” and “**II**” for the optional dual-connector configuration. Input termination can be set on the DIO panel to **HiZ** (approximately 10 k Ω) or to **75 Ω** .

The optical input is compatible with the Toslink® interface.

Digital input selection and interface configuration are set on the DIO panel, page 153.

NOTE: We recommend that you do not maintain connections to the balanced and unbalanced digital inputs simultaneously. Circuit conditions external to the 2700 series instrument could degrade the system performance. However, a connection to the optical input can be maintained simultaneous to a connection to either the balanced or unbalanced digital input. The DIO panel will select only one input at a time.

Electrical vs. Data Characteristics Across Formats

The various standards defining serial digital audio interface formats cover a broad number of characteristics, including line impedance, signal voltage, acceptable rise-time and jitter figures, and also the information carried as data on the interface.

Although the SYS-2722 balanced and unbalanced digital connections do satisfy the electrical requirements for certain standards, as mentioned above, selecting the balanced or unbalanced digital input or output does not configure the digital data stream. This is done in other fields on the DIO panel and on the Status Bits panel. See Chapters 9 and Appendix B for a full discussion of the serial digital data stream and status bits.

It is entirely possible to route digital audio data configured to the professional format standard (AES3) to the unbalanced output with voltage and impedance characteristics matching the consumer format standard (IEC 60958-3), as it is possible to route consumer-formatted data to the balanced output, at the professional format voltage levels and impedance values.

Parallel Digital Output and Input

Professional and consumer digital audio is invariably carried in a standard serial digital interface format, and the 2700 series front-panel digital output and input are designed to accommodate these serial formats.

Research and development in digital audio and especially converter design applications, however, may require that the digital audio be carried in a parallel format for connection to parallel-interfaced ADCs and DACs or for direct connection to DSP systems under test; or that a parallel output and input be used to address a serial interface adapter such as the Audio Precision PSIA-2722, which converts a parallel signal to a set of serial data and clock signals.




Figure 17. 2700 series rear panel connections, showing the parallel output and input connectors at the bottom of the subpanel.

For these applications the 2700 series provides general-purpose parallel digital output and input ports, mounted on a subpanel on the rear of the instrument. The parallel ports are configured as multiplexed dual channel, 24-bit two's complement format. Like the serial digital ports, these are selected and controlled on the DIO panel, discussed in Chapter 9.

The input port and output port each consist of a 50-pin dual-row shielded SCSI-type connector. These connectors are intended to be wired with twisted pairs for each data bit to maintain optimum waveshape and minimize radio-frequency interference. See the table on page 56 for pin assignments. To reduce the risk of damage it is strongly recommended that all connections to the parallel ports be made with power to the 2700 series instrument turned off.

There are 24 data lines, a channel select line, and a strobe line. The remaining pins are grounds, plus one +5 V power line (V_{cc} in the table). The table on page 56 lists the pinout of both input and output connectors. Figure 20 on page 56 shows the physical orientation of the pins on the connectors when viewed from the rear of the instrument.

Parallel Input

The parallel input accepts 24-bit data on the data lines and latches it when the strobe line makes a transition from low to high. The data is latched into the channel A input when the channel select line is held low and the strobe makes a transition from low to high. The data is latched into the channel B input when the channel select line is held high and the strobe makes a transition from low to high.




Figure 18. Parallel Input Port timing relationships.

Latching channel B data also generates an interrupt for the 2700 series instrument, causing it to read both channels of data just written to the latches. The channel select line must be held during the entire time the strobe line is low. A transition on the channel select line while the strobe line is low will cause an incorrect latch operation. Figure 18 illustrates the correct operation of the parallel input port and identifies the timing specifications for the operations. Note that data must always be supplied to Channel B since its latch operation triggers the DSP to read the data. If a single channel interface is desired, it must therefore be configured as Channel B and the channel select line connected to +5 V.

All data inputs are 3.3 V TTL. This allows connection to a wide variety of devices without loading concerns. The capacitance of each data line is approximately 10 pF. There are no termination resistors. If fewer than 24 bits are applied to the input, the data must be applied to the MSBs; the unused LSB input lines should be connected to ground.

Current in each data input must be limited to 10 mA or less. If the voltage at the source device outputs exceeds 3.3 V, a series resistor must be inserted in each data line to limit input current. The resistor value is calculated by

$$R = \frac{(V_{drive} - 4 \text{ V})}{10 \text{ mA}}$$

For a 5 V source output, the correct resistor value is 100 Ω .

The strobe line and channel select line inputs are 5 V TTL, compatible with 3.3 V TTL. The strobe and channel select inputs are internally pulled high with resistors. If the pins are not connected, this will suffice to maintain the signals high. However, if wires are attached to either of these lines and bundled into cables with the data lines, there may be sufficient capacitance and mutual inductance to couple transitions into one or both inputs, causing mis-operation of the interface. To reduce the magnitude of this coupling, the channel select and strobe lines should be driven from a low impedance source. Using twisted pair or ground-plane ribbon cable may reduce the coupling of data-line transitions into the strobe or channel-select inputs. However, the added load capacitance on the data lines may increase the noise created by data transitions. Placing resistors of from 22 Ω to 100 Ω in series with the source outputs will reduce the rise time of signals and reduce coupling into adjacent lines. On bundled cables there may be significant inductive coupling between the data lines and the strobe line. If this occurs, the strobe line may be removed from the bundle and run separately from the remaining lines. Terminating the strobe and channel select lines with a resistive pull-up/pull-down network at the connector may reduce the coupling and improve signal integrity. For most applications a 390 Ω pull-up to +5 V and a 220 Ω pull-down to ground will present an adequate load for each line. These two networks may be powered by the +5 V pin on the interface connector and should be mounted on the connector itself. Proportionately lower resistances may be required when the cable impedance is significantly lower.

Logic noise on the 2700 series instrument ground connections may induce noise in the analog portions of the circuit being measured if care is not taken in the connections. This has resulted in some low level spurious noise observed when measuring oversampling DACs with switched capacitor input circuits. Oversampling ADCs which use linear circuits for their loop filters have not shown similar sensitivity to ground noise, nor have conventional successive approximation converters. If ground noise effects are suspected, the grounds of the converter board under test and the 2700 series instrument may be isolated with ferrite beads in the ground conductors or by opto-isolators in the data link.

If some of the bits (especially the sign bit) are allowed to leak into the analog signal it will result in odd harmonic distortion (3rd, 5th, 7th, etc.) in the

measured results. Excessive distortion is often a clue to examine the leakage paths in the device under test.

Parallel Output

Note that dither is fully operational for the parallel digital output signal. See Dither on page 120 for details. The output bits below the dither point are truncated by the DSP.

The output port provides data on the data lines at all times. The channel select line determines which channel's data appears on these lines. The output strobe line causes both channels of data to be updated, and signals the 2700 series instrument processor that another pair of data words are required. The data is buffered with a two stage FIFO buffer which guarantees that data will be available when needed, rather than after the processor's service delay.

As long as the maximum sample rate restriction is obeyed, the two-stage buffer will never empty. Figure 19 illustrates correct operation of the parallel output port and identifies timing specifications for the operations.

Note that data may be read from one or both channels, as desired. However, the typical wiring connection to these ports provides an automatic strobe operation when the channels are read. If a single channel output is desired, the port should be configured as Channel B and the channel select line connected to the +5 V supplied on the interface.

There is no limitation that the input and output sample rates be exactly the same or synchronous. However, it is assumed that the sample data pairs are read and written at a constant sample rate. The small FIFO buffers will allow sample jitter in the input and output operations of as much as 3/4 of a sample period.

The strobe line and channel select line are TTL level high speed CMOS inputs. All outputs are CMOS with 50 Ω build-out resistances and rise time limiting networks in series. This allows connection to a wide variety of devices without loading concerns. If fewer than 24 bits are needed, the most significant bits should be used and the unused LSB lines must be left unconnected.

The channel select and strobe inputs are internally pulled high with resistors. If the pins are not connected, this will suffice to maintain the signals high. However, if wires are attached to either of these lines and bundled into cables with the data lines, there may be sufficient capacitance and mutual inductance to couple transitions into one or both inputs, causing mis-operation of the interface. To reduce the magnitude of this coupling, the channel select and strobe lines should be driven from a low impedance source. Using twisted pair or ground-plane ribbon cable may reduce the coupling of data-line transitions into the strobe or channel-select inputs. However, the added load capacitance on the data lines may increase the noise created by data transitions. On bun-





Figure 19. Parallel Output Port timing relationships.

dled cables there may be significant inductive coupling between the data lines and the strobe line. If this occurs, the strobe line may be removed from the bundle and run separately from the remaining lines. Terminating the strobe and channel select lines with a resistive pull-up/pull-down network at the connector may reduce the coupling and generally improve signal integrity. For most applications a 390 Ω pull-up to +5 V and a 220 Ω pull-down to ground will present an adequate load for each line. These two networks may be powered by the +5 V pin on the interface connector and should be mounted on the connector itself. Proportionately lower resistances may be required when the cable impedance is significantly lower.

Parallel Interface Connector Pin Assignments

Figure 20. Parallel I/O connector pin locations.



Pin #	Function	Pin #	Function
1	Channel	26	Vcc
2	Strobe	27	Ground
3	Bit 1	28	Bit 0
4	Bit 2	29	Ground
5	Bit 3	30	Ground
6	Bit 4	31	Ground
7	Bit 5	32	Ground
8	Bit 6	33	Ground
9	Bit 7	34	Ground
10	Bit 8	35	Ground
11	Bit 9	36	Ground
12	Bit 10	37	Ground
13	Bit 11	38	Ground
14	Bit 12	39	Ground
15	Bit 13	40	Ground
16	Bit 14	41	Ground
17	Bit 15	42	Ground
18	Bit 16	43	Ground
19	Bit 17	44	Ground
20	Bit 18	45	Ground
21	Bit 19	46	Ground
22	Bit 20	47	Ground
23	Bit 21	48	Ground
24	Bit 22	49	Ground
25	Bit 23 (MSB)	50	Ground

The +5 V power line provided on the connectors is intended only to be used to tie unused data or control inputs high or to power termination networks if necessary. The power supply of the 2700 series instrument has not been designed to source current to customer-supplied devices.

Chapter 5

Signal Analysis with the 2700 series

This chapter gives a brief overview of the tools a SYS-2722 instrument provides for signal analysis, and serves as an introduction to test and measurement techniques using a 2700 series instrument. The SYS-2722 model can test and measure analog audio signals, the serial digital interface signal, and the digital audio signal carried on the interface.

For each type of signal, SYS-2722 provides the capability to generate a variety of stimulus signals for input to the device under test (DUT), and the capability to analyze the output of the DUT in a number of different ways.

References link the key topics introduced here to later chapters where they are examined in detail.

Test Signal Generation in the 2700 series

Most audio testing requires that a stimulus signal be applied to the device under test (DUT). At its most basic, the stimulus may be just a 1 kHz sine wave at a nominal level; a more complex stimulus might be a sweep of frequencies, or a combination of tones used for intermodulation distortion (IMD) testing. An example of a very complex stimulus is a *multitone*, which has many precisely generated frequencies at a range of specific levels.

The signal generation systems in a 2700 series instrument use both precision analog circuits and digital signal processing (DSP) techniques to create a wide range of stimulus signals.

Two Audio Signal Generators

SYS-2722 has two independent audio signal generating systems: the Analog Generator, which provides signal to the Analog Outputs, and the Digital Generator, which is the source of the audio embedded in the Digital Output sig-

nal. The two generators are similar in operation and in the settings available on their respective control panels.

Analog Audio Signals

Analog Audio Generation and Output



The Analog Generator uses analog circuitry to generate most of its test signals, and can also output a number of signals created digitally in dedicated DSP. The Analog Generator panel also provides controls to select and configure the analog outputs.

The Analog Analyzer



The SYS-2722 analog inputs are selected and configured on the Analog Analyzer panel (see Chapter 8). These signals can be examined in the analog domain using the Analog Analyzer, or can be converted to the digital domain using high-performance analog-to-digital converters (ADCs) and analyzed by the Digital Analyzer.

The 2700 series Analog Analyzer is a high-performance, multi-functioned audio analyzer. Although many of its functions are duplicated in the Digital Analyzer's DSP Audio Analyzer, in most cases the Analog Analyzer produces measurements with lower distortion and noise, wider bandwidth and flatter response. The Analog Analyzer is the best choice for precision measurement of analog audio signals. It is discussed in detail in Chapter 8.

Digital Audio Signals

The Serial Digital Interface Signal



AES3/60958 digital audio is transmitted and received on a serial digital interface signal. The interface signal has characteristics which can be measured and tested, and SYS-2722 provides both a basic capability to do this in the Digital Input / Output (DIO) panel, and a more powerful capability in the Digital Interface Analyzer (Intervu), a DSP analysis tool in the Digital Analyzer.

Since the interface signal carries the digital audio, some characteristics of the interface signal can be observed by measuring the effects on the embedded audio signal.

The DIO panel also configures SYS-2722 to receive the data stream from the digital input, and passes the embedded audio on to other SYS-2722 functions.

All the input and output configuration of the digital interface signal is accomplished from the DIO panel. See Chapter 9 for detailed information on the DIO panel.

Digital Audio Generation

SYS-2722 can produce a wide range of digital audio signals in the Digital Generator (see Chapter 7). After generation, the digital audio is embedded in the serial digital interface signal (and configured for output on the DIO panel) before being applied to the input of a digital DUT as a stimulus signal.



The Digital Generator and the Analog Generator (discussed above) are similar in appearance and function.

The Digital Analyzer

The Digital Analyzer panel provides access to seven specialized software analysis tools. Selecting a Digital Analyzer tool loads a specific measurement program into the Digital Analyzer DSPs. Each Digital Analyzer tool changes the appearance of the Digital Analyzer panel, bringing its own set of input, setting, reading and other parameter choices.

The audio from the digital input is routed (via the DIO panel) to the Digital Analyzer, where the selected DSP analysis tool is applied. One tool, the DSP Audio Analyzer, is similar in function and operation to the Analog Analyzer. Additional DSP tools offer different audio analysis techniques, while others measure data and interface characteristics.

Click **Panels > Digital Analyzer** or the **Digital Analyzer** button on the Panels toolbar to open the Digital Analyzer panel.



Analog audio can be routed from the analog inputs to the Digital Analyzer as an alternative to using the Analog Analyzer. The analog signals must first be converted to the digital domain by high-performance ADCs, which are selected on the appropriate Digital Analyzer analysis tool panels.

Real-Time and Batch Mode Measurements

Many of the 2700 series meters and tools display their results in real time; that is, their displays update so quickly that moment-to-moment variations can be observed on a continuous basis. There is some variation in just how quick real-time measurements actually are; most of the 2700 series meters have variable detector rates, and the DIO interface monitors update at approximately 4 times per second. Within certain ranges, however, real-time measurements provide immediate results.


In the Digital Analyzer, four of the seven analyzer tools must first acquire a sample of the signal to be analyzed, and then perform DSP calculations on the

data before display. These are called “batch mode” measurements, since the data is acquired and processed in discrete “batches.” In batch mode there is always an initial acquisition, after which the data is in memory and different analyses can be performed.

Digital Analyzer analysis tools that use FFT techniques, including the FFT Spectrum Analyzer (FFT), the Digital Interface Analyzer (Intervu), the Multitone Audio Analyzer (Fasttest) and the Quasi-Anechoic Acoustical Analyzer (MLS), are all batch mode tools.

The Digital Analyzer Analysis Tools

Figure 21.
2700 series Digital
Analyzer tool
selection.



The Digital Analyzer analysis tools are discussed individually in subsequent chapters. They are:

- The DSP Audio Analyzer, Chapter 11.
- The FFT Spectrum Analyzer, Chapter 12.
- The Digital Interface Analyzer (Intervu), Chapter 13.
- The Multitone Analyzer (Fasttest), Chapter 14.
- The Quasi-Anechoic Acoustical Tester (mls), Chapter 15.
- The Digital Data Analyzer (bittest), Chapter 16.
- The Harmonic Distortion Analyzer, Chapter 17.

These seven chapters discuss every function, control and display available on each Digital Analyzer tool panel in detail. If you are new to the 2700 series and the 2700 series control software, you might want to start with the Quick Guides in *Getting Started with Your 2700 Series Instrument*, which will introduce you to the Digital Analyzer features.

Sweeps and Graphs

The Analog Generator, the Digital Generator, the Analog Analyzer, the Digital Analyzer and other 2700 series functions can be controlled from the Sweep Panel, which orchestrates sets of measurements and provides the means to collect, graph, edit, constrain and modify analysis data.



See Chapter 18 for information on using sweeps, Chapter 19 for graphing, Chapter 21 to learn about limits and Chapter 22 for performing computations on test results.



Chapter 6

The Analog Generator

Signals for Analog Measurements

The Analog Generator can create audio signals in analog hardware circuitry or in DSP. Which to choose? In many cases it makes little difference, but your measurement requirements will often point you clearly in one direction or the other. A few examples of differences between analog and DSP-generated waveforms follow.

Waveform characteristics:

- Analog-generated sine waves can be produced at much higher frequencies than the DSP sine waves, and they exhibit slightly lower distortion.
- DSP-generated sine waves will generally have superior frequency resolution and stability compared to the analog-generated sine waves, but distortion will be slightly higher due to DAC limitations.

Waveform choices:

- Some DSP waveforms (such as **Dual**, **Polarity**, **Arbitrary**, and others) are simply not available by analog generation in the 2700 series.

The S2-BUR and S2-IMD options function only in conjunction with the analog generator. There are DSP counterparts to these options, but with differences in features and performance.

- the S2-BUR option of the Analog Generator offers more noise waveform selections and different noise characteristics than the DSP noise.
- S2-BUR option bursts have the capability of responding to trigger and gate input signals. DSP bursts do not.

The Analog Outputs are configured (connector, grounding and impedance selection) by settings on the Analog Generator panel. See **Configuring the Analog Outputs** on page 95.

Signal generation in analog hardware

With no hardware options installed, the only signal SYS-2722 generates in analog hardware is the low-distortion sine wave (for both **Sine: Normal** and **Sine: EQ Sine** waveforms). With the BUR and IMD hardware options (see below) the Analog Generator can also produce tone bursts, square waves, IMD signals and noise waveforms in analog hardware.

Analog Generator hardware options

Two hardware options can be installed in a 2700 series instrument to add more analog-generated waveforms to the standard analog and DSP generated waveforms provided.

■ **The S2-BUR Option**

The BUR option adds tone bursts, which can be generated by fixed panel settings, or gated or triggered. BUR also adds square wave generation and white, pink and USASI noise waveforms.

■ **The S2-IMD Option**

The IMD option adds several specific twin-tone intermodulation waveforms, used for SMPTE/DIN, CCIR/DFD and DIM IMD testing.

NOTE: The S2-IMD option also adds complementary IMD measurement capabilities to the Analog Analyzer.

This manual is written with the assumption that these options have been installed in your 2700 series instrument. If these options are not installed in your instrument, some of the features and operation described will not apply.

Signal generation in DSP

The DSP-generated signals for the Analog Generator (marked “(D/A)” in the waveform lists) are produced digitally in dedicated DSP in the 2700 series, and are converted into the analog domain using high precision digital-to-analog converters (DACs). The resulting analog signals are buffered, conditioned and routed to the analog output circuitry.

The DSP waveform generator for the Analog Analyzer is independent from that used in the Digital Generator, which means that entirely different DSP-generated waveforms can be output from the two generators simultaneously.

The one exception to this generator independence is the Arbitrary Waveform. An arbitrary waveform is generated from a waveform file that has been read into memory, and the 2700 series offers only one memory buffer for this operation. If an arbitrary waveform is selected for both generators, it must be from the same waveform file.

DAC sample rates and bandwidth

Depending upon the DSP waveform selected, the DACs may be fixed at a particular sample rate or may offer selectable sample rate or bandwidth options.

- For the **Square (D/A)**, **IMD (D/A)** and **Special (D/A): Polarity** waveforms, the sample rate is fixed.
- For the **Sine (D/A)** and **Noise (D/A)** waveforms, the sample rate selections are presented as bandwidth choices at **30 kHz** and **60 kHz**. The **30 kHz** selection provides the best DAC performance, in terms of noise and distortion. **60 kHz** offers broader bandwidth at some cost in residual distortion and noise.
- For the **Special (D/A): Pass Thru** waveform, the sample rate is locked to the DIO System Sample Rate (SSR).
- When using an MLS waveform, it is essential that the generator and analyzer sample rates match exactly. For the **Arb Wfm (D/A)** and **MLS (D/A)** choices, the sample rate is selectable between **65,536 Hz**, **131,072 Hz**, System Sample Rate (SSR) or Input Sample Rate (ISR).

NOTE: The sample rates 65,536 and 131,072 are powers of two, as are the FFT Length selections in the 2700 series FFT-based analysis programs. Use of these sample rates when performing FFT analysis produces bin widths that are integer numbers of hertz. For example, with an analyzer FFT length of 32,768 samples and a 65,536 Hz sample rate, the resulting bin widths are exactly 2.00 Hz.

See **Setting the D/A Sample Rate** on page 94.

Performance Extremes versus Specifications

In this manual, we have made every attempt to be sure that the 2700 series input, output, signal and processing characteristics and ranges are correctly stated. Many allowed settings in the 2700 series control software, however, push the system to its performance extremes, sometimes beyond its published specifications. Such settings will not harm the instrument, but may slightly degrade performance.

For example, although **IMD (D/A): SMPTE** waveform generation will support a **High Freq.** sine wave up to 61.6651 kHz, a residual IMD $\leq 0.0010\%$ is only specified up to 50 kHz.


Be sure to check the appropriate 2700 series performance specifications (available in *Getting Started with Your 2700 Series Instrument* or on the Audio Precision Web site) whenever you have a question about such issues.

The Analog Generator Panel



Open the Analog Generator panel by choosing **Panels > Analog Generator**, by clicking the **Analog Generator** button on the Panel toolbar or by the keyboard shortcut **Ctrl+G**. Like most 2700 series panels, the Analog Generator can be viewed in two sizes. Double-click the panel Title Bar to change sizes.

Figure 22. The Analog Generator Panel.




The Analog Generator panel is divided into three areas:

- The upper area provides fields for choosing waveforms, setting amplitude and attaching EQ curves;
- the center area provides controls for output configuration, and
- the lower area provides fields to set reference values.

We will first look at general topics of setting frequency and amplitude and turning the generator **ON** and **OFF**; then we will examine the many waveform selections available in detail; then we will look at configuring the analog outputs and setting the analog references.

Frequency Units

Figure 23. Setting the Analog Generator Frequency.




Frequency may be expressed in absolute units (hertz) and in a variety of units relative to the value entered in the **Reference: Freq** field. See **Analog Generator References** on page 96 and **Frequency Units** on page 530.

Changing units does not change the frequency of the generator. The existing frequency will simply be re-stated in the new units. Also, the value displayed after pressing **Enter** may differ slightly from the value you typed in, since the control software will step to the nearest frequency increment.

Output ON/OFF and Channel Selection

Figure 24. Analog Generator ON / OFF.



The Analog Generator signal outputs are toggled **ON** and **OFF** by the **OUTPUTS** button. Additionally, each channel output can be switched individually on and off by the **CH A** and **CH B** buttons on either side of the **OUTPUTS** button. Both the main **OUTPUTS** button and an individual channel button must be switched on to route signal to the analog output circuitry.

Auto On

If the **Auto On** checkbox is checked, the Analog Generator is automatically switched **ON** when a sweep starts, and **OFF** when the sweep stops.

This is useful for power amplifier or loudspeaker testing. With the generator set to **OFF** and **Auto On** enabled, signal will only be applied to the DUT while the sweep is actually running.

See Chapter 18 for more information on sweeps. Also see **Pre-Sweep Delay** on page 418 for a discussion about avoiding transients in the **Auto On** mode.


Channel Invert

A 2700 series instrument maintains correct absolute signal polarity throughout the system. You can invert the polarity of either audio channel by clicking the **Invert** checkbox for that channel. When neither or both **Invert** boxes are checked, both channels have the same polarity.

Polarity inversion of one channel with respect to the other can be used to create the “difference” signal that modulates the subcarrier in some stereo multiplex systems.

Amplitude Control and Units

Figure 25. Setting the Analog Generator Amplitude.



If the **Track A** checkbox is checked, the amplitudes of both Channel A and Channel B are set by the Channel A **Amplitude** setting.

If the **Track A** checkbox is not checked, the amplitudes of the two Analog Generator channels can be controlled individually. Type a value in the **Amplitude** setting field for either Channel A or Channel B and press **Enter**.

You can choose an amplitude unit of measurement from the units drop-down list, shown in Figure 25. Changing a unit of measurement will not change the audio amplitude, only the expression of the value. See **Analog Amplitude Units**, page 530.

The value displayed after pressing **Enter** may differ slightly from the value you typed in, since the control software will step to the nearest amplitude increment.

The Analog Generator will not permit an output amplitude entry greater than 26.66 Vrms (37.70 Vp, or +30.7 dBu) when configured for a balanced output; or 13.33 Vrms (18.85 Vp, or +24.7 dBu) when configured for an unbalanced output. If you enter a value greater than these maximum values, or a combination of values (in **EQ Sine** mode, for example) that results in a greater value, an error message is displayed.


Waveforms other than a sine wave are calibrated in *peak equivalent sine wave* terms; that is, the **Amplitude** setting field is calibrated to show the rms

value of a sine wave with same peak value as the waveform selected. Selecting a square wave with an **Amplitude** value of 1.000 Vrms on the Analog Generator panel, for example, produces a 1.414 Vp square wave signal.

Choosing an Analog Generator Waveform

The Analog Generator offers a wide choice of test waveforms selectable from primary or secondary waveform lists. The primary list is on the left side of the panel; the secondary list is on the right.

Figure 26. Analog Generator Primary Waveform Selections.



The primary list selections are, for the most part, sorted by the shape of the waveform, such as sine wave, square wave, noise, and so on. Most waveform choices have an associated secondary list, from which you make your final waveform selection.

This chapter organizes the waveforms by shape, generally following the order of the primary waveform list. The variations available on the secondary lists are described under each section.

Designation of hardware and DSP generation

The **Sine**, **IMD**, **Square** and **Noise** waveforms are generated in analog hardware. All the waveforms followed by the designation “**(D/A)**,” for “digital-to-analog,” are digital in origin (**Arb Wfm** and **Pass Thru** from digital files or external input; the rest generated in DSP). These signals are converted for analog output by dedicated digital-to-analog converters (DACs).

Analog waveforms: speed versus accuracy

For analog-generated sine and square waveforms, the Analog Generator has two modes: **Fast** and **High Acc.**

■ Fast

The normal mode for analog frequency generation, **Fast** provides accurate, high-resolution waveforms with minimal generator settling times.

■ High Acc.

High accuracy mode provides greater accuracy and resolution, but requires longer generator settling times (ranging from 150 ms above 50 Hz to 750 ms at 10 Hz) when changing frequencies.

For analog-generated SMPTE and CCIF IMD waveforms, the Fast / High Acc. selection only affects the higher frequency (entered in the upper field.)


DSP waveforms: sample rate and bandwidth

Sample rate for the DACs can be selected from several choices; for **Sine (D/A)** and **Noise (D/A)**, see **Setting the D/A Bandwidth** on page 94. For **Arb Wfm (D/A)**, **MLS (D/A)** and **Special (D/A): Pass Thru**, see **Setting the D/A Sample Rate** on page 94.

Some waveforms, such as **IMD (D/A)** and **Special (D/A): Polarity**, have fixed DAC sample rates.

Sine waveforms

Figure 27. Analog Generator *Sine Waveform Selections.*




This section describes the low-distortion sine waveforms produced by the hardware Analog Generator, which cover the frequency range from 10 Hz to approximately 204 kHz.

Enter the desired frequency value into the setting field. Frequency setting fields will accept a “k” as shorthand for 1000. Sine wave frequency can be set in hertz or in a variety of relative units; see **Frequency Units**, page 530.

Wfm: Sine: Normal

Figure 28. Analog Generator *Sine: Normal.*



The normal sine waveform is the standard waveform for most audio testing, and is the default generator waveform.

Wfm: Sine: Burst

The three **Sine: Burst** selections for the Analog Generator require the S2-BUR hardware option. The tone burst choices are

- **Normal Burst** (free-running)
- **Gated Burst** (gated on and off by an external signal) or
- **Trig. Burst** (triggered by an external signal).

Tone Bursts

A tone burst is an audio signal (usually a sine wave) that is keyed on and off. Tone bursts are often used as stimulus signals, and can reveal characteristics of a DUT's performance which are not observable with continuous tones.


In a 2700 series instrument, analog tone bursts require the S2-BUR hardware option. The BUR option tone bursts are the only way to generate rectangular burst envelopes for the Analog Generator, and the only way to generate gated or triggered bursts for either generator.

*Without the S2-BUR option, shaped bursts (raised-cosine burst envelope) can be produced in the **Sine (D/A)** mode of the Analog Generator, and shaped and rectangular bursts can be produced in the Digital Generator.*

*See the **Tone Burst Definitions** sidebar on page 73.*

Wfm: Sine: Normal Burst

Figure 29. Analog Generator **Sine: Normal Burst** selections.




Wfm: Sine: Normal Burst produces a rectangular tone burst with definable **Burst On** and **Interval** durations and **Low Level** amplitude. The maximum level of the tone burst is set in the generator **Amplitude** setting field. **Normal** bursts are neither gated nor triggered.

See the **Tone Burst Definitions** sidebar on page 73.

Wfm: Sine: Gated Burst

Figure 30. Analog Generator **Sine: Gated Burst** selections.




Wfm: Sine: Gated Burst produces a rectangular tone burst with **Burst On** and **Interval** durations controlled by an external gating signal applied to the front panel **TRIG/GATE INPUT** BNC connector found in the **GENERATOR AUX SIGNALS** area on the lower-right sub-panel. **Low Level** amplitude is definable on the Analog Generator panel. The maximum level of the tone burst is set in the generator **Amplitude** setting field.

See the **Tone Burst Definitions** sidebar on page 73.

Wfm: Sine: Trig. Burst

Figure 31. Analog Generator **Sine: Trig. Burst** selections.



Wfm: Sine: Trig. Burst produces a rectangular tone burst with the **Interval** duration controlled by an external trigger signal applied to the front panel **TRIG/GATE INPUT** BNC connector found in the **GENERATOR AUX SIGNALS** area on the lower-right sub-panel. **Burst On** duration and **Low Level** amplitude are definable on the Analog Generator panel. The maximum level of the tone burst is set in the generator **Amplitude** setting field.

See the **Tone Burst Definitions** sidebar on page 73.

Tone Burst Definitions

Refer to Figure 32 for an illustration of the following definitions:

■ **Burst**

Enter a value in the **Burst On** field to set the duration of the tone burst. The maximum **Burst On** duration is 65,535 cycles of the sine waveform, if **Interval** is set to its maximum; the minimum is 1 cycle. **Burst On** can be set in units of **Cycles** or **secB** (seconds, Burst). Only **Burst On** durations which are less than the **Interval** durations can be entered.

■ **Interval**

Enter a value in the **Interval** field to set the period between the onset of the tone burst and the onset of the next burst. The maximum **Interval** is 65,536 cycles of the sine waveform; the minimum is 2 cycles. **Interval** can be set in units of **Cycles** or **secB**.

NOTE: **Interval** does not describe the time between the end of a burst and the beginning of the next, but the entire period from the beginning of one burst until the beginning of the next.

■ **Low Level**

When a tone burst is ON, the level of the sine wave in the burst is the same as the current **Amplitude** setting for the Analog Generator. When a tone burst is OFF, the low level is the ON level multiplied by the value set in the **Low Level** field. The OFF level is a ratio of the ON level, set here in units of **X/Y ratio**, **dB**, **%** (per cent), or **PPM**. See **Ratio Units**, page 536.

If **Low Level** is set to equal the burst high-level amplitude, no burst effect will occur and the output will be a continuous sine wave. At large amplitude ratios, the amplitude resolution of **Low Level** becomes poorer. The display will show the actual available resolution steps, rather than the value entered.

Zero-Crossing

The beginning and ending of any tone burst are always at the positive-going zero-crossing points of the sine wave, which eliminates transients from the output.

Because of the zero-crossing nature of the tone bursts, only integer numbers of cycles can be entered as a **Burst On** or **Interval** setting; if you are using **secB** units, only time durations which represent multiples of the full period of a cycle of the selected sine wave can be entered as a **Burst On** or **Interval** setting.





Figure 32. Tone Burst definitions.

Wfm: Sine: EQ Sine

Figure 33. Analog Generator Sine: EQ Sine.



The **Sine: EQ Sine** setting outputs a normal sine wave, with equalizing amplitude changes made in the generator level according to an attached EQ data file. This enables you to make a frequency sweep where the generator amplitude varies as instructed by the data in the attached file.

When you select **Sine: EQ Sine** and attach an EQ file (see below), a new field call **Post EQ** appears on the Analog Generator panel. The **Post EQ** field displays the generator amplitude to be applied to the DUT, which is the value entered in the **Amplitude** field corrected by the value (at that frequency) of the correction factor in the attached EQ file.

*NOTE: When **Sine: EQ Sine** is selected, the values in the **Amplitude** field are displayed in **blue** rather than **black**.*

To set the output amplitude, you can enter a value in either the **Amplitude** field or the **Post EQ** field, and the value in the other field will be properly adjusted according to the correction factor.

The Analog Generator will not permit an output amplitude entry greater than 26.66 Vrms (37.70 Vp, or +30.7 dBu) when configured for a balanced output; or 13.33 Vrms (18.85 Vp, or +24.7 dBu) when configured for an unbalanced output. If the value of the normal (pre-EQ) **Amplitude** field as modified by the equalization file would produce an amplitude greater than these maximum values, an error message is displayed.


If a frequency value outside the frequency range span of the EQ file is entered on the generator panel or occurs during a sweep, the **Post-EQ** amplitude will go to 0 V.

Sine waveforms from DSP

This section describes the sine waveforms produced in DSP and converted for output by the Analog Generator. These waveforms cover the frequency range from 10 Hz to either 30 kHz or 60 kHz, depending on the **D/A Bandwidth** setting. See **Setting the D/A Bandwidth** on page 94.


Sine wave frequency can be set in hertz or in a variety of relative units; see **Frequency Units**, page 530.

Figure 34. Analog Generator
Sine (D/A) Waveforms.



Wfm: Sine (D/A): Var Phase


Figure 35. Analog Generator
Sine (D/A): Var Phase



Specifying the EQ Curve

The EQ curve is embodied in an AP data file (usually an EQ file, with the extension .adq). Individual frequencies and the corresponding amplitude changes are listed in rows and columns, as shown in Figure 36.

Figure 36. EQ file attachment and editing.



Click the **EQ Curve** button to open the Equalization Curve dialog box, then click the browser button to open the Equalization Curve file browser.

When you have selected an EQ file, it will be attached to the generator panel and the file name will appear in the Equalization Curve dialog box. The default amplitude data column is **Column 2**; you can choose another column from the drop-down list in the Equalization Curve dialog box.

If you would like to view or edit the EQ file, click the **Edit** button to open the Attached File Editor (see page 465).

You can make custom EQ curves by manually creating a 2700 series EQ file, or by using the current sweep data in memory and a Compute function to produce an appropriate EQ file. See Chapters 21 and 22 for more information on saving data files and modifying EQ data from a sweep using Compute functions.

Typical Generator EQ Applications

The most common applications of generator equalization are to produce a nominally flat output from a device which contains a known equalization function. Typical examples include FM and TV aural broadcast transmitters with 50 μ s and 75 μ s preemphasis curves.

By attaching a generator equalization curve that is the inverse of the nominal curve used in the device under test, the resulting measured output should be flat. Small variations from flatness will be a measurement of the accuracy of equalization in the device, since the .adq curves provided are accurate to better than 0.01 dB and the specified generator flatness is of the same order.

This choice produces the selected frequency at both Channel A and B outputs, but the phase of the Channel B output is variable from -180° to $+179.99^\circ$ with respect to the Channel A output, as controlled by the **Phase B-A** field.

A positive value entered in the **Phase B-A** field will cause the Channel B output to lead the Channel A output. A negative value entered in the **Phase B-A** field will cause the Channel B output to lag the Channel A output. See the illustration below:





Figure 37. **Sine (D/A): Var Phase**, triggered on Channel A (the larger waveform). -90.00° has been entered in **Phase B-A** field, causing B (the smaller waveform) to lag A.

Wfm: Sine (D/A): Stereo


Figure 38. Analog Generator **Sine (D/A): Stereo**.



This selection produces independent sine waves on Channel A and Channel B. The **Frequency** field sets the frequency of the Channel A signal, and the **Frequency 2** field sets the frequency of the Channel B signal. Their amplitudes are independently set by the two **Amplitude** fields unless the **Track A** box is checked, in which case the amplitudes are equal and controlled by the Channel A **Amplitude** field.

Wfm: Sine (D/A): Dual

Figure 39. Analog Generator **Sine (D/A): Dual**.



This selection produces two independent sine waves which are summed to create a complex waveform. This complex waveform is sent to both channel outputs.


The **Frequency** and **Frequency 2** fields permit each component sine wave frequency to be set independently. The **Dual Ampl Ratio** field enables you to set the ratio by which the secondary (**Frequency 2**) sine wave component amplitude will be attenuated with respect to the amplitude of the primary (**Frequency**) sine wave component.

In **Sine (D/A): Dual**, the amplitude setting determines the sum of the amplitudes of the two components. A 1 V amplitude setting with a 25% ratio produces a waveform which is the sum of a 800 mV sine wave and a 200 mV sine wave.

The **Sine (D/A): Dual** signal is particularly useful as a calibration signal for harmonic distortion analyzers, where the **Frequency** signal at reference amplitude represents the fundamental signal. The secondary (**Frequency 2**) sine wave can be set to any desired harmonic of the primary (**Frequency**) “fundamental” sine wave, at an amplitude to represent any desired distortion level. For example, setting the primary (**Frequency**) at 1 kHz and the secondary (**Frequency 2**) at 3 kHz with a **Dual Amp** ratio of -40.0 dB (1%) produces a 1 kHz signal with third harmonic distortion of 1.0%.

Wfm: Sine (D/A): Shaped Burst

Figure 40. An example of a shaped burst.




The Analog Generator **Sine (D/A): Shaped Burst** signal is essentially identical to the Digital Generator **Sine: Shaped Burst** signal, and both are similar to the Digital Generator **Sine: Burst** signal.

For both generators, the **Sine (D/A): Shaped Burst** has a raised-cosine shaped envelope, creating a relatively narrow energy spectrum around the sine wave frequency. The **Sine: Burst** waveforms for both the Analog Generator and the Digital Generator have rectangular envelopes with fast rise and fall times and consequently a wider spectrum of energy. **Sine (D/A): Shaped Burst** cannot be triggered or gated.

See the **Tone Burst** and **Tone Burst Definitions** sidebars on pages 71 and 73.


Figure 41. Analog Generator **Sine: Shaped Burst** waveform.



The frequency of the sine wave is set in the **Frequency** field. The **Amplitude** field sets the generator amplitude at the maximum burst ON level.

Wfm: Sine (D/A): EQ Sine

Figure 42. Analog Generator **Sine (D/A): EQ Sine** waveform.




This is a DSP-generated waveform. Although the DSP sine wave is used, this waveform selection is otherwise identical in operation to the **Sine: EQ Sine** waveform, discussed beginning on page 74.

Square wave waveforms

Wfm: Square

Figure 43. Analog Generator **Square** Waveform.



The S2-BUR option is required to generate this waveform.


The frequency range for both analog-generated and DSP-generated square waves is from 20 Hz to 20 kHz. Risettime is typically 2.0 μ s.

The square wave amplitude is calibrated in peak equivalent sine wave terms. See **Amplitude Control and Units** on page 68. The maximum available amplitude of a square wave is equal to half the maximum available amplitude selectable for the Sine waveform.

NOTE: The generator output configuration (balanced or unbalanced) must match the external load. Connecting an unbalanced load to the balanced output will produce distorted square waves.

Wfm: Square (D/A)

Figure 44. Analog Generator **Square (D/A)** Waveform.



Although this choice is shown as a “(D/A)” selection, the square wave generation is actually done in dedicated hardware on the DSP board and routed directly to the Analog Generator, as opposed to the DSP-generated and DAC-converted technique used with other (D/A) waveforms. This technique produces a square wave that is not limited in frequency resolution by sample rate considerations.

The frequency range for both analog-generated and DSP-generated square waves is from 20 Hz to 20 kHz. Risettime is typically 2.0 μ s.

The square wave amplitude is calibrated in peak equivalent sine wave terms. See **Amplitude Control and Units** on page 68. The maximum available amplitude of a square wave is equal to half the maximum available amplitude selectable for the Sine waveform.

NOTE: The generator balanced or unbalanced configuration must match the external load. Connecting to an unbalanced load from the balanced output will produce distorted square waves.


Intermodulation Distortion (IMD) waveforms

Intermodulation distortion (IMD) testing requires a stimulus which is a combination of two waveforms, and a specific analysis technique to evaluate interaction of the waveforms within the DUT.

The Analog Generator with S2-IMD option provides both analog hardware generated and DSP generated IMD test signals. These signals complement the IMD analysis tools available in the Analog Analyzer (with the S2-IMD option) and in the DSP Audio Analyzer tool of the Digital Analyzer.

Although both the hardware and DSP selections offer the same choices, there are some differences in the waveforms. The S2-IMD option hardware choices will be described here first, followed by the DSP-generated (D/A) choices.


Figure 45. Analog Generator **Wfm: IMD** Waveform Selections (S2-IMD hardware-generated signals).



IMD signal amplitude is set in the Analog Generator **Amplitude** field. The IMD composite waveform amplitude is calibrated in peak equivalent sine wave terms. See **Amplitude Control and Units** on page 68.

Wfm: IMD: SMPTE/DIN 1:1

Figure 46. Analog Generator **Wfm: IMD** SMPTE/DIN 1:1.



The S2-IMD option is required to generate this waveform.

This selection produces a signal which is the linear combination of two sine waves.

The first sine wave, set in the **IM-Freq** field, is a lower-frequency tone produced in the IMD generator hardware. **IM-Freq** can be set to one of 8 frequencies: 40, 50, 60, 70, 100, 125, 250 or 500 Hz.

The second sine wave is produced in Analog Generator main oscillator. Its frequency is set in the **High Freq** field. For compatibility with the S2-IMD analyzer module, the main oscillator frequency must be 2 kHz or greater.

The low-frequency sine wave is linearly combined in a 1:1 amplitude ratio with the high-frequency sine wave.


Wfm: IMD: SMPTE/DIN 4:1

The S2-IMD option is required to generate this waveform.

This is the same as the **Wfm: IMD: SMPTE/DIN 1:1** selection, except that the amplitude ratio of the low-frequency sine wave to the high-frequency sine wave is 4:1.

Wfm: IMD: CCIF/DFD

Figure 47. Analog Generator *Wfm: IMD CCIF/DFD*.



The S2-IMD option is required to generate this waveform.


The CCIF/DFD is a “difference tone” waveform, generated by modulating a carrier tone with a lower-frequency tone to create upper and lower sidebands, with the carrier tone removed.

The signal from the main sine wave oscillator is fed to one input of a balanced modulator (on the IMD module), and a low-frequency tone from the IMD module is fed to the second input of the modulator. The output of the modulator is a double-sideband suppressed-carrier signal, with equal-amplitude sidebands spaced above and below the suppressed carrier.

The **Center Freq:** field sets the (main oscillator) carrier frequency, which is the center point between the sidebands. The **IM-Freq:** field sets the modulating frequency, which determines the spacing in hertz between the upper and lower sidebands.

Wfm: IMD: DIM 30 / DIM 100 / DIM B / DIM B-8K

Figure 48. Analog Generator **Wfm: IMD**
DIM.



The S2-IMD option is required to generate these waveforms.

DIM, or *dynamic intermodulation*, has also been called TIM, or *transient intermodulation*. In each of the DIM waveforms, a square wave near 3 kHz is generated in the IMD module and is linearly combined with the sine wave from the main generator. This square wave, being hardware generated, is not limited in frequency resolution by sample rate considerations. The peak-to-peak amplitude ratio of the square wave to the sine wave is 4:1.


For the DIM 30 and DIM 100 waveforms, the square wave frequency is set to 3.15 kHz and the sine wave frequency is set to 15 kHz, matching the DIM settings in the IMD analyzer module. For DIM 30, the square wave is passed through a single-pole 30 kHz low-pass filter; for DIM 100, the square wave is passed through a single-pole 100 kHz low-pass filter.

The DIM B (broadcast) waveform is similar. The square wave frequency is set to 2.96 kHz and the sine wave to 14 kHz. Like DIM 30, the DIM B signal is passed through a single-pole 30 kHz low-pass filter.

The DIM B-8k waveform is the same as the DIM B waveform, except that the sine wave frequency is 8 kHz rather than 14 kHz.

Wfm: IMD (D/A): SMPTE/DIN 1:1

Figure 49. Analog Generator
Wfm: IMD (D/A) SMPTE/DIN
1:1.



This selection produces a signal which is the linear combination of two sine waves.

The first sine wave, set in the **IM-Freq** field, is a lower-frequency tone that can be set anywhere in the range of 40 Hz to 500 Hz.

*NOTE: For compatibility with the S2-IMD hardware analyzer module, the **IM-Freq** tone must be set to one of the 8 frequencies listed on page 82. If S2-IMD is not to be used for analysis, you may set the **IM-Freq** tone to any suitable frequency.*

The second sine wave, set in the **High Freq** field, can be set anywhere in the range of 2 kHz to 61.66 kHz.


The low-frequency sine wave is linearly combined in a 1:1 amplitude ratio with the high-frequency sine wave.

Wfm: IMD (D/A): SMPTE/DIN 4:1

It is the same as the **Wfm: IMD (D/A): SMPTE/DIN 1:1** selection, except that the amplitude ratio of the low-frequency sine wave to the high-frequency sine wave is 4:1.

Wfm: IMD (D/A): CCIF/DFD

Figure 50. Analog Generator Wfm: IMD (D/A) CCIF/DFD.



The CCIF/DFD is a “difference tone” waveform. The hardware-generated version of this waveform is made with a suppressed-carrier balanced modulator. The DSP version creates the same result by generating two equal-amplitude sine waves whose frequencies are equally-spaced around a center frequency value.

The value set in the **IM-Freq** field determines the spacing between the two sine waves; the acceptable range for this spacing value is 80 Hz–2 kHz.

The frequency set in the **Center Freq** field acts as a central reference point, with the upper sine wave frequency half the **IM-Freq** (spacing) frequency above, and the lower sine wave set the same value below. Put another way,

$$Low\ Sine\ Freq = Center\ Freq - \left(\frac{IM\ Freq}{2} \right)$$

and


$$High\ Sine\ Freq = Center\ Freq + \left(\frac{IM\ Freq}{2} \right).$$

The acceptable range for **Center Freq** is 3 kHz to approximately 60 kHz (the fixed D/A Bandwidth), less half the **IM-Freq** (spacing) value. Once again,

$$3\text{ kHz} \leq \text{Center Freq} \leq \left(60\text{ kHz} - \left(\frac{\text{IM Freq}}{2} \right) \right)$$

Wfm: IMD (D/A): DIM 30 / DIM 100 / DIM B

Figure 51. Analog Generator **Wfm:** **IMD (D/A) DIM.**



These are DSP-generated waveforms. Like the hardware (S2-IMD) waveform selections (page 83), the three **IMD: (D/A) DIM** choices linearly combine a square wave near 3 kHz with a higher-frequency sine wave. Although these choices are “**(D/A)**” selections, the square wave generation and filtering is actually done in dedicated hardware on the DSP board. This technique produces a square wave that is not limited in frequency resolution by sample rate considerations. The peak-to-peak amplitude ratio of the square wave to the sine wave is 4:1.


For the **DIM 30** and **DIM 100** waveforms, the square wave frequency is set to 3.15 kHz and the sine wave frequency is set to 15 kHz. For **DIM 30**, the square wave is passed through a single-pole 30 kHz low-pass filter; for **DIM 100**, the square wave is passed through a single-pole 100 kHz low-pass filter.

The **DIM B** (broadcast) waveform is similar. The square wave frequency is set to 2.96 kHz and the sine wave to 14 kHz. Like **DIM 30**, the **DIM B** signal is passed through a single-pole 30 kHz low-pass filter.

These signals are compatible with the DIM analysis in the analog hardware IMD analyzer option.

Noise Waveforms

Figure 52. Analog Generator **Wfm: Noise** Waveform Selections (S2-BUR hardware-generated signals)



A 2700 series instrument fitted with the S2-BUR option can generate several different noise waveforms.

The analog hardware S2-BUR option includes both a true random noise generator and a pseudo-random noise generator. The outputs of both generators are available with white or pink spectral distribution. The pink noise signals can be passed through a sweepable 2-pole 1/3-octave bandpass filter.

There is also a DSP-generated white noise signal available.

Random vs. Pseudo-random

The random noise waveform is truly random and never repeats. A consequence of this is that readings made using **Noise: Random** will not be stable at any reading rate. The pseudo-random noise is random during a 262 ms period, but repeats every 262 ms. This repetition cycle synchronizes with the nominal 4/s reading rate of the 2700 series analyzers, producing stable displays.

The spectrum of the **Noise: Random** waveforms will have energy at all frequencies within the specified bandwidth; that is, the spectral lines will be infinitely closely spaced. In **Noise: Pseudo** waveforms, the spectral lines will be spaced at the repetition rate of the pseudo-random cycle, approximately every 3.8 Hz up to the upper bandwidth limit. The pseudo-random signal may not be acceptable for certain applications, particularly at very low frequencies. If the measurement interval is limited, however, there is no advantage in having a noise signal which repeats less often.

Noise amplitude calibration

As with other complex waveforms in the 2700 series, noise waveform amplitude is calibrated in peak equivalent sine wave terms (see page 68). Noise signals may appear to have considerably lower amplitudes than might be expected, but this is due to their high crest factor (the ratio of peak to rms; see a discussion of crest factor in the **Detector Sidebar**, page 145).

The S2-BUR option pseudo-random noise has a crest factor of 4:1, or 12 dB. Since a sine wave has a crest factor of 1.414:1, or 3 dB, the rms value of the **Noise: Pseudo** waveforms at any given **Amplitude** setting will be 9 dB less than that of a sine wave at that **Amplitude** setting.


Although the random noise waveform has a theoretical crest factor of ∞ :1, in practice it will exceed a 4:1 crest factor only 0.01% of the time. The **Noise: Random** calibration has been set to be approximately the same as **Noise: Pseudo**, with the result that occasional noise peaks may exceed the peak-to-peak value of a sine wave of the same **Amplitude** setting.

The **Noise (D/A)** waveform, which is white pseudo-random noise, has a crest factor of 1.73:1. Its amplitude calibration has been set to be approximately the same as **Noise: Pseudo** and **Noise: Random**.

The maximum available Amplitude setting in the noise modes is half that of the sine wave modes.

Wfm: Noise: Pseudo

Figure 53. Analog Generator **Wfm: Noise Pseudo** example.



White Noise Characteristics

The spectral distribution of white noise is characterized by equal noise energy per hertz. This means that the spectral range between 100 Hz and 200 Hz will have the same energy as the range between 10,000 Hz and 10,100 Hz.

If analyzed by a constant-bandwidth spectrum analyzer such as a superheterodyne or FFT analyzer, white noise will show a flat energy characteristic versus frequency (up to the bandwidth limitation).

*Analysis of white noise with a constant-percentage-bandwidth (constant Q) filter such as in the Audio Analyzer **Bandpass** mode (or as in most real-time analyzers) will show a rising characteristic versus frequency, at the rate of 3 dB per octave.*

Pink Noise Characteristics

The spectral distribution of pink noise is characterized by equal noise energy per octave. This means that the octave of pink noise between 5 kHz and 10 kHz will have the same energy as the octave between 300 Hz and 600 Hz.

*If analyzed by constant-percentage-bandwidth (constant Q) spectrum analyzers such as **Bandpass** mode (or as in most real-time analyzers), pink noise will show a flat energy characteristic versus frequency (up to the bandwidth limitation).*

Analysis of pink noise with a constant-bandwidth filter such as a superheterodyne or FFT analyzer will show a falling characteristic versus frequency, at the rate of 3 dB per octave.

In the S2-BUR option, pink noise is generated by filtering the basic white noise through a -3 dB per octave filter.

Pink noise will sound subjectively flat to the ear because sounds are perceived on a constant bandwidth basis.

The **Noise: Pseudo** waveforms are analog-generated pseudo-random noise signals. The S2-BUR option is required to generate these waveforms. Three variations of the S2-BUR pseudo-random noise waveform are available:

- **Wfm: Noise: Pink - Pseudo**
Pseudo-random pink noise.
- **Wfm: Noise: White - Pseudo**
Pseudo-random white noise.
- **Wfm: Noise: Pink BP - Pseudo**
Pseudo-random pink noise passed through a variable bandpass filter. See below.

See **Random vs. Pseudo-random** above for a comparison of the two noise generation techniques; see the sidebar for a discussion of white and pink noise characteristics.

Wfm: Noise: Random

Figure 54. Analog Generator Wfm: Noise Random example.




The **Noise: Random** waveforms are analog-generated true random noise signals. The S2-BUR option is required to generate these waveforms. Three variations of the S2-BUR random noise waveform are available:

- **Wfm: Noise: Pink - Random**
Random pink noise.
- **Wfm: Noise: White - Random**
Random white noise.
- **Wfm: Noise: Pink BP - Random**
Random pink noise passed through a variable bandpass filter. See below.

See **Random vs. Pseudo-random** above for a comparison of the two noise generation techniques; see the sidebar for a discussion of white and pink noise characteristics.

Variable Bandpass Filter for Pink Noise

Figure 56. Analog Generator **Wfm: Noise** BP example.




The random and pseudo-random pink noise signals can be passed through a 2-pole 1/3 octave tunable bandpass filter by choosing **Wfm: Noise: Pink BP - Pseudo** or **Wfm: Noise: Pink BP - Random**.

This filter is implemented by using the state-variable main oscillator in the Analog Generator, configured as a bandpass filter. Consequently, the center frequency of the filter is set in the **Frequency** field on the Analog Generator panel, and the filter center frequencies are available across the oscillator's range of 10 Hz to 204 kHz. The filter can be swept by selecting **Gen: Freq** as the **Source 1** or **Source 2** instrument in the **Sweep: Source** browser.

Wfm: Noise (D/A)

Figure 55. Analog Generator **Wfm: Noise (D/A)**.



The **Noise (D/A)** waveform is a DSP-generated white noise signal.

The noise is pseudo-random and has a length of 2^{20} or 1,048,576 samples, so with the Analog Generator **D/A Bandwidth** set to 30 kHz (a sample rate of 65.536 kHz) the noise pattern repeats about every 16 seconds. The noise has a zero mean, a crest factor of 1.73:1 and a rectangular probability distribution function. The spectrum of the noise is flat from just above 0 Hz to 30 kHz or 60 kHz, depending on the **D/A Bandwidth** selection. See **Setting the D/A Bandwidth** on page 93.

The **Noise (D/A)** waveform amplitude is calibrated to be about the same as the S2-BUR noise signals. See **Noise Amplitude Calibration**, just above.

Arbitrary Waveforms

Wfm: Arb Wfm (D/A)




Figure 57. Loading an arbitrary waveform.

The generator arbitrary waveform function enables you to load a properly formatted digital waveform file into the 2700 series DSP and route the waveform to the Analog Generator outputs.

Arbitrary waveforms files provided with the 2700 series include single tones, tone combinations for IMD testing, multitone waveforms and calibration tones, and other useful waveforms.

Waveform files must be of the Audio Precision .agm or .ags file types. See **Waveform Files** on page 28. You may also make custom arbitrary waveform files using a file creation utility provided with the 2700 series or with third-party applications such as MATLAB. See **Multitone Creation** on page 348.

Arbitrary Waveforms and D/A Sample Rate

See **Setting the D/A Sample Rate** on page 94.

For **Arb (D/A)** waveforms, the frequencies and bandwidth produced in the Analog Generator are dependent upon the sample rate set for the Analog Generator DACs.


To load a waveform file and then output the waveform so that the embedded audio tones are at the intended frequencies, the sample rate of the DACs must be set to the same sample rate that was used in creating the file. If you use a sample rate different from the sample rate at which the file was created, the frequency of the audio tones embedded in the output signal will be shifted by the ratio of the two sample rates.

The Arbitrary Waveform generation memory buffers of the Analog Generator and Digital Generator are shared. If both generators have **Arb Wfm** selected as the waveform, the same waveform file will be used for both and the same signal will be produced at both the analog and digital generator outputs.

MLS Waveforms

Wfm: MLS (D/A)

Figure 58. Analog Generator **Wfm:** **MLS (D/A)**.




MLS is a DSP-generated waveform. The Analog Generator can generate 16 variations of a *maximum length sequence* (MLS) waveform. An MLS waveform is a pseudo-random noise signal with the property that, when passed through a device and cross-correlated with the input signal, the result is the impulse response of the device. An FFT can then be performed on the impulse response to yield the frequency and phase response of the device. See Chapter 15 for a complete description of the MLS Analyzer and the use of the Analog Generator with MLS waveforms.

MLS Waveform Sample Rate

For **MLS (D/A)** waveforms, the generator DAC sample rate must match the analyzer ADC or digital input sample rate for proper cross-correlation and analysis. See **Setting the D/A Sample Rate** on page 94.


Special Waveforms

Figure 59. Analog Generator Special Waveform Selections.



Wfm: Special (D/A): Polarity

Figure 60. Analog Generator Special: Polarity.




The polarity waveform is designed to be obviously asymmetrical, so that it is easily apparent if signal is inverted or not. The waveform is the sum of the fundamental tone set in the **Frequency** field and its second harmonic, in a fixed phase relationship.

When the output of the DUT is viewed using an oscilloscope or the 2700 series Spectrum Analyzer in the time-domain view, the signal will reveal whether or not there has been a polarity inversion in the DUT or in the signal interconnections.

The only setting available for the polarity waveform is **Frequency**.

Wfm: Special (D/A): Pass Thru

Figure 61. Analog Generator Special: Pass Thru.



The **Special (D/A): Pass Thru** selection does not cause a waveform to be generated; instead, it converts the digital audio signal connected to the rear panel **AES/EBU REF IN** female XLR into an analog signal and passes it through to the Analog Generator outputs.

This is a convenient way to convert a digital test signal (from a CD, for example) to an analog test signal. If the **AES/EBU REF IN** signal is stereo, the output signal will also be stereo.

In **Pass Thru** mode, the sample rate of the Analog Generator DAC is set to the 2700 series System Sample Rate (SSR) indicated by the **D/A Sample Rate** field on the generator panel, which shows **SSR** in this mode. If the **AES/EBU**

REF IN signal has a different sample rate than the SSR, it is sample-rate-converted to the SSR.

The **AES/EBU REF IN** sample rate must be in the range between 28 kHz–200 kHz. Additionally, the ratio of the **REF IN** sample rate to the **SSR** must fall in the range between 1:8 to 7.75:1; or, stated another way,

$$\frac{SSR}{8} \leq \text{REF IN sample rate} \leq SSR \times 7.75.$$

The 2700 series sample rate converter is controlled to maintain the **AES/EBU REF IN** embedded audio at its original frequency. As a result, changing the SSR will not shift the audio frequency of the **REF IN** signal, but it will affect the signal's bandwidth. **REF IN** audio at frequencies above approximately $0.47 \times SSR$ will be greatly attenuated.

The default value of SSR is 48 kHz. To preserve bandwidth, for most Pass Thru audio testing SSR should not be lower than 44.1 kHz.

*NOTE: SSR cannot be directly set, but is equal to SR or $SR \times 2$, depending on the SR Range setting. See **SR Range** on page 156.*

The amplitude relationship between the **AES/EBU REF IN** signal and the Analog Generator output is such that a **REF IN** signal of 1.00 FS (0 dB FS) will result in a correctly calibrated analog output signal; that is, the signal will





Figure 62. Polarity waveform, normal polarity shown.

have peaks equal to those of a sine wave of the rms value set in the Analog Generator amplitude field.

Setting the D/A Bandwidth

For **Sine (D/A)** and **Noise (D/A)** waveforms, the Analog Generator bandwidth is dependent upon the sample rate set for the DACs used to convert the DSP-generated signals to analog audio. These DACs have two sample rate selections resulting in two different bandwidth options, set in the **D/A Bandwidth** field near the bottom of the Analog Generator panel.

Figure 63. Selecting the Analog Generator D/A Bandwidth.




- **30k** sets the sample rate of the DACs to 65,536 Hz, providing a generator bandwidth of approximately 0 Hz–30 kHz. This bandwidth setting provides the Analog Generator’s lowest possible distortion for “(D/A)” waveforms.
- **60k** sets the sample rate of the DACs to 131,072 Hz, providing a generator bandwidth of approximately 0 Hz–60 kHz, with slightly higher residual noise and distortion than in the **30k** mode.

Setting the D/A Sample Rate

When **Arb Wfm (D/A)** or **MLS (D/A)** are selected, a **Sample Rate** field appears on the lower portion of the Analog Generator panel.

Figure 64. Selecting an Arbitrary Waveform or MLS Sample Rate.



You can select from 4 sample rate choices for the DACs:

- **65536**, which is the lower fixed sample rate for the Analog Generator DACs.
- **131072**, the higher fixed sample rate.

- **SSR**, the System Sample Rate shown in the DIO panel. For arbitrary waveform files, the 2700 series offers two methods of setting DAC sample rates using the **SSR** selection. Go to the **General** tab of the Configuration panel at **Utilities > Configuration** to set the method you prefer, as follows:
 - If the **Set sample rate when loading generator waveforms** checkbox is checked, the control software will automatically set the DIO SSR to the sample rate of the arbitrary waveform file being loaded, up to a maximum limit of 108 kHz; or, if the waveform file has a sample rate of 131072 Hz, the DAC sample rate will be set to the 131072 Hz fixed rate.
 - If this checkbox is unchecked, you must manually adjust SSR by entering a value in the DIO Sample Rate (SR) field and selecting the SR Range setting that results in the desired SSR.


*NOTE: SSR has a range of 8 kHz–108 kHz, and arbitrary waveforms with sample rates beyond this range cannot be used with the Analog Generator when **SSR** is selected as the D/A Sample Rate. For a waveform file with a 131072 Hz sample rate, use the **131072** selection.*

*NOTE: Also see **Pass Thru Domain Preference** on page 503.*

- **ISR**, the **Input Sample Rate** read from the instrument’s serial digital input and displayed on the DIO panel.

Configuring the Analog Outputs

Figure 65. Analog Output Configuration.



The analog output configuration is controlled from the Analog Generator panel. Both A and B outputs are configured together. The choices are:

- **Bal - Float**
Bal-Float outputs a balanced signal on the XLR male connectors (pin 2 high) and on the double banana jacks. In this configuration the output transformer center tap is ungrounded or “floating.”
- **Bal - Gnd**
Bal-Gnd outputs a balanced signal on the XLR male connectors (pin 2

high) and on the double banana jacks. In this configuration the output transformer center tap is grounded through a 5 Ω resistor.

■ UnBal - Float

UnBal-Float outputs an unbalanced signal on the XLR male connectors (pin 2 high), the double banana jacks and on the BNC connector. In this configuration the low side of the line is ungrounded or “floating.”

■ UnBal - Gnd

UnBal - Gnd outputs an unbalanced signal on the XLR male connectors (pin 2 high), the double banana jacks and on the BNC connector. In this configuration the low side of the line is grounded through a 5 Ω resistor.

■ CMTST

CMTST outputs a common-mode test signal on the XLR male connectors (both pins 2 and 3 high) and on the double banana jacks.

You can also choose one of three output impedances using the option buttons. The impedances available for the balanced and common-mode configurations are **40 Ω** , **150 Ω** and **600 Ω** ; if your instrument was ordered with the European impedance option S2-EURZ, the choices are **40 Ω** , **200 Ω** and **600 Ω** . The impedances available for the unbalanced configuration are **20 Ω** and **600 Ω** .

See Chapter 4 for simplified schematics and more detailed information about the 2700 series Analog Outputs.

Analog Generator References

With the appropriate choice of units, amplitude and frequency settings in the Analog Generator can be made relative to reference values. These references are entered manually in the Analog Generator **References** area. **Freq** and **dBr** references can also be entered “on the fly” from the current generator settings, as explained below.

For the two power references (**dBm** and **Watts**), the 2700 series calculates and applies the correct voltage to the outputs that is necessary to produce the power specified in the **Amplitude** field in the external load impedance specified in the **dBm** or **Watts Reference** fields.

Figure 66. Analog Generator References.

References	
dBm: 600.0 Ohms	Freq: 1.00000 kHz
dBr: 387.3 mV	Watts: 8.000 Ohms
387.3 mV -8.239 dBV -6.021 dBu	

dBm Reference

Because dBm is a unit of power, a voltage reading in **dBm** units will only have meaning if the circuit impedance is known.

To use dBm levels, select **dBm** as the **Amplitude** unit of measurement, and then set the **dBm** impedance reference to the correct impedance value for your application. The default value is **600 Ω** .

*NOTE: dBm is rarely the correct choice of units for audio measurements. dBm units are often mistakenly chosen when dBu units should be used. See the sidebar **dBm versus dBu** on page 533.*

dBr Reference

The dBr (which is shorthand for “decibels relative to a reference”) reference is an easy way to set a nominal level against which your settings or readings are made. Enter a reference value in the **References: dBr** field, or load it “on the fly” from the current generator amplitude setting using the menu command **Edit > Set Generator dBr Ref** or the keyboard shortcut **F3**.

You can set an Analog Generator **dBr** reference in **V**, **dBV** or **dBu** units.

Frequency Reference

The *relative* units of frequency measurement for the Analog Generator are **F/R**, **dHz**, **%Hz**, **cent**, **octs**, **decs**, **d%**, and **dPPM**.

In a relative expression, the frequency setting or reading is expressed in relation to a second reference frequency. For Analog Generator relative frequency settings, this reference frequency is entered in hertz in the Analog Generator **References: Freq** field, or it can be entered “on the fly” from the current generator frequency setting with the menu command **Edit > Set Generator Freq Ref**, or with the keyboard shortcut **Ctrl+F3**.

Watts Reference

Because the watt is a unit of power, a voltage reading in **Watts** units will only have meaning if the circuit impedance is known.

To use watts levels, select **Watts** as the **Amplitude** unit of measurement, and then set the **Watts** impedance reference to the correct impedance value for your application. The default value is **8 Ω** .

Chapter 7


The Digital Generator

Signals for Digital Measurements

The Digital Generator creates audio signals in DSP that are then embedded in a *digital audio interface data stream*, such as described in the AES3 or IEC 60958 standards. This interface signal is configured for output by settings made in the Digital Input/Output (DIO) panel, which is discussed in detail in Chapter 9. See Appendix B for more information on the digital audio signal.

The Digital Generator Panel

Figure 67. The Digital Generator Panel.



Open the Digital Generator panel by choosing **Panels > Digital Generator**, by clicking the **Digital Generator** button on the Panel toolbar, or by the key-



board shortcut **Ctrl+D**. Like most 2700 series panels, the Digital Generator can be viewed in two sizes. Double-click the panel Title Bar to change sizes.


The Digital Generator panel is divided into three areas:

- The upper area, which provides fields for choosing waveforms, setting amplitude and attaching EQ curves;
- the center area, which offers control of dither, and
- the lower area, which provides fields to set references.

We will first look at general topics of setting frequency and amplitude and turning the generator **ON** and **OFF**; then we will examine the waveform selections available in detail; last we will look at choosing the dither type and setting the digital references.

Frequency Units

Figure 68. Setting the Digital Generator Frequency.




Frequency may be expressed in absolute units (hertz) and in a variety of units relative to the value entered in the **References: Freq** field. See **Digital Generator References** on page 121 and **Frequency Units** on page 530.

Changing units does not change the frequency of the generator. The existing frequency will simply be re-stated in the new units. Also, the value displayed after pressing **Enter** may differ slightly from the value you typed in, since the control software will step to the nearest frequency increment.

Output On/Off and Channel Selection

Figure 69. Digital Generator **ON / OFF**.



The Digital Generator signal outputs are toggled **ON** and **OFF** by the **OUTPUTS** button. Additionally, each channel output can be switched individually on and off by the **CH A** and **CH B** buttons on either side of the

OUTPUTS button. Both the main **OUTPUTS** button and an individual channel button must be switched on to route signal to the digital output circuitry.

Auto On

If the **Auto On** checkbox is checked, the Digital Generator is automatically switched **ON** when a sweep starts, and **OFF** when the sweep stops.

This is useful for power amplifier or loudspeaker testing. With the generator set to **OFF** and **Auto On** enabled, signal will only be applied to the DUT while the sweep is actually running.

See Chapter 18 for more information on sweeps. Also see **Pre-Sweep Delay** on page 418 for a discussion of avoiding undesirable measurement transients possible in the **Auto On** mode.


Channel Invert

A 2700 series instrument maintains correct absolute polarity throughout the system. You can invert the polarity of either audio channel by clicking the **Invert** checkbox for that channel. When neither or both **Invert** boxes are checked, both channels have the same polarity.

Polarity inversion of one channel with respect to the other can be used to create the stereo “difference” signal which modulates the subcarrier in some stereo multiplex systems.

Amplitude Control and Units

Figure 70. Setting the Digital Generator Amplitude.



If the **Track A** checkbox is checked, the audio amplitude of both Channel A and Channel B are set by the Channel A **Amplitude** setting.

If the **Track A** checkbox is not checked, the audio amplitudes of the two Digital Generator channels can be controlled individually. Type a value in the **Amplitude** setting field for either Channel A or Channel B and press **Enter**.

You can choose an amplitude unit of measurement in either the analog or digital domains from the units drop-down list, shown in Figure 70. The ability to state a digital audio amplitude in analog terms makes it easy to work with the analog output values while testing a D-to-A converter, for example, when the full scale analog output of that converter is known. Enter the DUT voltage which corresponds to digital full scale in the **References: Volts/FS** field (see page 121).

Changing a unit of measurement will not change the audio amplitude, only the expression of the value. See **Digital Amplitude Units**, page 534, and **Analog Amplitude Units**, page 530.

The value displayed after pressing **Enter** may differ slightly from the value you typed in, since the control software will step to the nearest amplitude increment.


The Digital Generator will not permit an output amplitude entry greater than 1.000 FFS (0 dB FS). If you enter a value greater than 1.000 FFS or a combination of values (in **EQ Sine** or **Sine+Offset** modes, for example) which would result in a value greater than 1.000 FFS, an error message is displayed.

Waveforms other than a sine wave are calibrated in *peak equivalent sine wave* terms; that is, the **Amplitude** setting field is calibrated to show the rms value of a sine wave with same peak value as the waveform selected. Selecting a square wave with an **Amplitude** value of 100.0 mVrms on the Digital Generator panel, for example, produces a 141.4 mVp square wave signal.

Choosing a Digital Generator Waveform

The Digital Generator offers a wide choice of test waveforms selectable from the primary and secondary waveform lists.

Figure 71. Digital Generator Primary Waveform Selections.



These list selections are, for the most part, sorted by the shape of the waveform, such as sine wave, square wave, noise, and so on. Most waveform


choices have an associated secondary list, from which you make your final waveform selection.

This chapter organizes the waveforms by shape. The variations available on the secondary lists are described under each section.

Sine waveforms


This section describes the sine waveforms available to the Digital Generator, which cover the frequency range from 10 Hz to just under 50% of the sample rate (which is approximately 24 kHz at a 48 kHz sample rate). The frequency can be set in hertz or in a number of relative units; see **Frequency Units**, page 530.

Figure 72. Digital Generator Sine Waveform Selections.



Wfm: Sine: Normal


Figure 73. Digital Generator Sine: Normal.



The normal sine waveform is the standard waveform for most audio testing, and is the default generator waveform.

Wfm: Sine: Burst

Figure 74. Digital Generator Sine: Burst.




The frequency of the sine wave is set in the **Frequency** field. The **Amplitude** field sets the generator amplitude at the maximum burst ON level. In the Digital Generator, **Sine: Burst** cannot be triggered or gated.

The Digital Generator **Sine: Burst** signal is essentially identical to the Analog Generator **Sine: Burst (D/A)** signal, and both are similar to the Analog Generator **Sine: Burst** signal.

See the **Tone Burst** and **Tone Burst Definitions** sidebars on pages 71 and 73.

Wfm: Sine: Var Phase

Figure 75. Digital Generator **Sine Var Phase**.



This selection produces the selected frequency at both Channel A and B outputs, but the phase of the Channel B output is variable from -180° to $+179.99^\circ$ with respect to the Channel A output, as controlled by the **Phase** field.

A positive value entered in the **Phase B-A** field will cause the Channel B output to lead the Channel A output. A negative value entered in the **Phase B-A** field will cause the Channel B output to lag the Channel A output. See the illustration below:





Figure 76. **Sine: Var Phase**, triggered on Channel A (the larger waveform). -90.00° deg has been entered in **Phase B-A** field, causing B (the smaller waveform) to lag A.

Wfm: Sine: Stereo


Figure 77. Digital Generator **Sine: Stereo**.



This waveform selection produces independent sine waves on Channel A and Channel B. The **Frequency** field sets the frequency of the Channel A signal, and the **Frequency 2** field sets the frequency of the Channel B signal. Their amplitudes are independently set by the two **Amplitude** fields unless the **Track A** box is checked, in which case the amplitudes are equal and controlled by the Channel A **Amplitude** field.

Wfm: Sine: Dual

Figure 78. Digital Generator **Sine: Dual**.




This selection produces two independent sine waves which are summed to create a complex waveform. This complex waveform is sent to both channel outputs.

The **Frequency** and **Frequency 2** fields permit each component sine wave frequency to be set independently. The **Dual Ampl Ratio** field enables you to set the ratio by which the secondary (**Frequency 2**) sine wave component amplitude will be attenuated with respect to the amplitude of the primary (**Frequency**) sine wave component.

The **Sine: Dual** signal is particularly useful as a calibration signal for harmonic distortion analyzers, where the **Frequency** signal at reference amplitude represents the fundamental signal. The secondary (**Frequency 2**) sine wave can be set to any desired harmonic of the primary (**Frequency**) “fundamental” sine wave, at an amplitude to represent any desired distortion level. For example, setting the primary (**Frequency**) at 1 kHz and the secondary (**Frequency 2**) at 3 kHz with a **Dual Amp Ratio** of -40.0 dB (1%) produces a 1 kHz signal with third harmonic distortion of 1.0%.

Wfm: Sine+Offset

Figure 79. Digital Generator Sine: Sine + Offset.



This waveform is a combination of a sine wave with a digital DC signal. Digital DC is essentially the same digital code sent for every sample; see **Wfm: Special: Constant Value** on page 116. The frequency of the sine wave for the **Sine+Offset** waveform, like the other Digital Generator sine waves, can be set to the range of 10 Hz to 50% of the sample rate; the sine wave level is set in the **Amplitude** field(s).


The digital DC signal amplitude, which can have a positive or negative value, is set in the **Offset** field. The sum of the sine wave and DC amplitudes may not exceed positive or negative full scale (FS). If the sine wave amplitude is 0 FS the **Offset** value may be set anywhere in the range between -1.0 FS and $+1.0$ FS; if the sine wave amplitude is at full scale, the **Offset** must be 0 FS.

Although the sine wave amplitude may be set independently for Channel A and Channel B, the **Offset** value is common to both channels.

A low-amplitude sine wave with an **Offset** value that positions the sine wave at a major bit-switching point of a ladder-type D-to-A converter is particularly useful for testing linearity at various points in the converter's operating range.

Wfm: Sine: EQ

Figure 80. Digital Generator Sine: EQ Sine.



The **Sine: EQ Sine** selection outputs a normal sine wave, with equalizing amplitude changes made in the generator level according to an attached EQ data file. This enables you to make a frequency sweep where the generator amplitude varies as instructed by the data in the attached file.

When you select **Sine: EQ Sine** and attach an EQ file (see below), a new field named **Post EQ** appears on the Digital Generator panel. The **Post EQ** field displays the generator amplitude to be applied to the DUT, which is the value entered in the **Amplitude** field, corrected by the value (at that frequency) of the correction factor in the attached EQ file.

NOTE: When **Sine: EQ Sine** is selected, the values in the **Amplitude** field are displayed in **blue** rather than **black**.

To set the output amplitude, you can enter a value in either the **Amplitude** field or the **Post EQ** field, and the value in the other field will be properly adjusted according to the correction factor.


The Digital Generator will not permit an output amplitude entry greater than 1.000 FFS (0 dB FS). If the value of the normal (pre-EQ) **Amplitude** field as modified by the equalization file would produce an amplitude greater than 1.000 FFS, an error message is displayed.

If a frequency value outside the frequency range span of the EQ file is entered on the generator panel or occurs during a sweep, the **Post-EQ** amplitude will go to 0 FFS.

For more information on generator equalization see the sidebar on **Specifying the EQ Curve** and **Typical EQ Applications** on page 76.

Wfm: Sine: Shaped Burst


Figure 81. Digital Generator **Sine: Shaped Burst**.



A tone burst is an audio signal (usually a sine wave) that is keyed on and off. Tone bursts are often used as stimulus signals, and can reveal characteristics of a DUT's performance which are not observable with continuous tones.

The Digital Generator **Sine: Shaped Burst** signal is essentially identical to the Analog Generator **Sine: Shaped Burst** signal, and both are similar to the Digital Generator **Sine: Burst** signal. **Sine: Shaped Burst** cannot be triggered or gated.

Figure 82. An example of a shaped burst.



For both generators, the **Sine: Shaped Burst** has a raised-cosine shaped envelope, creating a relatively narrow energy spectrum around the sine wave frequency. The Digital Generator **Sine: Burst** has a rectangular envelope with fast rise and fall times and consequently a wider spectrum of energy.


See the **Tone Burst** and **Tone Burst Definitions** sidebars on pages 71 and 73.

Intermodulation Distortion (IMD)

Intermodulation distortion (IMD) testing requires a stimulus which is a combination of two waveforms, and a specific analysis technique to evaluate interaction of the waveforms within the DUT.

The 2700 series Digital Generator provides a wide selection of standard IMD test signals.


Figure 83. Digital Generator IMD Waveform Selections.



IMD signal amplitude is set in the Digital Generator **Amplitude** field. The IMD composite waveform amplitude is calibrated in peak equivalent sine wave terms. See **Amplitude Control and Units** on page 101.

Wfm: IMD: SMPTE/DIN 1:1

Figure 84. Digital Generator **Wfm: IMD SMPTE/DIN 1:1**.



This selection produces a signal which is the linear combination of two sine waves. The first sine wave, set in the **IM-Freq** field, is a lower-frequency tone that can be assigned any frequency in the range of 40 Hz to 500 Hz. The frequency of the second sine wave, set in the **High Freq** field, can be anywhere in the range from 2 kHz to 50% of the sample rate.

The low-frequency sine wave is linearly combined in a 1:1 amplitude ratio with the high-frequency sine wave.


*NOTE: For compatibility with the S2-IMD hardware analyzer module, the **IM-Freq** tone must be set to one of the 8 frequencies listed on page 82. If S2-IMD is not to be used for analysis, you may set the **IM-Freq** tone to any suitable frequency.*

Wfm: IMD: SMPTE/DIN 4:1

This waveform is the same as the **Wfm: IMD: SMPTE/DIN 1:1** selection, except that the amplitude ratio of the low-frequency sine wave to the high-frequency sine wave is 4:1.

Wfm: IMD: CCIF/DFD

Figure 85. Digital Generator **IMD: CCIF/DFD**.



The CCIF/DFD is a “difference tone” waveform, created by generating two equal-amplitude sine waves whose frequencies are equally-spaced around a center frequency value.

The value set in the **IM-Freq** field determines the spacing between the two sine waves; the acceptable range for this spacing value is 80 Hz–2 kHz.

The frequency set in the **Center Freq** field acts as a central reference point, with the upper sine wave frequency half the **IM-Freq** (spacing) frequency above, and the lower sine wave set the same value below. Put another way,

$$\text{Low Sine Freq} = \text{Center Freq} - \left(\frac{\text{IM Freq}}{2} \right)$$

and


$$\text{High Sine Freq} = \text{Center Freq} + \left(\frac{\text{IM Freq}}{2} \right)$$

The acceptable range for **Center Freq** is 3 kHz to 50% of the sample rate, less half the **IM-Freq** (spacing) value. Once again,

$$3 \text{ kHz} \leq \text{Center Freq} \leq \left(\left(\frac{Fs}{2} \right) - \left(\frac{\text{IM Freq}}{2} \right) \right)$$

Wfm: IMD: DIM 30 / DIM 100 / DIM B

Figure 86. Digital Generator Wfm: IMD DIM.



DIM is an acronym for *dynamic intermodulation*; another term for this IMD test is TIM, or *transient intermodulation*. Like the Analog Generator DIM waveform selections (page 83), the three **IMD: DIM** choices linearly combine a square wave near 3 kHz with a higher-frequency sine wave. The peak-to-peak amplitude ratio of the square wave to the sine wave is 4:1.

Because the square wave component of the DIM waveforms is digitally generated, the available square wave fundamental frequencies are limited to even integer submultiples of the sample rate, as described the **Square wave** section below. The frequency of the sine wave component of the DIM waveforms is determined by an ideal ratio to the square wave, so it is also dependent on sample rate.

The effect of these constraints in the Digital Generator is to produce DIM waveforms whose component frequencies are sometimes (depending on sample rate) approximations of the ideal frequencies specified and generated in the Analog Generator. However, the approximations are close enough to be compatible with the DIM analysis in the analog hardware IMD analyzer option.

The table below illustrates these considerations:


Comparison of Ideal and Digitally-generated DIM Signals			
Sample Rate	Square wave	Sine wave	Ratio
DIM 30 and DIM 100			
—IDEAL—	3,150 Hz	15,000 Hz	100 / 21
44,100 Hz	3,150 Hz	15,000 Hz	100 / 21
48,000 Hz	3,000 Hz	14,285.7 Hz	100 / 21.00021
DIM B			
—IDEAL—	2,960 Hz	14,000 Hz	175 / 37
44,100 Hz	3,150 Hz	14,898.65 Hz	175 / 36.99999
48,000 Hz	3,000 Hz	14,189.14 Hz	175 / 37.00013

For **DIM 100**, no filtering other than the intrinsic band-limiting at $SR/2$ is applied.

For **DIM 30** and **DIM B** (broadcast), the square wave is passed through a 30 kHz low-pass filter if the SR is 60 kHz or higher; otherwise, the square wave is intrinsically band-limited at $SR/2$.

Square wave

Figure 87. Digital Generator Square wave Waveform.



Wfm: Square

The frequency range for square waves is from approximately 2 Hz to 1/6 of the sample rate (8 kHz at a 48 kHz sample rate; 7.35 kHz at a 44.1 kHz rate).

Digital square waves are generated by alternately turning the output ON and OFF for the same number of sample periods, which means the square wave is synchronous with the sample rate and has a time-symmetric duty cycle. This limits the square wave fundamental frequencies to *even integer submultiples* of the sample rate within the range mentioned above. The highest available frequency is $SR/6$ and the lowest frequency is $SR/2^{24}$.


For example, at a 48 kHz sample rate, the highest square wave frequencies are:

- 8 kHz (48000/6)
- 6 kHz (48000/8)
- 4.8 kHz (48000/10)
- 4.0 kHz (48000/12)
- 3.42857 kHz (48000/14), and so on.

The square wave amplitude is calibrated in peak equivalent sine wave terms. See **Amplitude Control and Units** on page 101.

Noise

Figure 88. Digital Generator Noise Waveforms.



The 2700 series Digital Generator offers three DSP-generated pseudo-random noise signal selections: **White**, **Pink** and **Burst USASI**. The noise waveform amplitudes are calibrated in peak equivalent sine wave terms. See **Amplitude Control and Units** on page 101.

Wfm: Noise: White

The DSP-generated white noise is pseudo-random and has a length of 2^{20} or 1,048,576 samples, which means that with the DIO SR set to a sampling rate of 48 kHz the noise pattern repeats about every 22 seconds. The noise has a zero mean, a crest factor of 1.73 and a rectangular probability distribution function (RPDF).

The spectrum of the noise is flat from just above 0 Hz to just below half the sampling rate, and consists of spikes spaced at $SR/2^{20}$ Hz.

See the **Noise** sidebar on page 87 for a discussion of white and pink noise characteristics.

Wfm: Noise: Pink

The DSP-generated pink noise is generated using the same algorithm that produces the pseudo-random white noise, but is also filtered to fall off with frequency at a rate of 3 dB per octave.


See the **Noise** sidebar on page 87 for a discussion of white and pink noise characteristics.

Wfm: Noise: Burst USASI

Noise: Burst: USASI selects a special two-level modulated waveform with a noise spectral distribution similar to voice and music program material. The Federal Communications Commission (FCC) in the USA specifies this waveform as a modulation source while using a radio-frequency spectrum analyzer to measure the occupied bandwidth of amplitude modulated broadcast transmitters.


Special Waveforms

Figure 89. Digital Generator *Special Waveform Selections.*



Wfm: Special: Monotonicity

Figure 90. Digital Generator *Special: Monotonicity.*



Monotonicity is a low-amplitude “staircase” waveform. It consists of five complete cycles of a square wave at each of the ten lowest non-zero digital amplitude states, plus the same time period at zero. Since this definition is with reference to the minimum possible amplitude, the absolute amplitude of the steps depends on the Output: Resolution value (word length, in bits) on the DIO panel. See **Output Resolution** on page 159.

The square wave half-cycle duration is controlled by the **Samples/Step** field. For example, with a **Samples/Step** value of **10** at a 48 kHz sample rate, the square wave half-period is 10/48,000 seconds, or 208.3 μ s; each equal-amplitude section is ten half-periods long, or 2.083 ms; and each eleven-step repetition occurs at a rate of 11 $\times$ 2.083 ms, or every 22.92 ms.




Figure 91. Monotonicity waveform. 24-bit resolution, 10 samples/step, 48 kHz sample rate.

Dither is disabled when the Monotonicity waveform is selected. See **Dither** on page 120.

The Monotonicity waveform is used principally in testing low-level linearity of DACs and digital domain devices by viewing their output in the time domain, using the Digital Analyzer Spectrum Analyzer tool.

*NOTE: In the Spectrum Analyzer panel, Select **Digital Gen** as the **Trigger: Source**. The **Wave Display** field on the panel should be set to either **Display Samples** or **Absolute Value**, but not **Interpolate**. See Chapter 12 for more information about using the Spectrum Analyzer.*

Non-linearity is shown by unequal step-to-step amplitudes. Non-monotonicity is indicated by a reversal in direction of the pattern of constant decrease from step to step.

Figure 91 shows an example of the Monotonicity waveform.

Wfm: Special: J-Test


J-Test is a waveform which produces a maximum amount of data-induced jitter on low-bandwidth digital transmission links. **J-Test** consists of a square wave at one-fourth the sample rate, combined with a second, low-frequency low-amplitude square wave that has a digital dc offset.

Dither is disabled for **J-Test** and no amplitude control is available, since the signal definition specifies exact data values. The **J-Test** signal would normally be transmitted while measuring jitter at the receiving end of a cable or digital

transmission system, to estimate the worst-case magnitude of jitter caused by reduced bandwidth of the transmission link. See **Dither** on page 120.

Wfm: Special: Polarity

Figure 92. Digital Generator **Special: Polarity**.



The polarity waveform is designed to be obviously asymmetrical, so that it is easily apparent if signal is inverted or not. The waveform is the sum of the fundamental tone set in the **Frequency** field and its second harmonic, in a fixed phase relationship.

When the output of the DUT is viewed using an oscilloscope or the 2700 series Spectrum Analyzer in the time-domain view, the signal will reveal if there has been a polarity inversion in the DUT or in the signal interconnections.





Figure 93. Polarity waveform, normal polarity shown.

The only setting available for the polarity waveform is **Frequency**.


Wfm: Special: Walking Ones and Walking Zeros

Figure 94. Digital Generator *Special: Walking Ones.*



Walking Ones is a signal in which only one bit is at logical “one” at any moment, with the others all at logical “zero.” The position of the bit which is at logical “one” is stepped through the word from LSB to MSB repeatedly, at a rate controlled by the **Samples/Step** field.

Figure 95. Digital Generator *Special: Walking Zeros.*



Walking Zeros is similar except that only one bit is at logical “zero” and all others are at logical “one.”

Walking Ones and **Walking Zeros** are typically used in troubleshooting circuitry where the digital word appears in parallel format, in order to find “stuck bits.” Dither is disabled for **Walking Ones** and **Walking Zeros**, and the amplitude is fixed. See **Dither** on page 120.

Walking Ones or **Walking Zeros** can be chosen as the Waveform selected for bit error analysis in the Digital Data Analyzer tool (see Chapter 16).

The walking waveforms can also be observed on the DIO panel by viewing the bit indicators in the **Data Bits** mode (rather than **Active Bits** mode). Set the **Samples/Step** value to approximately half the sample rate (24000 for a 48 kHz rate), which results in a 0.5 second per step walking rate.

Wfm: Special: Constant Value

The **Special: Constant Value** waveform provides essentially the same digital code at every sample. This is the digital domain equivalent of an analog DC signal. Digital DC is usually dithered, like most digital waveforms, so the actual values at each sample will vary slightly by the amount of the applied dither. See **Dither** on page 120.

There is no frequency control field for the **Constant Value** waveform. The output **Amplitude** fields set the amplitude of the DC for each channel.

Special: Constant Value can be chosen as the Waveform selected for bit error analysis in the Digital Data Analyzer tool (see Chapter 16).

Wfm: Special: Random

Special: Random is a specific, predictable pseudo-random waveform uniformly distributed across the entire range of code values between plus and minus full scale. It is intended for error-rate testing of communications links, AES3 interfaces, and digital recorders.

Special: Random can be chosen as the Waveform selected for bit error analysis in the Digital Data Analyzer tool (see Chapter 16).

Random is identical to the **Bittest Random** waveform of Audio Precision Systems One and Two and the **RAND** waveform of Portable One Dual Domain; it may be used with the bit error analysis capability of any of those instruments.

Dither is disabled for the **Random** waveform. See **Dither** on page 120.

Wfm: Special: Pass Thru

The **Special: Pass Thru** selection does not cause a waveform to be generated; instead, it passes the digital audio signal connected to the rear panel **AES/EBU REF IN** XLR connector through to the Digital Generator output.

Since the sample rate at the Digital Generator output is set at the DIO SR, this is a convenient way to synchronize an external test signal with the 2700 series instrument. You can also use **Pass Thru** to convert an external signal from one sample rate to another, as might be necessary when working at a 48 kHz sample rate but using a Compact Disc with test signals at a 44.1 kHz sample rate as a source.

A sample rate converter (SRC) is used to maintain the output audio frequency at the **REF IN** audio frequency value. The Digital Generator output signal is then synchronized and frame-synced to the converted **REF IN** signal.

The **AES/EBU REF IN** signal sample rate must be in the range between 28 kHz–200 kHz. Additionally, the ratio of the **REF IN** sample rate to the SR must fall in the range between 1:8 to 7.75:1; or, stated another way,

$$\frac{SR}{8} \leq \text{REF IN sample rate} \leq SR \times 7.75.$$

If the **REF IN** signal is stereo, the output signal will also be stereo. Status bits are not passed through to the output, but are set on the Status Bits panel as usual. You can choose whether or not to dither the re-sampled **REF IN** signal. See **The Status Bits Panel** on page 177 and **Dither** on page 120.


The amplitude relationship between the **REF IN** signal and the Digital Generator output is controlled by the Digital Generator output amplitude setting. A setting of 1.00 FS (0 dB FS) will pass the **REF IN** signal unattenuated, and lower settings of generator amplitude will attenuate the audio level.

Also see **Pass Thru Domain Preference** on page 503.

MLS Waveforms

Wfm: MLS

Figure 96. Digital Generator Wfm: MLS



The Digital Generator can generate 16 variations of a *maximum length sequence* (MLS) waveform. An MLS waveform is a pseudo-random noise signal with the property that, when passed through a device and cross-correlated with the input signal, the result is the impulse response of the device. An FFT can then be performed on the impulse response to yield the frequency and phase response of the device. See Chapter 15 for a complete description of the MLS Analyzer and the use of the Digital Generator with MLS waveforms.

MLS Waveform Sample Rate

For **MLS** waveforms, the generator output sample rate (SR) sample rate must match the analyzer ADC or digital input sample rate (ISR) for proper cross-correlation and analysis. See Sample Rate (SR) on page 157.

Arbitrary Waveforms




Figure 97. Loading an arbitrary waveform.

The generator arbitrary waveform function allows you to load a properly-formatted digital waveform file into the 2700 series DSP and route the waveform to the Digital Generator outputs.

Arbitrary waveform files provided with the 2700 series include single tones, tone combinations for IMD testing, multitone waveforms and calibration tones, and other useful waveforms.

Waveform files must be of the Audio Precision .agm or .ags file types. See **Waveform Files** on page 28. You may also make custom arbitrary waveform files using a file creation utility provided with the 2700 series or with third-party applications such as MATLAB. See **Multitone Creation** on page 348.

To load a waveform file and then output the waveform so that the embedded audio tones are at the intended frequencies, the DIO Sample Rate (SR) must be set to the same sample rate that was used in creating the file. The 2700 series offers two sampling rate options for loading an arbitrary waveform, which are set on the Configuration panel at **Utilities > Configuration**.

If the **Set sample rate when loading generator waveforms** checkbox on the Configuration panel is checked, the control software will automatically set the DIO SR to match the sample rate of the file being loaded. If this checkbox

is unchecked, you must manually enter the sampling rate you desire in the Sample Rate (SR) field on the DIO panel.

If you enter a sample rate different from the sample rate at which the file was created, the frequencies of the audio tones embedded in the output signal will be shifted by the ratio of the two sample rates.

The DSP processes in the multitone audio analyzer require that the multitone be precisely correct for synchronous operation. If the tones have been frequency-shifted, the Multitone Analyzer FFTs will not be synchronous, and an FFT windowing approach will be necessary. See Chapter 14 for more information on multitone testing.

*NOTE: The Arbitrary Waveform generation memory buffers of the Analog Generator and Digital Generator are shared. If both generators have **Arb Wfm** selected as the waveform, the same waveform file will be read into both generators.*


Dither

Dither is low-level noise that is combined with the signal to improve linearity, reduce distortion at low amplitudes, and extend the linear operating range below the theoretical minimum for undithered PCM signals of any particular resolution.

The dither is introduced before quantizing and serves to randomize the quantization distortion and produce an undistorted signal with a slightly higher noise floor. The elimination of quantization noise results in a more acceptable audio signal.

Dither Type

Figure 98. Digital Generator Dither settings.



The **Dither Type** list on the Digital Generator panel allows you to select three types of dither for the generator output signal, or none. The dither type names “rectangular” and “triangular” describe the shape of the graphs of the probability distribution function (PDF) of the noise signal chosen for dither. The effects of dither on a digital audio signal change with the level of dither applied and with the PDF of the dither noise signal.

The **Output Resolution** field on the DIO panel controls the amplitude of the dither added to the digital generator output. Proper dither amplitude for a

16-bit system, for example, is obtained by entering **16** in the **Output Resolution** field.

The **Dither Type** list choices are:

- **Triangular.** Triangular probability distribution function (TPDF) dither is the default setting in the 2700 series, and is recommended for most measurement applications. It produces a slightly higher noise floor than RPDF dither, but it imparts no noise modulation effect to the audio. Triangular dither can add or subtract up to one LSB peak amplitude at the selected resolution.
- **Rectangular.** Rectangular probability distribution function (RPDF) dither provides a better signal-to-noise ratio than triangular dither, but suffers from noise modulation effects. Rectangular dither can add or subtract up to one-half LSB peak amplitude at the selected resolution.
- **Shaped.** Shaped dither is TPDF dither shaped through a filter, resulting in a dither signal with a rising 6 dB-per-octave slope, set with the 0 dB effect point at one-half the sampling rate. This places most of the dither power at higher frequencies, where much of the resultant noise falls out-of-band for most devices, and where audibility is lower.
- **None.** No dither is applied.

Certain generator waveforms, such as **Monotonicity**, **J-Test**, **Walking Ones** or **Zeros**, and **Random** waveforms are only usable with no dither. When one of these waveforms is selected, dither is automatically disabled and the **Dither Type** field is not available.

Digital Generator References

With the appropriate choice of units, amplitude and frequency settings in the Digital Generator can be made relative to reference values. These references are entered manually in the Digital Generator **References** area.

Figure 99. Digital Generator References.

Reference Unit
387.3 mFFS
38.7298 %FS
-8.239 dBFS
-1.08 Bits
387.3 mV
547.7 mVp
1.095 Vpp
-6.021 dBu
-8.239 dBV
3248894 dec
3192FE hex

Volts for Full Scale Reference

Digital full scale (FS) is defined as the rms value of a sine wave whose peaks just touch the maximum values of the coding scheme. When expressed in analog domain units, there must be a reference given to establish the level relationship between the two domains. For Digital Generator settings, that reference is entered as the rms voltage which is to correspond to a full scale digital audio signal.

Set the Digital Generator volts for full scale reference in the **References: Volts/FS** field.

Frequency Reference

The *relative* units of measurement for the Digital Generator are **F/R, dHz, %Hz, cent, octs, decs, d%, and dPPM**.

In a relative expression, the frequency setting or reading is expressed in relation to a second reference frequency. For Digital Generator relative frequency settings, this reference frequency is entered in hertz in the Digital Generator **References: Freq** field.

dBr Reference

The dBr (which is shorthand for “decibels relative to a reference”) reference is an easy way to set a nominal level against which your settings or readings are made. Enter a reference value in the **References: dBr** field.

You can set a Digital Generator **dBr** reference in **FFS, %FS, dBFS, bits, V, Vp, Vpp, dBu, dBV, dec** or **hex** units.

Chapter 8

The Analog Analyzer

Overview

The Analog Analyzer is a hardware-implemented audio analysis tool. It is similar in function, appearance and capability to the software-implemented DSP Audio Analyzer (when that analyzer is set to an analog input) available on the Digital Analyzer panel. See Chapter 11 for a detailed discussion of the DSP Audio Analyzer.

Generally, the Analog Analyzer will provide better performance in the measurement of analog signals—flatter frequency response, lower noise and distortion figures, wider bandwidth—than the DSP Audio Analyzer. The DSP Audio Analyzer, however, is capable of faster operating speeds.

In addition to the audio analysis settings and readings for the Analog Analyzer, all 2700 series analog input selection and configuration settings (even when using DSP analysis) are also made on the Analog Analyzer panel.

This chapter examines each function, control and display of the Analog Analyzer in detail. If you are new to the 2700 series, you might want to start with the Quick Guides in *Getting Started with Your 2700 Series Instrument*, which will introduce you to Analog Analyzer features.

There are six meters on the Analog Analyzer which measure the input signal simultaneously:

- the two **Level** meters,
- the two **Freq.** (frequency) meters,
- the **Phase** meter, which measures the phase relationship between the two channels, and
- the **Function** meter, which is a single-channel multi-function meter that can be switched to either audio channel.




Figure 100. Conceptual Block Diagram, Analog Analyzer.

As on other 2700 series panels, you can select the units of measurement you prefer for each reading display. Other fields on the Analog Analyzer panel allow you to choose coupling, filter, detector and level reference options. Some of these options, however, apply only to the **Function** meters, as you will see later in this chapter.

Also see Chapter 5, **Signal Analysis**.

Analog Analyzer Options

The features of the Analog Analyzer can be expanded with the addition of optional hardware modules. These include:

- **Option filters**

Up to seven optional hardware filters can be mounted in the plug-in filter slots in a 2700 series instrument. These filters, which include weighting, bandpass, deemphasis, etc., can be selected and used in Function meter measurements of the Analog Analyzer. See **The “Fltr” Field** on page 149.

- The IMD Analyzer Option

The S2-IMD Option includes both an intermodulation distortion (IMD) generator (see Analog Generator Hardware Options, page 64) and an IMD analyzer (see IMD Measurements, page 137).

- The Wow and Flutter Option

The S2-W&F Wow and Flutter option adds a wow and flutter analyzer to the Analog Analyzer tools.

- The AES17 Filter Option

The S-AES17 Option adds a pre-analyzer filter module with additional option filters to facilitate measurements in the presence of high levels of out-of-band noise, as recommended in the AES17 standard.

The discussions in this chapter cover the use of option filters, and also assume the installation of both the IMD Option and the Wow and Flutter Option. If your 2700 series instrument does not have these options installed, these features will not be available.


See 2700 Series Hardware Options on page 34 for a full description of the various options available.

The Analog Analyzer Panel




Click **Panels > Analog Analyzer** or the **Analog Analyzer** button on the Panels toolbar to open the Analog Analyzer panel.

Figure 101.
The 2700 series Analog Analyzer panel.



Input Selection and Configuration

Figure 102.
Analog Analyzer panel inputs.



The two analog input channels can be configured independently, with Channel A input settings to the left of the panel and Channel B to the right.

Select the analog input source for each channel from the drop-down list, as shown in Figure 102. The choices are:

■ XLR-Bal

This selection attaches the input channel to the balanced XLR input connector, and also to the balanced double banana jacks. The banana jacks are hard-wired to the XLR connector, with the “+” jack wired to pin 2 and the “-” jack wired to pin 3 of the XLR connector.

- **BNC-Unbal**

This selection attaches the input channel to the unbalanced BNC input connection.

- **GenMon**

This selects the generator monitor path, which bypasses the external analog inputs and instead attaches the input channel to the Analog Generator output via an internal connection.

Source Input Termination

Next to each input source selection drop-down list is an input termination impedance drop-down list, as shown in Figure 102. The choices are:

- **300**

This selection sets the input impedance for the channel to 300 Ω .

- **600**

This selection sets the input impedance for the channel to 600 Ω .

- **100k**

This selection sets the input impedance for the channel to 100 k Ω (often called a *bridging* input).

The impedance chosen for the inputs remains attached to the connector at the selected value, even when the GenMon inputs are selected.

See Chapter 4, **Signal Inputs and Outputs**, for more details concerning the physical and electrical characteristics of the analog input connections.

DC Coupling of Analog Inputs

The 2700 series analog inputs can be dc coupled from the input connectors to Level, Frequency and Phase meters, and to the circuit point that is connected to the GENERATOR MONITORS isolation amplifiers and to the analog-to-digital converter (ADC) inputs. The ADCs are used to digitize analog signals for DSP analysis; when dc coupling is enabled, DSP acquisition of analog signals can be extended down to dc.

DC coupling also provides a superior common-mode rejection ratio (CMRR) at low frequencies, which is normally limited by the inevitable small mismatch in the values of the coupling capacitors that serve to block the dc.

You can choose to pass the dc component of either analog input signal to the ADCs by checking the **DC** checkbox for either channel, as shown in Figure 102.

- If the checkbox is checked, dc coupling is enabled for that channel.

- If the checkbox is unchecked, the dc component is blocked for that channel.

NOTE: The Analog Analyzer Function meter response extends well below 10 Hz, but the Function meter is not dc coupled.

The Level Meters

Figure 103.
The Analog Analyzer Level Meters.



Two Level meters are located near the top of the Analog Analyzer panel, one for each input channel. These meters display the audio amplitude of the input signals.

The Level meters are single-function, true rms amplitude meters. Unlike the Function meter, the Level meters have no selectable filters. The Level meters have a narrower dynamic range than the Function meter, with full specified accuracy and resolution extending down to only 5 mV. The Level meters are useful far below 5 mV, but with deteriorating accuracy and resolution.

Bandwidth and frequency response flatness of the Level meters are somewhat superior to those of the Function meter.

Level Meter Units

If you click on the arrow to the right of either Level meter reading field, a list of measurement unit choices will drop down.

The units list includes:


- analog domain units: **V**, **dBu**, **dBV**, **dBm** and **W** (watts), and
- relative units: **dBr A**, **dBr B**, **dBg A**, and **dBg B**.

For an explanation of the units of measurement used in the 2700 series and the references for the relative units, go to Appendix A, **Units of Measurement**.

The Frequency Meters

Figure 104.

The Analog Analyzer Frequency Meters.



The frequency readings of the signals on the two channels are shown in the Freq meter fields, just below the Level meter readings. In some documentation the frequency meters may be referred to as frequency counters.


The units of measurement include

- the absolute frequency in **Hz**, and
- a variety of relative frequency units: **F/R**, **dHz**, **%Hz**, **cent**, **octs**, **decs**, **d%** and **dPPM**.

All the relative frequency units are computed with respect to the Freq value entered in the References: Freq field lower on the panel. For specific definitions of these relative frequency units, see the **Frequency Units** discussion on page 530.

Input Ranging

Figure 105. Analog Analyzer input ranging.



Practical devices have an optimum amplitude operating range in which they exhibit their best performance. This is true for amplifiers, for measurement instruments and for the ADC circuits used in the 2700 series for conversion to the digital domain. The 2700 series uses selectable attenuators and amplifiers

to bring a wide range of input signals to the optimum amplitude for the measurement detectors.

You can choose automatic ranging (or *autoranging*) or manually set a fixed maximum range.

Analog input ranging and Function meter ranging is controlled from the Analog Analyzer panel. If you are using the DSP Audio Analyzer for analysis of analog input signals, additional ranging controls are available on that analysis tool, as explained on page 233.

Autoranging

The Analog Analyzer should normally be operated with automatic ranging, indicated by a check mark in each the appropriate Range check boxes. This provides operation with no possibility of clipping due to high-amplitude signals.

Uncheck the Range check box to defeat autoranging. The range setting field for that meter and channel will become active, and you can enter a fixed maximum range for that input.

Fixed Range


Using a fixed range produces faster measurements, which can be important when speed is at a premium, as within a repetitive routine in an automated testing procedure. However, you must know the probable range of the input signal and set a maximum above the highest expected level.

Manual range selection is also preferred when using signals which vary quickly, such as tone bursts or program material such as voice or music. Automatic ranging will constantly switch levels when a complex, wide-range signal is applied. This may make it difficult to adjust a device for minimum distortion or noise, for example.

The Phase Meter

Figure 107.

The Analog Analyzer Phase Meter.



The Phase meter measures the phase difference between the signals (which must be the same frequency) on the two input channels. The phase difference, always expressed in degree units, is shown in the Phase meter display.

The value displayed is “phase B–A,” the same expression used for the **Sine: Var Phase** waveforms of the Digital and Analog Generators. If Channel B leads Channel A, the display will show a positive reading; if Channel B lags Channel A, the display will show a negative reading.




Figure 106. Analog Analyzer phase display modes.

To the right of the Phase meter is a setting field, with a list of four options: **Auto**, **-180+180 deg**, **0+360 deg**, and **-90+270 deg**.

In **Auto**, the 2700 series reads absolute phase error. Delays in the DUT can cause signals to lag or lead by many waveform cycles, and for swept measurements **Auto** will correctly show and plot readings beyond ± 360 degrees. When viewing phase error in **Auto** without sweeping, the reading is reset at each waveform cycle and the phase error will always be displayed as within ± 360 degrees.

The **–180+180 deg**, **0+360 deg**, and **–90+270 deg** choices express the phase error in “windows” of 360°, with the window for each selection placed along a scale at a different positions in relation to 0°. See Figure 106.

Phase Meter Hardware

The Phase meter is connected across the two input channels of the Analog Analyzer, immediately following the input ranging circuitry. The Phase meter operates by measuring both the period of the reference channel and the time delay between the signal zero crossing on the selected channel versus the reference channel. Time delay to both positive-going and negative-going zero crossings are measured and averaged to avoid errors when measuring non-time-symmetric signals.

The Function Meter


Figure 108. Analog Analyzer Function meter (Reading meter).



The Function (also called the Reading meter) meter is the heart of the Analog Analyzer. Using a tunable bandpass-bandreject filter, selectable detectors, bandwidth-limiting and weighting filters and the processed outputs of the optional analyzer modules such as the IMD analyzer and the wow and flutter analyzer, the Function meter can measure a number of different audio functions.

Function Meter Units

Figure 109. Function meter units.




If you click on the arrow to the right of the Function meter reading field, a list of measurement unit choices will drop down. The choices available on the list vary depending upon the current function.

Changing a unit of measurement will not change the measurement, only the expression of the value.

For an explanation of the units of measurement used in the 2700 series and the references for the relative units, go to Appendix A, **Units of Measurement**.

Function Meter Ranging

Figure 110. Function meter ranging.



Like the Level meters, the Function meter has an amplitude ranging control, which is located lower on the Analog Analyzer panel beneath the Function meter reading field. See page 129 for a discussion of fixed and automatic ranging.

Function Meter Channel Selection


See Figure 108.

The Function meter is a single-channel meter. You must select the channel that the Function meter will measure, using the **A** or **B Function Reading** option buttons just above the function meter display.

*NOTE: A command to select the **A** or **B** channel can be programmed into an AP Basic macro to provide automatic switching for multiple channel measurements using the Analog Analyzer Function meter. Similarly, the **Stereo Sweep** selection on the Sweep panel first runs a sweep first for the **A** channel, then switches the Function meter channel selection to **B** and runs the sweep again.*

Function Meter Measurement Functions

Figure 111. Analog Analyzer Function meter Measurement Functions.



The Function meter measurement function selections are:


- **Amplitude**
- **Bandpass**
- **Bandreject**
- **THD+N Ampl**
- **THD+N Ratio**
- **SMPTE/DIN (IMD)**
- **CCIF (IMD)**
- **DIM (IMD)**
- **Wow and Flutter**
- **2-Ch. Ratio**
- **Crosstalk**
- **DFD (IMD)**

The **IMD** functions require the installation of the S2-IMD hardware option. The **Wow and Flutter** function requires the installation of the S2-W&F hardware option.

Some of the functions disable some or all of the selectable detectors, reading rates and filters for operation; these conditions are noted below in the detailed discussions of each function.

Amplitude

Figure 112. Analog Analyzer Function meter, **Amplitude** function.



The **Amplitude** function measurements are similar to the Level meter measurements, with the addition of selectable detectors and filtering. In certain configurations an **Amplitude** function reading will be identical to the Level meter reading for that channel.

Amplitude measurements can differ from Level meter measurements for several reasons:


- **Amplitude** measurements are affected by the highpass, lowpass, and weighting filter selections made in the BW and Fltr fields, while Level meter readings are always unfiltered.
- **Amplitude** function measurements may be made using one of several of detectors; the Level meters use only a true rms detector.
- **Amplitude** function measurements as always ac coupled to the input signal; Level meter measurements can also be dc coupled.

Since the Level meters have no equalization or filtering available, you must use the **Amplitude** function for weighted or band-limited noise measurements.

In the **Amplitude** function, detector, reading rate and high-pass, low-pass, weighting and option filter selection are enabled.

Bandpass

Figure 113. Analog Analyzer Function meter, **Bandpass** function.




The **Bandpass** function is a selective voltmeter (a function sometimes called a *wave analyzer*). The selected channel is passed through a four-pole 1/3-octave tunable bandpass filter before its amplitude is measured, to accomplish a frequency-selective amplitude measurement. The bandpass filter center frequency can be set in the range between 10 Hz and approximately 204 kHz. The center frequency may be fixed, or may track one of several parameters; see **BP/BR Filter Tuning** on page 149.

In the **Bandpass** function, detector, reading rate and high-pass and low-pass filter selection are enabled. Weighting and option filter selection is disabled.

Bandreject

Figure 114. Analog Analyzer Function meter, **Bandreject** function.




In the **Bandreject** function, the selected channel is passed through a tunable bandreject (notch) filter before its amplitude is measured. The bandreject filter center frequency can be set in the range between 10 Hz to approximately 204 kHz. The center frequency may be fixed, or may track one of several parameters; see **BP/BR Filter Tuning** on page 149

In the **Bandreject** function, detector, reading rate and high-pass, low-pass, weighting and option filter selection are enabled.

THD+N Ampl

Figure 115. Analog Analyzer Function meter, **THD+N Ampl** function.



In the **THD+N Ampl** (amplitude) function, the selected channel signal is passed through a tunable bandreject (notch) filter in order to reject the fundamental component of an applied single sine wave test signal before the amplitude of the remaining distortion and noise components is measured and displayed. The filter is continuously adjusted for maximum rejection of the highest-amplitude frequency component of the signal.

The bandreject filter center frequency can be set in the range between 10 Hz and approximately 204 kHz. The center frequency may be fixed, or may track one of several parameters; see **BP/BR Filter Tuning** on page 149.


The **THD+N Ampl** function expresses the amplitude of the distortion products and noise in absolute units, independent of the amplitude of the fundamental signal. Although the next function, **THD+N Ratio**, is used much more commonly, **THD+N Ampl** is particularly useful when performing amplitude sweeps of audio devices, since it helps make clear that the noise component is at a constant amplitude and is unrelated to the signal amplitude.

When using the **THD+N Ampl** function the list of units and their references for both analog and digital signals is the same as described above in the **Level Meter Units** topic on page 128.

In the **THD+N Ampl** function, detector, reading rate and high-pass, low-pass, weighting and option filter selection are enabled.

THD+N Ratio

Figure 116. Analog Analyzer Function meter, **THD+N Ratio** function.



In the **THD+N Ratio** function, the selected channel signal is filtered in the same way as the **THD+N Ampl** function, above. The difference is in the expression of the result.

The **THD+N Ratio** function expresses the sum of the distortion products and noise amplitudes relative to the amplitude of the unfiltered signal (as measured by the **Level** meter for the selected channel); in other words, the result is a THD+N-to-signal ratio. Units of **%** and **dB** (decibels below the fundamental) are ordinarily used with the **THD+N Ratio** function.


THD+N Ratio is the most common way to express distortion. However, in an amplitude sweep **THD+N Ratio** appears to show increasing distortion and noise with decreasing signal amplitude because the distortion and noise is stated as a ratio to the decreasing signal. The **THD+N Ampl** function may be more useful for amplitude sweeps.

Results using the **THD+N Ratio** function may be expressed in **%**, **dB**, or **X/Y** units.

In the **THD+N Ratio** function, detector, reading rate and high-pass, low-pass, weighting and option filter selection are enabled.

IMD Measurements: SMPTE/DIN

Figure 117. Analog Analyzer Function meter, **SMPTE/DIN** function.



The **S2-IMD** “IMD” option must be installed for Analog Analyzer IMD functions to operate.

SMPTE/DIN (intermodulation distortion to the SMPTE or DIN standards) measures the amplitude of the IMD residuals created below the high-fre-

quency component of a two-tone test signal. These are recovered by first passing the signal through a 2 kHz high-pass filter and then demodulating, filtering and measuring the amplitude of the sidebands.

Appropriate two-tone test signals can be generated by the Analog or the Digital Generator; for measurement using the IMD option, the lower-frequency sine wave must be in the range of 40 Hz to 250 Hz, and the higher-frequency sine wave must be in the range of 2 kHz to 100 kHz.

The combined amplitude of the recovered lower sidebands is stated as a ratio to the amplitude of the high-frequency tone, with units of % or dB being the most common.


In **SMPTE/DIN** and all IMD functions, detector, reading rate and weighting and option filter selection are enabled. High-pass and Low-pass filter selection are disabled, since selection of these filters could cause erroneous readings.

IMD Measurements: CCIF and DFD

The **S2-IMD** “IMD” option must be installed for Analog Analyzer IMD functions to operate. In **CCIF**, **DFD** and all IMD functions, detector, reading rate and weighting and option filter selection are enabled. High-pass and Low-pass filter selection are disabled, since selection of these filters could cause erroneous readings.

CCIF

Figure 118. Analog Analyzer Function meter, **CCIF** function.



The Analog Analyzer **CCIF** function measures intermodulation distortion to the CCIF standard. A specific CCIF test signal comprised of two tones, F1 and F2, is applied to the DUT, and **CCIF** measures the amplitude of the difference product ($F2 - F1$). This is recovered by first passing the signal through a 30 Hz high-pass filter and a 2.45 kHz low-pass filter, then applying a narrow bandpass filter that is automatically tuned to the difference frequency product.


Appropriate two-tone test signals can be generated by the Analog or the Digital Generator; the two sine waves are equal in amplitude and are described as being spaced around a center frequency value. The spacing between the sine waves must be in the range of 80 Hz to 1 kHz; the center frequency value must

be in the range of 3 kHz to 100 kHz. For detailed information on generator settings to create these stimulus waveforms, see page 82 for the Analog Generator and page 109 for the Digital Generator.

The amplitude of the difference frequency is stated as a ratio to the amplitude of the test signal components, with units of % or dB being the most common.

DFD


Figure 119. Analog Analyzer Function meter, DFD function.



The **DFD** (difference frequency distortion) IMD measurement is made in the same way as a CCIF measurement, differing only by amplitude calibration. DFD results are expressed as values 6.02 dB lower than CCIF.

IMD Measurements: DIM (TIM)

Figure 120. Analog Analyzer Function meter, DIM function.



The **S2-IMD** “IMD” option must be installed for Analog Analyzer IMD functions to operate.

The DIM (dynamic intermodulation) measurement is sometimes called TIM (transient intermodulation).


The Analog Analyzer **DIM** function measures intermodulation distortion to the IEC-268-3 standard. A specific DIM test signal is applied to the DUT, and **DIM** measures the amplitude of the fifth- and sixth-order IMD products. These are recovered by first passing the signal through a 400 Hz high-pass filter and a 2.45 kHz low-pass filter. The test signal is designed so that the fifth- and sixth-order products fall into the spectrum below 2.45 kHz, and only these products pass the filter for measurement.

An appropriate test signal can be generated by the Analog or the Digital Generator; the signal combines a square wave of approximately 3 kHz with a sine wave of approximately 15 kHz. For detailed information on generator settings to create these stimulus waveforms, see page 83 for the Analog Generator and page 110 for the Digital Generator.

In **DIM** and all IMD functions, detector, reading rate and weighting and option filter selection are enabled. High-pass and Low-pass filter selection are disabled, since selection of these filters could cause erroneous readings.

Wow and Flutter Measurements

Figure 121. Analog Analyzer Function meter, **Wow and Flutter** function.



The **S2-W&F** option must be installed for Analog Analyzer Wow and Flutter functions to operate.

The **W&F** function measures wow and flutter to four standards: IEC, DIN, NAB and JIS, and also provides a capability to measure high-band scrape flutter. Wow and flutter is generally measured as the DUT plays a stimulus tone from a test disc or test tape.

For low-band measurements to the standards, a stimulus tone of about 3 kHz (depending on the standard) is played from the DUT, and **W&F** measures the weighted amplitude of the frequency modulation products in the signal. The frequency of the stimulus tone, the weighting, the detector type and the dynamic response of the detector ("ballistics") vary among the four standards.

For high-band measurements, a playback stimulus tone of 12.5 kHz is recommended, although other high-frequency tones can be used.

The high-pass and low-pass filter selections are disabled for wow and flutter measurements. The Detector selection field offers only the detector types specified in the standards, and the Weighting Filter field offers only the special weighting filters appropriate for wow and flutter testing.

Wow and Flutter

Wow and flutter is the undesirable frequency modulation of an audio signal due to instantaneous speed variations caused by mechanical imperfections in a recording and playback mechanism such as a tape recorder or turntable. “Wow” refers to low-frequency modulation of the signal, heard as cyclic pitch variations or “wowing.” “Flutter” refers to higher-frequency modulations, audible as either very fast pitch variations or, with “scrape flutter,” as intermodulation distortion.

Wow and flutter measurements are usually made with a test tape or disk that has a pre-recorded tone containing very little residual frequency modulation. The reproduced tone is bandpass-filtered to limit potential wideband interference and is applied to an FM discriminator. The output of the discriminator is an ac signal with amplitude proportional to the instantaneous frequency deviation of the test tone.

For most measurements this signal is passed, before detection, through a selectable weighting filter with a peak response centered at about 4 Hz. The purpose of the weighting filter is to produce numerical results that parallel the human ear’s sensitivity to different frequency components of wow and flutter. Unweighted measurements simply bypass this weighting filter.

Ranging Considerations

Tape dropouts or other signal interruptions can cause autoranging to search for a new range. Since the stimulus signal is expected to be of a constant amplitude, all autoranging should be disabled for wow and flutter testing.

FM discriminator

The S2-W&F option includes a frequency modulation (FM) discriminator to extract the modulation products for measurement. The instantaneous output voltage of the FM discriminator is proportional to the instantaneous peak frequency deviation of the test signal. The input to the discriminator is filtered by one of two bandpass filters, discussed below.

Weighting and Bandpass Filters

One of two bandpass filters is inserted before the FM discriminator, and one (or none) of several weighting filters can be inserted between the discriminator and the measurement detector. These filters are selected from list in the Fltr field, as shown in Figure 121.

■ Weighted

This is the setting for “normal” (rotationally-caused) wow and flutter. The signal is passed through a 2 kHz–4 kHz bandpass filter that accommodates the standard 3.0 kHz and 3.15 kHz test signals, before the FM

discriminator, and through a weighting filter with a peak response at about 4 Hz after the discriminator and before the detector.

- **Unweighted**

The signal is passed through a 2 kHz–4 kHz bandpass filter that accommodates the standard 3.0 kHz and 3.15 kHz test signals, before the FM discriminator. No weighting filter is used.

- **Weighted-High Band**

The signal is passed through a 0.5 Hz–200 Hz bandpass filter before the FM discriminator, and through a weighting filter with a peak response at about 4 Hz after the discriminator and before the detector.

- **UnWeighted-High Band**

The signal is passed through a 0.5 Hz–200 Hz bandpass filter before the FM discriminator. No weighting filter is used.

- **Wide-High Band**

The signal is passed through a 0.5 Hz–5 kHz bandpass filter before the FM discriminator. No weighting filter is used.

- **Scrape-High Band**

The signal is passed through a 200 Hz–5 kHz bandpass filter before the FM discriminator. No weighting filter is used.

Detector Selection

After the bandpass filter, FM discriminator and optional weighting filter, the wow and flutter signal is applied to the selected W&F detector and the measured value is displayed on the Analog Analyzer panel. The detectors are selected by the standards recommending them.

- **IEC/DIN**

A quasi-peak detector is used in IEC (DIN) specified W&F measurements. The recommended stimulus tone for these standards is 3.15 kHz.

- **NAB**

An average-responding (rms calibrated) detector is used in NAB specified W&F measurements. The recommended stimulus tone for these standards is 3.0 kHz.

- **JIS**

An average-responding detector is used in JIS specified W&F measurements. This detector has a longer time-constant than the detector used for NAB measurements, and is referred to as having an “effective” response in the standard. The recommended stimulus tone for these standards is 3.0 kHz.

*NOTE: FFT analysis using the Spectrum Analyzer (see Chapter 12) is another powerful technique for observing and measuring wow and flutter components. Spectrum analysis can be performed directly on the 3 kHz or 3.15 kHz tone; or, if you have S2-W&F installed and selected, you can apply FFT analysis to the FM discriminator output by selecting **Anlr Rdg Ratio** as Source on the Spectrum Analyzer panel.*

2-Ch. Ratio

Figure 122. Analog Analyzer Function meter, **2-Ch. Ratio** function.



The **2-Ch Ratio** function displays the ratio of the Function meter reading for the selected channel to the Level meter reading for the opposite channel.


NOTE: The amplitude for the Function meter reading will be affected by detector and filter settings, but the Level meter readings will not.

2-Ch Ratio may be expressed in %, dB, or X/Y units. The **2-Ch Ratio** function is useful while balancing stereo channels, for example; or for measuring gain or loss in a DUT by connecting the Analog Analyzer A channel across the DUT input and the B channel across the DUT output.

In the **2-Ch Ratio** function, detector, reading rate and high-pass, low-pass and option filter selections are enabled.

Crosstalk

Figure 123. Analog Analyzer Function meter, **Crosstalk** function.



In the **Crosstalk** function, detector, reading rate and high-pass, low-pass and option filter selections are enabled.

The **Crosstalk** function measures the leakage, or crosstalk, of a sine wave from one channel to the other. A typical crosstalk test uses a stereo stimulus with only one channel driven, or with each channel driven with a sine wave of different frequency.

The Analog Analyzer **Crosstalk** function displays the ratio of the bandreject-filtered Function meter reading for the selected channel to the broadband Level meter reading for the opposite channel. The Analog Analyzer bandpass filter is steered to the frequency in the opposite channel. See **BP/BR Filter Tuning** on page 149.

The amplitude measured at this frequency is the absolute crosstalk value. The percentage of the opposite channel's signal amplitude (as measured by the **Level** meter) represented by the absolute crosstalk value of the channel under consideration is displayed in the Function meter.

For example, consider a stimulus with a 1 kHz sine wave on Channel A and a 2 kHz sine wave on Channel B. In the Analog Analyzer, the selected (Channel A) bandpass filter is steered to 2 kHz, a measurement is made, and the percentage of the Channel B Level meter reading this crosstalk measurement represents is computed and displayed in the Function meter display.


Crosstalk is a ratio, expressed as:

$$\text{Crosstalk from B to A} = \frac{\text{Level of } F_1 \text{ in A}}{\text{Level of } F_1 \text{ in B}}$$

Crosstalk may be expressed in %, **dB**, or **X/Y** units. The **BW** (high-pass and low-pass) and **Fltr** (weighting) filter selections are not available for the **Crosstalk** function.

Detector Type

Figure 124. Analog Analyzer Detector type.



Five different detector responses are available for the Function meter: **RMS**, **Average**, **Peak**, **Q-Peak** and **S-Peak**. The Level meters are always rms responding.

Detectors

A detector converts the analog audio signal to a varying dc voltage that is a function of the amplitude of the analog audio signal. The dc voltage is converted to a numerical or graphical display representing the amplitude function.

True rms detectors have a dc voltage output proportional to the rms (root-mean-square) value of the audio signal input, which is proportional to the heating value (power, assuming constant load impedance) of the signal. For most applications, the true rms detector is the best way to compare the amplitude of non-sinusoidal signals, especially those with significant amounts of noise.

Average-responding rms calibrated detectors produce an output dc voltage proportional to the average value of the absolute value of the input signal. For many years average detectors were much less expensive to implement and much more robust than true rms detectors, and many modern analyzers still include average-responding detectors for purposes of correlating to measurements made with older instruments, or to comply with older specifications such as Dolby CCIR-ARM or the SINAD method of specifying communications receiver sensitivity. Average responding detectors are normally calibrated with a sinusoidal input signal and are adjusted to read the same as a true rms signal on that waveform. They will provide results identical to an rms detector when measuring a single sine wave, but will differ from an rms detector for all complex waveforms.

A peak detector provides a dc voltage proportional to the peak voltage of the input signal. Practical peak detectors have some minimum signal repetition period at which they meet specified accuracy, with decay of the previous impulse detracting from accuracy beyond that value.

A Quasi-peak detector is the specific modification of a true peak detector required to meet the specifications of CCIR Recommendation 468. CCIR 468 quasi-peak detectors are normally used in conjunction with the CCIR 468 weighting filter.

The S-Peak (sine wave scaled peak) uses the peak detector and multiplies the result by 0.707, displaying the amplitude of a sine wave that would have the same peak value.


- **RMS** provides true rms detection with a measurement time approximately the reciprocal of the selected reading rate. See **Detector Reading Rate**, below.
- **Average** provides average detection that is rms-calibrated for sine waves.
- **Peak** provides a good approximation of peak signal levels for most repetitive waveforms.

- **Q-Peak** (quasi-peak) provides a response conforming to the IEC468 specification for noise measurements, and is normally used with the CCIR (IEC468) weighting filter.
- **S-Peak** (sine-scaled peak) provides peak-reading detection, with the results scaled to give the rms amplitude of a sine wave with the same peak value. This selection can be useful in tone burst measurements.

See the **Detectors** sidebar on page 145.

Detector Reading Rate

Figure 125. Analog Analyzer
Detector reading rate..



The left-hand field following the “**Det**” label controls the detector reading rate, the rate at which all of the Analog Analyzer meters updates. This is also called *integration time*. The selections are **Auto**, **4/sec**, **8/sec**, **16/sec**, **32/sec**, **64/sec**, **128/sec**, **Auto-Fast** and **Auto-Precise**.

Normally, **Auto** will be the best choice, with the most important exception being noise measurements, discussed below. The **Auto** algorithm takes into account the both signal frequency being measured and the use of the bandpass filter, and then selects the fastest reading rate that will deliver the specified accuracy under the conditions.

In some cases, it may be desirable to force a faster reading rate to obtain greater testing speed at some cost in accuracy; in others, to force a slower rate to obtain greater resolution at a cost in speed. **Auto-Fast** makes reading rate selections more aggressively than the normal **Auto** rate selection, favoring speed over precision. **Auto-Precise** makes reading rate selections more conservatively than **Auto**, favoring precision over speed.

For noise measurements, the **4/sec** selection is recommended to provide integration of noise over a longer period. You might also choose **4/sec** when measuring periodic waveforms for the best accuracy and repeatability at very low frequencies.

The **8/sec**, **16/sec**, **32/sec**, **64/sec**, and **128/sec** choices provide progressively faster measurements. If you are watching a bargraph display while making ad-

justments to a DUT, for example, the faster rates better approximate real-time readings and will give you better feedback.

However, low-frequency measurement accuracy is reduced at faster rates. Each step faster in reading rate raises the low-frequency limit to accurate measurement. Faster reading rates are also less tolerant of noise in the signal.

The Bandwidth and Filter Fields

Below the detector fields are three fields which allow selection of various filter options for the Function meter. The first two are labeled “**BW**” for bandwidth, and consist of highpass and lowpass filter options. The third field is labeled “**Filtr**” and provides access to filters installed in any of the seven option filter slots. Graphs of the common filter curves are shown in the **Specifications** chapter in *Getting Started with Your 2700 Series Instrument*.

BW: The Highpass Filter

Figure 126. Analog Analyzer Function meter Highpass filter.

Det:	Auto	RMS	BP/BR Fitr Freq
BW:	< 10 Hz	> 500 kHz	Sweep Track
Fitr:	< 10 Hz		
Ref:	100 Hz		
	400 Hz		
dBr A:	387.3 mV	Watts:	8.000 Ohms
dBr B:	387.3 mV	dBm:	600.0 Ohms
		Freq:	1.00000 kHz


There are two **BW** (bandwidth) filter control fields. The left field is the highpass field.

The highpass filter is effective in all Function meter functions except **W&F** and the IMD functions. This field allows you to select essentially flat response at low frequencies (the **<10 Hz** selection) or specific highpass filters at **22 Hz**, **100 Hz** or **400 Hz**. A highpass filter, when selected, is connected in the measurement paths of the Function meter, but does not affect the **Level** or **Frequency** meters.

The 22 Hz, 100 Hz and 400 Hz high-pass filters are three-pole (18 dB/octave) designs.

BW: The Lowpass Filter

Figure 127. Analog Analyzer Function meter Lowpass filter.



The right **BW** (bandwidth) filter control field is the lowpass field.


The lowpass filter is effective in all Function meter functions except **W&F** and the IMD functions. This field allows you to select essentially flat response at high frequencies (the **>500 kHz** selection) or specific lowpass filters at **80 kHz**, **30 kHz**, or **22 kHz**. Any lowpass filter, when selected, is connected in the measurement paths of the Function meter but does not affect the Level or Frequency meters.

The 80 kHz and 30 kHz lowpass filters are three-pole (18 dB/octave) designs; the 22 kHz lowpass filter is a five-pole (30 dB/octave) design.

Selection of the 22 kHz lowpass filter when making THD+N measurements is particularly important in measuring converters with large amounts of noise shaping.

The “Filtr” Field

Figure 128. Analog Analyzer Function meter “Filtr” field.



The **Filtr** provides access to filters installed in any of the seven option filter slots in the 2700 series instrument. Each filter manufactured by Audio Precision carries an identifying filter number that is read by the control software (if Auto Detect is checked on the **Configure Filters** tab of the **Utilities > Configuration** menu) and displayed here. You can select any one of the installed filters by clicking on the identifying line in this list.


You can also specify a slot number rather than a filter ID to use an unidentified (custom user) filter installed in a particular slot.

See **Configure Filters** on page 521.

This field is not available for the **Bandpass** or **Crosstalk** functions.

Bandpass/Bandreject Filter Tuning

Figure 129. Analog Analyzer
Function meter Bandpass/
Bandreject filter tuning.



The Function meter includes a four-pole bandpass or bandreject filter tunable from 10 Hz to 204 kHz. The filter is not used in the Amplitude, 2-Ch. Ratio or W&F functions. In the IMD function the filter is used to improve measurement performance and is not independently steerable.

The bandpass or peaking form of the filter is used in two Analog Analyzer functions:

- **Crosstalk** and
- **Bandpass**.

The bandreject or notch form of the filter is used in three other Analog Analyzer functions:


- **Bandreject**
- **THD+N Ratio** and
- **THD+N Ampl.**

Either the bandpass or bandreject form of the filter may be fixed in frequency, or may be “steered” to automatically track a parameter during a sweep test. You can select the source of frequency steering information in the **BP/BR Filter Freq** field, located in the lower-right area of the Analog Analyzer panel. The selections are:

- **Counter Tuned**
When **Counter Tuned** is selected, the frequency measured by the Freq. meter becomes the filter steering source. Use this method when making **THD+N** or **Crosstalk** measurements from an external signal, such as the playback of a compact disc or the reception of a signal from a distant source.
- **Sweep Track**
When **Sweep Track** is selected, the filter tracks the frequency of which-ever generator is selected in the **Source 1** or **Source 2** fields of the Sweep panel.
- **AGen Track**
When **AGen Track** is selected, the bandpass/bandreject filter tracks the frequency of the Analog Generator. This mode is useful for testing ADCs driven from the 2700 series analog output.
- **DGen Track**
When **DGen Track** is selected, the filter will automatically track the frequency of the Digital Generator. This mode is normally used when sweeping input-to-output through a digital device with the stimulus tone coming from the 2700 series Digital Generator.
- **Fixed**
When **Fixed** is selected, the field immediately below (which is grayed out in other modes) becomes active. The filter will be set to the frequency entered in this field.
It is also possible to vary the filter frequency in this mode as part of a sweep test. Although this is similar to the **Sweep Track** choice above, in this case the filter can be swept independent of generator frequency.
See Chapter 18 for more information on sweeps.

References

Figure 130. Analog Analyzer References.



The bottom area of the Analog Analyzer panel includes five fields in which you can enter reference values. Each reference serves as a basis for its corresponding unit of measurement on the panel.

- **dBr A and dBr B**

The values entered in **dBr A** and **dBr B** serve as the references for the **dBr A** and **dBr B** unit choices available for the Analog Analyzer Level and Function meters.

- **Freq**

The frequency (**Freq**) value serves as the reference for the relative frequency units (**octaves, decades, % Hz**, etc.) for the Analog Analyzer frequency meters.

- **Watts**

The watt is a unit of power, not voltage. Since power calculations are dependent on the circuit impedance, the load impedance encountered in your test must be entered as a reference for accurate display of watts (W) measurements. $8\ \Omega$ is the default impedance for the **Watts** reference.

- **dBm**

The dBm, like the watt, is a unit of power (decibels relative to 1 mW). Since power calculations are dependent on the circuit impedance, the load impedance encountered in your test must be entered as a reference for accurate display of dBm measurements. $600\ \Omega$ is the default impedance for the **dBm** reference.

*NOTE: dBm is rarely the correct choice of units for audio measurements. dBm units are often mistakenly chosen when dBu units should be used. See the sidebar **dBm versus dBu** on page 533.*

Chapter 9

The Digital I/O Panel

Overview

This chapter discusses the Digital I/O panel (also called the Digital Input/Output panel or simply the DIO panel). The DIO panel serves as the hub for all digital signal input and output configuration. Additionally, a number of interface signal parameters can be monitored or changed on the DIO panel and on the linked Status Bits panel.




Figure 131. The Digital Input/Output (DIO) panel.

See Appendix B for an explanation of the characteristics of digital audio signals, including the serial digital interface signal and the embedded digital audio it carries. The digital input and output hardware connections are discussed in Chapter 4.

On the left of the DIO panel is the **Output** section, which includes configuration settings and a number of output signal impairment selections. The rest of the panel is the **Input** section, which includes input configuration and monitoring. A button near the bottom of the panel accesses the Status Bits panel.

The DIO Output Section

Figure 132. The DIO Output Section.


The screenshot shows the 'Output' section of the DIO panel. It contains several configuration options: 'Connector' set to 'XLR', 'SR Range' set to 'Auto', 'Sample Rate (SR)' set to '192.000 kHz', 'SSR' set to '96.0000 kHz', 'Voltage' set to '5.000 Vpp', 'Audio Format' set to 'Linear' with a '24' bit depth, 'PreEmphasis' set to 'Off', and 'Scale Freq. by' set to 'Output Rate (SR)'. Below these are checkboxes for 'Invert', 'Parity Error', 'Cable Simulation', and 'Send Invalid'. There are also fields for 'Rise/Fall Time' and 'Interfering Noise' with 'FIX' and 'OFF' buttons. The 'Common Mode Sine' section has 'Amplitude' and 'Frequency' fields with an 'OFF' button. The 'Jitter Generation' section has a dropdown set to 'Off', an 'EQ Curve...' button, and 'Amplitude' and 'Frequency' fields.

The routing and configuration of the digital interface output signal are set in the **Output** section of the DIO panel. Some settings which modify the embedded audio, such as **μ-Law** and **PreEmphasis**, show up in this area of the panel as well.

The controls in the bottom half of the panel enable you to impair the digital output in several ways. An impaired digital interface signal can be useful in testing proper operation of interface signal receivers.

Connector

Figure 133. The DIO Output Connector Selections.



The first setting field is **Connector**. Select the serial digital interface output connector(s) and interface format from the list.

- **XLR**
This choice selects the balanced digital output. The signal voltage maximum is 5.08 Vpp, typical of the AES3 professional standard.
- **BNC**
This choice selects the unbalanced digital output. The signal voltage maximum is 2.54 Vpp, more than sufficient for the AES3id professional standard (nominally 1 Vpp) and the IEC 60958-3 consumer standard (nominally .5 Vpp). This output is electrically compatible with the SPDIF digital interface.
- **Optical**
This choice selects the Toslink® output, which carries the serial interface signal by optical modulation.
- **PSIA**
This choice selects the 50-pin PARALLEL OUTPUT port on the rear of the instrument, and also enables the PSIA Transmitter panel.
- **Parallel**
This choice selects the 50-pin PARALLEL OUTPUT port on the rear of the instrument, without enabling the PSIA Transmitter panel.
- **Dual XLR**
The two balanced digital outputs provided (**I** and **II**) can be used in conjunction with each other, as explained in the **Dual Connector Mode** sidebar below. In this mode the **Sample rate (SR)** field sets the overall data rate across both outputs, so that the rate per output (also called the *cable rate*) is $SR / 2$.
- **Dual BNC**
Same operation as **Dual XLR** for the unbalanced output.


Dual Connector Mode

Dual Connector Mode is provided only for compatibility with some early high sample rate audio devices.

*In a typical single-cable AES3 interconnection, the alternate data subframes normally carry the left and right audio channels. In the **Dual XLR** and **Dual BNC** modes, each frame of the AES3 interface signal on each connector or cable carries two words of a single channel of audio, the first word in subframe A and the second in subframe B. Two connections (**I** and **II**) are required to carry two-channel audio. Normally, Connector I carries the “A” or left audio channel and Connector II carries the “B” or right audio channel.*

SR Range

Figure 134. The DIO SR Range selections.



Also see Figure 135.

The SR Range selection determines the relationship between SR and SSR.

The SR Range choices are:

- **Auto**

In **Auto** mode, SSR is determined by SR.

For sample rates from 8 kHz to 108 kHz,
 $SSR = SR$.

For sample rates above 108 kHz,
 $SSR \times 2 = SR$.

The SSR multiplier of 1 or 2 is automatically switched as SR is changed or swept across 108 kHz.

- **8k-108k**

In **8k-108k** mode, SR is always equal to SSR. Rates are limited to the range between 8 kHz and 108 kHz.

- **27k-216k**

In **27k-216k** mode, SR is always twice SSR. SR rates are limited to the range between 27 kHz and 216 kHz, and in this mode SSR rates are limited to the range between 13.5 kHz and 108 kHz.

Relationships of SR and SSR		
SR Range Control setting	Value set or swept	Relationship
Auto	8 kHz–108 kHz	SR=SSR
	108 kHz–216 kHz	SR=2xSSR
8k-108k [locked]	8 kHz–108 kHz	SR=SSR
27k-216k [locked]	27 kHz–216 kHz	SR=2xSSR

Sample Rate (SR)

Figure 135. The DIO **Sample rate (SR)**, **SR Range** and **SSR** fields.

The screenshot shows three fields in a light gray box. The first field is labeled 'SR Range:' and has a dropdown menu set to 'Auto'. The second field is labeled 'Sample Rate (SR):' and has a dropdown menu set to '192.000 kHz'. The third field is labeled 'SSR:' and displays the value '96.0000 kHz'.

The **Sample rate (SR)** field (labeled **Rate** on the small form of the DIO panel) allows you to set a value for the sample rate (or SR). The default SR is 48 kHz. Click on the field and enter a new rate from the keyboard. The **SR** may be set in the range between 8 kHz to 216 kHz. A drop-down list allows you to specify the units of measurement for the SR.

SR is also a selection for frequency scaling in the **Scale Freq. by** lists for the DIO output and input settings. On these lists SR is called **Output Rate (SR)**.

The Sample Rate (SR) may be swept as part of a test by selecting **Dio** as the browser instrument and **Sample Rate at Source 1** or **Source 2** on the Sweep panel.

NOTE: When using the Dolby Digital Generator the Sample Rate is limited to the range of 30 kHz to 50 kHz.

System Sample Rate (SSR)

See Figures 135 and 134 for reference.

The System Sample Rate (SSR) is shown in the read-only SSR field. SSR is an internal clock rate used as a reference in sample rate generation.

SSR is available on the Digital Analyzer panel as a sample rate choice for the input ADCs. **SSR** also shows up on the Analog Generator panel as a sample rate selection for the DACs used in arbitrary waveform conversion, and as the **Pass Thru** sample rate.

When using the Dual Connector modes, ADCs or DACs using **SSR** as a sample rate selection are clocked at the connector (cable) rate, which is SSR. Frequency scaling, however, is always by “overall” dual connector rate, which is SR.

SR and SSR Applications		
	SR	SSR
Output Sample Rate	X	
AES/EBU REFERENCE OUTPUT jack	X	
TRANSMIT FRAME SYNC jack	X	
DIO Output Scale Freq. by	X	
DIO Input Scale Freq. by	X	
Dual Connector Mode Sample Rate (Overall Rate)	X	
Dual Connector Mode Cable Rate		X
Digital Analyzer HiRes A/D and HiBW A/D ADCs		X
Analog Generator Arbitrary Waveform DACs, Pass Thru		X

The SSR may be swept as part of a test by selecting **Dio** as the browser instrument and **SSR** at **Source 1** or **Source 2** on the Sweep panel.

SR, SSR and OSR

In APWIN, the control software for earlier Audio Precision instruments including System Two Cascade and Cascade Plus, most digital sample rates were referenced to OSR, the Output Sample Rate.

In AP2700, the functions of OSR have been split into two new sample rate references. Sample Rate (SR) is the digital output sample rate and can be set by the user to any valid sample rate; SSR is an internal reference that is either equal to SR or is one-half the value of SR, depending upon user settings.

Whereas in APWIN OSR was both the output rate and an optional reference for the ADC and DAC sample rates, in AP2700 SR is the output rate and SSR is the optional ADC and DAC sample rate reference.

Voltage

The **Voltage** field displays the output amplitude of the serial digital interface signal. Serial digital interface signal voltage is measured in volts, peak-to-

peak (Vpp). This field is not available when **Optical**, **Parallel** or **PSIA** are selected as the digital output connector.


The signal voltage maximum for the **XLR** connector setting is 5.10 Vpp, typical of the AES3 professional standard; voltage maximum for the **BNC** connector setting is 2.54 Vpp, more than sufficient for the AES3id professional standard (nominally 1V pp) and the IEC 60958-3 consumer standard (nominally .5 V pp).

The voltage of the interface signal can be varied to simulate cable attenuation and test the performance of an interface receiver. Type in the **Voltage** field to enter a new interface voltage. The output voltage can also be swept as part of a test by selecting **Dio** as the browser instrument and **Output Voltage at Source 1** or **Source 2** on the Sweep panel.

The XLR and BNC digital outputs are calibrated with the assumption that the signal is terminated in the proper impedance (110 Ω for the balanced output; 75 Ω for the unbalanced). If the signal isn't properly terminated the actual output voltage will differ from the voltage set on the DIO panel.

Output Audio Format

Figure 136. The DIO Output Audio Format selections.



The **Audio Format** sets the output interface audio format. Selections are

- **Linear**
- **μ-Law**
- **A-Law**
- **IEC 61937**

The output audio format is independent of the input audio format.

Linear

Select **Linear** to set the output interface audio format to linear pulse code modulation (PCM). When either **Linear** or **IEC 61937** is selected, you can set the output resolution (word length) to any integer value from 8 bits to 24 bits by typing the value in the field to the right and pressing the **Enter** key.

Internal to the 2700 series instrument, the digital signal is generated at a word length greater than 24 bits. When a word length is selected in the **Linear** resolution field, dither is added at the appropriate amplitude for that length and

the audio signal is truncated to the specified value before insertion into the interface signal (for PCM) or before it is applied to the IEC 61937 encoding.

The output resolution is independent of the input resolution.

The output resolution may be swept as part of a test by selecting **Dio** as the browser instrument and **Output Resolution** at **Source 1** or **Source 2** on the Sweep panel.

μ-Law and A-law Compression

See Figure 136 for reference.

The selection of **μ-Law** or **A-law** compression overrides the word length selected in the **Audio Format** resolution field, which is grayed out under these conditions. Instead, one of two compression techniques is applied to the digital audio signal.

Choose **μ-Law** or **A-law** to enable the compression, or **Linear** to return to uncompressed PCM.

*NOTE: The Digital Generator outputs a 14-bit or 13-bit audio signal when the **Audio Format** is set to **μ-Law** or **A-Law**. Dither, if enabled, is properly scaled to these word lengths.*

See the sidebar on **μ-Law** and **A-law** below for more information on these companding techniques.

μ-Law and A-Law

The International Telecommunication Union (ITU) specifies in its standard G.711 two similar approaches for reducing the bit rate in digital voice telephony. Called μ-Law and A-Law, these techniques have been widely used in digital telecommunications for a number of years.

μ-Law and A-Law are known as companders, converting 14-bit linear PCM samples (μ-Law) or 13-bit linear PCM samples (A-Law) to an 8-bit pseudo floating-point representation via compression at the encoder and expansion at the decoder.


IEC 61937 (Dolby Digital)

The IEC 61937 output Audio Format selection enables the IEC 61937 / Dolby Digital panel (if your instrument has the OPT-2711 Dolby Digital Generator option installed and activated) and routes the encoded bitstream to the digital output. The IEC 61937 / Dolby Digital panel gives you control over the Dolby Digital encoding and metadata parameters and access to general IEC 61937 bitstream controls.

NOTE: The output Audio Format control on the DIO panel is the same control as Audio Format on the IEC 61937 panel. Output Audio Format settings made on either panel are equivalent.

Preemphasis

Figure 137. The DIO Preemphasis selections.



The embedded audio of the digital output signal may be transmitted without preemphasis, as is normal, or preemphasized according to one of two different functions. In practice, preemphasis is rarely used.


The consumer format has only one defined preemphasis condition, the 50/15 µs Compact Disc preemphasis. The professional format adds the CCITT J17 preemphasis.

Either preemphasis function may be selected at normal gain, or with a head-room allowance of –12 dB (50/15 µs) or –20 dB (J17) if there is a concern that high-level test signals would exceed clipping (digital full scale) after preemphasis has been applied.

Matching deemphasis and gain selections are available in the **Deemphasis** field of the **Input** section of the DIO panel to provide overall unity gain and flat response.

Scale Freq. by

Figure 138. The DIO Scale Freq. by selections.



For a digital audio signal of a given sample rate, the embedded audio will be shifted in frequency when the digital signal is re-sampled or converted using a different sample rate. The audio frequency will change by the ratio of the two sample rates.

For example, a 1 kHz audio signal generated in DSP at a 48 kHz sample rate would be shifted to 666.67 Hz if converted at a 32 kHz sample rate.

The 2700 series offers the capability to scale the embedded frequency independent of the interface output or input sample rates.

In the output **Scale Freq. by** field you can select one of three sample rate choices as a reference by which to scale the embedded frequency of the digital output signal. The choices are:

- **Output Rate (SR)**, the default, selects Sample Rate (SR) as the scaling reference.
- **Meas Input Rate** selects Sample Rate (ISR), which is the rate measured at the serial digital input, as the scaling reference.
- **Meas Output Rate** selects the rate measured at pin 2 of the PARALLEL OUTPUT as the scaling reference when output Connector is set to **PSIA** or **Parallel**. Pin 2 is the “strobe” connection and reads the sample rate from the DUT in a parallel configuration. When an output connector other than **PSIA** or **Parallel** is selected, **Meas Output Rate** defaults to **Output Rate (SR)** for the scaling reference, providing the same functionality as the **Output Rate (SR)** selection.
- **DIO Rate Ref** sets the scaling reference rate to the value entered in the **Rate Ref** field on the DIO panel.

Output Impairments

A variety of impairments can be applied to the serial digital output signal to test a DUT’s ability to receive a less-than-perfect serial digital interface signal. Any of these impairments can be applied to the balanced and unbalanced digital outputs. Jitter is the only impairment that can be applied to the optical or parallel outputs.

The Output Impairment Checkboxes

Figure 139. The DIO Output Impairment Checkboxes.

☐ Invert	☐ Parity Error
☐ Cable Simulation	☐ Send Invalid

Invert

The polarity of the serial digital interface bitstream output can be inverted by checking the **Invert** checkbox. Properly-designed AES3 receivers should function correctly with either polarity of input bitstream.

Cable Simulation

Serial interface signals are degraded by transmission through long cables by attenuation and high-frequency loss due to cable reactance. Check the **Cable**

Simulation checkbox to switch a hardware filter into the path to the XLR or BNC digital output connectors, simulating the effect of a long cable (approximately 1,000 meters) to test the ability of a DUT to receive impaired serial interface signals.

This cable simulation is approximately the inverse of the hardware cable equalization function (**XLR w/EQ**, **BNC w/EQ**, etc.) selectable in the Digital Input **connector** field.

Cable simulation is not available at the optical or parallel outputs.

Time Slots 28–31

Four bits are sent at the end of each frame of AES3/IEC60958 data: the Validity bit (time slot 28), the User bit (slot 29), the Channel Status bit (30) and the Parity bit (31).

The states of the Validity bit and the Parity bit can be set in the Output section of the DIO panel.

User bits are neither set nor displayed in 2700 series instruments.

Status bits are set and displayed in the Status Bits panel, page 177.

See the Appendix B for more information about Status Bits and the AES3/IEC 60958 interface.

Changing the Parity bit

This bit will be either high or low to maintain even parity within the frame. Setting a parity error by checking the **Parity Error** checkbox will invert the state of the Parity bit (bit 31), giving each frame odd parity. The DUT should correctly recognize odd parity.

Parity

Every AES3 subframe is 32 bits in length. Depending on the data carried in the subframe, there will be either an odd or even number of bits in a particular state in the subframe.

As a means of error detection, AES3 subframes are defined to have even parity, that is, an even number of bits in the high state. As each subframe is generated, the parity of bits 0–30 is checked. If it is odd, bit 31, the parity bit, is set high to make even parity. In this way, every subframe in the interface signal is ensured to have even parity, and odd parity detected upon reception indicates that an error has been introduced into that subframe.

Although an even number of errors in one subframe would not violate parity and would pass undetected, such occurrences are rare enough to be ignored.

Sending a high Validity bit

When the Validity bit (bit 28) is low (logical 0), the audio sample word is suitable for conversion to an analog audio signal; when it is high (logical 1) it is not. There is no default state for the Validity bit. Checking the **Send Invalid** checkbox will set the Validity bit high. The DUT should correctly recognize the invalid flag.

Rise/Fall Time

Figure 140. The DIO Rise/Fall Time and Interfering Noise interface impairments.



The rise and fall times of the serial interface bitstream at the XLR and BNC outputs may be varied from 12 to 400 nanoseconds to simulate the bandwidth reduction typical with increasing cable length. When this impairment is set to **Fix**, the rise and fall times are at their fastest, about 12 ns. Click the button to **Var** to enter other values, or to sweep the rise/fall time as part of a test by selecting **Dio** as the browser instrument and **Rise/Fall Time** at **Source 1** or **Source 2** on the Sweep panel.

Variable Rise/Fall Time is not available at the optical or parallel outputs.

Interfering Noise


See Figure 140.

To test the noise rejection capability of a digital device's input, interfering random white noise of variable amplitude can be added to the serial bitstream. This is added at the BNC output and as a “normal mode” signal (as opposed to “common mode;” see below) at the balanced XLR output.

Click the Interfering Noise **ON/OFF** button to toggle the noise on and off. The maximum amplitude available is 25% of the maximum pulse amplitude at the selected output, and the amplitude can be swept as part of a test by selecting **Dio** as the browser instrument and **Noise Amp** at **Source 1** or **Source 2** on the Sweep panel.

Common Mode Sine

Figure 141. The DIO Common Mode Sine interface impairment.



A “common mode test” (or CMT) applies an interfering signal equally to both sides of a balanced connection to test the common mode signal and noise

rejection capabilities of a DUT balanced input. For the balanced XLR connections of the 2700 series, the CMT signal is injected between center tap and ground of the output transformer secondary and appears between ground and pins 2 and 3, in phase and at the same level at both of the pins.

A sine wave of selectable amplitude and frequency can be added as a CMT signal to the balanced digital output. Click the **Common Mode Sine** button to ON (lighted green) to apply the CMT signal. Enter a CMT signal amplitude and frequency for your test.


The CMT signal amplitude or frequency can be swept as part of a test by selecting **Dio** as the browser instrument and **Common Mode Ampl** or **Common Mode Freq** at **Source 1** or **Source 2** on the Sweep panel.

NOTE: Since a common mode test is relevant only to balanced transmission lines, this feature is not available at the BNC, optical or parallel outputs.

Jitter Generation

In a digital interface data stream, jitter is a variation in time of the pulse transitions from an ideal clock timing. The 2700 series can add jitter modulation to the serial interface bitstream. Several jitter waveforms can be selected.

Figure 142. The DIO Jitter Generation selections.



Jitter Type

- **Off**
Off disables jitter generation.
- **Sine**
Sine modulates the interface transition times with sinusoidal jitter.
- **EQ Sine**
EQ Sine adds sinusoidal jitter in the same way as the previous choice, but attaches an EQ file to the sine wave. This causes the output jitter amplitude to vary as a function of jitter frequency, corresponding to the values in the EQ file selected. Use the **EQ Curve** browser to attach the file.

■ Square wave

Square wave modulates the interface transition times with square wave jitter.

■ Wideband Random

Wideband Random modulates the interface transition times with a jitter signal that has a $\sin(x)/x$ power spectrum with the first null at the sample rate, resulting in a -3 dB point at $0.44 \times SR$. Note that the probability distribution function of this jitter is not Gaussian and that it consists of peaks at plus-and-minus the jitter amplitude setting.

The jitter amplitude can be swept for any of these jitter waveforms as part of a test by selecting **Dio** as the browser instrument and **Jitter Ampl** at **Source 1** or **Source 2** on the Sweep panel. Jitter frequency can be swept for Sine and Square waveforms by selecting **Jitter Freq** at **Source 1** or **Source 2**.

Amplitude

Enter the amplitude of the jitter in this field. The units available are **UI** (unit intervals), **dBUI** (decibels referred to 1.00 UI) and **sec** (seconds). Jitter amplitudes are calibrated in terms of the peak value of a sine wave.

NOTE: It may seem unusual to measure amplitude in units of time, but jitter is a variation in time. High levels of jitter produce large time displacements.

The Unit Interval

The unit interval is defined as the shortest nominal time interval in the coding scheme. Since an AES3 signal has 64 bits per frame and the bi-phase coding of the interface nominally doubles this rate, there are 128 UI per AES3 frame.

The UI is useful because it scales with the interface data rate. In the case of a 48 kHz sample rate and an AES3 frame as described above:

$$1\text{UI} = \frac{1}{(128 \times 48000/\text{s})} = 163 \text{ ns};$$

or, with a 44.1 kHz sample rate:

$$1\text{UI} = \frac{1}{(128 \times 44100/\text{s})} = 177 \text{ ns}.$$

Jitter amplitude may be swept as part of a test by selecting **Dio** as the browser instrument and **Jitter Ampl** at **Source 1** or **Source 2** on the Sweep panel.

Frequency

Enter the frequency of the jitter sine wave in this field.

Jitter frequency may be swept as part of a test for all waveforms except **Wideband Random** by selecting **Dio** as the browser instrument and **Jitter Freq** at **Source 1** or **Source 2** on the Sweep panel.

EQ Curve

The jitter sine wave generator can be equalized in the same way as the 2700 series signal generators.

Click the **EQ Curve...** button to select an EQ file to attach to the jitter generator. See **Specifying the EQ Curve** on page 76 for general information on using EQ files with generated signals.

NOTE: The jitter impairment, when selected, is normally applied only to the front-panel AES/EBU (XLR) and AES3id/IEC 60958 (BNC) outputs, and to the rear-panel PARALLEL OUTPUT. It can also be applied to the MASTER CLK OUT and TRANSMIT FRAME SYNC rear panel outputs (BNC) by checking the Jitter Clock Outputs checkbox on the Sync/Ref Input/Output panel. Jitter is NEVER applied to the rear panel AES/EBU REF OUT (XLR) signal.

The DIO Input Section

Input

Connector: XLR (bal) ☒ I ☐ II

Z-In: 110 Ohms

Sample Rate-ISR: 192.000 kHz

Voltage: 4.375 Vpp

Audio Format: Linear 24

DeEmphasis: Off

Scale Freq. by: Meas Input Rate

Rate Ref: 48.0000 kHz

Delay from Ref Out: 3.934 usec

Channel A: 0.000 dBFS

Channel B: 0.000 dBFS

Mode: 1/2 Pk-Pk

24 20 16 12 8 4

A: ☒ ☐ ☐ ☐ ☐ ☐ ☒ Active Bits

B: ☒ ☐ ☐ ☐ ☐ ☐ ☐ Data Bits

Error Flags

confidence lock coding parity Ch A Ch B

☐ ☐ ☐ ☐ ☐ ☐ invalid invalid

Jitter Measurement

Jitter: 5.266 mUI ☒ UI ☐ Sec

B/W: 700Hz to 100kHz ☒ Pk ☐ Avg

Status Bits...

Figure 143. The DIO Input Section.

The routing and configuration of the serial digital interface input signal are set in the **Input** section of the DIO panel.


At the top area of the panel, meters display the measured input sample rate (**ISR**) and the interface bitstream voltage level. Some settings which affect the reception of the embedded audio, such as **Audio Format** and **DeEmphasis**, are also in this area of the panel.

The middle of the panel shows data monitors, embedded audio peak level meters and interface error flag indicators.

At the bottom of the panel are jitter measurement displays and settings, and a button to open the Status Bits panel.

Connector

Figure 144. The DIO Input **Connector** Selections.



The first setting field is **Connector**. Select the serial digital interface input connector(s) and interface format from the list.

- **XLR (bal)**

This choice selects the balanced digital input. When the impedance at **Z-In** is set to 110 Ω , this input satisfies the electrical aspects of the AES3 professional standard.

- **BNC (unbal)**

This choice selects the unbalanced digital input. With impedance at **Z-In** set to 75 Ω , this input satisfies the electrical aspects of the AES3id professional standard; with impedance at **HiZ**, this input satisfies the IEC 60958-3 consumer standard.

- **Optical**

This choice selects the Toslink® optical input.

- **GenMon**

This choice selects the generator monitor path, which bypasses the external digital input connector and instead attaches the digital input to the Digital Generator output via an internal connection.

- **XLR w/EQ**

This choice selects the balanced XLR digital input as described above, with added equalization to compensate for 1000 m cable roll-off.

- **BNC w/EQ**

This choice selects the unbalanced BNC digital input as described above, with added equalization to compensate for 1000 m cable roll-off.

- **XLR Common**

This choice applies the common mode signal that appears at the center

tap of the digital input transformer (referenced to ground) to the serial receiver input.

- **PSIA**

This choice selects the 50-pin PARALLEL INPUT port on the rear of the instrument and also enables the PSIA Receiver panel.

- **Parallel**

This choice selects the 50-pin PARALLEL INPUT port on the rear of the instrument, without enabling the PSIA Receiver panel.

- **Dual XLR (bal)**

This choice selects the Balanced Dual Connector mode. Both balanced digital inputs (**I** and **II**) are used in conjunction with each other, as explained in the **Dual Connector Mode** sidebar on page 156.

- **Dual BNC (unbal)**

This choice selects the Unbalanced Dual Connector mode. Both unbalanced digital inputs (**I** and **II**) are used in conjunction with each other, as explained in the **Dual Connector Mode** sidebar on page 156.

- **Dual XLR w/EQ**


This is the balanced dual XLR mode as described above, with added equalization to compensate for 1000 m cable roll-off.

- **Dual BNC w/EQ**

This is the unbalanced dual BNC mode as described above, with added equalization to compensate for 1000 m cable roll-off.

Input Impedance

Figure 145. The DIO Input Impedance selection field.




Under the Connector selection field is the **Z-In** field, which allows you to choose the input impedance for the digital input. The impedance choices are different for the balanced and unbalanced inputs.

- **110 Ω** is the low-impedance selection for the balanced input, which satisfies electrical aspects of the AES3 professional standard.
- **75 Ω** is the low-impedance selection for the unbalanced input, which satisfies the AES3id professional standard.
- **HiZ** is the high-impedance selection, which when used with the unbalanced input satisfies the IEC 60958-3 consumer standard.

These selections are maintained independently for the XLR and BNC inputs, and remain in effect in GenMon operation.

Connector I & II Selection

Figure 146. The DIO Input Connector I / II selection buttons.



Normal Operation

If there are two independent serial digital signals connected to the Digital Input **Connector I** and **Connector II** jacks, the **Connector I** and **Connector II** buttons act as a cable switcher, enabling you to choose one or the other serial bitstream for measurement.

On the DIO panel, the Sample Rate-ISR, Voltage and jitter meters measure only the bitstream selected by the **Connector I** / **Connector II** buttons. The Digital Analyzer measurement tools (DSP Audio Analyzer, Spectrum Analyzer, Multitone Analyzer, MLS Analyzer or Digital Data Analyzer) measure the two multiplexed channels of audio (channels A and B) embedded in the selected bitstream; when the Digital Interface Analyzer is selected, it analyzes the characteristics of the selected bitstream.

Dual Connector Operation

When any of the dual connector modes is selected in the Input **Connector** field, the selected Digital Analyzer measurement program (DSP Audio Analyzer, Spectrum Analyzer, Multitone Analyzer, MLS Analyzer or Digital Data Analyzer) always routes the audio embedded in the **Connector I** bitstream to the left (1) channel of the analyzer, and the audio embedded in the **Connector II** bitstream to the right (2) channel of the analyzer. In these modes, switching the state of **Connector I** / **Connector II** buttons has no effect on the routing of the embedded audio.

However, the DIO panel Sample Rate-ISR, Voltage and jitter meters and the Digital Interface Analyzer measure the bitstream selected by the **Connector I** / **Connector II** buttons.

Sample Rate-ISR

Figure 147. The DIO Sample rate-ISR and Voltage selections.



The **Sample rate-ISR** field (labeled **Rate** on the small form of the DIO panel) displays the measured input sample rate (or **ISR**) at the **Connector I** digital input. In dual-connector mode, the **Sample Rate-ISR** field displays the sample rate of either the **Connector I** or **Connector II** inputs, as selected. In-

put sample rates from 28 kHz to 200 kHz are accepted. A drop-down list allows you to specify the units of measurement for the **ISR**.

The input sample rate displayed here, the **ISR**, is also available as an embedded frequency scaling factor selection in the **Scale Freq. by** field in both the **Output** and **Input** sections of the DIO panel, where it is called the **Meas Input Rate**.

The input sample rate may be used to control a sweep as part of a test by selecting **Dio** as the browser instrument and selecting the reading **Input Sample Rate** at **Source 1** or **Source 2** on the Sweep panel.

Voltage

Figure 148. The DIO Input Voltage reading.


The image shows a software interface element for the DIO Input Voltage reading. It consists of a label 'Voltage:' followed by a black rectangular display area containing the text '4.375 Vpp' in green.

The **Voltage** field displays the input amplitude of the serial digital interface signal. Serial digital interface signal voltage is measured in volts, peak-to-peak (Vpp). The Voltage field is not available when **Optical**, **Parallel** or **PSIA** is selected as the digital input **Connector**.

The serial interface input voltage may be used to control a sweep as part of a test by selecting **Dio** as the browser instrument and selecting the reading **Input Voltage** at **Source 1** or **Source 2** on the Sweep panel.

Input Audio Format

Figure 149. The DIO Input Audio Format selections.



The **Audio Format** control sets the input audio format for the digital interface. Selections are

- **Linear**
- **μ-Law**
- **A-Law**

The input audio format is independent of the output audio format.

Linear

Select **Linear** to set the input interface audio format to linear pulse code modulation (PCM).

The actual resolution or word length of the incoming digital signal is shown in the **Active Bits** display below. The **Audio Format** resolution field sets the resolution or word width to be enforced on the incoming digital signal. When **Linear** is selected, you can set the resolution to any integer value from 8 bits to 24 bits by typing in the value and pressing the **Enter** key.

If the value entered in the **Audio Format** resolution field matches or exceeds the resolution of the incoming digital signal, the signal is passed on unchanged. If the value entered is lower than the incoming resolution, the digital audio signal is truncated at the LSB.

The value of quantization noise and distortion of the audio of PCM input signals measured by the Digital Analyzer tools will be affected by the input **Audio Format** resolution setting.

If the input PCM signal being measured is using the Aux bits for another signal, the input resolution must be set to 20 bits or fewer to strip off the Aux signal before measurement by one of the Digital Analyzer tool. See Appendix B for an explanation of Aux bits in the digital audio word.

The input resolution is independent of the output resolution.

The input resolution may be swept as part of a test by selecting **Dio** as the browser instrument and **Input Resolution** at **Source 1** or **Source 2** on the Sweep panel.

μ -Law and A-law Expansion

See Figure 149 for reference.


The selection of **μ -Law** or **A-law** expansion overrides the word length selected in the **Audio Format** resolution field, which is grayed out under these conditions. Instead, one of two expansion techniques is applied to the digital audio signal.

Choose **μ -Law** or **A-law** to enable the expansion, or **Linear** to return to linear PCM.

See the sidebar on μ -Law and A-law on page 160 for more information on these companding techniques.

Deemphasis

Figure 150. The DIO DeEmphasis selections.



A digital signal transmitted with preemphasis must be deemphasized on reception. Since preemphasis is rarely used, deemphasis is rarely needed.


See **Preemphasis** on page 161.

To properly deemphasize a signal you must select deemphasis curves and gain (50/15 µs Compact Disc at 0 dB or +12 dB; or CCITT J17 at 0 dB or +20 dB) that are complementary to the preemphasis conditions, to provide overall unity gain and flat response.

The deemphasis (and gain, if any) is implemented after the **Channel A** and **Channel B Peak Monitors**, so the monitor readings will not be affected as deemphasis is turned on and off.

Scale Freq. by

Figure 151. The DIO Scale Freq. by selections.



The instrument must normalize the frequency of an incoming digital audio signal to a local sample rate before display, whether the signal is to be displayed numerically or as a frequency component on an FFT graph. Depending on the application, there are several sources of sample rate which may be appropriate for normalization.

The 2700 series offers the capability to select one of four sample rate choices as a reference by which to scale the embedded frequency of the digital input signal. The choices are:

- **Output Rate (SR)**, which is the rate set in the **Sample Rate (SR)** field.
- **Meas Input Rate**, which is the measured input sample rate (**ISR**).
- **Status Bits**, which is the value of the sample frequency encoded into the received Channel A status bits.

- **DIO Rate Ref**, which is a reference value you can enter on the Input side of the DIO.

Generally, **Meas Input Rate** will be used as the scaling source so that audio signal frequency measurements follow any changes in sample rate from the source.


If the actual measured value is unstable, you may enter the nominal incoming sample rate in the **Rate Ref** field and select **DIO Rate Ref** for stable audio frequency scaling.

The **Output Rate (SR)** selection can be used to measure the frequency-shifting effects of digital processors and sample rate converters.

The **Status Bits** selection refers frequency measurements to the nominal, standard sample rate (if in fact the sample rate is actually encoded into the status bits) and will be independent of any moment-to-moment variations in the actual received sample rate.

Delay from Ref Out

Figure 152. The DIO Delay from Ref Out field.



The time delay of the selected serial digital input with reference to the rear panel AES/EBU REF OUT signal is displayed in the DIO Delay from Ref Out field.

When applying the instrument's serial digital output to a DUT, this feature will measure the time delay introduced in the DUT.

NOTE: Delay from Ref Out is not meaningful when measuring a serial digital signal that is unrelated to the 2700 series serial digital output, or when using the parallel or PSIA digital input.

The range of the delay measurement is one frame. If the delay exceeds one frame, the measurement result “wraps” back within the one-frame range. The range extends from -10% to $+90\%$ of the frame length; in other words, from

$$\begin{aligned} & \text{FrameStart} - (0.1 \times \text{FrameLength}) \\ & \text{to} \\ & \text{FrameStart} + (0.9 \times \text{FrameLength}). \end{aligned}$$

Figure 153 gives an example of the delay measurement range for a frame length of $20.83\ \mu\text{s}$, the length of an AES3 frame at a sample rate of 48 kHz.




Figure 153. The Delay from Ref Out measurement range, showing times that correspond to a sample rate of 48 kHz.

It is possible to insert delay in the 2700 series serial digital output using the Delay, Out from Ref Out control on the Sync panel. Any delay inserted will add to the measured delay displayed in the DIO Delay from Ref Out field. See Chapter 25 for more information on the Sync panel.

To plot Delay from Ref Out as a function of a swept parameter, select **Dio** as the browser instrument for sweep **Data** and **Delay from Ref Output** as the parameter to be plotted.

Rate Ref


Figure 154. The DIO Rate Ref entry field.

Rate Ref: 48.0000 kHz

Rate Ref is a reference field. A sample rate entered here can be selected as a reference for digital input or output frequency scaling. The acceptable range for **Rate Ref** is 8 kHz to 216 kHz.

Peak Monitors

Figure 155. The DIO Input Peak Monitors.



The DIO panel provides the capability to view the peak levels of the embedded audio signals. These meters indicate the digital input levels prior to the application of deemphasis, if used.

The **Mode** field between the numeric display fields enables selection among four types of displays:

- **Pos. Peak**

displays the greatest positive value during each measurement interval, which is approximately 1/4 second for all peak monitor display modes.

- **Neg. Peak**

displays the greatest negative value during each measurement interval.

- **Abs. Peak**


displays the absolute value of the greatest positive-going or negative-going value during each measurement interval. **Abs. Peak** is always positive.

- **½ Pk-Pk**

displays the value which is one-half the peak-to-peak range measured during the measurement interval.

Data Bit Indicators

Figure 156. The DIO Data Bit Indicators.



The Data Bit indicators show a bit-by-bit view of the embedded data in the digital signal audio word for each subframe. The two subframes correspond to Channel A and Channel B.


The bits are numbered from the most significant bit (MSB, or bit 24 of the word) on the left, to the least significant bit (LSB, or bit 1 of the word) on the right. The Data Bit indicators examine the signal in repeated periods of approximately 1/4 second.

The Data Bit indicators have two modes, selectable by the option buttons to the right of the indicator rows.

- When **Data Bits** is selected, the indicators display green for a bit that is at data 1 at the moment of measurement, and black for a bit that is at data 0.
- When **Active Bits** is selected, the indicators display green for a bit that has changed state during the measurement period, and black for a bit that has not.

Error Indicators

Figure 157. The DIO Error Indicators.



The DIO panel contains four error indicators for characteristics of the serial digital signal. The indicators are labeled **Confidence**, **Lock**, **Coding**, and **Parity**. Proper operation is indicated when none of the indicators is lighted. When an indicator lights, it shows that some characteristic of the digital input signal is marginal or unacceptable.

The Digital Interface Analyzer can select a **Parity**, **Coding**, **Lock**, or **Confidence** error flag to act as a trigger.

Two more indicators, labeled **Ch A invalid** and **Ch B invalid**, light when the Validity bit (bit 28, the V bit) in either subframe is asserted.

The Confidence Indicator

The **Confidence** indicator lights when the ratio between the amplitude of the 3 UI-long pulse and the following 1 UI-long pulse in a subframe preamble becomes large enough to cause an increasing probability of errors when “slicing” the input signal into logic high and low values. This large ratio occurs when the transmission bandwidth has been reduced to marginal or unacceptable values.

The Lock Indicator

The **Lock** indicator lights when the digital input phase-locked loop is unable to lock to the incoming signal.

The Coding Indicator

The **Coding** indicator shows a deviation from proper bi-phase coding in the input serial bitstream. Since the subframe preambles deliberately deviate from the bi-phase coding rules in order to provide a unique synchronization signal, preambles are excluded from the function of the **Coding** indicators.

The Parity Bit Indicator

The **Parity** bit indicator indicates a parity error within a subframe. Correct parity is determined by comparing the parity bit (bit 31, the “P” bit) with the sum of the remaining 31 bits in each subframe. Any one bit error or odd number of bit errors introduced in transmission will cause a **Parity** error indication.

A deliberate parity bit error (the “P” bit set high) can be transmitted from the instrument digital output by checking **Parity** in the DIO Output **Send Errors** section.

Unfortunately, even numbers of bit errors within a subframe cannot be detected by the parity technique.

The Validity Bit Indicators


Two additional indicators show whether the Channel A and B validity bits (bit 28, the “V” bit) are asserted or not.

A validity bit is associated with each subframe. Exactly how (or if) the validity bit is set depends upon the design of the particular digital device being measured. For example, a DAT machine may set its “V” bit to *invalid* (“V” bit set high) when the tape is not playing and to *valid* (set low) when the tape is moving.

The “V” bit transmitted by the instrument can be set high (both Channel A and B are set together) by checking **Invalid** in the DIO Output **Send Errors** section.

Jitter Measurement

Figure 158. DIO Jitter Measurement.



Jitter is the variation in the time of an event—such as a regular clock signal—from nominal.

The jitter of the digital interface signal is shown in the DIO Panel **Jitter Measurement** display. This measurement is made from the error signal of the AES receiver input phase lock loop, and is sensitive to jitter of the total signal, including transitions in both the preamble and the data sections of the frames. Jitter measurements may be displayed in units of **UI** (unit intervals) or **Sec** (seconds, typically nanoseconds).

You can choose one of two detector responses, **Pk** (peak) and **Avg** (average) for the jitter meter. Both detectors are calibrated in terms of the peak value of a sine wave.

The averaging detector is typically used for making frequency response plots of the jitter signal, while the peak detector should be used for characterizing actual interface jitter. Peak jitter measurements will almost always give a higher number than average measurements, depending upon the crest factor of the jitter waveform.

Jitter is often dominated by low-frequency noise, so the value of jitter measured is likely to be a strong function of the bandwidth of the measurement. Four bandwidth selections may be selected for jitter measurements:

- 50 Hz–100 kHz
- 120 Hz–100 kHz
- 700 Hz–100 kHz, and
- 1200 Hz–100 kHz.

Jitter may be plotted on a graph as a function of a swept parameter such as time or transmitted jitter amplitude; choose **Dio** as the Sweep **Data** browser instrument and **Interface Jitter** as the parameter.

Using the **Spectrum Analyzer** analysis tool, you can select the **Jitter** signal and display either the jitter waveform or an FFT spectrum analysis of the jitter signal. See **Spectrum Analyzer Signal Inputs** on page 262.

NOTE: Jitter may also be measured according to an entirely different technique by the Digital Interface Analyzer analysis tool, described in Chapter 13.

The Status Bits panel

Channel status bits are metadata carried in the AES3 and IEC 60958 serial digital interfaces. Each subframe has one “C” (Channel Status) bit, bit number 30. The bits are gathered and arranged into channel status blocks of 192 bits, marked off by the block start code which occurs in the interface preamble at intervals of 192 subframes.

Bit 0 in the status block identifies the format as professional or consumer. The information in the status blocks differs between the two formats. See page 544 for more information about Channel Status.

The 2700 series Status Bits panel gives you the ability to set transmit status bits to any state and to view received status bits. Choose **Panels > Status Bits** to open the panel, or click the **Status Bits** button on the Toolbar or on the DIO panel.

Status Bits -- Digital I/O

Transmit: ☒ A ☐ B ☐ A & B

☐ Consumer ☒ Professional

☒ Normal ☐ Non-Audio

Emphasis: None

Freq Mode: Locked

Sample Freq: 48 kHz

Channel Mode: 2-channel

User Bits: 192-bit block

Auxiliary Bits: 20-bit not def

Audio Wordlen: Not indicated

Ref Signal: Not a ref. sig

Origin: DAT1 Dest: 2722

Local Address: 1424 ☐ Auto Incr

Time-of-day: 151526

Reliability Flags: ☒ 0-5 ☐ 14-17 (set = unreliable) ☐ 6-13 ☒ 18-21

CRC Enable ☒

Receive A:

Mode: Professional

Audio Mode: Normal

Emphasis: None

Freq Mode: Locked

Sample Freq: 48 kHz

Channel Mode: 2-channel

User Bits: 192-bit block

Auxiliary Bits: 20-bit not define

Audio Wordlen: Not indicated

Ref Signal: Not a ref. signal

Origin: DAT1

Dest: 2722

Local Address: 1424

Time-of-day: 151526

Reliability Flags: ☐ 0-5 ☐ 14-17 (On = unreliable) ☐ 6-13 ☐ 18-21

CRC Valid: ☐

Receive B:

Mode: Professional

Audio Mode: Normal

Emphasis: None

Freq Mode: Locked

Sample Freq: Not Indicated

Channel Mode: Not Indicated

User Bits: None

Auxiliary Bits: 20-bit not define

Audio Wordlen: Not indicated

Ref Signal: Not a ref. signal

Origin:

Dest:

Local Address: 0

Time-of-day: 0

Reliability Flags: ☐ 0-5 ☐ 14-17 (On = unreliable) ☐ 6-13 ☐ 18-21

CRC Valid: ☐

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
Transmit A:	85	88	00	00	00	00	C4	C1	54	31	32	37	32	32	90	05	00	00	E6	4F	02	00	90	00
Receive A:	85	88	00	00	00	00	C4	C1	54	31	32	37	32	32	90	05	00	00	E6	4F	02	00	90	82
Transmit B:	05	00	00	00	00	00	20	20	20	20	20	20	20	20	20	00	00	00	00	00	00	00	00	00
Receive B:	05	00	00	00	00	00	20	20	20	20	20	20	20	20	20	00	00	00	00	00	00	00	00	ED

Figure 159. The Status Bits panel.

Transmit Status Bits

The left side of the status bits panel has a number of fields to select status bit conditions for the transmitted serial interface signal appearing at the 2700 series digital output.

The first three option buttons select whether the settings you make operate on Channel A, Channel B, or both.

To select the format, click **Consumer** or **Professional**. Since the consumer and professional formats vary greatly in the status bit fields available, the choice of format will bring an entirely different set of options to the panel. We will look at the Consumer format options first.

Consumer Format Status Bits

Figure 160. Transmitting Consumer Format Status Bits.



The screenshot shows a software panel titled "Status Bits -- Digital I/O". It contains several rows of radio buttons and a section of drop-down menus. The radio buttons are arranged in two columns. The first row has three radio buttons labeled "A", "B", and "A & B", with "A" selected. The second row has two radio buttons labeled "Consumer" and "Professional", with "Consumer" selected. The third row has two radio buttons labeled "Audio Mode" and "Data Mode", with "Audio Mode" selected. The fourth row has two radio buttons labeled "Copyright" and "Non-Copyright", with "Non-Copyright" selected. The fifth row has two radio buttons labeled "No pre-emph" and "50/15µs", with "No pre-emph" selected. The sixth row has two radio buttons labeled "2 Channel" and "4 Channel", with "2 Channel" selected. Below the radio buttons is a section with five drop-down menus. The first is labeled "Category Code:" and has "General" selected. The second is labeled "Source Num:" and has "Don't care" selected. The third is labeled "Channel Num:" and has "Don't care" selected. The fourth is labeled "Sample Freq:" and has "44.1 kHz" selected. The fifth is labeled "Clock Accuracy:" and has "Level 2" selected.

Transmit:	☒ A	☐ B	☐ A & B
	☒ Consumer	☐ Professional	
	☒ Audio Mode	☐ Data Mode	
	☐ Copyright	☒ Non-Copyright	
	☒ No pre-emph	☐ 50/15µs	
	☒ 2 Channel	☐ 4 Channel	
Category Code:	General		
Source Num:	Don't care		
Channel Num:	Don't care		
Sample Freq:	44.1 kHz		
Clock Accuracy:	Level 2		

With the option buttons and drop-down lists shown here, you can set any of the consumer format status bit conditions. See page 544 for more information about Channel Status and for detailed tables of the consumer format status bit fields and interpretations.

Professional Format Status Bits

Figure 161. Transmitting Professional Format Status Bits.

Status Bits -- Digital I/O

Transmit: ☒ A ☐ B ☐ A & B

☐ Consumer ☒ Professional

☒ Normal ☐ Non-Audio

Emphasis: None

Freq Mode: Locked

Sample Freq: Not Indicatec

Channel Mode: Not Indicatec

User Bits: None

Auxiliary Bits: 20-bit not def

Audio Wordlen: Not indicated

Ref Signal: Not a ref. sigr

Origin: DAT1 Dest: 2722

Local Address: 0

Time-of-day: 0

Reliability Flags: ☐ 0-5 ☐ 14-17
(set = unreliable) ☐ 6-13 ☐ 18-21

CRC Enable ☒

With the option buttons and drop-down lists shown here, you can set any of the professional format status bit conditions. See page 544 for more information about Channel Status and for detailed tables of the professional format status bit fields and interpretations.

Local Address and Time of Day entry

If the **Auto** box is checked, the 2700 series control software automatically enters a continuously increasing count, in audio samples, in both the **Local Address** and the **Time of Day** fields. The count begins at the moment the professional format is selected, or at the moment the **Auto** box is checked, whichever occurs later.

If the **Auto** box is not checked, you may enter a fixed number into either field.

CRC entry

The AES3 professional standard defines status byte 23 as a cyclic redundancy code (CRC) byte, to assist the receiver in detecting errors in the first 23 bytes (bytes 0–22). If the **CRC Enable** box is checked, the control software automatically computes a CRC byte based on the data in bytes 0–22, and transmits that byte as status byte 23. This is normal operation.

If the **CRC Enable** box is not checked, the CRC is not computed and you may enter arbitrary values into byte 23 of the Hex Transmit field to test the error detection capability of the receiver in the DUT.

Receive Status Bits

Figure 162. Display of Received Status Bits, Channel A showing Professional Format and Channel B showing Consumer Format.

Receive A:		Receive B:	
Mode:	Professional	Mode:	Consumer
Audio Mode:	Normal	Audio Mode:	Audio Mode
Emphasis:	None	Copyright:	Non-Copyright
Freq Mode:	Locked	Emphasis:	No pre-emph.
Sample Freq:	48 kHz	Channel Mode:	2 Channel
Channel Mode:	2-channel	Category Code:	General
User Bits:	None	Source Num:	Don't care
Auxiliary Bits:	20-bit not define	Channel Num:	Don't care
Audio Wordlen:	Not indicated	Sample Freq:	44.1 kHz
Ref Signal:	Not a ref. signal	Clock Accuracy:	Level 2
Origin:	DAT1		
Dest:	2722		
Local Address:	1424		
Time-of-day:	151502		
Reliability Flags:	☐ 0-5 ☐ 14-17 (On = unreliable) ☐ 6-13 ☐ 18-21		
CRC Valid:	☒		

The right side of the Status Bits panel displays the conditions read in the incoming interface data. This display is updated approximately four times per second. If there are no incoming data, the panel display defaults to the consumer format fields.

The professional format **Reliability Flags** display OFF (black) for normal received data and ON (green) for unreliable data. The **CRC Valid** flag is ON (green) for valid received CRC, and OFF (black) for invalid CRC.

Hex Control and Display

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
Transmit A:	05	00	00	00	00	00	C4	C1	54	31	32	37	32	32	00	00	00	00	00	00	00	00	00	00
Receive A:	05	00	00	00	00	00	C4	C1	54	31	32	37	32	32	00	00	00	00	00	00	00	00	00	8E
Transmit B:	04	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00
Receive B:	04	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	00	5A

Figure 163. Hexadecimal Display and Control of Status Bits.

At the bottom of the Status Bits panel are hexadecimal status bit setting fields and display fields. The hex codes for the channel status conditions are detailed in the AES3 and IEC 60958 standards.

The hex fields set (white with black text) and display (black with green text) the same status conditions as are set and displayed above in the high-level English display. A setting made in a high-level transmit field will be echoed in the corresponding hex transmit field; a setting made in a hex transmit field will be echoed in the corresponding high-level transmit field.

To make an entry in a hex field, click the cursor in the field desired and move back and forth with the arrow keys. Overtyping the hex code or codes shown with the new value, and press the **Enter** key to make the change.

Dual Connector Mode and Status Bits

In single-connector mode Channel A and Channel B status bits (corresponding to the A and B subframes in the data stream) can be set and read.

In dual-connector mode, the Channel A labels on the Status Bits panel refer to the Connector I signal, and the Channel B labels refer to the Connector II signal.

In this mode the received status bits are read from subframe A on each of the two signals; subframe B status bits are ignored. Transmitted status bits, in dual-connector mode, are identical in both subframes.

Chapter 10

The Dolby Digital Generator

Overview

This chapter discusses the Dolby Digital Generator option and the associated IEC 61397 panel. Although you can view the IEC 61397 panel and the Dolby Digital controls in Demo Mode, you must have purchased and installed the OPT-2711 Dolby Digital Generator option for this feature to operate. OPT-2711 includes a software key and proprietary streaming interface hardware to enable the Dolby Digital Generator. See **OPT-2711 Required Components** on page 222.

Dolby Digital is an audio distribution system that can provide reduced bit-rate high-quality discrete multichannel audio capabilities with sophisticated metadata control, carried on a single IEC 60958 (AES3 / SPDIF) digital interface signal. In creating a Dolby Digital signal, the original multichannel audio is first preprocessed and digitally compressed. Metadata is added, and the resulting data is inserted into the IEC 60958 bitstream as AC-3 data according to the IEC 61937 standard. Dolby Digital audio is used in theatrical films, in digital television broadcast, in laserdisc and various DVD applications and in Internet audio distribution.

The OPT-2711 Dolby Digital Generator can encode into Dolby Digital any of the wide range of digital stimulus signals available from a 2700 series instrument, with both the stimulus generation and the Dolby Digital and IEC 61937 parameters under programmatic control (using AP Basic), if desired. The decoded multichannel outputs of the DUT can be routed through an audio switcher and into the 2700 series analyzer, once again under programmatic control. The stimulus signals and the integrated control of switching, sweeps, measurement and display can thoroughly and quickly test DUTs that incorporate Dolby Digital decoder functions.

Connections




Figure 164. Typical connections for Dolby Digital receiver testing.

Using the Dolby Digital Generator

NOTE: You must have the necessary OPT-2711 hardware and licensing key installed and activated for your instrument for the Dolby Digital Generator feature to operate. See *OPT-2711 Required Components* on page 222.



The Dolby Digital Generator controls are found on the IEC 61937 panel. You can open the panel directly by going to **Panels > IEC 61937 > Dolby Digital** or by clicking the **IEC 61937 / Dolby Digital** button on the panels toolbar. When the panel opens, set Audio Format to **IEC 61937** to enable the panel controls.




Figure 165. Audio Format control set to enable the IEC 61937 panel.

Set the Audio Format to **IEC 61937** to enable the panel controls.

NOTE: The Audio Format control on the IEC 61937 panel is the same control as output Audio Format on the DIO panel. Output Audio Format settings made on either panel are equivalent.

Data-type




Figure 166. Data-type control set to Dolby Digital.

At the top of the panel the Data-type control selects the type of IEC 61937 data to be inserted into the output (IEC 60958 / AES3) bitstream. Current choices include

- **Idle** (IEC 61937 Idle data; see page 213)
- **Pause** (IEC 61937 Pause data; see page 216)
- **Dolby Digital** (Dolby Digital AC-3 data; see page 192).

In a New Test, the IEC 61937 panel opens with Data-type set to **Dolby Digital**. Also see the IEC 61937 sidebar on page 213.




Figure 167. The IEC 61937 panel, shown with Data-type = Dolby Digital at Normal level of control.

The IEC 61937 / Dolby Digital panel gives you control over the Dolby Digital encoding and metadata parameters and access to general IEC 61937 bitstream controls. Additional controls help you set the instrument's routing of stimulus signals to the Dolby Digital main, surround and LFE channels. The appearance and function of the panel will change according to the Data-type and level of control selected.

The Dolby Digital controls are discussed here first. For more information on the general IEC 61937 controls, go to page 213.

Levels of control




Figure 168. Level of control settings.

The Dolby Digital and IEC 61937 bitstream parameters on the IEC 61937 panel can be accessed with different levels of control.

Normal provides a familiar control view and offers the basic selections that may be needed for simple IEC 61937 / Dolby Digital setups.

Advanced provides a grid view of the controls and offers a greater selection of IEC 61937 and Dolby Digital controls and options. Preambles controls are also available at the Advanced level.

Expert also uses the grid view, but is only available for Dolby Digital controls. Preambles controls are also available at the Expert level.

The selected level of control affects the interface view and capability across the available IEC 61937 data-types (currently Idle, Pause and Dolby Digital). Selecting **Normal** or **Advanced** in any data-type will switch the level of control in the other data-types as well. Since there is no **Expert** level for Idle or Pause, choosing **Expert** level in Dolby Digital will select **Advanced** level for Idle and Pause. However, the Dolby Digital level will remain in **Expert** when you return to that data-type.

Settings that are only available at **Expert** or **Advanced** level will be lost (re-set to their defaults) if you move from a higher to a lower level of control. When settings will be affected by such a change, a dialog box will warn you and give you the opportunity to remain at the higher level of control.

In a New Test, the IEC 61937 panel opens with the level of control set to **Normal**.

Dolby Digital at Normal Level of Control

This is the default IEC 61937 panel that will open in a New Test. The routing controls at the bottom of the panel are not shown here; see page 193 for a discussion of channel routing.

If you open this panel before setting the Output Audio Format to IEC 61937, most of the panel will be grayed out. You can set the Audio Format control from this panel or from the DIO panel. Drop the Audio Format list at the upper left of the panel and select IEC 61937.




Figure 169. Dolby Digital controls, shown at Normal level of control.

The **Normal** level of control gives access to the most commonly adjusted Dolby Digital settings in a view similar to other Audio Precision panels.

Some options that appear at this level of control are not available because of the state of other controls; Dolby Surround Mode (**dsurmode**), for example is grayed out because it is not defined at the current setting (3/2) of Audio coding mode (**acmod**).

Other controls may only allow only a subset of their settings while at **Normal** level. Some controls do not appear at all at this level.

Dolby Digital at Advanced or Expert Levels of Control




Figure 170. Dolby Digital controls, shown at Expert level of control.

The **Advanced** level of control gives access to a higher level of Dolby Digital settings in an grid view.

The **Expert** level of control gives access to the highest level of Dolby Digital settings, also shown in an grid view. Bitstream impairments are available at this level of control.

Channel Routing to the Dolby Digital inputs

The Digital Generator provides two channels of digital audio to the DIO for output in the normal IEC 60958 bitstream. Dolby Digital, however, can encode as many as six channels of digital audio into the bitstream. The channel routing feature at the bottom of the IEC 61937 panel (when Data-type is set to **Dolby Digital**) allows you to specify the routing of the two generator channels

to the six Dolby Digital channels before encoding. The input routing feature can be addressed in a **Normal** or a **Follow Switcher** mode.

Normal

Figure 171. Normal view, Dolby Digital channel routing.

Normal provides a straightforward matrix in which the two Digital Generator output channels can be assigned to any (or none) of the Dolby Digital encoder inputs.

Follow Switcher

Figure 172. Follow Switcher view, Dolby Digital channel routing.

Often multichannel tests (such as surround sound tests) are performed using an Audio Precision input switcher (such as an SWR-2755F or U) between the DUT and the measurement instrument, for the purpose of selecting which pair of surround sound outputs to apply to the Analyzer inputs. When using a switcher in this manner, the Analyzer input channel switching is controlled by settings on the Switcher panel or in equivalent AP Basic commands, in conjunction with Sweep operations.

Follow Switcher channel routing assumes that you are using a switcher in this manner, and allows you to set the Digital Generator-to-Dolby Digital encoder patching to follow or “track” the switcher patching.

Dolby Digital controls

The Dolby Digital bitstream includes metadata to provide synchronization and error correction, to indicate encoding settings and to pass decoding recommendations to the Dolby Digital decoder. Many of the Dolby Digital metadata control words are available in the Audio Precision Dolby Digital Generator as Dolby Digital controls. These are grouped both in the screen grid and here by their application.

The entire specification of Dolby Digital (AC-3) and its application are subjects much too complex to address in this User's Manual. For more information we refer you to the sources listed on page 224.

Audio Service Configuration

Audio service configuration designates a group of Dolby Digital controls that includes **frmsizecod**, **fsmod** and **fsmod mode**, **acmod**, **lfeon**, **bsmod**, **dialnorm** and **dialnorm2**.

frmsizecod

frmsizecod is a Dolby Digital control term. The term is an abbreviation for “frame size code.”

frmsizecod, in conjunction with **fsmod**, determines the data rate (the number of kilobits of encoded data per second). The range of available selections varies with the **acmod** setting. For detailed information see the Frame Size Code table in the ATSC Standard document A/52A.

The selections available are

- **56 kbps**
1/0 audio coding mode only.
- **64 kbps**
1/0 audio coding mode only.
- **80 kbps**
1/0 audio coding mode only.
- **96 kbps**
1/0, 2/0 and 1+1 audio coding modes only.
- **112 kbps**
1/0, 2/0 and 1+1 audio coding modes only.
- **128 kbps**
1/0, 2/0, 3/0 and 1+1 audio coding modes only.

- **160 kbps**
1/0, 2/0, 3/0 and 1+1 audio coding modes only.
- **192 kbps**
1/0, 2/0, 3/0, 3/1 and 1+1 audio coding modes only.
- **224 kbps**
All audio coding modes.
- **256 kbps**
All audio coding modes.
- **320 kbps**
All audio coding modes.
- **384 kbps**
All audio coding modes.
- **448 kbps**
All audio coding modes.
- **512 kbps**
All audio coding modes.
- **576 kbps**
All audio coding modes.
- **640 kbps**
All audio coding modes.

fscod mode

fscod mode selects whether **fscod** is automatically set, or whether the user can **Override** the automatic setting with a fixed setting. This setting is only available at Expert level.

fscod mode is forced to **Auto** when not at Expert level.

fscod

fscod is a Dolby Digital control term, an abbreviation for “sampling frequency (Fs) code.” The **fscod** field in the bitstream indicates the sampling frequency of the PCM audio before encoding, and in conjunction with **frmsizecod** determines the data rate (the number of kilobits of encoded data per second). For detailed information see the Frame Size Code table in the ATSC Standard document A/52A.

fscod is automatically set when **fscod mode** is set to **Auto**. **fscod** can be set to a fixed value of your choice when **fscod mode** is set to **Override**.

This setting is only available at Expert level.

acmod

acmod is a Dolby Digital control term, an abbreviation for “audio coding mode.” This control selects which of the main service channels is in use. **1+1** (dual mono) is only available at Expert level.

Available settings are:

- **1+1**
Sets audio coding mode to 1+1 (Ch1, Ch2) (dual mono).
[Expert Mode only].
- **1/0**
Sets audio coding mode to 1/0 (C).
- **2/0**
Sets audio coding mode to 2/0 (L, R).
- **3/0**
Sets audio coding mode to 3/0 (L, C, R).
- **2/1**
Sets audio coding mode to 2/1 (L, R, S).
- **3/1**
Sets audio coding mode to 3/1 (L, C, R, S).
- **2/2**
Sets audio coding mode to 2/2 (L, R, SL, SR).
- **3/2**
Sets audio coding mode to 3/2 (L, C, R, SL, SR).

lfeon

lfeon is a Dolby Digital control term. The term is an abbreviation for “low frequency effects on.”

The **lfeon** control switches the LFE (low frequency effects/subwoofer) channel **ON** or **OFF**.

At Expert level, **lfeon** can be switched **ON** or **OFF** independent of the audio coding mode (**acmod**). At Normal and Advanced levels, **lfeon** is forced **OFF** for audio coding modes **1/0** and **2/0**.

bsmod

bsmod is a Dolby Digital control term. The term is an abbreviation for “bitstream mode.” **bsmod** indicates the type of service that the bitstream conveys.

Available service types are:

- **main audio service: complete main (CM).**
- **main audio service: music and effects (ME).**
- **associated service: visually impaired (VI).**
- **associated service: hearing impaired (HI).**
- **associated service: dialog (D).**
- **associated service: commentary (C).**
- **associated service: emergency (E).**
- **main audio service: karaoke.**
(only available when **acmod** is 2/0, 3/0, 2/1, 3/1, 2/2, or 3/2).
- **associated service: voice over (VO).**
(replaces karaoke when **acmod** is 1+1 or 1/0).

dialnorm

dialnorm is a Dolby Digital control term, an abbreviation for “dialog normalization.”

This 5-bit field indicates how far the average dialog level is below digital 100 percent. **dialnorm** may be set from –1 dB to –31 dB with respect to digital 100%. The value 0 is reserved, and is only available at Expert level.

The **dialnorm** control word commands the decoder to adjust the playback level, serving as an automatic level control. For speech, the **dialnorm** figure is the equivalent loudness level with respect to full-scale, and the attenuation introduced in the decoder is $(31 + \text{dialnorm})$ dB with **dialnorm** being negative. A **dialnorm** figure of –5 produces an attenuation of 26 dB; a **dialnorm** figure of –31 produces an attenuation of 0 dB.

dialnorm2

dialnorm2 is a Dolby Digital control term, an abbreviation for “dialog normalization for the second audio program.”

dialnorm2 has the same meaning as **dialnorm**, except that it applies to the second audio channel when **acmod** indicates two independent channels (dual mono 1+1 mode). This setting is only available at Expert level.

Bitstream information

Bitstream information designates a group of Dolby Digital controls that includes **cmixlev**, **surmixlev**, **dsurmod**, **copyrightb**, **origbs**, **audprodie**,

mixlevel, **roomtyp**, **audprodi2e**, **mixlevel2**, **roomtyp2**, **langcod**, **langcode**, **langcod2** and **langcod2e**.

cmixlev

cmixlev is a Dolby Digital control term, as abbreviation for “center mix level.”

When 3 front channels are in use (**acmod** 3/0, 3/1, 3/2) this field indicates the nominal downmix level with respect to the left and right channels.

Only certain settings are valid for this control. Keyboard entries are rounded to the nearest valid setting.

Available settings are:

- **707 mX/Y (–3.0 dB).**
- **595 mX/Y (–4.5 dB).**
- **500 mX/Y (–6.0 dB).**

surmixlev

surmixlev is a Dolby Digital control term, an abbreviation for “surround mix level.” When surround channels are in use (**acmod** 2/1, 3/1, 3/1, 3/2) this field indicates the nominal downmix level of the surround channels with respect to the left and right channels.

Only certain settings are valid for this control. Keyboard entries are rounded to the nearest valid setting.

Available settings are:

- **707 mX/Y (–3.0 dB).**
- **500 mX/Y (–6.0 dB).**
- **0 mX/Y (off).**

dsurmod

dsurmod is a Dolby Digital control term, an abbreviation for “Dolby Surround mode.” When **acmod** is 2/0, this field indicates whether or not the stereo channels are Dolby Surround encoded or not. The “reserved” value of this setting is only available at Expert level.

Available settings are:

- **not indicated.**
- **not Dolby Surround encoded.**
- **Dolby Surround encoded.**
- **reserved.**

copyrightb

copyrightb is a Dolby Digital control term, an abbreviation for “copyright bit.”

When this bit is **1 (On)**, the information in the bitstream is indicated as protected by copyright. It has a value of **0 (Off)** if the information is not indicated as protected.

origbs

origbs is a Dolby Digital control term, an abbreviation for “original bitstream.” This bit is **1 (On)** if this is an original bitstream. The bit has a value of **0 (Off)** if this is a copy of another bitstream.

audprodie

audprodie is a Dolby Digital control term, an abbreviation for “audio production information exists.” When this bit is a 1, the **mixlevel** and **roomtyp** words exist, indicating information about the audio production environment (mixing room).

mixlevel

mixlevel is a Dolby Digital control term, an abbreviation for “mixing level.” This field indicates the absolute acoustic sound pressure level of an individual channel during the final mixing session. The available values are **80 dB SPL** to **111 dB SPL**. This setting is only available when **audprodie** is set to **On**.

roomtyp

roomtyp is a Dolby Digital control term, an abbreviation for “room type.” This field indicates the type and calibration of the mixing room used for the final audio mixing session. This setting is only available when **audprodie** is **On**.

Available settings are:

- not indicated.
- large room, X curve monitor.
- small room, flat monitor.
- reserved.

audprodi2e

audprodi2e is a Dolby Digital control term, an abbreviation for “audio production information for the second audio program exists.” **audprodi2e** has the same meaning as **audprodie**, except that it applies to the second audio channel when **acmod** indicates two independent channels (dual mono 1+1 mode). When this bit is a 1, the **mixlevel2** and **roomtyp2** words exist, indicating information about the audio production environment (mixing room). This setting is only available at Expert level.

mixlevel2

mixlevel2 is a Dolby Digital control term, an abbreviation for “mixing level for the second audio program.” **mixlevel2** has the same meaning as **mixlevel**, except that it applies to the second audio channel when **acmod** indicates two independent channels (dual mono 1+1 mode). This setting is only available at Expert level when **audprodi2e** is **On**.

roomtyp2

roomtyp2 is a Dolby Digital control term, an abbreviation for “room type for the second audio program.” **roomtyp2** has the same meaning as **roomtyp**, except that it applies to the second audio channel when **acmod** indicates two independent channels (dual mono 1+1 mode). This setting is only available at Expert level when **audprodi2e** is **On**.

langcode

langcode is a Dolby Digital control term, an abbreviation for “language code exists.” When this bit is a 1 (**On**), the next 8 bits represent a language code word **langcod**. This setting is only available at Expert level.

langcod

langcod is a Dolby Digital control term, an abbreviation for “language code.” This is an 8-bit reserved value. At Expert level when **langcode** is set to **On**, **langcod** can be set to a fixed value in the range 0 through 255.

langcod2e

langcod2e is a Dolby Digital control term, an abbreviation for “language code for the second audio program exists.” **langcod2e** has the same meaning as **langcode**, except that it applies to the second audio channel when **acmod** indicates two independent channels (dual mono **1+1** mode). This setting is only available at Expert level.

langcod2

lancod2 is a Dolby Digital control term, an abbreviation for “language code for the second audio program.” **langcod2** has the same meaning as **langcod**, except that it applies to the second audio channel when **acmod** indicates two independent channels (dual mono **1+1** mode). This setting is only available at Expert level when **langcod2e** is **On**.

Extended Bitstream information

Extended bitstream information designates a group of Dolby Digital controls that enable the selection of the extended bitstream syntax, the value used in the bitstream identification word (**bsid**), and the controls for the extended bitstream syntax including **xbsi1e**, **xbsi2e**, **dmixmod**, **ltrtcmixlev**, **ltrtsurmixlev**, **lorocmixlev**, **lorosurmixlev**, **dsurexmod**, **dheadphonmod**, **adconvtyp**, **xbsi2** and **encinfo**. The Time Code controls are also listed in this area of the grid, although they are not used in the extended bitstream.

See the sidebar on the legacy and extended bitstream syntaxes.

Extended bitstream

The Dolby Digital word **bsid** carries information about the version of Dolby Digital conveyed in the bitstream. When **bsid mode** is set to **Follow Extended bitstream setting**, **bsid** is set by the Extended bitstream selection here.

Selections are

- **On** (default).
if **bsid mode** is set to **Follow Extended bitstream setting**, **bsid** is set to **6** (Extended bitstream).
- **Off**.
if **bsid mode** is set to **Follow Extended bitstream setting**, **bsid** is set to **8** (legacy bitstream).

This setting is only available at Expert level.

The legacy bitstream and Extended bitstream syntaxes

The AC-3 (Dolby Digital) bitstream syntax described in ATSC A-52/A has been superseded by an extended bitstream syntax that includes the changes in A-52/A Annex C. The earlier syntax is referred to here as the legacy bitstream, and the current syntax is referred to as the Extended bitstream.

*The **bsid** value for the Extended bitstream is **00110** (=6); for the legacy bitstream it is **00100** (=8). Extended bitstream is the default bitstream syntax.*

*The **timecod1**, **timecod1e**, **timecod2** and **timecod2e** syntactical elements only exist in the legacy bitstream. These are replaced by the syntactical elements **xbsi1e**, **dmixmod**, **ltrcmixlev**, **ltrtsurmixlev**, **lorocmixlev**, **lorosurmixlev**, **xbsi2e**, **dsurexmod**, **dheadphonmod**, **adconvtyp**, **xbsi2**, and **encinfo** in the Extended bitstream.*

bsid mode

This command selects whether **bsid** automatically follows the setting in Extended bitstream, or whether the user can **Override** the automatic setting with a fixed setting. This setting is only available at Expert level.

Available settings for **bsid mode** are:

- **Follow Extended bitstream setting**
Uses the appropriate **bsid** value for either legacy bitstream or Extended bitstream, depending upon the Extended bitstream setting.
- **Override**
Allows you to enter a fixed value for **bsid**.

bsid

bsid is a Dolby Digital control term. **bsid** is an abbreviation for “bitstream identification.”

The value **6** identifies the bitstream as entirely compatible with the Extended bitstream, the Dolby Digital AC-3 bitstream defined in ATSC A/52-A Annex C. The Extended bitstream is the default setting.

The value **8** identifies the bitstream as entirely compatible with the legacy Dolby Digital AC-3 bitstream defined in ATSC A/52-A, without Annex C.

bsid is forced to follow the Extended bitstream setting except at Expert level, where a **bsid mode Override** is available.

xbsi1e

xbsi1e is a Dolby Digital control term, an abbreviation for “extra bitstream information #1 exists.” **xbsi1e** is only used in the Extended bitstream syntax. When this bit is **1 (On)**, the following settings are available: **dmixmod**, **ltrtcmixlev**, **ltrtsurmixlev**, **lorocmixlev** and **lorosurmixlev**. **xbsi1e** is set to **On** at Normal and Advanced levels, and may be set **Off** at Expert level.

dmixmod

dmixmod is a Dolby Digital control term, an abbreviation for “downmix mode.” **dmixmod** is only used in the Extended Bitstream syntax when **xbsi1e** is **On**. **dmixmod** indicates the type of stereo downmix preferred by the mastering engineer. The meaning of this field is only defined if **acmod** is 3/0, 2/1, 3/1, 2/2 or 3/2. This setting is only available at Advanced and Expert levels.

The available settings are:

- **not indicated.**
- **Lt/Rt downmix preferred.**
- **Lo/Ro downmix preferred.**
- **reserved.**

lorocmixlev

lorocmixlev is a Dolby Digital control term, an abbreviation for “Lo/Ro center mix level.” **lorocmixlev** is only used in the Extended Bitstream syntax when **xbsi1e** is **On**. **lorocmixlev** indicates the nominal downmix level of the center channel with respect to the left and right channels in an Lo/Ro (stereo) downmix. The meaning of this field is only defined if **acmod** is 3/0, 3/1 or 3/2. This setting is only available at Advanced and Expert levels.

Only certain settings are valid for this control. Keyboard entries are rounded to the nearest valid setting. Available settings are:

- **1.414 X/Y (+3.0 dB).**
- **1.189 X/Y (+1.5 dB).**
- **1.000 X/Y (0.0 dB).**
- **.841 X/Y (–1.5 dB).**
- **.707 X/Y (–3.0 dB).**
- **.595 X/Y (–4.5 dB).**
- **.500 X/Y (–6.0 dB).**
- **0 X/Y (–inf dB).**

lorosurmixlev

lorosurmixlev is a Dolby Digital control term, an abbreviation for “Lo/Ro surround mix level.” **lorosurmixlev** is only used in the Extended Bitstream syntax when **xbsile** is **On**. **lorosurmixlev** indicates the nominal downmix level of the surround channels with respect to the left and right channels in an Lo/Ro (stereo) downmix. The meaning of this field is only defined if **acmod** is 2/1, 3/1, 2/2 or 3/2. This setting is only available at Advanced and Expert levels.

Only certain settings are valid for this control. Keyboard entries are rounded to the nearest valid setting.

Available settings are:

- **1.414 X/Y (+3.0 dB).**
- **1.189 X/Y (+1.5 dB).**
- **1.000 X/Y (0.0 dB).**
- **.841 X/Y (–1.5 dB).**
- **.707 X/Y (–3.0 dB).**
- **.595 X/Y (–4.5 dB).**
- **.500 X/Y (–6.0 dB).**
- **0 X/Y (–inf dB).**

ltrtcmixlev

ltrtcmixlev is a Dolby Digital control term, an abbreviation for “Lt/Rt center mix level.” **ltrtcmixlev** is only used in the Extended Bitstream syntax when **xbsile** is **On**. **ltrtcmixlev** indicates the nominal downmix level of the center channel with respect to the left and right channels in an Lt/Rt (Dolby Surround) downmix. The meaning of this field is only defined if **acmod** is 3/0, 3/1 or 3/2. This setting is only available at Advanced and Expert levels.

Only certain settings are valid for this control. Keyboard entries are rounded to the nearest valid setting.

Valid settings are:

- **1.414 X/Y (+3.0 dB).**
- **1.189 X/Y (+1.5 dB).**
- **1.000 X/Y (0.0 dB).**
- **.841 X/Y (–1.5 dB).**
- **.707 X/Y (–3.0 dB).**

- **.595 X/Y (–4.5 dB).**
- **.500 X/Y (–6.0 dB).**
- **0 X/Y (–inf dB).**

ltrtsurmixlev

ltrtsurmixlev is a Dolby Digital control term, an abbreviation for “Lt/Rt surround mix level.” **ltrtsurmixlev** is only used in the Extended Bitstream syntax when **xbsi1e** is **On**. **ltrtsurmixlev** indicates the nominal downmix level of the surround channels with respect to the left and right channels in an Lt/Rt (Dolby Surround) downmix. The meaning of this field is only defined if the **acmod** is 2/1, 3/1, 2/2 or 3/2. This setting is only available at Advanced and Expert levels.

Only certain settings are valid for this control. Keyboard entries are rounded to the nearest valid setting.

Available settings are:

- **1.414 X/Y (+3.0 dB).**
- **1.189 X/Y (+1.5 dB).**
- **1.000 X/Y (0.0 dB).**
- **.841 X/Y (–1.5 dB).**
- **.707 X/Y (–3.0 dB).**
- **.595 X/Y (–4.5 dB).**
- **.500 X/Y (–6.0 dB).**
- **0 X/Y (–inf dB).**

xbsi2e

xbsi2e is a Dolby Digital control term, an abbreviation for “extra bitstream information #2 exists.” **xbsi2e** is only used in the Extended Bitstream syntax. When this bit is **1 (On)**, the following settings are available: **dsurexmod**, **dheadphonmod**, **adconvtyp**, **xbsi2** and **encinfo**. **xbsi2e** is set to **On** at Normal and Advanced levels, and may be set **Off** at Expert level.

dsurexmod

dsurexmod is a Dolby Digital control term, an abbreviation for “Dolby Surround EX mode.” **dsurexmod** is only used in the Extended Bitstream syntax when **xbsi2e** is **On**. **dsurexmod** indicates whether or not the program has been encoded in Dolby Surround EX. The meaning of this field is only defined if **acmod** is 2/2 or 3/2. This setting is only available at Expert level.

Available settings are:

- not indicated.
- not Dolby Surround EX encoded.
- Dolby Surround EX encoded.
- reserved.

dheadphonmod

dheadphonmod is a Dolby Digital control term, an abbreviation for “Dolby Headphone mode.” **dheadphonmod** is only used in the Extended Bitstream syntax when **xbsi2e** is **On**. **dheadphonmod** indicates whether or not the program has been Dolby Headphone-encoded. The meaning of this field is only defined if **acmod** is 2/0. This setting is only available at Advanced and Expert levels.

Available settings are:

- not indicated.
- not Dolby Headphone encoded.
- Dolby Headphone encoded.
- reserved.

adconvtyp

adconvtyp is a Dolby Digital control term, an abbreviation for “A/D converter type.” **adconvtyp** is only used in the Extended bitstream syntax when **xbsi2e** is **On**. This field indicates the type of A/D converter technology used to capture the PCM audio. This setting is only available at Advanced and Expert levels.

Available settings are:

- Standard.
- HDCD.

xbsi2

xbsi2 is a Dolby Digital control term, an abbreviation for “extra bitstream information #2.” **xbsi2** is only used in the Extended bitstream syntax when **xbsi2e** is **On**. This field is reserved for future assignment. This setting is only available at Advanced and Expert levels.

encinfo

encinfo is a Dolby Digital control term, an abbreviation for “encoder information.” **encinfo** is only used in the Extended bitstream when **xbsi2e** is **On**. This field is reserved for use by the encoder and is not used by the decoder.

This setting is only available at Advanced and Expert levels.

Time Code

Time Code designates a group of controls that are only used in the legacy bitstream syntax, including **timecod1e**, **timecod2e**, **hours**, **minutes**, **seconds**, **frames** and **64ths of a frame**. This field is only available at Expert level.

timecod1e

timecod1e is a Dolby Digital control term, an abbreviation for “time code first half exists.” **timecod1e** is only used in the legacy bitstream syntax, when Extended bitstream is set to **Off**. This field indicates whether the low resolution half of the time code information (**timecod1**, designating **hours**, **minutes** and **8-second** intervals) follows in the bitstream. This setting is only available at Expert level.

timecod2e

timecod2e is a Dolby Digital control term, an abbreviation for “time code second half exists.” **timecod2e** is only used in the legacy bitstream syntax, when Extended bitstream is set to **Off**. This field indicates whether the high resolution half of the time code information (**timecod2**, designating **seconds** from 0 to 7, **frames**, and **1/64ths of a frame**) follows in the bitstream. This setting is only available at Expert level.

Preprocessing

Preprocessing designates a group of controls that affect the audio signal before it is encoded to become the Dolby Digital signal. These include phase shift, and lowpass and highpass filters.

Channel Lowpass

Channel lowpass is a Dolby Digital preprocessing option that can apply a channel bandwidth lowpass filter to the main audio input channels for anti-aliasing. The cutoff frequency varies with data rate.

This filter is **Off** by default. Setting the filter **On** may affect frequency response.

This setting is only available at Expert level.

DC Highpass

DC highpass is a Dolby Digital preprocessing option that can apply a DC highpass filter to all audio input channels. Since the Audio Precision Digital Generator has no DC output unless specifically requested (for example, the **Sine: Sine + Offset** waveform), this filter is **Off** by default.

This setting is only available at Expert level.

LFE Lowpass

LFE lowpass is a Dolby Digital preprocessing option that can apply a 120 Hz lowpass filter to the LFE input channel for anti-aliasing purposes. This filter is On by default. The filter can be set to Off at Expert level when **lfeon** is set to **On**.

Phase Shift

Phase shift is a Dolby Digital preprocessing option that can apply a 90-degree Surround phase shift to the surround channels, when surround channels are in use (**acmod** 2/1, 3/1, 3/1, 3/2) enabling a true Dolby Surround Lt/Rt downmix to be created. When Phase Shift is on, the non-surround channels are time-delayed to match the delay created by the filter. Time Delay Only enables only the delay feature for all channels. This setting is not available at Normal level.

Phase shift is normally set **Off** for test signals and calibration, and on the IEC 61397 panel it is **Off** by default.

The selections available are:

- **Off.**
- **Time Delay Only.**
- **Surround Phase Shift.**

Dynamic Range Compression

Dynamic range compression designates a group of Dolby Digital controls that play a role in the dynamic range compression (DRC) of the signal.

Line mode compression

Line mode compression provides settings that affect the generation of the Line mode compression word **dynrng**. Generally, Line mode compression provides less aggressive gain reduction than RF mode compression. **dynrng** words occur at 5.3 ms intervals at a 48 kHz sample rate.

The first six settings (**None**, **Film Standard**, **Speech**, etc.) select the compression profile used by the dynamic range control (DRC) algorithm in computing the **dynrng** gain word. **Fixed** enables you to enter a fixed gain word in **dynrng**.

dynrng (dynamic range gain word exists) is set **Off** (bit set to **0**) when Line mode compression is set to **None**, and also whenever the value of **dynrng** = **0**. **dynrng** is **On** (bit set to **1**) when Line mode compression is **Fixed**. When Line mode compression is set to one of the five compression profiles **dynrng** may be **On** or **Off** in each audio block, depending upon the audio signal.

Available settings are:

- **None.**
No compression profile, **dynrng** set to 0.
- **Film Standard.**
Film Standard compression profile.
- **Film Light.**
Film Light compression profile.
- **Music Standard.**
Music Standard compression profile.
- **Music Light.**
Music Light compression profile.
- **Speech.**
Speech compression profile.
- **Fixed.**
No compression profile, **dynrng** set to fixed value entered in **dynrng**.

dynrng

dynrng is a Dolby Digital control term. **dynrng** is an abbreviation for “dynamic range gain word,” also called the “Line mode compression word.” This 8-bit word may be used to scale the audio dynamic range.

dynrng words are one of two forms of compression gain words used in Dolby Digital DRC (Dynamic Range Compression), the other form being **compr**.

When Line mode compression is set to **Fixed**, you can enter a fixed value for the **dynrng** compression gain word that will be applied to each audio block in the bitstream. However, if the DRC algorithm determines that there is danger of downmix overload for a particular audio block, the compression gain word for that audio block may be reduced from your desired value.

When **Fixed** is selected, the applied gain can be set as a decibel value. Allowable decibel values are within the range **-24.08** to **+23.95**.

RF mode compression

RF mode compression provides settings that affect the generation of the RF mode compression word **compr**. Generally, RF mode compression provides more aggressive overload protection than Line mode compression. **compr** words occur at 32 ms intervals at a 48 kHz sample rate.

The first six settings (**None**, **Film Standard**, **Speech**, etc.) select the compression profile used by the dynamic range control (DRC) algorithm in computing the **compr** gain word. **Fixed** enables you to enter a fixed gain word in **compr**.

compre (compression gain word exists) is set **On** (bit set to **1**) at all times.

compr words are intended for use in RF Mode; they occur at 32 ms intervals at a 48 kHz sample rate and generally yield greater negative values due to more aggressive overload protection than the **dynrng** words.

Available settings are:

- **None.**
No compression profile.
- **Film Standard.**
Film Standard compression profile.
- **Film Light.**
Film Light compression profile.
- **Music Standard.**
Music Standard compression profile.
- **Music Light.**
Music Light compression profile.
- **Speech.**
Speech compression profile.
- **Fixed.**
No compression profile, **compr** set to fixed value entered in **compr**.

compr

compr is a Dolby Digital control term, an abbreviation for “compression gain word,” also called the “RF mode compression word.” This 8-bit word may be used to scale the audio dynamic range.

compr words are one of two forms of compression gain words used in Dolby Digital DRC (Dynamic Range Compression), the other form being **dynrng**.

When RF mode compression is set to **Fixed**, you can enter a fixed value for the **compr** compression gain word that will be applied to each audio block in the bitstream. However, if the DRC algorithm determines that there is danger of downmix overload for a particular audio block, the compression gain word for that audio block may be reduced from your desired value.

When **Fixed** is selected, the applied gain can be set as a decibel value. Allowable decibel values are within the range **-48.16** to **+47.89**.

Impairments

Impairments designates a group of Dolby Digital controls that affect or describe the integrity of the bitstream, including **syncword**, **syncword mode**, and **crc1** and **crc2** enable. The normal settings can be overridden to test the behavior of a DUT when decoding an impaired bitstream.

crc1

crc1 is a Dolby Digital control term. **crc1** is an abbreviation for “cyclic redundancy check 1.” Dolby Digital frames use two CRC words. **crc1** comes first in the bitstream and covers the first 5/8 of the frame. **crc2** comes second in the bitstream and covers the entire frame.

crc1 is normally enabled but may be turned off at the Expert level of control.

Available settings at the Expert level of control are:

- **On** (valid checksums computed for CRC1 word).
- **Off** (CRC1 word set to all zeros).

crc2

crc2 is a Dolby Digital control term. **crc2** is an abbreviation for “cyclic redundancy check 2.”

Dolby Digital frames use two CRC words. **crc1** comes first in the bitstream and covers the first 5/8 of the frame. **crc2** comes second in the bitstream and covers the entire frame.

crc2 is normally enabled but may be turned off at the Expert level of control.

Available settings at the Expert level of control are:

- **On** (valid checksums computed for CRC2 word).
- **Off** (CRC2 word set to all zeros).

syncword

syncword is a Dolby Digital control term, an abbreviation for “synchronization word.” The 16-bit syncword is always sent, and in normal operation is always **0x0B77** (0000 1011 0111 0111). **syncword** can be set to other values when **syncword mode** is set to **Override**. This setting is only available at Expert level.

syncword mode

syncword mode selects whether **syncword** is set normally or whether the user can **Override** that setting by entering a value in **syncword**. This setting is only available at Expert level.

IEC 61937 bitstream and controls

NOTE: Streaming audio hardware components and application-specific software must be purchased, installed and licensed for your instrument for IEC 61937 features to function. See OPT-2711 Required Components on page 222.

See the IEC 61937 sidebar below.

The entire specification of the IEC 61937 bitstream and its application are subjects much too complex to address in this User’s Manual. For more information we refer you to the sources listed on page 224.

An IEC 61937 bitstream consists of data-bursts and “stuffing” inserted into the IEC 60958 bitstream. The data-bursts consist of burst-preamble words and burst-payload words.

IEC 61937

In the standard document IEC 61937, the International Electrotechnical Commission (www.iec.ch) defines a means of conveying non-linear PCM encoded bitstreams embedded in an IEC 60958 bitstream. IEC 61937 provides a mapping into IEC 60958 along with bitstream preambles and idle and pause modes to maintain a consistent and robust signal. Most of the IEC 61937 bitstream is left available for carrying encoded audio and metadata related to the encoding system.

Various encoding systems have been designed to convey audio using IEC 61937, including Dolby Digital (AC-3), DTS, MPEG and ATRAC systems.

Choosing the Data-type selects the type of burst-payload that is inserted into the bitstream and displays the controls available for that data-type. The Dolby Digital data-type is discussed beginning on page 192; the Idle and Pause data-types are discussed below.

The IEC 61937 Preambles controls enable you to make settings that affect certain burst-preamble words. Preambles controls are discussed beginning on page 115.

Levels of Control

The IEC 61937 Idle, Pause and Preambles controls are subject to level of control settings. Idle and Pause can be viewed at Normal and Advanced levels of control; Preambles controls are only visible at Advanced and Expert levels. See page 191 for more information about levels of control.

IEC 61937 Idle Data-type (Null data-bursts)

The IEC 61937 bitstream Data-type can be set to Idle when there is no audio data to be sent. When the bitstream is idle, a null data-burst is inserted occasionally in to the bitstream. Placement of null data bursts allows sync codes to be detected, enabling a decoder with autodetection to realize that the subframe contents should be considered to be IEC 61937 data and not linear PCM audio. The use of null data-bursts is optional.

At the Normal level of control when the Data-type is set to **Idle**, a null data-burst is sent at intervals of 4096 samples. There are no user settings available for the IEC 61937 Idle bitstream at the Normal level of control.




Figure 173. The IEC 61937 panel with Data-type = Idle at Advanced level of control.

Send Null Data-Bursts

Send Null Data-Bursts is an IEC 61937 control that inserts null data-bursts into the IEC 61937 bitstream to indicate that the IEC 61937 interface is operating but idle, for those decoders that do not check the IEC 60958 validity bit. This setting is only available at Advanced level when Data-type is set to Idle.

Available settings are:

- **On.**
- **Off.**

When Send null data-bursts is **On**, the Null data-burst repetition period control becomes active, and you can specify the interval between null data-bursts. The acceptable range is **3** to **65535** samples (IEC 60958 frames). A value of 4096 or less is recommended for reliable autodetection.

Null data-burst repetition period

This is an IEC 61937 setting, only available at the Advanced level of control when Data-type is set to Idle.

This field specifies how often a null data-burst is sent. The range is **3** to **65535** samples (IEC 60958 frames). The recommended value is 4096 or fewer samples.

Null data-burst repetition period is forced to 4096 at the Normal level of control.

Pause Data-type

Occasionally, discontinuities may occur in the IEC 61937 bitstream between audio data-bursts due to bitstream switching. Pause data-bursts enable the decoder to conceal the discontinuity; pause data-bursts can also be used before transmission of a first audio data-burst for synchronization purposes. The length of the discontinuity is called the *gap*.

When the bitstream Data-type is set to **Pause**, a pause data-burst is inserted into the bitstream.




Figure 174. The IEC 61937 panel with Data-type = Pause at Normal level of control.

Pause data-burst repetition

Only one user setting is available for the IEC 61937 Pause bitstream at the Normal level of control, **Pause data-burst repetition**.

Pause data-burst repetition sets the pause data-burst repetition period to the recommended or mandatory period in samples (IEC 60958 frames) for various encoding systems, set by choosing the encoding system. The control shown at the Normal level of control is a subset of Pause data-burst repetition mode control available at the Advanced level and described below. In a New Test Pause data-burst repetition is set to **Dolby Digital (3 samples)**.




Figure 175. The IEC 61937 panel with Data-type = Pause at Advanced level of control.

(Pause) Data-burst repetition mode

Pause data-burst repetition mode sets Pause data-burst repetition period to the recommended or mandatory period in samples (IEC 60958 frames) for various encoding systems, set by choosing the encoding system. This setting can be overridden by selecting Override and entering a value in Pause data-burst repetition period.

Choose from the following selections:

- **Dolby Digital (3 samples).**
Dolby Digital (AC-3) [Recommended repetition period: 3 samples].
- **MPEG-1/2 (32 samples).**
MPEG-1 layer 1, 2 or 3 and MPEG-2 [Mandatory repetition period: 32 samples].
- **MPEG-2 low Fs (64 samples).**
MPEG-2 layer-1, 2 or 3 low sampling frequency [Mandatory repetition period: 64 samples].
- **DTS (3 samples)**
DTS Type I, II, or III. [Recommended repetition period: 3 samples].
- **MPEG-2 AAC (32 samples).**
MPEG-2 AAC [Recommended repetition period: 32 samples].
- **Override.**
Advanced level of control only. Enables entry in data-burst repetition period. The range is **3** to **65535** samples.

At the Normal level of control, the pause data-burst repetition period is forced to the recommended or mandatory value for the selected encoding system.

(Pause) data-burst repetition period

Pause data-burst repetition period is an IEC 61937 control that determines how often the pause data-burst is sent. The range is **3** to **65535** samples (IEC 60958 frames). The default varies with the encoding system, but is 3 samples for Dolby Digital. This setting is only available at Advanced level, when Pause data-burst repetition mode is set to **Override**.

gap-length mode and gap-length

When a pause data-burst is sent, the expected length of stream gaps or audio gaps may be optionally sent. This information is called the *audio gap length parameter* or *gap length*.

At the Advanced level of control, you may select these options for gap length mode:

- **Not Specified.**

Not Specified does not specify a gap length. The gap-length word is set to all zeros.

- **Normal.**

In Normal mode, the gap length in samples (IEC 60958 frames) is set to equal the current Pause data-burst repetition period.

- **Override.**

Override enables a gap length value to be specified in the gap length field. Gap length can be set from **3** to **65535** samples (IEC 60958 frames).

At the Normal level of control, the gap length mode is forced to **Normal**.

Preambles controls

Each IEC 60937 data-burst contains a burst-preamble consisting of four preamble words: Pa, Pb, Pc and Pd.

Pa and Pb are used for synchronization.

At the Advanced and Expert levels of control, at the bottom of the IEC 61937 panel grid is a group of Preambles controls. These allow you to make settings in the Pc preamble word (**data-type**, **reserved bits**, **error-flag**, **data-type-dependent info** and **bitstream number**) and in the Pd preamble word (**length-code**).

Data-type mode

This is an IEC 61937 bitstream setting.

The preamble data-type mode selects whether the data-type indicated in the IEC 61937 burst-info preamble is set by the Data-type selection at the top of the panel, or whether the preamble indication is to be overridden. This setting is only available at Advanced level.

Available settings for preambles Data-type mode are:

- **Normal.**

Normal uses the data-type set in the IEC 61937 panel Data-type control.

- **Override.**

Override uses the data-type set in the following field, the preambles Data-type field.

Data-type mode is forced to Normal at the Normal level of control.

NOTE: Data-type mode only sets the indicated data type, bits 0 thru 4 of the burst-preamble. It does not change the actual format of the burst-payload. Use the Data-type drop-down to change the format of the burst-payload.

Data-type (preambles)

Data-type (preambles) sets the IEC 61937 burst-info preamble indication (bits 0 thru 4) of the type of data-bursts in the bitstream: pause data-bursts, null data-bursts or audio data-bursts; further, for audio data-bursts it indicates the audio coding system. This setting is only available at the Advanced or Expert level when Data-type mode is set to **Override**.

On the IEC 61937 panel, the format of the burst-payload and the preambles data-type indication is normally set by the Data-type control, which appears as a drop-down list at the top of the panel.

At Advanced and Expert levels of control, the data-type code in the burst-preamble may be overridden by the Data-type mode and Data-type (preambles) field. Note that this changes the preamble bit, but does not change the format of the burst-payload.

One of the following settings may be selected:

- **Null Data.**
- **AC-3 Data (Dolby Digital).**
- **Pause.**
- **MPEG-1 Layer 1 Data.**
- **MPEG-1 Layer 2 or 3, or MPEG-2 No Extension.**
- **MPEG-2 with Extension.**
- **MPEG-2 AAC ADTS.**
- **MPEG-2 Layer 1 Low Sampling Freq.**
- **MPEG-2 Layer 2 or 3 Low Sampling Freq.**
- **DTS Type I.**
- **DTS Type II.**
- **DTS Type III.**
- **ATRAC.**
- **ATRAC2/3.**
- **Numeric Code.**

Data-type code

Data-type code sets the value of the 5-bit IEC 61937 data-type code in the burst-info preamble when the preambles Data-type control is set to **Numeric Code**. Values range from **0** to **31**. This setting is available at the Advanced and Expert levels of control.

Reserved bits

There are two reserved bits (bits 5 and 6) in the IEC 61937 burst-info preamble, normally set to 0. At Advanced or expert level the reserved bits can be set to a fixed integer value in the range **0** through **3**.

Error flag

An error flag (bit 7 of the burst-preamble) can be set if the contents of the data-burst contain data errors. At Advanced or Expert level the error-flag bit can be fixed at **0** or **1**.

Data-type-dependent info mode

Data-type-dependent information varies with the data-type. For example, in Dolby Digital, the data-type-dependent information carries the value of **bsmod** in the AC-3 elementary stream. For MPEG data types, the data-type-dependent information can indicate the use of second stereo or karaoke channels, and existence of dynamic range control.

On the IEC 61937 panel, the data-type-dependent information normally tracks the Data-type setting. At the Advanced or Expert level of control, this behavior can be overridden.

Available settings for data-type-dependent info mode are:

- **Normal.**

Normal uses the data-type-dependent information for the current Data-type.

- **Override.**

Override uses the data-type-dependent information value set in the following field, the Data-type-dependent info field.

Data-type-dependent info mode is forced to **Normal** at the Normal level of control.

Data-type-dependent info

Data-type-dependent information varies with the Data-type.

For Audio Precision testing, the data-type-dependent information normally tracks the Data-type. At the Advanced or Expert level of control when Data-type-dependent-info mode is set to **Override**, this behavior can be overridden, and a numeric value may be entered in the Data-type-dependent-info field.

Bitstream number mode

Bitstream number mode selects whether Bitstream number is set normally or whether the user can **Override** that setting by entering a value in Bitstream number. Preambles controls are not available at Normal level of control, and will be reset to default values when Normal level of control is selected.

Bitstream number

Up to 8 independent IEC 61937 bitstreams may be carried in the IEC 60958 bitstream in a time multiplex. Bitstream number indicates to which bitstream the data-burst belongs. At the Advanced or Expert level when Bitstream number mode is set to **Override**, Bitstream number can be set to a fixed integer value in the range **0** through **7**. Preambles controls are not available at Normal level of control, and will be reset to default values when Normal level of control is selected.

Length-code mode

Length-code mode selects whether Length-code is set normally or whether the user can **Override** that setting by entering a value in Length-code. This setting is only available at the Advanced or Expert level of control.

Length-code

The length-code indicates the length of the burst-payload in bits. The size of the preamble is not counted in the value of the length code.

At the Advanced or Expert level when Length-code mode is set to **Override**, Length-code can be set to a fixed integer value in the range **0** through **65535**.

Sweepable parameters

The following Dolby Digital parameters can be swept:

- cmixlev.
- compr.
- dialnorm.
- mixlevel.
- surmixlev.

Sweep settling and IEC 61937 processing

The digital audio signal is delayed as it passes through the Dolby Digital / IEC 61937 encoding process. The amount of signal delay varies with the sample rate.

A new checkbox has been added to the bottom of the Settling panel, allowing you to modify the settling algorithms to account for the encoding delay.

OPT-2711 Required Components

To use the Dolby Digital Generator, you must have the OPT-2711 hardware components installed in your Audio Precision instrument, and you must have the instrument activated via the Audio Precision Web site using your software license key code. Both installation and activation are normally done by the factory or factory representative before delivery.

APSI: the Audio Precision Streaming Interface

When you purchase the OPT-2711 Dolby Digital Generator option, hardware components for the Audio Precision Streaming Interface (APSI) are installed in your instrument.

APSI is a proprietary high-speed two-way streaming audio interface that enables your instrument to exchange streaming audio data with the control PC via a USB 2.0 connection for IEC 61937 and Dolby Digital processing. APSI does not replace the Audio Precision Interface Bus (APIB) control connection, which is still necessary for system control. The APSI connector is on the instrument rear-panel DDR panel of all recent 2700 series instruments, but the internal APSI circuitry is only installed with the OPT-2711 option.

To verify the installation of APSI hardware, go to **Utilities > Hardware Status** as shown in Figure 176.

Figure 176. Hardware Status panel confirming installation of APSI hardware.



Using the cable provided with your OPT-2711 installation kit, connect the APSI to a USB 2.0 port on your PC.

OPT-2711 Licensing

The software features associated with the OPT-2711 Dolby Digital Generator will not function without connection to a measurement instrument that has an activated software license. This activation is normally provided from the factory or factory representative with purchase of OPT-2711. The activation is keyed to the instrument, not to the software or the PC.

Go to **Utilities > Manage Software Licenses** to view or change the activation status of your OPT-2711 Dolby Digital Generator license. If your PC is connected to an instrument with an activated a license, the panel will identify it as shown in Figure 177.




Figure 177. Manage Software Licenses panel confirming active Dolby Digital license.

It is possible to move a software license from one Audio Precision instrument to another (although both instruments must have the APSI hardware in-

stalled). Your OPT-2711 License document has your activation code and instructions for connecting to the Internet and the steps to take to activate your license on a different instrument. Contact your Audio Precision distributor or visit the Audio Precision Web site at www.audioprecision.com for more information.

References

Information on Dolby Digital can be obtained from Dolby Laboratories at www.dolby.com/tech.

The AC-3 (Dolby Digital) encoding, bitstream and metadata are defined in the Advanced Television Systems Committee (ATSC) standard document “The Digital Audio Compression Standard—ATSC A/52-A and Annex C to that document. ATSC A/52-A can be obtained from Dolby or the ATSC at www.atsc.org.

The IEC 61937 standard is defined in the document “IEC 61937—Digital audio—Interface for non-linear PCM encoded audio bitstreams applying IEC 60958,” available from the International Electrotechnical Commission at www.iec.ch.

Chapter 11

The DSP Audio Analyzer

Overview

The DSP Audio Analyzer is a DSP analysis tool selection on the Digital Analyzer panel. Similar in a number of ways to the Analog Analyzer, it is one of the key audio analysis tools available in the 2700 series. The DSP Audio Analyzer can measure audio level, frequency, noise, THD+N, crosstalk, phase and more, with a wide selection of filters and detector characteristics.

This chapter examines each function, control and display of the DSP Audio Analyzer in detail. If you are new to the 2700 series, you might want to start with the Quick Guides in *Getting Started with Your 2700 Series Instrument*, which will introduce you to DSP Audio Analyzer features.

The DSP Audio Analyzer will measure either digital or analog domain audio input signals, as selected by the Input field. It is a two-channel analysis tool, capable of performing measurements on both channels of a stereo signal at the same time. For an analog signal, the DSP Audio Analyzer can measure a frequency range from DC to about $0.45 \times F_s$, where F_s is the sample rate of the ADC selected from the Input list; for digital signals, the DSP Audio Analyzer can measure a frequency range from DC to $0.5 \times F_s$.

There are three pairs of meters on the DSP Audio Analyzer that measure the input signal simultaneously:

- the **Level** meters,
- the **Freq.** (frequency) meters, and
- the **Function Reading** meters, which display the results of the current selected analysis tool.

These are discussed in detail later in the chapter. As on other 2700 series panels, you can select the units of measurement you prefer for each reading display. Other fields on the DSP Audio Analyzer panel allow you to choose cou-





Figure 178. Conceptual Block Diagram, DSP Audio Analyzer. The gray block represents the main DSP analysis module of the DSP Audio Analyzer, which can be set to operate in one of eight measurement modes, selectable from the Measurement Function list on the DSP Audio Analyzer panel.

pling, filter, detector and level reference options. Some of these options, however, apply only to the Function meters.

The Measurement Function selection determines the analysis tool to be used by the DSP Audio Analyzer and the type of results shown in the Function meter displays; unit, detector and filter options available are a consequence of this selection.

Loading the DSP Audio Analyzer

Figure 179. Loading the DSP Audio Analyzer.



To use the DSP Audio Analyzer, first open the Digital Analyzer panel. The Digital Analyzer panel is a command selection on the Panel menu, and is also available by the keyboard shortcut **Ctrl+Y**, or by clicking the **Analyzer** button on the Toolbar.



Figure 180.
The DSP Audio Analyzer panel.



Signal Inputs

Figure 181.
DSP Audio Analyzer panel inputs.



The Input field enables you to choose the digital input or the analog inputs (converted to digital) as the signal applied to the DSP Audio Analyzer. The selections are:

- **Digital @ISR**
- **HiRes A/D @65536**
- **HiBW A/D @131072**
- **HiBW A/D @262144**
- **HiRes A/D @SSR**
- **HiBW A/D @2xSSR**

The digital input and converter choices are the same for all five of the DSP audio analysis tools (DSP Audio Analyzer, Spectrum Analyzer, Multitone Analyzer, MLS Analyzer and Harmonic Distortion Analyzer).

Digital @ISR

The **Digital @ISR** choice selects the current digital input signal at the input sample rate (ISR).

The digital signal is routed through the instrument digital input, which is selected and configured on the DIO panel and applied directly to the Digital Analyzer. To configure digital input connectors, digital input format and other aspects of interface, go to the DIO panel (see Chapter 9).

HiRes A/D & HiBW A/D

The five analog choices (the A/D choices) select the current analog input signals. Analog signals are routed through the instrument analog inputs, which are selected and configured on the Analog Analyzer panel and are digitized by precision ADCs before being applied to the Digital Analyzer. To configure analog input connectors and analog domain range, coupling, etc., go to the Analog Analyzer panel (see Chapter 8).

Converter and Sample Rate Selection

The Digital Analyzer tools perform their signal analysis in DSP, and analog input signals must be converted to the digital domain using analog-to-digital converters (ADCs). 2700 series instruments with both analog and DSP capabilities are equipped with a 24-bit high-resolution ADC (**HiRes A/D**) and a 16-bit high-bandwidth ADC (**HiBW A/D**). You can choose either of these ADCs at various sample rates from the Input selection list.

- **HiRes A/D @65536.** This selection uses the high-resolution ADC and is the normal choice for most audio testing. The high-resolution ADC provides 10 dB to 15 dB better residual distortion than the high-bandwidth ADC, and when the ADC sample rate selection is 65,536 Hz the frequency response extends past the audio band to 30 kHz.
- **HiBW A/D @131072.** This selection uses the 16-bit high-bandwidth ADC, which offers considerably higher sample rates and signal bandwidths than the high-resolution ADC, at the trade-off of lower resolution. When set at a sample rate of 131,072 Hz, the frequency response increases to 60 kHz.
- **HiBW A/D @262144.** This selection uses the high-bandwidth ADC. At this sample rate setting, the frequency response is extended to 120 kHz.
- **HiRes A/D @SSR.** This selection uses the high-resolution ADC, but the value of the sample rate is the System Sample Rate (SSR). You cannot directly set SSR, but it is related to the Sample Rate (SR) setting on the Digital Input/Output (DIO) panel. The range of SSR is from 8 kHz to 108 kHz.
Some tests, such as multitone analysis, require that the digital signal applied to the DSP be synchronous with the SSR, and the **SSR** and **2xSSR** selections can accommodate that synchronization. See **Sample Rate (SR)**, **Sample Rate Range** and **System Sample Rate (SSR)** beginning on page 157.
- **HiBW A/D @2xSSR.** This selection uses the high-bandwidth ADC, but the value of the sample rate is twice the System Sampling Rate (SSR). The range of 2xSSR is 16 kHz to 216 kHz.

NOTE: The sample rate values 65,536 and 131,072 are powers of two, as are the FFT Length selections in the 2700 series FFT-based analysis programs. Use of these sample rates when performing FFT analysis produces bin widths that are integer numbers of hertz. For example, with an analyzer FFT length of 32,768 samples and a 65,536 sample rate, the resulting bin widths are exactly 2.00 Hz.

Source


Although other Digital Analyzer DSP tools offer Source selection to specify channel acquisition, analyzer connection point or jitter acquisition, for the DSP Audio Analyzer the signal channel sources are fixed and there is no Source selection field.

For the **Digital @ISR** input, the embedded channel A audio is routed to Channel A of the DSP Audio Analyzer, and the embedded channel B audio is routed to Channel B.

For the analog (**A/D**) inputs, the digitized signal from Analog Input A is routed to DSP Audio Analyzer Channel A, and the signal from Input B is routed to Channel B. The ADCs pick up the analog input signals after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; these are the same circuit points that appear as **Anlr-A** and **Anlr-B** in other Digital Analyzer DSP tools Source selection lists, and are essentially the same points that are connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL A and CHANNEL B, which appear on the front panel on BNC connectors.

Coupling

Figure 182.
The DSP Audio Analyzer Coupling Selections.



The Coupling selections in the DSP Audio Analyzer affect only the Level meter readings. The Function tools always have a high-pass filter in the measurement path, and therefore are always ac coupled. See the block diagram in Figure 178.

The Coupling functions are accomplished in DSP. The choices are:

- **AC Coupled**

AC Coupled provides flat response across the audio passband to below 10 Hz. The dc component of the signal is blocked.

- **DC Coupled**

DC Coupled provides flat response across the audio passband to 0 Hz (dc).

■ DC Only

DC Only implements a low-pass filter that has a very low corner frequency, essentially removing the audio signal and leaving only the dc component.

For analog inputs to the DSP Audio Analyzer, there is an additional Coupling selection affecting the signal in the analog domain. This control is located on the Analog Analyzer panel. When an analog input is selected for the DSP Analog Analyzer, you must consider the effects of the both coupling selections. See **DC Coupling of Analog Signals** on page 127.

When making common-mode tests, small dc offsets from the DUT can result in significantly different measurements. If your test objectives do not require measurements that extend below the audio range to dc, it is advisable to use ac coupling, blocking any dc offset.

The Level Meters

Figure 183.
The DSP Audio Analyzer Level Meters.



Two Level meters are located near the top of the DSP Audio Analyzer panel, one for each input channel. The Level meters display the audio amplitude of the input signals. These meters are true rms meters, using a normal or a fast rms detector as selected in the right-hand Detector (Det) field lower on the panel. Level meters have selectable coupling, as discussed above.

The meter detectors are discussed in more detail on page 249.

*NOTE: Detector choices affect both the Level meters and the Function meters. However, the **Q-Peak** choice is only effective on the Function meters. If **Q-Peak** is selected, the Level meters use a normal rms detector.*

Level Meter Units

If you click on the arrow to the right of either Level meter reading field, a list of measurement unit choices will drop down. The units shown on the list depend upon whether an analog converter or **Digital@ISR** is selected in the Input field.

With **Digital@ISR** selected as the input, the units list includes

- digital domain units: **FFS**, **dBFS**, **%FS** and **Bits**;
- relative units: **dBr A** and **dBr B**;
- and units relative to the analog domain: **V**, **dBu**, and **dBV**.

These analog domain units are calculated relative to the value you enter in the **V/FS** field in the References area of the panel, and can be helpful in cross-domain measurements. When measuring an ADC, for example, you could enter the full-scale analog input voltage of the converter into the **V/FS** field and view your results here using one of the analog domain units available.

With an analog converter selected as the input, the units list includes:

- analog domain units: **V**, **dBu**, **dBV**, and **W** (watts).
- relative units: **dBr A**, **dBr B**, **dBg A**, **dBg B**;
- and units relative to the digital domain: **FFS**, **dBFS** and **%FS**.

For an explanation of the units of measurement used in the 2700 series and the references for the relative units, go to Appendix A, **Units of Measurement**.

The Frequency Meters

Figure 184.
The DSP Audio Analyzer
Frequency Meters.



The frequency of the signals on the two channels are shown in the Freq meter fields, just below the Level meter readings. In documentation, the frequency meters are sometimes called frequency *counters*.

The units of measurement include:

- the measured frequency in **Hz**, and
- relative frequency units: **F/R**, **dHz**, **%Hz**, **cent**, **octs**, **decs**, **d%** and **dPPM**.

All the relative frequency units are computed with respect to the frequency value entered in the Digital References: Freq field lower on the panel. For specific definitions of these relative frequency units, see the **Frequency Units** discussion on page 530.

Meter Ranging

Figure 185.
The DSP Audio Analyzer
Ranging / Autoranging controls.



Most devices have an optimum amplitude operating range in which they exhibit their best performance. The 2700 series gives you the choice of automatic ranging (or *autoranging*) or a manually-set fixed maximum range.

There are two independent ranging functions within the DSP Audio Analyzer, as shown on Figure 185. On the panel, the upper set of Ranging controls acts on the channel A or B signals applied to the Level meters and Frequency meter displays. The lower set of Ranging controls acts on the two channels of the Function meter.

NOTE: There are additional ranging functions in the analog input circuits. If you are using an analog converter input to the DSP Audio Analyzer, the settings of the upper pair of ranging controls on the Analog Analyzer panel will also affect your measurement. See page 129.

Autoranging

The DSP Audio Analyzer is normally operated with automatic ranging, indicated by a check mark in each of the appropriate Range check boxes. This provides operation with no possibility of clipping due to high-amplitude signals.

Click the Range check box to defeat autoranging. The range setting field for that meter and channel will become active, and you can enter a fixed maximum range for that input.

Fixed Range


Using a fixed range produces faster measurements. This can be important when speed is at a premium, as within a repetitive routine in an automated testing procedure. However, you must know the probable range of the signal and set the fixed range maximum above the highest expected level.

Manual range selection is also preferred when listening to program material such as voice or music on the built-in loudspeaker or via the headphone jack. Automatic ranging will constantly switch levels when a complex, wide-range signal is applied. This may make it difficult to adjust a device for minimum distortion or noise, for example.

The 2700 series ranges are implemented in discrete steps. When selecting a fixed range, enter the maximum expected value into the Range field. The control software will select the next range which accommodates that value.

The Function (Reading) Meters

Figure 186.
The DSP Audio Analyzer
Function Meters.



The Function (Reading) meters located in the center of DSP Audio Analyzer panel can measure the input signal in a number of different ways by applying different measurement functions, with added options such as signal filtering and additional an detector selection.

*NOTE: Due to panel space limitations, the Function (Reading) meters are labeled **Reading** on the DSP Audio Analyzer panel. In documentation, they are generally referred to as the Function meters.*

The Function meters are the real power of the DSP Audio Analyzer. Most of the measurements you will make with the DSP Audio Analyzer will be using the Function meters, with the Level meters as secondary signal monitors.

Function Meter Measurement Functions

The Function meter measurement function selections are:

- **Amplitude**
- **2-Ch Ratio**
- **Crosstalk**
- **THD+N Ratio**
- **THD+N Ampl**
- **Bandpass**
- **SMPTE/DIN**
- **Phase**

Each function is discussed in detail below.

Amplitude Function

Figure 187 shows a conceptual block diagram of the DSP Audio Analyzer with the **Amplitude** function selected.




Figure 187. Conceptual Block Diagram, DSP Audio Analyzer, **Amplitude** function.

The **Amplitude** function measurements are similar to the Level meter measurements. In certain configurations the **Amplitude** function readings will be identical to the Level meter readings.

Amplitude function measurements can differ from Level meter measurements for several reasons:

- Ranging can be set independently for the Level and Function meters.
- Level meters have selectable coupling, while the Function meters are always ac coupled.
- In addition to the two rms detectors, Function meter measurements may be made with the quasi-peak detector; the Level meters always use one of the rms detectors.
- Function meter **Amplitude** measurements are affected by the highpass, lowpass, and weighting filter selections made in the BW and Fltr fields, while Level meter readings are always unfiltered.

Since the Level meters have no equalization or filtering available, you must use the **Amplitude** function for weighted or band-limited noise measurements.

2-Channel Ratio Function

Figure 188 shows a conceptual block diagram of the **DSP Audio Analyzer** with the **2-Channel Ratio** function selected.




Figure 188. Conceptual Block Diagram, **DSP Audio Analyzer, 2-Channel Ratio Function.**

The **2-Ch Ratio** function displays the ratio of the signal amplitudes in the two channels, A and B. The Channel A Function meter shows the ratio A/B, and the Channel B Function meter shows the ratio B/A.

2-Ch Ratio may be expressed in %, dB, or X/Y units. The **2-Ch Ratio** function is useful while balancing stereo channels, for example; or for measuring gain or loss by connecting the **DSP Audio Analyzer** A channel across the DUT input and the B channel across the DUT output.

Crosstalk Function

Figure 189 shows a conceptual block diagram of the DSP Audio Analyzer with the **Crosstalk** function selected.




Figure 189. Conceptual Block Diagram, DSP Audio Analyzer, **Crosstalk** Function.

The **Crosstalk** function measures the leakage, or crosstalk, of a sine wave from one channel to the other. A typical crosstalk test uses a stereo stimulus, with each channel driven with a sine wave of different frequency.

For each analyzer channel, a bandpass filter is steered to the frequency in the opposite channel. The amplitude measured at this frequency is the absolute

crosstalk value. The percentage of the opposite channel's signal amplitude (as measured by the **Level** meter) represented by the absolute crosstalk value of the channel under consideration is displayed in the channel's function meter.

For example, consider a stimulus with a 2 kHz sine wave on Channel A and a 5 kHz sine wave on Channel B. In the DSP Audio Analyzer, the Channel A bandpass filter is steered to 5 kHz, a measurement is made, and the percentage of the Channel B Level meter reading this crosstalk measurement represents is computed and displayed in the Channel A Function meter display.

Likewise, the DSP Audio Analyzer Channel B bandpass filter is steered to 2 kHz, a measurement is made, and the percentage of the Channel A Level meter reading this crosstalk measurement represents is computed and displayed in the Channel B Function meter display. Choose frequencies that are at least one octave apart to minimize errors due to overlap of the filters.

Crosstalk is a ratio, expressed as:

$$\text{Crosstalk from B to A} = \frac{\text{Level of } F_1 \text{ in A}}{\text{Level of } F_1 \text{ in B}}$$

When only one channel is driven, a **Crosstalk** percentage reading for the driven channel will display absurdly high percentages, since the denominator of the fraction (the un-driven channel level) is very close to zero. Also, since the source of the denominator is a Level meter, which is unfiltered, spurious frequencies and noise may produce erroneous **Crosstalk** ratios. In this case, a pre-analyzer filter may be useful.

Crosstalk may be expressed in %, dB, or X/Y units. The Channel A Function meter shows the percentage of the signal crossed from B into A, and the Channel B Function meter shows the percentage of the signal crossed from A into B.

Since the bandpass filter will reject most wide-band noise, the **Crosstalk** function provides more accurate measurements of low-amplitude signals in the presence of noise. The filter must be tuned to the frequency of the signal on the opposite channel; see **BP/BR Filter Tuning** on page 257.

The **BW** (high-pass and low-pass) and **Fltr** (weighting) filter selections are not available for the **Crosstalk** function.

THD+N Ratio and Amplitude Functions

Figure 190 shows a conceptual block diagram of the **DSP Audio Analyzer** with the THD+N functions selected.




Figure 190. Conceptual Block Diagram, DSP Audio Analyzer, THD+N Functions.

The two THD+N (total harmonic distortion plus noise) functions use bandreject (notch) filters to remove the fundamental sine wave signal so that the detector can measure the remaining harmonic distortion products and noise.

The bandreject filter center frequencies may be fixed, or may track one of several parameters. See **BP/BR Filter Tuning** on page 257.

THD+N Ratio Function

The **THD+N Ratio** function expresses the sum of the distortion products and noise amplitudes relative to the amplitude of the unfiltered signal (as measured by the **Level** meter); in other words, the result is a THD+N-to-signal ratio. Units of % and **dB** (decibels below the fundamental) are ordinarily used with the **THD+N Ratio** function.

THD+N Ratio is the common way to express distortion. However, in an amplitude sweep **THD+N Ratio** appears to show increasing distortion and noise with decreasing signal amplitude because the distortion and noise is stated as a ratio to the decreasing signal. The **THD+N Ampl** function may be more useful for amplitude sweeps.

Results using the **THD+N Ratio** function may be expressed in %, **dB**, or **X/Y** units.

THD+N Amplitude Function

The **THD+N Ampl** (amplitude) function expresses the amplitude of the distortion products and noise in absolute units, independent of the amplitude of the fundamental signal. Although the previous function, **THD+N Ratio**, is used much more commonly, **THD+N Ampl** is particularly useful when performing amplitude sweeps of audio devices, since it helps make clear that the noise component is at a constant amplitude and is unrelated to the signal amplitude.

When using the **THD+N Ampl** function the list of units and their references for both analog and digital signals is the same as described above in the **Level Meter Units** topic on page 128.

Bandpass Function

Figure 191 shows a conceptual block diagram of the **DSP Audio Analyzer** with the **Bandpass** function selected.




Figure 191. Conceptual Block Diagram, DSP Audio Analyzer, **Bandpass** Function

The **Bandpass** function is a selective voltmeter (a function sometimes called a *wave analyzer*) implemented by DSP techniques. Each channel includes a narrow bandpass filter of approximately 1/13 octave ($Q=19$, -3 dB bandwidth approximately 5.2% of center frequency). The bandpass filter cen-

ter frequency may be fixed, or may track one of several parameters. See **BP/BR Filter Tuning** on page 257.

The filter may be tuned to the steering source fundamental frequency or to its 2nd, 3rd, 4th, or 5th harmonic. This harmonic tracking ability permits swept measurements of individual harmonic distortion products, limited in frequency to a maximum value of 47% of the sample rate.

The **BW** (high-pass and low-pass) filter selections are not available for the **Bandpass** function.

SMPTE / DIN IMD Function

Figure 192 shows a conceptual block diagram of the DSP Audio Analyzer with the SMPTE / DIN function selected.




Figure 192. Conceptual Block Diagram, DSP Audio Analyzer, SMPTE / DIN function

SMPTE / DIN IMD (intermodulation distortion to the SMPTE or DIN standards) measures the amplitude of the IMD residuals created below the high-frequency component of a two-tone test signal. These are recovered by first passing the signal through a 2 kHz high-pass filter and then demodulating and filtering the sidebands. Appropriate two-tone test signals can be generated by

the Analog or the Digital Generator. The combined amplitude of the recovered sidebands is stated as a ratio to the amplitude of the high-frequency tone, with units of % or **dB** being the most common.

The **BW** (high-pass and low-pass) filter selections are not available for the **SMPTE/DIN** function.

Phase Function

Figure 193 shows a conceptual block diagram of the DSP Audio Analyzer with the **Phase** function selected.




Figure 193. Conceptual Block Diagram, **Phase** Function

The **Phase** function measures the phase difference between the signals (which must be the same frequency) on the two input channels. The phase difference, always expressed in degree units, is shown in the left-hand Function meter display.

The value displayed is “phase B–A,” the same expression used for the **Sine: Var Phase** waveforms of the Digital and Analog Generators. If Channel B leads Channel A, the display will show a positive reading; if Channel B lags Channel A, the display will show a negative reading.

When using **Phase**, the right-hand **Function** meter display becomes a setting field, with a list of four options: **Auto**, **–180+180 deg**, **0+360 deg**, and **–90+270 deg**.

In **Auto**, the meter reads absolute phase error. Delays in the DUT can cause signals to lag or lead by many waveform cycles, and for swept measurements **Auto** will correctly show and plot readings beyond ± 360 degrees. When viewing phase error in **Auto** without sweeping, the reading is reset at each waveform cycle and the phase error will always be displayed as within ± 360 degrees.

The **–180+180 deg**, **0+360 deg**, and **–90+270 deg** choices express the phase error in “windows” of 360° , with the window for each selection placed along a scale at a different positions in relation to 0° . See Figure 194.

The **BW** (high-pass and low-pass) filter selections are not available for the **Phase** function.




Figure 194. DSP Audio Analyzer phase display modes

Function Meter Units

As with the Level meters, the units available for the Function meters depend upon whether the analyzer Input is set to an analog converter or **Digital@ISR**. The measurement function you choose for the Function meters will change the unit options as well.

- In the amplitude measurement functions (**Amplitude**, **THD+N Amplitude**, and **Bandpass**), the analog and digital units and their references are exactly as described in **Level Meter Units** on page 128.

- In the various ratio-measurement functions (**2-Channel Ratio**, **Crosstalk**, **THD+N Ratio**, and **SMPTE IMD**), the available units are **%**, **dB**, and **X/Y**, independent of whether an analog converter or **Digital@ISR** input is selected.
- In **Phase** function, the only unit available is degrees.

For an explanation of the units of measurement used in the 2700 series and the references for the relative units, go to **Units of Measurement**, Appendix A.


Function Meter Ranging

Like the Level meters, the Function meters have a set of amplitude ranging controls, which are located lower on the DSP Audio Analyzer panel beneath the Function meter Reading fields.

The Function meter ranging control operate in exactly the same manner as the Level meter ranging controls, which are discussed in detail on page 233.

Detector Type

Figure 195. The DSP Audio Analyzer
Detector selections.



The right-hand field following the “**Det**” label permits selection of detector type for the Function meters of the DSP Audio Analyzer. The available selections are **RMS**, **Fast RMS**, and **Quasi-Peak**.

*NOTE: These choices also affect the Level meters. When either rms detector is selected for the Function meters, the Level meters use the same type of detection. When **Quasi-Peak** is selected for the Function meters, the Level meters use normal **RMS** detection.*

Detectors and Crest Factor

3.5000 VDC is always 3.5000 VDC. But ac voltages, by definition, are always changing. We must agree to measure ac (including audio signals) in a way that is consistent and appropriate for the use at hand. Historically, AC was simply rectified with a diode (a detector; in radio terms) for measurement. But what kind of a detector? Half-wave? Full-wave? How quickly should our detector respond? How long do we gather signal before we report the voltage?

As time went on, standard ac measurement terms including “peak,” “peak-to-peak,” “average” and “rms” were agreed upon. For many purposes, rms (root mean square) ac measurements were often the most useful, especially for audio work.

The decision to use one or another detector is dependent on what aspect of an audio signal you are interested in measuring. Different detectors, and signals with different crest factors, will give you different results.

Crest factor is the ratio of a signal’s peak amplitude to its rms amplitude. Crest factor is a term describing how “peaky” or “smooth” a waveform is. A signal with many high-amplitude, narrow transients (such as Gaussian white noise) has a high crest factor; a consistent waveform (such as a flute tone) has a low crest factor.

■ RMS

The **RMS** choice provides conventional true rms detection with a measurement time approximately the reciprocal of the selected reading rate. See **Detector Reading Rate**, below.

■ Fast RMS


The **Fast RMS** selection provides synchronous rms detection for periodic signals such as sine waves and square waves, making accurate measurements in as little as one cycle of signal. **Fast RMS** is useful for very rapid frequency response sweeps.

The measurement period is synchronized with zero crossings of the signal waveform and will always be an integer number of signal cycles. The actual measurement time is the reciprocal of the detector reading rate value plus the time necessary for completion of the cycle of signal in progress when the reading rate period expires. For example, if the reading rate is set to **64/sec** (a period of 15.6 ms) and the signal being measured is a 500 Hz signal (which has a 2 ms period), the total time of each measurement could vary between 15.6 ms to almost 17.6 ms, depending on the phase of the signal.

- **Quasi-Peak** provides a response conforming to the IEC468 specification for noise measurements, and is normally used with the CCIR (IEC468) weighting filter.

Detector Reading Rate

Figure 196. The **DSP Audio Analyzer** **Reading Rate** selections.



The left-hand field following the “**Det**” label controls the detector reading rate, the rate at which all the DSP Audio Analyzer meters update. This is also called *integration time*. The selections are **Auto**, **4/sec**, **8/sec**, **16/sec**, **32/sec**, **64/sec**, **128/sec**, and **256/sec**.

The actual measurement time for a given selection depends on the detector response type selected. For **RMS** and **Quasi-Peak**, the measurement time will be approximately the period of the selected rate (for example, about 125 ms at 8/sec). For the **Fast RMS** detector, the rate selected will set the minimum measurement period. The actual period may be longer, since with **Fast RMS** the measurement continues until the next positive-going zero crossing of the signal cycle.

Normally, **Auto** will be the best choice, with the most important exception being noise measurements, discussed below. The **Auto** algorithm takes into account the signal frequency being measured and whether or not the bandpass filter is in use, and then selects the fastest reading rate which will deliver the specified accuracy under these conditions.

For noise measurements, the **4/sec** selection is recommended to provide integration of noise over a longer period. You might also choose **4/sec** when measuring periodic waveforms for the best accuracy and repeatability at very low frequencies.

The **8/sec**, **16/sec**, **32/sec**, **64/sec**, **128/sec**, and **256/sec** choices provide progressively faster measurements. If you are watching a bargraph display while making adjustments to a DUT, for example, the faster rates better approximate real-time readings and will give you better feedback.

However, low-frequency measurement accuracy is reduced at faster rates. Each step faster in reading rate raises the low-frequency limit to accurate measurement. Faster reading rates are also less tolerant of noise in the signal.


The Bandwidth and Filter Fields

Below the detector fields are three fields which allow selection of various filter options for the Function meters. The first two are labeled “**BW**” for bandwidth, and consist of highpass and lowpass filter options. The third field is la-

beled “**Filtr**” and provides weighting filter selections for some instrument functions and control over the bandpass/bandreject filters for other functions. Graphs of all the filter curves are shown in the **Specifications** chapter in *Getting Started with Your 2700 Series Instrument*.

BW: The Highpass Filter

Figure 197. The DSP Audio Analyzer
BW: Highpass Filter.



There are two **BW** (bandwidth) filter control fields. The left field is the highpass field.

The highpass filter is effective in all Function meter functions except **Crosstalk**, **Bandpass**, **SMPTE** and **Phase**. This field allows you to select essentially flat response at low frequencies (the **<10 Hz** selection), specific highpass filters at **22 Hz**, **100 Hz**, **400 Hz**, or a **User HP**. A highpass filter, when selected, is connected in the measurement paths of both **Function** meter channels, but does not affect the **Level** or **Frequency** meters.


The 22 Hz and 100 Hz high-pass filters are four-pole (24 dB/octave) designs in all functions of the **Function** meter.

In the two **THD+N** functions, the 400 Hz filter also has four poles; however, in the **Amplitude** or **2-Ch Ratio** functions, the 400 Hz filter becomes an extremely sharp, high-rejection ten-pole elliptic high-pass filter. Selecting the 400 Hz filter in these functions permits quantization noise and distortion measurements of ADCs and digital systems.

You can also use a custom highpass filter file by selecting **User HP**. See **User Filters**, page 255.

BW: The Lowpass Filter

Figure 198. The DSP Audio Analyzer
BW: Lowpass Filter



The right **BW** (bandwidth) filter control field is the lowpass field.

The lowpass filter is effective in all **Function** meter functions except **Crosstalk**, **Bandpass**, **SMPTE** and **Phase**. This field allows you to select essentially flat response at high frequencies (the **Fs/2** selection), specific lowpass filters at **20 kHz**, **15 kHz**, or a **User LP**. F_s refers to the currently selected sample rate, as determined in the settings in the DIO panel for digital signals; or in the Input ADC selection on this panel for analog signals. Any lowpass filter, when selected, is connected in the measurement paths of both **Function** meter channels, but does not affect the **Level** or **Freq.** meters.

The 20 kHz and 15 kHz lowpass filters are six-pole elliptic designs.

Selection of a 15 kHz or 20 kHz lowpass filter when making THD+N measurements is particularly important in measuring converters with large amounts of noise shaping.

Performance of the 15 kHz and 20 kHz lowpass filters is independent of sample rate at sample rates above approximately 44 kHz. As sample rates decrease toward twice the corner frequency of the selected filter, it essentially becomes the same as the **Fs/2** selection.

You can also use a custom lowpass filter file by selecting **User LP**. See **User Filters**, page 255.


The “Filtr” Field

The field labeled “**Filtr**,” just below the bandwidth filter fields, has different operations in different functions of the Function meter.

- In the **Amplitude**, **2-Ch Ratio**, and the two **THD+N** functions, this field allows selection of weighting filters, as discussed below.
- In the **Bandpass** function, the field permits selection of whether the bandpass filter is tuned to the fundamental frequency of the source being tracked, or to the 2nd, 3rd, 4th, or 5th harmonic. See **BP/BR Filter Tuning** on page 257.
- In the **Crosstalk**, **SMPTE/DIN** and **Phase** functions, the field disappears.

Filtr: Weighting Filters

Figure 199. The DSP Audio Analyzer **Filtr** selections.



Weighting filters provide response curves that emphasize parts of the audio spectrum for specific measurement purposes. Weighting response curves can be used to mimic or compensate for the response characteristics of human hearing, and are frequently required for noise or THD+N measurements that consider the listener. Standards often specify weighting filters for certain measurements. See the **Specifications** chapter in *Getting Started with Your 2700 Series Instrument* for graphs of the filter curves.

Several selections are provided in the weighting filter field—**None**, **“A” Weighting**, **CCIR Weighting**, **“F” Weighting**, **CCITT Weighting**, **C-message Weighting**, **HI-2 Harmonic Weighting** and **User Weighting Filter**. When any of these weighting filters is selected, it affects the **Function** meter measurement paths of both channels. The **Level** and **Frequency** meters are always unfiltered.

- **None** applies no weighting filter.
- **“A” Weighting** processes the signal through a psophometric weighting filter meeting the ANSI A-weighting specification. An A-weighting filter in combination with the THD+N function is frequently used for dynamic range measurements of ADCs.
- **CCIR Weighting** processes the signal with the weighting filter described in IEC468. It is normally used in one of two ways:
 - When used with an rms detector, this filter produces measurements in accordance with the Dolby Labs CCIR/ARM method.
 - When used with the **Q-Peak** detector at a reading rate of **4/sec**, this filter produces measurements satisfying the IEC468 standard.

*NOTE: The IEC468 standard specifies that the unity gain point in the test intersect the weighting curve at 1 kHz, rather than the 2 kHz intersection specified for the Dolby Labs CCIR/ARM method. The control software automatically makes the 6 dB level adjustment to accomplish this when **IEC468 Weighting** and **Q-Peak** are selected together.*

- The **“F” Weighting** filter is based on psychoacoustic research and relates to typical human hearing sensitivity at a sound pressure level of 15 phons.
- **CCITT Weighting** and **C-message Weighting** filters are essentially voice-band filters sometimes required for telecommunications applications.
- The **HI-2 Harmonic Weighting** filter is intended for use only when the **Function** meters are in **THD+N Ratio** or **THD+N Amplitude** functions. The primary purpose of the **Harmonic Weighting** filter is for rub and buzz measurements on loudspeakers. This filter has a rising 12 dB/oct-

tave response with the unity gain frequency four times higher than (two octaves above) the frequency of the THD+N notch filter, which means it emphasizes the effect of signals above the fourth harmonic and reduces the effect of signals below the fourth harmonic. Maximum gain of the **Harmonic Weighting** filter is limited to 28 dB.

- **User Weighting** provides a way to insert a custom weighting filter into the **Function** meter paths. See **User Filters**, below.

NOTE: The A, IEC468, and F weighting filters are specified to 20 kHz; at sample rates below 44 kHz, their response within a few kilohertz of $F_s/2$ will deviate from specification.

Weighting filter responses are perfectly accurate at the following sample rates:

Sample rates that produce precise filter responses.		
32.000 kHz	65.536 kHz	131.072 kHz
44.100 kHz	88.200 kHz	176.400 kHz
48.000 kHz	96.000 kHz	192.000 kHz

At any other sample rate, the filter shape is preserved but the filter “slides” up or down in frequency by the ratio of the actual sample rate in use to the nearest sample rate from the list above.

User Filters

User downloadable filters (or *user filters*) are custom-designed software filters which can be designed for use in any of the three DSP Audio Analyzer filter groups.

You can select a user downloadable filter for the DSP Audio Analyzer in the same way that you choose one of the standard DSP filters.

The low-pass and high-pass filters are selected in the two fields to the right of the **BW** (bandwidth) designation. The weighting filters are selected in the **Filtr** (filter) field.

*NOTE: DSP filters are not available in every measurement function of the DSP Audio Analyzer. Set the Function meter function to **Amplitude**, **2-Channel Ratio** or one of the two **THD+N** modes to choose DSP filters.*

Click the arrow to drop down the list of filters for any of these fields. The last filter option on all lists selects the downloadable filter type appropriate for that setting: **User HP**, **User LP** or **User Weighting Filter**.

Although you can save many different user filter files for use with your 2700 series instrument, you can only select one user file for each of the three filter positions at any one time. When the control software is launched, by default no user filter files are selected. To choose your filters, click the browser button to the right of the **Filtr** field. A file browser opens that enables you to select filter files for any of the three filter types: low-pass, high-pass and weighting. You can also view the filter **Info** string for any of the three selected filters.




Figure 200. The DSP Audio Analyzer **User Filter** file browser.

When you have chosen downloadable filters and closed the browser, notice that the **BW** and **Filtr** fields have been automatically set to **User** to reflect your choices. As long as you do not exit the 2700 series control software or load a test file, these downloadable filter files will remain attached to their filter lists. You still have the option, however, of choosing other filters (or **None**) from the lists without losing the link to the file you have selected.

A test saved with an attached user filter will re-attach the filter to the DSP Audio Analyzer when the test is loaded.

If you select **User** from any of the three filter lists and a user filter file has not been previously selected for that setting, the user filter file browser will appear and prompt you to choose a filter file.

User filter files created to a number of specifications are provided on the Audio Precision Resources Disc, and are also available for download from our Web site at ap.com.


Audio Precision provides a utility program called FDP as a download from our Web site as an aid to creating your own downloadable filters.

Several Matlab functions are also available on the Audio Precision Resources Disc and on the Web site, which will be helpful to Matlab users in cre-

ating properly-formatted downloadable filter files use with the 2700 series. See Appendix D for more information.

Bandpass/Bandreject Filter Tuning

Figure 201. The DSP Audio Analyzer BP/BR Filter selections.



The **BP/BR Filt Freq** (bandpass/bandreject filter frequency) controls affect only the Function meters, and only in certain functions, as listed below. The filter does not affect the Level meter or Freq. counter readings.

This is a highly selective filter of approximately 1/13 octave bandwidth. $Q=19$, giving a -3 dB bandwidth of 5.2% of the center frequency. The filter is tunable across the audio spectrum from 0.04% to 42% of the sample rate (20 Hz to 20 kHz at a 48 kHz sample rate).

The bandpass or peaking form of the filter is used in two DSP Audio Analyzer functions:

- **Crosstalk** and
- **Bandpass.**

The bandreject or notch form of the filter is used in two other DSP Audio Analyzer functions:

- **THD+N Ratio** and
- **THD+N Ampl.**

Either the bandpass or bandreject form of the filter may be fixed in frequency, or may be “steered” to automatically track a parameter during a sweep test. You can select the source of frequency steering information in the **BP/BR Filter Freq** field, located in the lower-right area of the DSP Audio Analyzer panel. The selections are:

- **Counter Tuned**
- **Sweep Track**
- **AGen Track**
- **DGen Track** and
- **Fixed.**

When the DSP Audio Analyzer is using the **Bandpass** function, you can further modify the filter steering source value by changing the setting in the “**Filtr**” field, located below the **BW** (bandwidth) setting fields. See **Selecting Harmonics in Bandpass** on page 259.

- When **Counter Tuned** is selected, the frequency measured by the **Frequency** meter becomes the filter steering source. Use this when making **THD+N** or **Crosstalk** measurements from an external signal, such as the playback of a compact disc or the reception of a signal from a distant source.
- When **Sweep Track** is selected, the filter tracks the frequency of whichever generator is selected in the **Source 1** or **Source 2** fields of the Sweep panel.
- When **AGen Track** is selected, the bandpass/bandreject filter tracks the frequency of the Analog Generator. This mode is useful for testing ADCs driven from the 2700 series analog output.
- When **DGen Track** is selected, the filter will automatically track the frequency of the Digital Generator. This mode is normally used when sweeping input-to-output through a digital device with the stimulus tone coming from the 2700 series Digital Generator.

Figure 202. The DSP Audio Analyzer
BP/BR Filter, Fixed.


Det: Auto	RMS	BP/BR Filtr Freq
BW: < 10 Hz	Fs/2	Fixed
Filtr: None	...	1.00000 kHz

- When **Fixed** is selected, the field immediately below (which is grayed out in other modes) becomes active. The filter will be set to the frequency entered in this field.
It is also possible to vary the filter frequency in this mode as part of a sweep test. Although this is similar to the **Sweep Track** choice above, in this case the filter can be swept independent of generator frequency. To sweep the filter frequency during a test, first be sure you have selected **Fixed** in the **BP/BR Filter Freq** field here on the Analyzer panel. Then, go to the Sweep panel, open the **Source 1** or **Source 2** browser and choose **DSP Anlr**. Click on **Bandpass A** or **Bandpass B** in the right-hand browser window (**Settings** selected) and click **OK**. See Chapter 18 for more information on sweeps.

Filtr: Selecting Harmonics in Bandpass

In **Bandpass** function, the **Filtr** field offers the selections of **Narrow**; **Narrow, Freq x2**; **Narrow, Freq x3**; **Narrow, Freq x4**; and **Narrow, Freq x5**.

Figure 203. The DSP Audio Analyzer **Narrow Filtr** harmonic selections.



The default setting, **Narrow**, sets the filter at the source frequency. The other choices (**Narrow, Freq x2**; **Narrow, Freq x3** and so on) move the filter to multiples of the source frequency, allowing you to make individual harmonic distortion measurements of the 2nd through 5th harmonic.


The filter bandwidth is fixed at the normal 5.2% bandwidth value under all of these selections, but its center frequency is steered to different integer multiples of the **BP/BR Source** steering frequency. See **BP/BR Filter Tuning** on page 257.

References

The bottom area of the DSP Audio Analyzer panel includes four fields in which you can enter reference values. Each reference serves as a basis for its corresponding unit of measurement on the panel. **dBr 1** and **dBr 2** are digital references only; **Freq.** and **V/FS** are valid references when using either digital or analog inputs.

Digital Analyzer References

Figure 204. Digital Analyzer **Digital References**



■ dBr 1 and dBr 2

The values entered in **dBr 1** and **dBr 2** serve as the digital references for the **dBr 1** and **dBr 2** unit choices available for the DSP Audio Analyzer Level and Function meters.

■ Freq

The frequency (**Freq**) value serves as the reference for the relative frequency units (**octaves**, **decades**, **% Hz**, etc.) for the DSP Audio Analyzer frequency meters.

■ V/FS

In some setups when the 2700 series is measuring a signal in one domain (digital or analog), you may find it more convenient to enter or view the equivalent of the signal in the other domain. The **V/FS** (volts for full scale) value is the analog-to-digital scaling value.

When testing an external ADC, for example, enter the value of analog input voltage that produces digital full scale output into this field. Then you can select amplitude meter units as **V**, **Vp**, **Vpp**, **dBu**, or **dBV** to express the measured digital amplitude in terms of the analog input value to the converter.

In the same way, the **dB_r 1** and **dB_r 2** reference values may also be entered as digital or analog domain units, with the **V/FS** reference value being used to scale the references.

Analog References for the DSP Audio Analyzer


When the DSP Audio Analyzer input is set to an analog converter, the units **dB_r 1** and **dB_r 2** do not appear as choices on the units drop-down lists, and the Level and Function meter displays cannot be referenced to these digital references. Instead, four new analog reference choices appear on the list: **dB_r A**, **dB_r B**, **dB_g A** and **dB_g B**.

The values for the **dB_r A** and **dB_r B** references are set at the bottom of the Analog Analyzer panel. **dB_g A** and **dB_g B** are always referenced to the values entered in the Analog Generator Amplitude fields.

Chapter 12

The Spectrum Analyzer

Figure 205. The Spectrum Analyzer panel.



Introduction

The **Spectrum Analyzer** is a DSP analysis tool selection on the Digital Analyzer panel. It is named “**Fft**” on instrument browser lists and in OLE references.

The **Spectrum Analyzer** is a general-purpose waveform display and spectrum analyzer for 2700 series. It provides both

- time domain (oscilloscope) display of waveforms, and
- frequency domain (spectrum analyzer) views.

The **Spectrum Analyzer** can analyze and display digital signals up to SR/2, and analog input signals up to 120 kHz (using the high-bandwidth ADC).


Features include large, dedicated memory buffers, flexible triggering, averaging techniques, waveform processing, selectable display methods, a wide choice of FFT windowing functions, and the capability of shifting a sine wave signal to a bin center for synchronous analysis.

This chapter examines each function, control and display of the **Spectrum Analyzer** in detail. If you are new to Audio Precision instruments, you might want to start with the Quick Guides in *Getting Started with Your 2700 Series Instrument*, which will introduce you to the **Spectrum Analyzer** features.

See **Appendix C** for a conceptual overview of FFTs.

Loading the Spectrum Analyzer

Figure 206. Loading the Spectrum Analyzer.




To use the **Spectrum Analyzer**, first open the Digital Analyzer panel. The Digital Analyzer panel is a command selection on the Panel menu, and is also available by the keyboard shortcut **Ctrl+Y**, or by clicking the **Analyzer** icon on the Toolbar.

Now select **FFT Spectrum Analyzer** from the list on the Analyzer panel. This loads the Spectrum Analyzer software into DSP.

Signal Inputs

Figure 207. Spectrum Analyzer panel inputs.



The Input field enables you to choose the digital input or the analog inputs (converted to digital) as the signal applied to the Spectrum Analyzer. The selections are:

- **Digital @ISR**
- **HiRes A/D @65536**
- **HiBW A/D @131072**
- **HiBW A/D @262144**
- **HiRes A/D @SSR**
- **HiBW A/D @2xSSR**

The digital input and converter choices are the same for all five of the DSP audio analysis tools (DSP Audio Analyzer, Spectrum Analyzer, Multitone Analyzer, MLS Analyzer and Harmonic Distortion Analyzer). Go to **Signal Inputs** on page 228 in the **DSP Audio Analyzer** chapter for detailed information about the Digital Analyzer Inputs.

Source Selection

The Source selection choices depend on the Input selected; the lists are different for the **Digital @ISR** input and for the analog (A/D) inputs.

Digital @ISR Sources




Figure 208. Spectrum Analyzer Source selection, digital input.

When **Digital @ISR** is the analyzer input, the source selections for each analyzer channel are:

- **A**
The embedded channel A audio is routed to the analyzer channel.
- **B**
The embedded channel B audio is routed to the analyzer channel.

- **None**

Acquisition is disabled for the analyzer channel, preserving any signal previously in the acquisition buffer. This permits acquisition of signals into the Ch 1 and Ch 2 buffers at two different times for comparison of different devices or of the same device under different conditions.

Analog (A/D) Sources




Figure 209. Spectrum Analyzer Source selection, analog input.

When one of the ADCs is the analyzer input, the source selections for each analyzer channel are:

- **Anlr-A**

The Channel A analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL A output, which appears on the front panel on a BNC connector.

- **Anlr-B**

The Channel B analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL B output, which appears on the front panel on a BNC connector.

- **Anlr Rdg Ampl**

The final analog-processed Analog Analyzer function reading meter signal, just before the detectors. This point follows all highpass, lowpass and option filtering and the bandpass/bandreject filter. This is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS READING output, which appears on the front panel on a

BNC connector.

In either THD+N mode, the bandreject filter will reduce the test signal fundamental to a low level, but up to 60 dB gain is added to the broadband signal after the notch filter, with the result that the residual noise and distortion components are passed to the ADCs at levels typically 60 dB higher than normal, resulting in virtually no contribution of distortion from the ADC. This selection is an amplitude and is expressed in units of absolute amplitude.

- **Anlr Rdg Ratio**

This Source choice selects the same signal as **Anlr Rdg Ampl** but expressed as a ratio. For Analog Analyzer functions **THD+N**, **IMD**, **Ratio** and **Crosstalk** the reference is the Analog Analyzer Level meter; for the **W&F** function the reference is an internal calibration factor equal to 100% wow and flutter.

- **Ch. A Generator**

The Channel A Analog Generator monitor signal. This signal is a fixed-amplitude replica of the Analog Generator output waveform, essentially identical to the GENERATOR MONITOR CHANNEL A output, which appears on the front panel on a BNC connector.

- **Ch. B Generator**

The Channel B Analog Generator monitor signal. This signal is a fixed-amplitude replica of the Analog Generator output waveform, essentially identical to the GENERATOR MONITOR CHANNEL B output, which appears on the front panel on a BNC connector.

- **Jitter Signal (UI)**

A signal proportional to the jitter of the incoming serial digital interface signal, in UI. This is the same signal whose integrated value is displayed in the Jitter Measurement reading on the DIO panel.

- **Jitter Signal (sec)**


The same jitter signal, expressed in seconds rather than UI.

- **None**

Acquisition is disabled for the analyzer channel, preserving any signal previously in the acquisition buffer. This permits acquisition of signals into the Ch 1 and Ch 2 buffers at two different times for comparison of different devices or of the same device under different conditions.

Peak Level Monitors

Figure 210. Spectrum Analyzer peak level meters.



The two **Peak Mon** meters on the Spectrum Analyzer panel continuously display the peak amplitude of the digital signal as it is presented to the **Spectrum Analyzer**. Only digital domain units (FFS, dBFS, %FS, or bits) are available for these meters.

The primary purpose of the peak monitors is to avoid overload of the input analog-to-digital converter (ADCs). When signal is being acquired from the analog source and **Auto Range** is in use on the Analog Analyzer panel, ADC overload should never be a problem. If any of the Analog Analyzer input range controls is fixed, you must verify that the maximum signal amplitude never exceeds digital full scale.

Acquiring, Transforming and Processing

The Spectrum Analyzer analysis tool acquires, transforms, processes and displays data in distinct steps. For a frequency domain (spectrum) view, there are three steps:

- acquiring the data,
- performing the FFT, and
- processing the results for graphing.

Usually the three steps are performed in quick succession for each spectrum display. In other situations, only the last step or two are performed on an acquisition or set of transform results already in memory.

For a time domain (oscilloscope) view, there are only two steps:

- acquiring the data, and
- processing the results for graphing.

Three sets of commands control the Spectrum Analyzer processes:

- **Sweep > Start (F9) (Go)**

These commands are all equivalent, and perform all three steps: a new acquisition is made, the data is transformed, and the results are processed for display.

- **Sweep > Transform w/o Acquire (F6)**

These two commands are equivalent, and perform the two last steps: the acquired data is transformed, and the results are processed for display. No new acquisition is made.

- **Sweep > Reprocess Data (Ctrl-F6)**

These two commands are equivalent, and perform the last step: the results are processed for display. No new acquisition is made and no new transform is performed.

For the time domain view, **F6** and **Ctrl-F6** have the same result.

Making a new acquisition is usually the most time-consuming step in the process; performing the transform is next, and processing the results for display is usually the fastest step. When time becomes an important consideration, as in repeated automated processes, you should take care to include only necessary FFT steps.

The Acquisition Record

See Appendix C for a conceptual overview of FFTs, including a discussion of the acquisition record and FFT length.

In performing an FFT the 2700 series instrument first acquires data to be analyzed. This acquired data is called the *acquisition record*, and it is stored in a location in the instrument's DSP memory called the *acquisition buffer*. The two channels of a stereo acquisition are maintained in two separate acquisition buffers.

Acquiring the data and performing the FFT are two separate steps. You can choose to acquire new data with each execution of an FFT, or you can re-transform the same acquired data repeatedly, using different processing or timing settings with each FFT.

Both channels of the acquired waveform remain in the DSP acquisition buffer until one of the following events occurs:

- a **Sweep > Start (F9) (Go)** command is issued to acquire new waveforms;
- a different Digital Analyzer analysis tool is loaded;
- mains power is turned off to the instrument; or

- a different acquisition waveform is loaded from disk as described in **Loading Acquired Waveforms** on page 293.


While the waveform is still present in the acquisition buffer, full flexibility exists to change back and forth between time and frequency domain analysis. View the waveform in the frequency domain by selecting **FFT.Frequency** for **Source 1** and choosing the desired **Start** and **Stop** values on the Sweep panel. View it in the time domain by selecting **FFT.Time** for **Source 1**. See Chapter 18, **Sweeps and Sweep Settling**. A quick way to set up a new FFT or toggle between time domain and frequency domain is to use the **Sweep Spectrum/Waveform Button**, which is discussed on page 293.

You may view different time portions of the record, perform FFTs of different transform lengths, position the transform starting point at different places in the record, change window functions, change FFT post-processing modes, change time domain processing modes, etc. The results of any of these different modes of analysis may be saved as .at27 test files.

Saving a test file, however, does not save the acquired waveform, only the test setup and results. It is possible to also save the acquired waveform, which can be reloaded at a later time for further analysis. See **Saving Acquired Waveforms** on page 292.

Acquisition Length

Figure 211. Spectrum Analyzer Acquire selections.




Set the length of the acquisition by selecting a value from the **Acquire** list. The **512k**, **1M**, **2M** and **4M** choices are only available with 2700 series or Cascade *Plus* instruments.

The acquisition lengths are stated in samples; the duration of the acquisition will depend on the sample rate in use. At a sample rate of 48 kHz, a 4 M acquisition will have a duration of 87.38 seconds. Acquisitions can be equal to or longer than the FFT length you intend to use. A longer acquisition enables you to perform transforms at different points along the length of the acquired record.

By choosing **Track FFT**, you can set the instrument to acquire only the amount of data needed for the present transform length, which is set in the **FFT** field to the left. This provides faster performance than acquiring more data than is needed. See **FFT Length**, below.

FFT Length

Figure 212. FFT length selections.



The transform length and sample rate determine the bin width (or frequency resolution) of an FFT. See Appendix C for a conceptual overview of FFTs, including a discussion of the relationship between transform length, sample rate and bin width.

Set the length of the transform by selecting a value from the **FFT** list.

When you are performing an FFT on an acquisition record that is longer than the transform length, only the number of samples specified in the **FFT** field will be transformed.


FFT Window Selection

An FFT window is an amplitude envelope imposed upon the transform data to reduce the broadband noise introduced by the abrupt data transitions in asynchronous FFTs. See Appendix C for a conceptual overview of FFTs, including a discussion of FFT windowing.

Each window function has a different set of trade-offs between effective selectivity and the potential of amplitude measurement error. The Hamming and

Hann windows, for example, have the best selectivity near the top of the window but limited rejection of signals more distant from the center. The Blackman-Harris, Equiripple, and Rife-Vincent windows have much better rejection of more distant signals. The Flat-Top window has the poorest selectivity, but virtually no amplitude error across the center three bins.

Figure 213. Spectrum Analyzer FFT Window selections.



Select the appropriate window for your test from the list. The selectivity curves are compared in Figures 214 and 215, which are followed by discussions of the characteristics of each window function.

The window function is applied after signal acquisition and before the transform, which means that you can change the FFT Window selection and re-transform the data using the **F6** command, without making another acquisition. You can compare the effects of several different window functions on the same signal acquisition by checking the Append box on the Sweep panel and using **F6** to re-transform the data with new window settings.




Figure 214. FFT Window Functions: Flat-Top, Hann, Blackman-Harris and Equiripple.




Figure 215. FFT Window Functions: Hamming, Gaussian, Rife-Vincent 4 and 5. Equiripple shown for comparison.

Hann Window

The Hann window is a raised cosine window that provides good selectivity near the top of the main lobe (about -6 dB at one bin away from center and about -30 dB at two bins away), with no side lobes. Its skirts more than 3 bins off center are not as steep as the Blackman-Harris window. The Hann window causes approximately -1.5 dB maximum amplitude error due to window attenuation, if the signal is at the extreme edge of the bin.

Blackman-Harris Window

The Blackman-Harris window is a 4-term minimum side lobe window. When compared to the Hann window, it is not quite as selective across the central several bins (about -3 dB in the adjacent bins and about -14 dB at two bins off), but has steeper skirts beyond that point. The Blackman-Harris window has side lobes below -92 dB (response fall-off is not monotonic). It has a reasonably flat top with a maximum amplitude error of about -0.8 dB if the signal is at the extreme edge of the bin.

Flat-Top Window

The Flat-Top window is designed for the greatest amplitude measurement accuracy. It provides a maximum amplitude error due to window attenuation of less than -0.02 dB. However, its selectivity is poorer than the other windows. The Flat-Top window is the appropriate window for accurate amplitude measurements (such as when measuring individual harmonics) except when signals are so closely spaced that its selectivity becomes a problem.

Equiripple Window

The Equiripple window, developed at Audio Precision, is an approximation to the Dolph-Chebyshev window that has the narrowest main lobe width for a given maximum side lobe depth. The main lobe is approximately 12 bins wide; that is, the first null is about six bins from the main lobe center. The first side lobe, which is also the highest, is -147 dB from the main lobe. The maximum amplitude error with a signal at the bin boundary is about 0.5 dB.

Hamming Window

The Hamming window has the sharpest selectivity of all the windows provided. Adjacent bins average about -7 dB and two bins away the response is about -40 dB. Amplitude error is about -1.7 dB for a signal at the extreme edge of a bin. The side lobes of the Hamming start at only -40 dB to -50 dB below the top of the main lobe, about 4 bins away from the center bin. The response fall-off is not monotonic.

Gaussian Window

The Gaussian window main lobe width is only slightly wider than the Blackman-Harris window and the nearby rejection is considerably better than Blackman-Harris, reaching an average of -100 dB down in the fifth bin away from center. The side lobes are down more than -130 dB, compared to about -100 dB for Blackman-Harris. Maximum amplitude error is about -0.7 dB for a signal at bin edge.

Rife-Vincent Windows

Both Rife-Vincent windows have smooth, monotonically-falling responses with no side lobes. The Rife-Vincent 4 window has about -0.6 dB maximum amplitude error, is about -100 dB at 7 bins off center and about -150 dB at 15 bins off. The Rife-Vincent 5 is slightly wider at the top of the main lobe, with about -0.5 dB maximum amplitude error. It has sharper skirts with attenuation reaching about -106 dB at 7 bins off center and about -150 dB at 12 bins off.

None (No Window or Rectangular Window)

The **None** selection (sometimes called a rectangular window) does not apply any window function before the FFT. This mode is normally used only with synchronous signals; it is not generally useful for non-synchronous signals since energy will be spread across the entire spectrum unless the signal is exactly at bin center. The amplitude error due to the rectangular window attenuation is about 4 dB.

None, move to bin center

This choice also does not apply a window function, but it is not restricted to signals that are synchronous. **None, move to bin center** may be used with any signal which consists only of a single sine wave and any harmonically-related distortion products. For signals that are non-synchronous, this selection modifies the signal so that it becomes synchronous.

None, move to bin center shifts the fundamental frequency of the signal to the center of the nearest bin, which is the same as stretching or compressing the waveform so that an integer number of cycles fits exactly in the transform length. See Appendix C for a conceptual overview of FFTs, including basic information on synchronous FFTs.

When used with a single sine wave, this technique results in excellent selectivity, with the signal spreading to the adjacent FFT bin normally 120 dB down or more. Due to the correction, the signal in the DSP buffer will now be at an exact bin center and NOT at the original frequency.

Here's an example: assume that you want to test an ADC operating at a 48.00 kHz sample rate, using a test signal frequency of 997 Hz. This frequency is often chosen because it is non-synchronous with the sample rate and causes the converter under test to be exercised through a large number of its possible states.

With an FFT length of 16,384 samples, the two nearest synchronous frequencies are 996.09375 Hz (exactly 340 cycles in the buffer) and 999.0234375 Hz (exactly 341 cycles). The **None, move to bin center** mode of the FFT program will shift the frequency of the acquired 997 Hz signal in DSP memory down to 996.09375 Hz (the nearest synchronous frequency) and then perform a windowless FFT.

The result: the ADC under test was exercised at 997 Hz, as desired; and the frequency correction yielded an unwindowed FFT with high selectivity, as if the signal had been at the synchronous frequency of 996.09375 Hz.

The frequency correction technique has a maximum correction range of $\pm 4\%$. At the low end of the frequency range there will be frequencies that are more than 4% from a bin center. For example, with a 16,384-sample transform and 48 kHz rate, 37 Hz is approximately the lower limit above which a sine wave at any arbitrary frequency can be guaranteed to be brought to a synchronous frequency.

The technique will work at still lower frequencies if the signal frequency is within 4% of a synchronous bin center frequency. Bin center frequencies may be computed from the equation

$$\text{Frequency} = \frac{(N \times \text{Sample Rate})}{\text{Transform Length}},$$


where N is the integer number of cycles in the transform.

For example, with $N = 7$ (exactly seven complete cycles in the FFT buffer), a transform length of 16,384 and a 48 kHz rate, the synchronous frequency is 20.5078125 Hz. A $\pm 4\%$ range around that frequency extends from approximately 19.7 Hz to 21.3 Hz, and a sine wave within that range will be corrected to the synchronous frequency.

When using Sweep **Append** and Sweep **Repeat** with **None**, **move to bin center** as the **Window** selection, the frequency shift will be performed only once and not with every **Append** or **Repeat** operation.

Quasi-AC Coupling

Figure 216. Spectrum Analyzer coupling selections.



The Spectrum Analyzer can be dc coupled to the input signal, or can operate in one of two modes of quasi-ac coupling. The field at the right of the **Window** selection field offers three choices:

■ DC Coupled

■ Subtract Avg (Quasi-AC Coupled)

When **Subtract Avg** is selected, the DSP computes the average value of all samples in the acquisition buffer and subtracts that computed value from the value of each sample, before the FFT or waveform display is performed. For noisy signals, the **Subtract Avg** selection generally results in better dc rejection than the **Subtract ½ pk-pk** selection.

■ Subtract ½ pk-pk (Quasi-AC Coupled)

The **Subtract ½ pk-pk** selection computes the maximum difference between positive and negative peak values in the acquisition buffer and subtracts half that amount from each sample, before the FFT or waveform display is performed. For symmetric, low-noise signals, the **Subtract ½ pk-pk** selection generally results in better dc rejection than the **Subtract Avg** selection.

The general effect of either of these selections is similar to having used ac coupling before acquiring the signal, as long as no signal peaks exceeded digital full scale.

Use of either of the quasi-ac coupling functions may be valuable when examining low-level signals that have large dc offsets, particularly in time domain (oscilloscope) presentations where the dc offset might otherwise cause

the signal to be off-screen. Either selection may introduce dc error, particularly on very low frequency signals.

Also see **Triggering with Quasi-AC Coupling** on page 290.

Averaging

Figure 217. Spectrum Analyzer Averaging selections.

Aves:	Power (spectrum only)	1
Wave:	Power (spectrum only)	1
	Sync, re-align	2
	Sync	4
		8
		16
		32
		64
		128
		256
		512
		1024
		2048
		4096

The Spectrum Analyzer provides two fundamentally different averaging techniques for better ability to measure program material and noise, or low-level and other noisy signals. These are:

- synchronous averaging, and
- power (spectrum) averaging.

Both techniques average the signal over a specified number of acquisitions. They do this by summing the signals from all acquisitions and dividing the result by the number of acquisitions.

Synchronous averaging operates on the time-domain signal, which makes it useful not only for time-domain (oscilloscope) display but also for frequency-domain (spectrum) analysis, since the source of the signal for spectrum analysis is the time-domain signal.

Power (spectrum) averaging operates only on the frequency-domain result. After each FFT is performed, the power spectra for all passes are summed and then divided by the number of passes.

During an averaging process, the Status Bar at the lower left of the 2700 series workspace counts down through the number of acquisitions as they are performed.

Averaging factors from **2** to **4096** are available. A selection of **1** disables averaging.

Synchronous Averaging

The primary purpose of synchronous averaging is to reduce noise levels in order to provide more accurate measurements of signals which would otherwise be lost in the noise.

Synchronous averaging is performed on the acquired (time domain) signal, so it can be used when viewing noisy signals in the time domain in oscilloscope view.




Figure 218. A time-domain view of –85 dBFS and –100 dBFS 16-bit sine wave signals, normal dither, no averaging.

Figure 218 shows a time domain display of –85 dBFS and –100 dBFS 16-bit sine wave signals with normal triangular dither and no averaging. All that can really be seen is that one signal occupies the five lowest-amplitude digital codes and the other occupies the three lowest codes.




Figure 219. A time-domain view of -85 dBFS and -100 dBFS 16-bit sine wave signals, normal dither, 256x synchronous averaging, triggered from digital generator.

Figure 219 is the same signal with 256x synchronous averaging, triggered from the digital generator. The sinusoidal waveform is now clearly visible.

Signal Alignment for Synchronous Averaging

In order for the amplitude of coherent signals to be preserved during synchronous averaging, each new acquisition must be accurately time-aligned with the previous acquisitions before it is added to the accumulating signal in DSP memory. For some signals, time alignment may be accomplished by proper triggering at acquisition. Other signals may require a DSP re-alignment process. Also see **Triggering with Synchronous Averaging** on page 289.

Because of the frequency-shifting that occurs using the **None, move to bin center** Spectrum Analyzer Window selection, the synchronous averaging choices change with the FFT windowing mode. For all FFT Window selections except **None, move to bin center** the synchronous choices are:

- Sync, re-align and
- Sync.

If **None, move to bin center** is selected as the FFT **Window**, there are four synchronous choices:

- Sync, re-align, move center first
- Sync, re-align, average first
- Sync, move center first, and
- Sync, average first.

Sync (without re-align)

When you are confident that nature of the signal and the triggering selections on the Spectrum Analyzer panel are sufficient to cause each acquisition to start at the same relative point on the waveform, choose one of the synchronous selections that do *not* re-align. The “sync without re-align” options require less digital signal processing and are faster.

Sync, re-align

For some signals, re-alignment may be necessary for synchronous averaging. Choose one of the **Sync, re-align** options to select this technique.

With re-align, signal is first acquired with any triggering selection (including **Free-running**, which is untriggered). The DSP then “slides” the signal forward or backward in time until it is aligned with the sum of already-accumulated signals.

The final averaged result will start at the value set in the **Delay** field and continue from that point for the **Length** value. Any signal before and after is erased.

For example, if **8192** is selected in the **FFT** field and **100 ms** is entered in the **Delay** field (assuming that the **Acquire** field value is sufficiently long to contain 100 ms plus 8192 samples), the final averaged result will start at 100 ms and continue for a bit more than 8192 samples beyond that point (to approximately 271 ms at a 48 kHz sample rate). A time domain view or an FFT may then be made anywhere within that 8192 samples.

An FFT of a synchronously-sampled signal will be correct only if the signal transformed, as determined by **FFT Start Time** and **Length**, lies completely within the occupied portion of the buffer. In the example above, any **FFT Start Time** less than 100 ms would produce erroneous data. Any combination of **Start Time** and **Length** extending beyond the 271 ms point would also produce bad data.

Synchronous Averaging for “Move to bin center”

With **None**, **move to bin center** in the **Window** field, time aligning is more complicated because of the frequency shift imposed upon the acquired signal. The two “**average first**” selections will provide faster operation since the “**move to bin center**” operation is only done once, following all acquisitions and averaging. The “**move center first**” selections perform the bin centering operation at each acquisition, increasing the measurement time.

However, if the signal frequency changes from acquisition to acquisition because of flutter or drift, the **move center first** selections may provide more accurate measurements. Frequency changes during synchronous averaging will

result in amplitude errors since the signals will not be time-aligned at the end of the buffer even if they are synchronized at their initial zero crossing.




Figure 220. Low-level signal viewed in the frequency domain, no averaging

Synchronous Averaging and Frequency Domain Views

As stated before, synchronous averaging is performed on the signal acquisition in the time domain. Since the frequency domain (spectrum) view uses this time domain acquisition, synchronous averaging is also useful for frequency domain views.

With synchronous averaging and time alignment via proper triggering or the **Sync, re-align** mode, coherent components will be unchanged by the averaging process. The average value of noise components will be reduced by 3 dB for each doubling of the averaging factor. Figures 220 and 221 show the same signal conditions, but Figure 221 has been averaged over 128 acquisitions using synchronous averaging. Note that the peak-to-peak variance of the noise is still approximately as it was with no averaging, but the average level of the noise is now approximately -180 dBV. This lowered noise floor makes clearly visible a 9 kHz distortion product, another peak at 12 kHz and the hint of another at 6 kHz.




Figure 221. Low-level signal viewed in the frequency domain, averaged with 128x synchronous (time domain) averaging. Average noise level is reduced from noise level shown in Figure 220, with no change in noise variance.

Power (Spectrum) Averaging

Spectrum averaging operates only on the frequency domain (amplitude vs. frequency) results following an FFT. It will not operate if a time domain display (**Fft.FFT Time** at **Source 1**) has been selected.

The primary purpose of spectrum averaging is to provide a more accurate measurement of the amplitude versus frequency characteristics of varying signals. The 2700 series uses power-law (root-mean-square) averaging to correctly average noise signals.

Averaging over many seconds or minutes of noise or of program material such as music or voice is very useful in order to determine the long-term average amplitude vs. frequency distribution.

Coherent (steady or continuous) signals will be unaffected by spectrum averaging. Variable signals such as noise and program material will converge to their average values at each frequency as the averaging factor is increased. The result is that the peak-to-peak variance in the displayed noise floor or program material is reduced while coherent signal amplitudes are unchanged. The average level of the noise floor is not changed.




Figure 222. Low-level signal viewed in the frequency domain, 128x Power (spectrum Only) averaging. Noise variance is reduced from noise variance shown in Figure 220, with no change in average noise level.

Figure 222 shows the same signal illustrated in Figure 220 after 128x spectrum averaging. Note that the average level of the noise is about -160 dBV in either case, but the peak-to-peak variance in the noise has been reduced by the spectrum averaging. The slight rise in noise levels at high frequency due to noise-shaped dither is visible in the averaged result but not on any single acquisition and FFT.


Coherent signals very near the noise floor, such as the distortion product at 9 kHz in Figure 222, may become visible as the noise converges to its average value.

Spectrum averaging is selectable in the Avgs: field as **Power (spectrum only)**.

*NOTE: If a time domain view is selected following a spectrum averaging process, the **Reprocess Data** command (**Ctrl+F6**) must be used to view the time domain data, rather than the **Transform Data w/o Acquire** (**F6**) command. Only the last acquisition of the series of averaged acquisitions will be viewed. See page 266 for more information.*

Display Processing

Figure 223. Spectrum Analyzer Display Processing.



Five methods are available in the Spectrum Analyzer to process the sampled signal before display.

The first four methods (discussed below) process the amplitude-versus-time relationship of the signal, and are applicable only to time domain (oscilloscope) views. These methods have no effect on FFT frequency domain (spectrum) analysis views.

The fifth method (discussed on page 285) is only available with 2700 series and Cascade *Plus* instrument hardware. This method, **Smooth (spectrum only)**, processes the amplitude-versus-frequency relationship of the sampled signal, and is applicable only to frequency domain (spectrum) views. This method has no effect on FFT time domain (oscilloscope) views.

Waveform (time domain) Display Processing

Four methods are available in the Spectrum Analyzer for processing the amplitude-versus-time relationship of a sampled signal before displaying the waveform. These methods are applicable only to time domain (oscilloscope) views and have no effect on frequency domain FFT spectrum analysis views.

The display processing setting determines how the data is modified for display when the spacing of the sweep points is different from the spacing of sample points in the acquisition.

The four time-domain modes available in the Wave Display field are:

- **Interpolate**
- **Display Samples**
- **Peak Values** and
- **Absolute Values.**

Interpolate

When **Interpolate** is selected the DSP compares the density of sweep points requested with the density of sample points available in the acquisition, for the time span of the current sweep and graph.

If the requested points are much more sparse than the acquisition points, the DSP uses a bipolar peak sensing mode to eliminate potential graphic aliasing problems; otherwise, it interpolates. See **Graphic Aliasing** on page 284.

In the bipolar peak sensing mode, the signal waveform is not faithfully represented but is replaced with an approximation indicating the positive and negative peak excursions of the signal.

If you use the graph **Zoom** and **Zoomout** commands, the time span represented on the graph changes. When **Interpolate** is selected, Wave Display au-

tomatically switches between bipolar peak sensing mode and interpolation mode for the best display.

The **Interpolate** selection produces a much more accurate display of the signal waveform than the **Display Samples** mode when the signal frequency is high (such as sample rate/100 or higher).

Display Samples

When **Display Samples** is selected, for each display point requested the DSP sends the amplitude of the nearest-in-time acquired sample to the computer for plotting. Acquisition sample values may be repeated or dropped, depending upon the relationship of acquisition sample density to display point density.

This mode is useful when examining the true, quantization-limited waveforms of very low amplitude digital domain signals.

When the signal frequency is low compared to the sample rate, **Display Samples** will produce an acceptable representation of the original signal waveform. At high signal frequencies, the waveform may be unrecognizable because of graphic aliasing (see page 284); in such a case, the **Interpolation** mode should normally be used.

Peak Values

When **Peak Values** is selected, the DSP searches all sample amplitudes in the acquisition buffer between each pair of X-axis time values plotted, and sends to the computer for plotting the largest positive or negative value in that span, preserving the sign.

Since all sample values are examined, no signal peaks can be missed.

Absolute Values

When **Absolute Values** mode is selected, the DSP searches all sample amplitudes in each plotted-point-to-plotted-point span as it does in **Peak Values** mode, but takes the absolute value of the largest positive or negative value, always sending a positive number to the computer.

Logarithms may be computed when all the numbers involved are positive, so **Absolute Values** mode brings the advantage that decibel units may be used on the Y-axis to display the waveform.

Waveform display with **Absolute Values** mode can create a wide dynamic range oscilloscope view that displays the envelope of an audio signal, calibrated in units such as dBV, dBu, and so on.

NOTE: **Absolute Values** mode is most effective at representing the signal envelope when the X-axis span and the Sweep panel **Points** values are selected to produce approximately two plotted points per cycle of the waveform being graphed. For example, if an envelope display of tone burst waveforms of a 1 kHz signal (1 ms period) is being plotted across a 50 ms span, the **Points** value on the Sweep panel should be set to approximately 100.

Graphic Aliasing




Figure 224. An example of graphic aliasing, where a large number of samples is represented by a small number of graph points, resulting in the display of an alias waveform.

When the density of samples is high compared to the density of graph points requested by the sweep **Steps** setting, many samples will be skipped and not plotted. Depending upon the signal and settings, waveforms very different from the signal waveform may be displayed. This is called graphic aliasing.

The 2700 series provides several display processing modes (discussed in detail previously) that minimize graphic aliasing problems. You can help avoid graphic aliasing in the following ways, as appropriate to your test:

- Use a larger number of sweep **Steps**.
- Use a shorter sweep span.
- Use the **Interpolate** display processing mode. **Interpolate** automatically switches from interpolation to bipolar peak sensing to avoid graphic aliasing.
- Use the **Peak Values** or **Absolute Values** modes, if appropriate.

The **Display Samples** display mode is most likely to exhibit graphic aliasing. If you use **Display Samples**, be sure that the number of graph points is sufficient to correctly display the number of sample points in the time span.

Spectrum (frequency domain) Display Processing

Octave Smoothing

Octave smoothing is a common technique in loudspeaker response measurement, useful in revealing trends by smoothing out anomalies in the response curve. Choose **Smooth (spectrum only)** in the Wave Display field to select octave smoothing.

When this method is selected the Smoothing field (just below Wave Display) becomes active. Specify the degree of smoothing you desire (see the next paragraphs) by entering a value between **0** and **2.64** octaves.

Unlike FFT power averaging, which takes the average of a number of measurements, octave smoothing is a display method that shows the results of one measurement as modified by a smoothing algorithm.

The 2700 series implementation of octave smoothing uses a hybrid FFT bin-averaging and interpolation technique to achieve smooth results even at very low bin densities. Smoothing effectively passes the raw frequency-domain response data through multiple constant-Q bandpass filters, one filter centered on each frequency requested from the Sweep panel. The bandwidth of these filters, in octaves, is specified in the Smoothing field.

The **Smooth (spectrum only)** display method affects only the frequency-domain, spectrum view of the acquired data.

Peak Picking

If the distance between the **Steps** in a sweep is greater than the width of one bin, plotted points are selected by a mechanism called *peak picking*. With peak picking, the DSP searches all bins between the previous plotted point and the current point, and plots the highest bin amplitude within that range. This ensures that no peaks are missed. Peak picking is used for all 2700 series FFT-generated frequency-domain displays.

FFT Start Time

You can select any point in the acquired signal record as the beginning of the portion to be transformed. This is the FFT Start Time.

The FFT is then computed for the contiguous section of samples starting at the FFT Start Time, and continuing for the number of samples chosen in the FFT transform length field. This permits selective spectrum analyses of different sections of complex signals such as program material, or special test signals such as sine wave bursts.


To change the value of FFT Start Time, click in the field and type in a new number from the keyboard. The acceptable range of numbers depends upon

the sample rate of the input signal for any particular acquisition buffer length, in samples. At a 48 kHz sample rate with a 16,384 sample acquisition buffer, for example, the FFT Start Time field will accept numbers up to 341 ms.

If the original signal acquisition was made with a negative value in the trigger Delay field, negative values up to and including that same value may be used as FFT Start Time values, permitting spectrum analysis of the pre-trigger section of the acquired record.

Triggering

Figure 225. Spectrum Analyzer Trigger Source selections.



The Trigger section of the Spectrum Analyzer consists of the Delay and Source setting fields, a dependent setting field labeled either Sens (sensitivity) or Lev (level) that becomes active for certain trigger Source selections, and the Slope option buttons.

Acquisition of signal into the FFT acquisition buffer may start immediately at Sweep Start, or may wait for a trigger event, depending upon the setting of the Trigger Source field.

Free Run

When **Free Run** is selected, signal acquisition begins immediately after Sweep **Start** (F9 or Go) is initiated, regardless of signal amplitude.

Auto

The **Ch. 1 Auto** and **Ch. 2 Auto** selections will cause triggering at one-half the peak-to-peak value if the selected channel has a signal amplitude greater than digital infinity (zero).

Fixed Sensitivity

Ch. 1 Fixed Sens and **Ch. 2 Fixed Sens** use the value set in the **Sens** (sensitivity) field as the triggering threshold. The **Sens** field is active only when one of these two selections is made.

An FFT acquisition will trigger on the first zero crossing of the selected slope (positive or negative, set with the adjacent option buttons) that occurs after the signal amplitude is sufficient to swing both through zero and the **Sens** value.

If the signal contains a sufficient DC offset such that it does not swing through zero, no triggering will take place. In this case, use one of the quasi-AC coupling modes (**Subtract Avg** or **Sub ½ pk-pk**) that will cause the processed signal to pass through zero and permit triggering to function.

Trig In (Ext)

The **External** selection refers to the **EXT TRIGGER IN** BNC connector on the rear of the 2700 series instrument. The trigger circuitry is edge-sensitive, and an FFT acquisition will trigger on a positive-going or negative-going edge of the signal at this connector, depending upon the setting of the trigger **Slope** buttons.

Digital Gen

If the Digital Generator is outputting any waveform except an Arbitrary Waveform, a **Digital Gen** trigger occurs at each cycle of the waveform.

If the Digital Generator is outputting an Arbitrary Waveform (that is, a signal from a waveform file), a **Digital Gen** trigger occurs at the first sample of the waveform.

Analog Gen

If the Analog Generator is outputting any waveform except an Arbitrary Waveform, an **Analog Gen** trigger occurs at each cycle of the waveform.

If the Analog Generator is outputting an Arbitrary Waveform (that is, a signal from a waveform file), an **Analog Gen** trigger occurs at the first sample of the waveform.

AC Mains

The **AC Mains** provides a trigger at each cycle of the AC waveform of the mains line powering the 2700 series instrument.

Jitter Gen

The **Jitter Gen** selection provides a trigger at each cycle of the waveform selected in the **Jitter Generation** section on the DIO panel. This provides stable viewing of the jitter waveform generated by the instrument.


Fixed Level

The **ChA Fixed Lev** and **ChB Fixed Lev** fields operate identically to conventional oscilloscope triggering.

When either of these trigger selections is chosen, the level (**Lev**) setting field becomes active. Positive or negative values may be entered into this field. An acquisition will be triggered the first time the signal with the specified slope (positive or negative) passes through this level.

Trigger Delay Time

Figure 226. Trigger Delay and Slope selections.



*NOTE: If a negative value was entered in the trigger **Delay** field before **Sweep Start** was pressed, the portion of the record selected for transform by the **FFT Start Time** field can extend back into the pre-trigger portion of the record by entering a negative value in the **FFT Start Time** field.*

The Spectrum Analyzer can fill the acquisition buffer with signal samples beginning at the moment of the triggering event, or beginning at a defined time before or after the triggering event occurs. This time is set in the trigger **Delay** field.

This enables analysis of signal conditions both before and after the triggering event.

A negative value entered in the **Delay** field determines the length of time prior to the trigger event signal that samples are retained. The total length of signal acquired will be as defined in the **FFT** transform length field, with the remainder of the acquisition buffer filled after the trigger.

For example, with the **Acquire** set to **24k** the length of the acquisition buffer for each channel is 512 ms at a 48 kHz sample rate. If the trigger **Delay** time value is **-50 ms**, then 462 additional milliseconds of signal following the trigger will also be acquired to fill the entire 512 ms buffer.

Trigger Slope

See Figure 226.

To the right of the trigger **Source** field are the trigger **Slope** buttons. Selecting **Pos** causes triggering to occur on the positive-going portion of the trigger source signal, while **Neg** causes triggering on a negative-going waveform.

Triggering with Synchronous Averaging

Synchronous averaging, which depends on the precise alignment of many acquisitions, requires careful consideration of triggering techniques. See **Synchronous Averaging** on page 273.

Without Re-alignment

If synchronous averaging without re-align mode is used, proper triggering is absolutely essential. Random, untriggered acquisitions will not be aligned in time, resulting in cancellation of coherent signals and large amplitude errors.

In stimulus-response testing using the 2700 series generators, either the **Analog Gen** or **Digital Gen** (as appropriate) FFT trigger sources should be used. If an external signal is presented from another signal source, one of the **Ch. 1** or **Ch. 2** selections should be used as a trigger source.

If signals are being acquired on both channels without re-alignment, they must be at the same frequency or must have harmonically-related frequencies. **Sync without re-align** will properly measure only signals harmonically related to the trigger source. A signal whose frequency is not related to the trigger source may have large amplitude errors or may entirely disappear.

With Re-alignment

The re-align mode should be used for accurate amplitude measurements on all signals above about 10% of the sample rate. Without realignment, the random time relationship between the signal itself and the 2700 series sample clock will cause random misalignment up to one-half clock period, resulting in partial cancellation that becomes objectionable at high frequencies. Realignment works with interpolated versions of the signal and aligns accurately, producing accurate amplitude measurements even at high frequencies.

The re-align mode works independently on each channel. If the two channels carry different frequency signals, re-align mode must be used.

The primary disadvantage of the re-align mode is the additional time taken by the DSP to do the operation after each acquisition.

The synchronous averaging with re-align

- acquires signal according to whatever triggering selections are in use,

- interpolates the acquired signal between the actual sample values,
- locates the first positive-going zero crossing in the interpolated data,
- time-aligns that with the first zero crossing in the accumulated record, and
- adds the signal from that point onwards into the averaging buffer.

This process is carried out after each of the series of acquisitions to be averaged, resulting in precise time alignment.

Triggering is not critically important in this mode if the signal is not noisy and the signal repetition rate is relatively high, since the necessary alignment takes place in the DSP buffer after acquisition.

Noisy signals may not be correctly aligned by this mode, resulting in amplitude error.

Triggering with Quasi-AC Coupling

The Spectrum Analyzer's quasi-ac coupling (see page 274) occurs before acquisition triggering, so the selection must be considered when attempting to trigger on a low-level portion of a signal.

In the synchronous averaging mode, the DSP must find a zero crossing in order to time-align waveforms for averaging. If the waveform contains sufficient dc, there will be no zero crossings. If this dc is removed before averaging there will be zero crossings, permitting alignment.

The **Subtract Avg** mode may introduce error on low frequency signals that could be a problem for the DSP in finding zero-crossing locations. For well-behaved signals the **Subtract ½ pk-pk** function should produce acceptable results.

References

Analog and digital amplitude and frequency references for the Spectrum Analyzer are the same as for other Digital Analyzer analysis tools. See **Digital Analyzer References** on page 151.

The Sweep Spectrum/Waveform Button



The 2700 series provides a dedicated FFT button for simplified Sweep panel setup and easy switching between frequency domain and time domain viewing. This button is called the **Sweep Spectrum/Waveform** button and is located on the Standard Toolbar. It is available when the Spectrum Analyzer, the Multitone Audio Analyzer, the Digital Interface Analyzer or the MLS Ana-


lyzer is the Digital Analyzer analysis tool, and is grayed out under other conditions.

In a new test, first select the Spectrum Analyzer as the Digital Analyzer tool, then click the **Sweep Spectrum/Waveform** button. This will automatically enter Sweep panel settings for a two-channel FFT spectrum display. Click Sweep **Start** and you will see the FFT plot on the Graph panel.

Click the **Sweep Spectrum/Waveform** button again, and the Sweep panel settings will be re-set for a two-channel waveform display. Click again and the display will toggle back to a spectrum display.

Clicking the **Sweep Spectrum/Waveform** button does not acquire or re-acquire data; it only re-transforms the acquired waveform for time domain or frequency domain display. Click Sweep **Start** to acquire new data.

Figure 227. Sweep panel showing “Waveform” toggle button.



Once an FFT spectrum or waveform view has been set up on the Sweep panel, a new button appears on the panel. In waveform view, this button is labeled **Spectrum**; in spectrum view, it is labeled **Waveform**. This button controls the same toggling functions as the **Sweep Spectrum/Waveform** button.

Acquired Waveform Files

As with other 2700 series tests, you can save the setup and results of any Spectrum Analyzer tests as an .at27 test file. The acquired waveform in the FFT acquisition buffer, however, is not saved as part of a test. If you want to keep the acquired data record for further analysis, you must save it as an .aam (mono) or .aas (stereo) acquired waveform file.

Single-channel “mono” waveforms saved at different times can later be individually loaded into the two channels of the FFT acquisition buffer to become “stereo” acquisitions for comparison in the time or frequency domains.

Saving Acquired Waveforms

Figure 228. Spectrum Analyzer Save Stereo Waveform dialog box.



To save an acquisition, select the **File > Save As** menu command, choosing either the **Stereo Waveforms** (.aas) or **Mono Waveforms** (.aam) as the file type.

A stereo acquisition waveform file consists of two waveforms joined together into a single file; a mono acquisition waveform file contains a single waveform. To simultaneously save the waveforms from both acquisition buffer channels 1 and 2, select the stereo choice. To save only one of the channels, select mono.

The left half of the dialog box defines what will be saved into the first section of a waveform file and the right half defines what will go into the second section of a stereo waveform. If the **File > Save As > Mono Waveform** option was selected, the right half of the dialog will be gray.

You can save the entire acquisition record or just the portion currently designated for transformation from either the channel 1 or channel 2 acquisition data. If the transform length is shorter than the acquisition record length, the waveform file will be correspondingly smaller.

Opening Acquired Waveforms

Figure 229. Spectrum Analyzer Open Stereo Waveform dialog box.



To open an acquired waveform file, select the **File > Open** menu command, choosing either the **Stereo Waveforms** (.aas) or **Mono Waveforms** (.aam) as the file type.

You can load one waveform or simultaneously load both waveforms into memory from a stereo file, and you can choose to assign the waveform to either FFT channel and to the acquisition or the transform buffers. A mono file only contains one waveform, but you have the same flexibility to load it into either channel or either buffer. When opening a mono waveform file, the right half of the dialog box will be gray.

NOTE: If acquisition in a file to be opened is greater than the length of the specified buffer, an error message will be displayed and the file will not be opened. If the acquisition length in the file is shorter than the buffer size, erroneous analysis will result if the selected FFT length extends beyond the last data sample in the buffer. You can view the data in the time domain to determine exactly where the signal ends.

Combining two Mono acquisitions to Stereo

To compare two single-channel acquisitions made at different times or under different conditions, open the file containing the first acquisition data. Assign the waveform to FFT channel A or B and load the data. Then open the second waveform file and do the same, this time loading the data into the opposite FFT channel.

The resulting two-channel acquisition can be transformed, processed and viewed, and can be saved as a new stereo waveform file.

Compatibility of Acquired Waveform Files

The waveform files used by both the Spectrum Analyzer and the Multitone Audio Analyzer have the same format, and with certain restrictions on length, can be used by either analysis tool.

The Spectrum Analyzer has a larger acquisition buffer, and can open waveform files up to 4 M (for 2700 series and Cascade *Plus*) samples in length. Multitone is limited to opening files with acquisitions of 32k or fewer samples.

Also, although any multitone waveform can be analyzed by the Spectrum Analyzer, only properly-formatted waveform files are useful in Multitone. See Chapter 14 for more information about the Multitone Audio Analyzer.

Chapter 13

The Digital Interface Analyzer

Overview

The Digital Interface Analyzer is a DSP analysis tool selection on the Digital Analyzer panel. It is named “Intervu” on Analyzer tool browser lists and in AP Basic command references.

The Digital Interface Analyzer provides the capability for in-depth analysis of the serial digital interface signal.

2700 series Digital Interface Analyzer Tools

The AES3/IEC 60958 serial digital interface signal that carries the embedded audio can be analyzed as a signal in its own right.

- Basic interface measurements are made as the signal is received. Real-time voltage and jitter amplitude measurements are displayed on the DIO panel, and four error types are flagged by DIO panel indicators. Also, the jitter signal detected at the AES receiver appears as an input selection to the Spectrum Analyzer for further analysis. For more information, see Chapter 9 regarding interface measurements on the DIO panel, and Chapter 12 for jitter analysis with the Spectrum Analyzer.
- In-depth interface signal analysis is made possible with the Digital Interface Analyzer, which uses a dedicated high-speed analog-to-digital converter (ADC) connected across the digital input with specialized FFT analysis and display tools.

See Appendix B for a discussion of digital audio and the serial digital interface signal.

The Digital Interface Analyzer ADC

The dedicated Digital Interface Analyzer ADC digitizes the interface waveform as it enters the instrument, providing a source of acquisitions for the Digital Interface Analyzer FFT analysis. The ADC is an 8-bit converter with an 80.00 MHz sample rate, providing an analysis capability with approximately 30 MHz bandwidth. The Digital Interface Analyzer acquires 1,572,864 samples into its acquisition buffer, resulting in 19.66 ms of data.

Digital Interface Analyzer Capabilities


The Digital Interface Analyzer provides analysis results in three different types of displays:

- time-domain waveform displays, including interface signal waveforms, interface signal eye patterns and jitter signal waveforms,
- frequency-domain displays, including interface signal spectrum and jitter signal spectrum, and
- statistical displays, including histograms of interface amplitude, interface rate, interface bit width and jitter amplitude.

The Digital Interface Analyzer uses FFT analysis techniques that have much in common with the techniques discussed in Chapter 12. Also see Appendix C for a conceptual overview of FFTs.

Loading the Digital Interface Analyzer

Figure 230. Loading the Digital Interface Analyzer.




To use the **Digital Interface Analyzer**, first open the Digital Analyzer panel. The Digital Analyzer is a command selection on the Panel menu, and is also available by the keyboard shortcut **Ctrl+Y**, or by clicking the **Analyzer** button on the Toolbar.

Now select **Digital interface analyzer (intervu)** from the list on the Analyzer panel. This loads the Digital Interface Analyzer program into DSP.

The Digital Interface Analyzer panel

Figure 231.

The Digital Interface Analyzer panel.



Unlike the other Digital Analyzer analysis tools, the Digital Interface Analyzer panel has no real-time meter displays. Although a number of settings and preferences are made on the panel, all the results are displayed on the Graph panel in conjunction with settings on the Sweep panel.

Later in this chapter we will look at the Digital Interface Analyzer panel in detail, but first we will look at the Sweep panel settings necessary to create the nine basic Digital Interface Analyzer views.

The chart in Figure 232 shows the nine views and the Sweep **Source 1** and **Data 1** (and **Data 3**, for Eye Pattern) settings which define the views. Also see **InterVuMenu.apb** on page 308. InterVuMenu.apb is a sample macro that makes the Digital Interface Analyzer setup a one-click process, combining a graphical menu interface with automated setup for the nine Digital Interface Analyzer views. Visit the Audio Precision Web site at ap.com to download sample macro and test files.




	Data 1: Intervu.Jitter(sec) Intervu.Jitter(UI)	Data 1: Intervu. Probability	Data 1: Intervu. Amplitude	Data 1: Intervu.Lower Eye Opening
				Data 3: Intervu.Upper Eye Opening
Source 1: Intervu.Ampl		Interface Amplitude Histogram 		
Source 1: Intervu.Freq	Jitter Spectrum 	Interface Bit-Rate Histogram 	Interface Spectrum 	
Source 1: Intervu.Time	Jitter Waveform 	Interface Pulse Width Histogram 	Interface Waveform 	Eye Pattern 
Source 1: Intervu.Jitter		Jitter Histogram 		

Figure 232. Sweep panel selections for the Digital Interface Analyzer views. Invalid Source and Data combinations are indicated by a slashed circle symbol.

Digital Interface Analyzer Waveform Views

The Digital Interface Analyzer offers two waveform (time domain) views of the digital interface signal and one of the interface jitter signal.

Interface Waveform

The interface waveform view shows the bitstream, which is the serial digital interface signal in a time-domain view. The 3 UI-wide preamble cell is clearly visible in this view, shown in Figure 233. See page 538 for an explanation of the *unit interval*, or UI.




Figure 233. Digital Interface Analyzer interface waveform display. “Y” preamble followed by six data cells shown.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1 = Intervu.Time**, and

- **Data 1 = Intervu.Amplitude**.

Source 1 range should be about ± 5 V.

Data 1 range will vary according to your requirements, signal conditions, sample rate, triggering choices and so on. A range of 0 s to 4 μ s with a 48 kHz sample rate will show a preamble and a few data cells, as in Figure 233; shorter spans will show pulse aberrations and rise and fall times; a range of 0 s to 25 or 35 μ s displays an entire frame.

On the Digital Interface Analyzer panel, the Amplitude vs Time wave display can be set to any choice except **Eye Pattern**.

Eye Pattern

The eye pattern is a special view of the interface waveform which gives a quick estimation of the quality of the signal.

With conventional oscilloscopes, the eye pattern is created by setting the horizontal sweep to about one UI, triggered at the cell rate (2 UI). The persistence of the screen phosphors (or the storage capabilities of the scope) display an overlay of hundreds or thousands of data cells.

This produces a one-cell-wide display with a shape like an eye. The inside of the eye is reduced horizontally by jitter (which moves the left and right sides of the eye in and out); the eye is reduced vertically by noise (which moves the top and bottom of the eye up and down) or by reduced signal level; bandwidth reductions tip the leading or trailing sections of the eye opening.

The Digital Interface Analyzer collects a long series of data cells (about 120,000 at a 48 kHz sample rate) and produces a graphic display equivalent to the inside of an eye pattern on an oscilloscope.

AES3 specifies a minimum eye opening of 200 mV vertically by 0.5 UI horizontally. The AES3 minimum can be superimposed as a reference on the eye pattern display by entering these values into a Limit file. The file 48kAES3 Eye-Pattern.adl is provided as a sample of such a Limit file.

On the Digital Interface Analyzer panel, the Amplitude vs Time wave display field must be set to **Eye Pattern**.




Figure 234. Digital Interface Analyzer eye pattern (48 kHz rate).

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1 = Intervu.Time,**
- **Data 1 = Intervu.Lower Eye Opening,** and
- **Data 3 = Intervu.Upper Eye Opening.**

If you set Amplitude vs Time to **Eye Pattern** and then check **Stereo Sweep** on the Sweep panel, these selections will be automatically made.

Source 1 range should be **0 ns** to about **165 ns**, and **Data 1** and **Data 3** ranges should be about ± 3 V. These will vary according to your requirements, signal conditions, sample rate, triggering choices and so on.

Jitter Waveform

The jitter modulating the interface waveform can be recovered and viewed as a signal in its own right. This selection shows the jitter waveform in the time domain.




Figure 235. Digital Interface Analyzer jitter waveform. 10 kHz sine wave jitter from DIO jitter generator.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1 = Intervu.Time,** and
- **Data 1 = Intervu.Jitter(sec)** or **Intervu.Jitter(UI)**

Jitter is a time modulation, and jitter amplitude is expressed in units of time, either in seconds or in UI. You choose between the two expressions when you make your jitter selection in the **Data** instrument browser.

The **Source 1** range will vary with the frequency of the jitter signal. Jitter frequencies can range from almost 0 Hz to several tens of kilohertz. Figure 235 shows a jitter sine wave with a period of about 100 μ s, giving a fundamen-

tal frequency of about 10 kHz; **Source 1 Stop** is set at 200 μ s. The **Data 1** range will vary with the jitter amplitude. Typical jitter amplitude ranges from 5 ns to 20 ns or more; Figure 235 shows a range of ± 20 ns.

On the Digital Interface Analyzer panel, the Amplitude vs Time wave display can be set to any choice except **Eye Pattern**.

See **Jitter Detection** on page 312 for more information.

Digital Interface Analyzer Spectrum Views

The Digital Interface Analyzer provides spectrum (frequency domain) views of the both the digital interface signal and the jitter signal extracted from the interface signal.

Interface Spectrum

The interface spectrum view shows a spectrum analysis of the serial digital interface signal, covering a frequency range extending from 0 Hz to over 30 MHz.




Figure 236. Digital Interface Analyzer interface signal spectrum analysis, 48 kHz rate.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1** = **Intervu.Freq**, and
- **Data 1** = **Intervu.Amplitude**.

Source 1 range should be **0 Hz** to about **35 MHz**; **Data 1** range about **0 dBV** to **-100 dBV**. These will vary according to your requirements, signal conditions, triggering choices and so on.

On the Digital Interface Analyzer panel, Amplitude vs Time can be set to any choice except **Eye Pattern**.

Jitter Spectrum

The jitter spectrum view shows a spectrum analysis of the jitter signal modulating the interface signal, covering a frequency range extending from 0 Hz to over 1.5 MHz, depending on the jitter detection employed. When excessive jitter has been determined to be a problem, spectrum analysis of the jitter signal is a powerful tool in locating the probable source.




Figure 237. Digital Interface Analyzer spectrum analysis of jitter signal.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1 = Intervu.Freq,** and
- **Data 1 = Intervu.Jitter(sec) or Intervu.Jitter(UI).**

Source 1 range should be **0 Hz** to about **1.5 MHz**; **Data 1** range about **1 ps** to **20 ns** on a log scale. These settings will vary according to your requirements, signal conditions, sample rate, triggering choices and so on.

When jitter signals below 120 kHz are being studied, use of the Spectrum Analyzer analysis tool with the Jitter Signal source will provide superior frequency resolution compared to the Digital Interface Analyzer. Jitter signal analysis using the Spectrum Analyzer is discussed in Chapter 12.

NOTE: Calibration for Digital Interface Analyzer jitter measurements is in terms of rms values, contrasting with the peak or average values selectable for the DIO panel jitter meter. The DIO panel jitter generator is calibrated in peak values.

Digital Interface Analyzer Histograms

A histogram is a statistical view, showing the probability of occurrence of a set of events throughout a range of possibilities.

Here's an example: the interface waveform nominally moves across a 5 Vpp range with very quick transitions. The probability of the instantaneous voltage being either +2.5 V or -2.5 V is high, and all other voltages have a low probability. The interface amplitude histogram shown in Figure 238 displays these probabilities.

Interface Amplitude Histogram

The interface amplitude histogram view shows a graph of the probability of the interface signal being at particular points across a range of amplitudes. When characterizing the squareness of a digital signal it is often convenient to view a histogram of the signal amplitude.

With no impairment of the interface signal, the resulting histogram will consist essentially of two vertical spikes. One is located at approximately the signal negative peak value and the other at the positive peak value.

If the interface signal pulse top and bottom are clean and level (no tilt or aberrations), the spikes will be narrow and of high probability values. Slower rise and fall times cause each spike to broaden in the direction of zero volts. Normal-mode noise causes broadening of each spike to both lower and higher amplitude values. If these impairments are severe enough, the two spikes will merge into a low probability lump spread across the peak-to-peak voltage range of the signal.




Figure 238. Digital Interface Analyzer interface signal amplitude probability, 5 Vpp signal.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1** = Intervu.Ampl, and
- **Data 1** = Intervu.Probability.

Source 1 range should be about ± 5 V; a **Data 1** range of 0% to about 20% on a linear scale is useful for this view.

Interface Pulse Width Histogram

The interface pulse width histogram view displays the probability of various values of width for interface signal pulses.

With no impairment of the interface signal, the resulting histogram will consist essentially of three vertical spikes at the 1 UI, 2 UI, and 3 UI points on the horizontal axis. The height of each UI spike shows the probability of pulse widths of that value occurring. For typical audio data, the 1 UI and 2 UI spikes will be approximately equal, indicating approximately equal numbers of one and two UI-wide pulses (logical ones and zeros in the embedded audio data). The 3 UI spike is significantly shorter (lower probability) since pulses of that width occur only in the preamble. Impaired rise and fall time and/or interfering noise will cause each spike to become wider, at correspondingly lower probability for any specific pulse width value.

The displayed time resolution of the pulse width histogram depends upon the span between the **Source 1 Start** and **Stop** values and the **Source 1 Steps** value.




Figure 239. Digital Interface Analyzer interface pulse width (interface timing) probability, 48 kHz rate.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1** = Intervu.Time, and
- **Data 1** = Intervu.Probability.

Source 1 range should be about **0 to 600 ns**; a **Data 1** range of **0.01%** to about **10%** on a logarithmic scale is useful for this view.

On the Digital Interface Analyzer panel, the Amplitude vs Time wave display can be set to any choice except **Eye Pattern**.

Interface Bit-Rate Histogram

The interface bit-rate histogram view displays the probability of occurrence of the various instantaneous frequency values of the interface waveform.

The Digital Interface Analyzer can “invert” the pulse width histogram described above to obtain a bit-rate histogram. The reciprocal of the time between each successive pair of zero crossings of the interface signal is measured and these times are sorted into bins depending upon their value.

Figure 240 shows three spikes, corresponding to the frequency equivalents of the 3 UI, 2 UI, and 1 UI pulses that make up the signal. At a 48 kHz sample rate, the 3 UI pulses are equivalent to a frequency of about 2.07 MHz, the 2 UI pulses correspond to a frequency of about 3.10 MHz, and the 1 UI pulses are equivalent to a frequency of about 6.16 MHz. Jitter will spread each spike across the nearby spectrum.




Figure 240. Digital Interface Analyzer interface rate probability, 48 kHz rate.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1** = Intervu.Freq, and

- **Data 1 = Intervu.Probability.**

Source 1 Stop should be set to about **7 MHz**; a **Data 1** range of **0%** to about **100%** on a linear scale is useful for this view.

Jitter Histogram

The jitter histogram view displays the probability distribution of the amplitude of the jitter signal.

The width of the histogram represents the peak-to-peak jitter amplitude. The breadth of the display near its mid-section is indicative of the average jitter amplitude.

A jitter signal with low average jitter will be represented by a high probability of near-zero values. Signals with high average jitter are represented by values falling into bins farther away from zero.

Square wave jitter will tend to produce a strong pair of peaks at the positive and negative peak jitter amplitudes, with a low amplitude area between them. Sine wave jitter will also produce a graph with two peaks, but the curve between them will follow a gentle arc. Random jitter histograms will vary from acquisition to acquisition, while jitter dominated by a coherent signal will tend to be more consistent.




Figure 241. Digital Interface Analyzer jitter probability.

As indicated in Figure 232, this view requires these Sweep settings:

- **Source 1 = Intervu.Jitter,** and
- **Data 1 = Intervu.Probability.**

An initial **Source 1** range should be about ± 50 ns. **Data 1** should be set on a linear scale, with **0%** at the bottom, and a top value between a few percent up to **50%**.

NOTE: When comparing histograms to the DIO panel jitter meter, remember that the DIO panel meter calibration is in terms of peak or average values, while the Digital Interface Analyzer jitter calibration is in terms of rms values.

Quick Launch Digital Interface Tests



One of the Quick Launch programs provided with AP2700 acts as a simple “front end” to access the different Digital Interface Analyzer views. On the Quick Launch toolbar, click the Digital Interface Analyzer (Intervu) button.





Figure 242. InterVuMenu.apb menu screen.

This Quick Launch program provides a graphical user interface (shown above) that loads a selection of sample tests that can be viewed as an introduction to the Digital Interface Analyzer, or that can be modified and saved for your own interface measurements.


Digital Interface Analyzer panel settings

Figure 243. The Digital Interface Analyzer panel.



Amplitude vs Time Displays (Time Domain view only)

Figure 244. Digital Interface Analyzer panel Amplitude vs Time selections.



Four modes are available in the Digital Interface Analyzer for processing the amplitude-versus-time relationship of a sampled signal before displaying the waveform. These modes are applicable only to time domain (oscilloscope) views and have no effect on Digital Interface Analyzer spectrum analysis or histogram views.

The display processing setting determines how the data is modified for display when the spacing of the sweep points is different from the spacing of sample points in the acquisition.

The four modes available in the Amplitude vs Time field are:

- **Interpolate**
- **Display Samples**
- **Peak Values**
- **Eye Pattern**

Interpolate, **Display Samples**, and **Peak Values** offer the same wave display processing as do those choices in the **Spectrum Analyzer**.

Interpolate

When **Interpolate** is selected the DSP compares the density of sweep points requested with the density of sample points available in the acquisition, for the time span of the current sweep and graph.

If the requested points are much fewer than the acquisition points, the DSP uses a bipolar peak sensing mode to eliminate potential graphic aliasing problems; otherwise, it interpolates.

In the bipolar peak sensing mode, the signal waveform is not faithfully represented but is replaced with an approximation indicating the positive and negative peak excursions of the signal. See **Graphic Aliasing** on page 284.

If you use the graph **Zoom** and **Zoomout** commands, the time span represented on the graph changes. When **Interpolate** is selected, the wave display automatically switches between bipolar peak sensing mode and interpolation mode for the best display.

The **Interpolate** selection produces a much more accurate display of the signal waveform than the **Display Samples** mode when the signal frequency is high (such as sample rate/100 or higher).

Display Samples

When **Display Samples** is selected, for each display point requested the DSP sends the amplitude of the nearest-in-time acquired sample to the computer for plotting. Acquisition points may be repeated or dropped, depending upon the relationship of acquisition point density to display point density.

When the signal frequency is low compared to the sample rate, this may produce an acceptable representation of the original signal waveform. At high signal frequencies, the waveform may be entirely unrecognizable in the **Display**

Samples mode because of graphic aliasing (see page 284). **Interpolate** mode should normally be used in this case.

Peak Values

When **Peak Values** is selected, the DSP searches all sample amplitudes in the acquisition buffer between each pair of X-axis time values plotted, and sends to the computer for plotting the largest positive or negative value in that span, preserving the sign.

Since all sample values are examined, no signal peaks can be missed. However, since most of the time domain signals are bipolar, this display method can produce odd displays; we recommend that you use **Interpolate**.

Eye Pattern

When **Eye Pattern** is selected, an entirely different sort of processing takes place in the DSP. **Eye Pattern** overlays many one-UI-segments of the acquired data on top of one another.

Following acquisition of the digital interface signal and extraction of an average clock signal from it, the worst-case (nearest to 0 V) amplitude is determined for each time increment relative to the beginning of each data cell. These values are plotted when **Intervu.Upper Eye Opening** and **Intervu.Lower Eye Opening** are selected as **Data 1** and **Data 3** parameters, resulting in a plot of the worst-case inside of the eye.

See page 300 for more information on the eye pattern.

*NOTE: The **Intervu.Upper Eye Opening** and **Intervu.Lower Eye Opening** selections will not be available in the Data browser unless **Eye Pattern** is selected in the Amplitude vs Time wave display field on the Digital Interface Analyzer panel. Conversely, if **Eye Pattern** is selected, conventional amplitude vs. time displays will not be available.*

Audible Monitoring in the Digital Interface Analyzer

Figure 245. Digital Interface Analyzer Audio Monitor.



The embedded audio or the extracted jitter signals may be selected for monitoring via the Headphone/Speaker panel and the instrument front panel Digital Signal Monitors.

Audio Monitor

It can be useful to listen to the audio on the digital interface signal being measured, enabling you to make a quick confidence check. It can also help you determine if the errors being measured correspond to the particular audible defect detected.


When the Digital Interface Analyzer is selected as the analysis tool, the audio channels embedded in the digital interface signal appears as the **DSP Monitor A** and **DSP Monitor C** selections on the Headphone/Speaker panel. These can be auditioned in either mono or stereo. The signals also appear at the DIGITAL SIGNAL MONITORS, CHANNEL 1 and CHANNEL 2 BNCs on the instrument front panel.

Jitter Signal

It is also possible to listen to the jitter extracted from the interface signal. This can provide clues to the source of the jitter, and it may help correlate audible distortions with the underlying jitter interference. Jitter is a mono signal, and is applied to both the **DSP Monitor A** and **C** Headphone/Speaker selection points.

Jitter Detection

Figure 246. Digital Interface Analyzer panel Jitter Detection selections.



The Digital Interface Analyzer is capable of measuring jitter both on AES3/IEC 60958 interface signals and on simple square wave clock signals typically used in ADCs and DACs. The Jitter Detection interface signal selections are:

- **Stable Bits**
- **All Bits**
- **Preambles**

The Jitter Detection square wave selections are:

- **Square wave Rising**
- **Square wave Falling**

These modes are described in the following sections.

AES3/IEC 60958 Jitter Detection

The AES3/IEC 60958 digital interface encodes two channels of digital audio into a single serial data stream. The serial signal consists of 32 cells (bits) per subframe and two subframes (left and right channels) per frame, for a total of 64 data cells per frame.

The frame rate is equal to the sample rate of the embedded audio.

There are 64 cells (bits) in a complete frame, and the cell rate is 1/64 the audio sample rate. The first four cells of each subframe are the preamble. The preamble always starts with a 3 UI (1.5 cell) wide pulse followed by sequences of 1 UI, 2 UI, and 3 UI pulses which are different among the three possible preambles. See Appendix B for more information on the serial digital interface signal.

An ideal pulse train would have regular transitions at exactly equal intervals corresponding to a master clock frequency. Jitter is the difference in timing of actual transitions of the pulse train from the instants when the transitions should theoretically have occurred. Therefore, jitter measurements require a stable, ideal clock signal to use as a reference for comparison of the actual transition times.

Part of the Digital Interface Analyzer's acquisition and processing of the digital interface signal involves reconstruction of an ideal clock for use as the reference for jitter measurements. The first three choices in the **Jitter Detection** field select the transitions at which the clock timing is compared to the interface signal.




Figure 247. Digital Interface Analyzer Jitter Detection Selections.

Stable Bits

The **Stable Bits** selection derives the stable reference clock at 1/4 the actual cell (bit) rate, which is 8 times the audio sample rate. **Stable Bits** is synchronized to the beginning transition of the preamble. If **Stable Bits** is used, the upper jitter detection frequency limit is reduced by 4:1 compared to **All Bits**. This provides an analysis frequency range of approximately 380 kHz at a 48 kHz sample rate.

Stable Bits and **Preambles** will result in the lowest residual measurement jitter. **Stable Bits** will be sensitive to all sources of jitter in a typical system, including jitter induced on an interconnect cable.

All Bits

The **All Bits** selection derives the stable reference clock at the actual cell (bit) rate, which is 64 times the audio sample rate. **All Bits** provides the maximum jitter detection analysis frequency range of approximately 1.5 MHz at a 48 kHz sample rate.

Preambles

The **Preambles** selection uses the average rate of the trailing edge of the first 3-UI-wide pulse in each preamble as the stable clock reference. Signal transitions at the same point are compared to that average reference to obtain jitter values for display. Since this derived reference clock rate is low (only twice the audio frame rate), the effective jitter measurement bandwidth equals the audio frame rate (sample rate) when **Preambles** is selected.

Preambles and **Stable Bits** will result in the lowest residual measurement jitter. Since the 3-UI pulse in a preamble is the most robust portion of the digital interface signal and is least affected by reduced bandwidth in the cable or system, **Preambles** will be relatively immune to cable effects and will be dominated by jitter in the source.

*NOTE: The filter algorithm used for the Amplitude vs Time **Interpolate** setting requires seven samples of input signal before displaying an output. This may make the jitter vs. time display show zeros for the first few microseconds.*


Square wave (Converter Clock) Jitter Detection

In addition to measuring jitter on an AES3 or IEC 60958 digital interface signal, the Digital Interface Analyzer can also measure jitter on any square wave connected to the digital input connector, for a range of 5 kHz to 15 MHz. This feature permits measurement of jitter directly on the clock signal of ADCs and DACs. The waveform of the jitter may be displayed in the time domain view, or a spectrum analysis of the jitter may be performed using the frequency domain view.

Select **Squarewave Rising** to measure jitter on rising edges of the signal and **Squarewave Falling** to measure on falling edges.

Averages

Figure 248. Digital Interface Analyzer panel Averages selections.




The Digital Interface Analyzer allows you to average the results of multiple acquisitions for certain displays, in order to reduce the variance of noise and to make coherent signals stand out more clearly. Averaging is available for the following displays:

- Interface Spectrum
- Jitter Spectrum
- Interface Pulse-Width Histogram
- Interface Bit-Rate Histogram
- Interface Jitter Histogram
- Eye Pattern

The **Averages** field selects the number of acquisitions to be averaged, from **2** to **128**. A selection of **1** disables averaging.

FFT Windows for the Digital Interface Analyzer

Figure 249. Digital Interface Analyzer panel Window selections.



The Digital Interface Analyzer has the several FFT windowing functions available for its frequency domain views, listed here:

- **Blackman-Harris**

The **Blackman-Harris** window provides a good trade-off between a window's ability to separate closely spaced spectral peaks and its ability to discriminate between moderately-spaced spectral peaks that are quite different in amplitude. Depending on whether or not the tone being measured is centered in the bin, there can be as much as 0.8 dB of error in the amplitude measurement.

■ **Hann**

The **Hann** window provides good selectivity near the top of the main lobe (about -6 dB one bin away from center and about -30 dB two bins away), with no side lobes. Its skirts more than 3 bins off center are not as steep as the **Blackman-Harris** window. The **Hann** window causes approximately -1.5 dB maximum amplitude error due to window attenuation, if the signal is at the extreme edge of the bin.

■ **Flat-Top**

The **Flat-Top** window provides measurements accurate to a few hundredths of a decibel for any spectral peak, but sacrifices selectivity for closely spaced tones.

■ **Equiripple**

The **Equiripple** window has the narrowest main lobe width for a given maximum side lobe depth. The main lobe is approximately 12 bins wide; that is, the first null is about six bins from the main lobe center. The first side lobe, which is also the highest, is -147 dB from the main lobe. The maximum amplitude error with a signal at the bin boundary is about 0.5 dB.

■ **None**

The **None** selection (sometimes called a rectangular window) does not apply any window function before the FFT. This mode is normally used only with synchronous signals; it is not generally useful for non-synchronous signals since energy will be spread across the entire spectrum unless the signal is exactly at bin center. The amplitude error due to the rectangular window attenuation is about 4 dB.


General purpose spectrum analysis applications, such as displaying the interface signal spectrum, can use the **Blackman-Harris** window. When making FFT-based amplitude measurements of a discrete-frequency jitter component, the **Flat-Top** window should be used.

See the discussions of FFT windowing in Chapter 12 and in Appendix C for more information on the window shapes and their relative advantages and disadvantages.

NOTE: The amplitude calibration for FFT spectrum analysis of jitter is in terms of the rms value of the jitter signal, such that a 1 kHz sine wave jitter signal measured at 10 ns peak on the DIO panel and displayed as a waveform of 20 ns peak-to-peak in waveform display mode will have an FFT peak at 1 kHz of about 7 ns ($\text{rms} = \text{peak} \times 0.707$).

Trigger Source

Figure 250. Digital Interface Analyzer panel Trigger Source selections.



When an acquisition is initiated (by clicking **Go [F9]** on the Sweep panel) the timing of the beginning of the Digital Interface Analyzer acquisition is determined by the settings made in Trigger Source, Receive Error, Trigger Slope and Data Acquisition.

The Trigger Source choices include several points in the digital interface signal at the digital input, the digital output or the AES/EBU REF input; from an square wave at the EXT TRIGGER IN jack, and from the instrument digital generator and jitter impairment generator. The trigger from the digital interface signals can be selected to correspond with the beginning of each Channel A subframe, Channel B subframe or at the beginning each status block, which occurs every 192 frames.

Most of these alternative triggering sources will not cause any difference in either spectrum or waveform display of the jitter signal, or of spectrum display of the interface signal waveform. The differences in triggering will be seen only when displaying the interface signal waveform (the time domain view) with a narrow span (a few microseconds) between the **Source 1 Start** and **Stop** times so that the 3-UI, 2-UI, and 1-UI pulse widths that make up the preamble can be distinguished.

The Trigger Source selections are:

■ ChA Rcv Preamble

An acquisition is triggered at the beginning of each Channel A subframe (each X-preamble and Z-preamble) of the interface signal received at the digital input. If there is jitter in the received waveform, that jitter (attenuated by the low-pass characteristics of the receiver circuit) will be reflected in the trigger waveform.

NOTE: For the various preamble trigger sources, the trigger operation is such that the trailing edge of the first 3-UI pulse of the preamble occurs nominally at time zero. The first information displayed after time zero in these cases will be the remaining 5 UIs of the selected preamble, followed by the first bit in the data area.

■ ChA Xmit Preamble

An acquisition is triggered at the beginning of each Channel A subframe (each X-preamble plus each Z-preamble) in the interface signal transmitted at the digital output. If jitter has been added as an impairment to the digital output, that jitter will be reflected in the trigger waveform.

NOTE: The transmit preamble selections have the same triggering characteristics as the receive preamble selections as mentioned in the note above. This triggering selection permits measurement of time delay through a digital device or system under test.

■ ChB Rcv Preamble

An acquisition is triggered at the beginning of each Channel B subframe (each Y-preamble) of the interface signal received at the digital input. If there is jitter in the received waveform, that jitter (attenuated by the low-pass characteristics of the receiver circuit) will be reflected in the trigger waveform.

■ ChB Xmit Preamble

An acquisition is triggered at the beginning of each Channel B subframe (each Y-preamble) in the interface signal transmitted at the digital output. If jitter has been added as an impairment to the digital output, that jitter will be reflected in the trigger waveform.

■ Receive Error

Four “receive error” conditions in the interface waveform are defined and flagged. See **Error Indicators** on page 178. Check the boxes in the Receive Error Triggers area of the panel to set the error condition(s) that you would like to use as triggers. When any of these selected conditions occurs in the interface signal received at the instrument digital input, an acquisition will be triggered.

■ Receive Block

An acquisition is triggered at the beginning of each Status Block frame (each Z-preamble) in the interface signal received at the digital input. This occurs once every 192 frames.

NOTE: The Transmit and Receive Block selections cause signal to be acquired at the first Channel Status Block Preamble transmitted or received. The Receive Block is delayed by two full frames by the AES receiver.

■ **Jitter Generator**

An acquisition is triggered at every zero crossing of the current Jitter Generator waveform, when Jitter Generation on the DIO panel is turned **ON**. This selection will provide a stable display of the received jitter waveform when measuring through a digital device. See **Output Impairments** beginning on page 162.

■ **External**

Acquisition is triggered on the next sample after an edge of the selected Trigger Slope (Pos or Neg) is detected at the EXT TRIGGER IN rear-panel BNC connector.

■ **Common Mode Signal**

An acquisition is triggered at each zero crossing of the Common Mode Sine impairment. See **Output Impairments** beginning on page 162.

■ **Interfering Noise**

An acquisition is triggered at each repetition of the pseudo-random noise impairment. See **Output Impairments** beginning on page 162.

■ **Digital Generator**

An acquisition is triggered at each zero crossing of the waveform being generated by the Digital Generator; for an arbitrary waveform, the acquisition is triggered at the beginning of each loop of the waveform.

■ **Transmit Block**

An acquisition is triggered at the beginning of each Status Block frame (each Z-preamble) in the interface signal transmitted at the digital output. This occurs once every 192 frames.

■ **ChA Sync Preamble**

An acquisition is triggered at the beginning of each Channel A subframe (each X-preamble plus each Z-preamble) in the interface signal received at the AES/EBU REF IN digital input.

■ **ChB Sync Preamble**

An acquisition is triggered at the beginning of each Channel B subframe (each Y-preamble) in the interface signal received at the AES/EBU REF IN digital input.

■ **Sync Error**

Four “receive error” conditions in the interface waveform are defined and flagged. See **Error Indicators** on page 178. Check the boxes in the Receive Error Triggers area of the panel to set the error condition(s) that you would like to use as triggers. When any of these selected conditions

occurs in the interface signal received at the AES/EBU REF IN input, an acquisition will be triggered.

■ **Sync Block**

An acquisition is triggered at the beginning of each Status Block frame (each Z-preamble) in the interface signal received at the **SYNC/REF IN** input. This occurs once every 192 frames.

■ **Input Zero Crossing**

An acquisition is triggered at each zero crossing (of the selected Trigger Slope, Pos or Neg) of the digital input signal.

■ **ChA Ref Out Preamble**

An acquisition is triggered at the beginning of each Channel A subframe (each X-preamble plus each Z-preamble) in the interface signal transmitted at the AES/EBU REF OUT digital output. Since this reference output cannot have a jitter impairment applied, a trigger extracted from this signal will not be jittered.

■ **ChB Ref Out Preamble**

An acquisition is triggered at the beginning of each Channel A subframe (each X-preamble plus each Z-preamble) in the interface signal transmitted at the AES/EBU REF OUT digital output. Since this reference output cannot have a jitter impairment applied, a trigger extracted from this signal will not be jittered.

Triggering for Square Wave Jitter Detection

None of the serial digital interface trigger sources (receive and transmit block, error and sub-frame sources) is useful when measuring square wave (converter clock) jitter.

For stable triggering on a square wave signal, split the connection with a BNC “T” adapter and connect the two resultant lines to the 2700 series DIGITAL INPUT and the EXT TRIGGER IN rear panel connection. Select **External** as the Trigger Source.

The **Jitter Generator** trigger mode can be useful when looking at jitter on a square wave clock that is derived from an AES3 signal fed from the 2700 series digital generator output.

Trigger Slope

*Figure 251. Digital Interface Analyzer
Trigger Slope & Data Acquisition*



The Trigger Slope selections enable you to choose whether the Digital Interface Analyzer acquisition triggers on the positive-going (rising) or negative-going (falling) slope of the trigger waveform selected in the Trigger source field.


Data Acquisition

The Digital Interface Analyzer data acquisition length is fixed at 1,572,864 samples, which, at the 80 MHz sample rate of the Digital Interface Analyzer ADC, gives an acquisition duration of 19.66 ms. The Data Acquisition selections choose whether the acquisition is the 19.66 ms before the trigger event (Pre-trig), or the 19.66 ms after the trigger event (Post-trig).

See Figure 251.

Receive Error Triggers

Figure 252. Digital Interface Analyzer panel Receive Error Trigger selections.




The receive error selections cause data to be acquired when the AES3 receiver detects one or more parity, coding, lock, or confidence errors. The checkboxes permit the selection of any or all these types of error to cause triggering.

Sync Error is identical to Receive Error, but pertains to a signal connected to the rear panel AES/EBU REF IN connector rather than the front panel digital input.

Depending upon whether **Pre-trig** or **Post-trig** Data Acquisition was selected, the data in the buffer will precede or follow the first error detection.

References

Figure 253. Digital Interface Analyzer panel References.



The **Freq.** value serves as the reference for relative frequency units used in the Digital Interface Analyzer. Relative frequency units are useful for displaying the spectra relative to the interface sample rate or relative to the jitter frequency.

There are several choices of relative frequency units in the 2700 series, including **F/R**, **dHz**, **%Hz**, **octs**, **decs**, **d%** and **dPPM**. These are available when the Sweep **Source** or **Data** parameter is set to **Intervu.Frequency**. For a complete discussion of these units and their definitions see Appendix A.

Saving and Loading Interface Waveforms

As with other 2700 series tests, you can save the setup and results of any Digital Interface Analyzer test as an .at27 test file. The acquired waveform in the Digital Interface Analyzer acquisition buffer, however, is not saved as part of a test. If you want to keep the acquired data record for further analysis, you must save it as an .aai acquired waveform file.

When the Digital Interface Analyzer is selected as the analysis tool, the **File > Open > Intervu Waveforms** and **File > Save As > Intervu Waveforms** menu commands become available.

These commands allow you to save a Digital Interface Analyzer (Intervu) acquisition waveform to disk as an .aai file, or to open an existing .aai (Intervu) file and load the waveform into the acquisition buffer.


Chapter 14

The Multitone Audio Analyzer

Introduction

The Multitone Audio Analyzer is a DSP analysis tool selection on the Digital Analyzer panel. It is an FFT-based analysis tool for use with both analog and digital audio signals. Multitone is called “Fasttest” on instrument browser lists and in AP Basic macro references.

Figure 254. The Multitone Audio Analyzer panel.



Overview: Multitone Testing

The Multitone Analyzer uses a synchronous FFT to analyze a special multitone waveform that is a combination of many sine waves. Figure 255 shows the spectrum of a signal made up of 36 tones.

NOTE: For more information about synchronous FFTs and other concepts used in FFT analysis, see Appendix C.




Figure 255. Spectrum View of Typical Multitone Stimulus Signal.

Although it can be output by either the Analog or the Digital Generators, a multitone waveform is generated in DSP and is designed so that all the sine waves will be synchronous.

The multitone signal is applied to the DUT and an acquisition of the device's output is made for analysis. Since the waveform is synchronous, each sine wave falls only into its own bin, maximizing frequency resolution. Any harmonic distortion products created in the DUT will also be synchronous, and each of these products will fall into its own bin as well.


The FFT data can then be interpreted in several ways, extracting amplitude, phase, distortion, noise and crosstalk results. Multitone can provide detailed, accurate and very fast measurements using a short multitone “burst.”

The Multitone Analyzer normally provides a frequency domain (spectrum analyzer) view of the signal. A time domain (oscilloscope) view is also available but is rarely used.

Multitone Waveform requirements

A multitone test signal is a complex waveform, the combination of two or more sine waves. There are typically from 3 to 30 or more tones in a multitone signal; to the ear, it sounds like a dissonant organ chord.

Figure 256. Example of multitone stimulus spectra.



We will look at different types of multitone measurements in the next sections; for our example diagrams we will assume the use of the multitone stimulus signal diagramed in Figure 256. This multitone example has ten tones on Channel A and ten on Channel B. For crosstalk measurements, two tones on each channel are unique (F9 and F11 on Channel A, and F10 and F12 on Channel B).

The number and approximate frequencies of the tones in a multitone waveform are determined by the type of test you are performing. If you are making a 1/3-octave spectrum analysis, for example, you would choose 31 tones, each very near to one of the frequencies specified for the standard ISO 31 test.

The exact frequencies selected for the 31 tones must each be synchronous for the record length of the FFT. This is accomplished by making each tone an integer multiple of a base frequency which is synchronous.

Sample multitone waveforms

In the 2700 series, multitone waveforms are generated using the Arbitrary Waveform function in either generator, which loads and “plays” a waveform file from disk. Many multitone waveform files (such as ISO 31) are included with the 2700 series, ready to load and use.

Creating custom multitone waveforms

You can also create your own waveform files using the Multitone Creation Utility. See **Creating Multitone Waveform Files** on page 348.

Multiple Synchronous Tones in One Waveform

The lowest synchronous frequency for an FFT is the frequency for which one cycle fits exactly in the transform buffer, calculated by dividing the signal sample rate by the transform length in samples. For example, a sample rate of 48 kHz and a transform length of 8192 samples gives a base frequency of 5.859375 Hz. That frequency and all integer multiples of that frequency are valid tones to use in a 48 kHz multitone waveform being measured by an FFT analyzer using an 8192 sample acquisition.

That's a lot of calculations for a 31-tone waveform created for three different sample rates. Instead of pencil and paper, use the Multitone Creation Utility (page 348) to facilitate creation custom multitone waveforms.

“Inside Information”: Multitone Generator Settings


To make multitone analysis fast and consistent, the Multitone Audio Analyzer requires information about the nature of the multitone file in use.

The Analyzer must “know” what tones are in the multitone waveform, the sample rate at which they were generated, etc. In most cases, this information is passed from the 2700 series generator directly to the Multitone Analyzer with no user input needed.

This is not possible when the multitone waveform is being played from an audio tape or a CD, or if it is being transmitted from a remote location. In these cases, you must load a multitone waveform into one of the 2700 series generators. This waveform must have the same characteristics as the multitone being used for the test. The audio output of the generator is not used, but the waveform information is sent to inform the analyzer of the multitone conditions.

The Multitone Audio Analyzer panel

Figure 257. Loading the Multitone Audio Analyzer.




To use the Multitone Audio Analyzer, first open the Analyzer panel. The Analyzer panel is a command selection on the Panels menu, and is also available by the keyboard shortcut **Ctrl+Y**, or by clicking the **Analyzer** icon on the Toolbar.



Now select **FASTTEST Multitone Audio Analyzer** from the list on the Analyzer panel. This loads the Multitone Audio Analyzer program into DSP.

Signal Inputs

Figure 258. Multitone Audio Analyzer Signal Inputs.



The Input field enables you to choose the digital input or the analog inputs (converted to digital) as the signal applied to the Multitone Analyzer. The selections are:

- **Digital @ISR**
- **HiRes A/D @65536**
- **HiBW A/D @131072**
- **HiBW A/D @262144**
- **HiRes A/D @SSR**
- **HiBW A/D @2xSSR**


The digital input and converter choices are the same for all five of the DSP audio analysis tools (DSP Audio Analyzer, Spectrum Analyzer, Multitone Analyzer, MLS Analyzer and Harmonic Distortion Analyzer). Go to **Signal Inputs** on page 228 in the **DSP Audio Analyzer** chapter for detailed information about the Digital Analyzer Inputs.

Source Selection

The Source selection choices depend on the Input selected; the lists are different for the **Digital @ISR** input and for the analog (A/D) inputs.

Digital @ISR Sources

Figure 259. Multitone Audio Analyzer Source Selection, digital input.




When **Digital @ISR** is the analyzer input, the source selections for each analyzer channel are:

- **A**
The embedded channel A audio is routed to the analyzer channel.
- **B**
The embedded channel B audio is routed to the analyzer channel.
- **None**
Acquisition is disabled for the analyzer channel, preserving any signal previously in the acquisition buffer. This permits acquisition of signals into the Ch 1 and Ch 2 buffers at two different times for comparison of different devices or of the same device under different conditions.

Analog (A/D) Sources

Figure 260. Multitone Audio Analyzer Source Selection, analog input.



When one of the analog-to-digital converters is selected as Input, the Source choices list the same set of analyzer analog source options available for the Spectrum Analyzer, which are each discussed beginning on page 264. However, only the **Anlr A**, **Anlr B** and **None** sources are likely to be used with the Multitone Analyzer.

■ Anlr-A

The Channel A analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL A output, which appears on the front panel on a BNC connector.

■ Anlr-B


The Channel B analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL B output, which appears on the front panel on a BNC connector.

■ None

Acquisition is disabled for the analyzer channel, preserving any signal previously in the acquisition buffer. This permits acquisition of signals into the Ch 1 and Ch 2 buffers at two different times for comparison of different devices or of the same device under different conditions.

Peak Level Monitors

Figure 261. Multitone Audio Analyzer Peak Level Monitors.




The two Peak Mon meters on the Multitone panel continuously display the peak amplitude of the digital signal as it is presented to the Multitone Audio Analyzer. Only digital domain units (**FFS**, **dBFS**, **%FS**, or **bits**) are available for these meters.

The primary purpose of the peak monitors is to avoid overload of the input analog-to-digital converters (ADCs). When signal is being acquired from the analog source and **Auto Range** is in use on the Analog Input panel, ADC over-range should never be a problem. If any of the Analog Input range controls is fixed, you must verify that the maximum signal amplitude never exceeds digital full scale.

Multitone Measurements

Once a multitone signal has been routed through the DUT, an acquisition is made and an FFT is performed. The Measurement field selects the type of post-processing performed on the FFT results before they are displayed or compared to limits.

Figure 262. Multitone Measurement selections.




Frequency Domain Views by default

The display for each of these measurement modes is by default a frequency domain view, plotting the results on amplitude vs. frequency graph. **Spectrum** and **Response** measurement results can also displayed as phase vs. frequency plots by choosing a **Fasttest.Phase** instrument in the Sweep **Data** browser.

Spectrum

Figure 263 shows a diagram representing an FFT spectrum display of the signal at the DUT output, for our example multitone of Figure 256. Note that the illustration shows that the DUT has modified the response and has added noise and distortion to the signal.

Figure 263. Example of a multitone spectrum.



The 2700 series **Spectrum** Multitone Measurement selection provides a normal FFT spectrum display with no processing except for peak picking (see page 285) when necessary. Since **Spectrum** mode shows the amplitude (or phase, if selected) of every bin without discrimination, it is useful for verification of signal presence but not for analysis.





Figure 264. Typical Multitone **Spectrum** measurement.

Spectrum normally displays amplitude vs. frequency, but will show phase vs. frequency if **Fasttest.Phase** is selected as a Sweep **Data** instrument.

Response


Response mode displays a response curve drawn through the amplitude (or phase, if selected) measured in each of the bins that correspond to a stimulus tone in the multitone signal. This gives the frequency response (or phase response) of the DUT.

Figure 265. Example of a multitone frequency response.



In the multitone frequency response example diagramed in Figure 265, the amplitude in each of the bins which are known to have tones is shown as a light gray line. The dark line represents the frequency response curve.

Figure 266. Example of a multitone phase response.



Response normally displays amplitude vs. frequency, but will show phase vs. frequency if **Fasttest.Phase** is selected as a Sweep **Data** instrument.

In the multitone phase response example diagramed in Figure 266, the phase in each of the bins which are known to have tones is shown as a light gray line. The dark line represents the phase response curve.

You can measure either the absolute phase relative to the generator, or the phase difference between Channel B and Channel A. See Phase Measurements, page 342.

The 2700 series **Response** Multitone Measurement selection provides a response curve as shown in Figure 267.





Figure 267. Typical Multitone **Response** measurement, amplitude vs. frequency.

Distortion

Figure 268. Example of a multitone distortion response.



In a conventional distortion test where only a single tone is in the stimulus, only that fundamental frequency needs to be removed. What's left is the total harmonic distortion and noise.

For a multitone distortion reading using our example waveform, the bins containing tones F1 through F10 are rejected from the reading, as shown by the dotted lines in Figure 268. The residual is the noise and distortion products, shown as light gray lines. The values in these residual bins are *rss* (root sum square) summed between sweep steps, and a distortion response curve (the dark line) is drawn through these results for display.

A typical display of an the 2700 series Multitone **Distortion** measurement is shown in Figure 269.





Figure 269. Typical Multitone **Distortion** measurement.

Noise

Figure 270. Example of a multitone noise response.



In many devices, noise is not constant but varies according to the applied signal. Multitone is the only technique that can measure noise in the presence of signal.

To measure noise without measuring the applied signal, the Multitone FFT Length must be set to twice the length of the stimulus waveform. In the 2700 series Multitone Audio Analyzer, this is accomplished when the FFT Length is set to **Auto**.

Under such conditions the analyzer frequency resolution is twice the resolution of the generated signal, with twice the bins of an FFT that matches the waveform length. The power in these “extra” bins is a measurement of the noise generated in the DUT in the presence of applied signal, excluding the signal itself. See the sidebar for more detail.

Odd bins only

In multitone tests, the length of the waveform and the length of the transform buffer are normally set to be the same; in our example, 8192 samples, giving a frequency resolution or bin width of about 5.86 Hz at a sample rate of 48 kHz.

For a measurement of noise in the presence of signal, the length of the transform buffer is set to be exactly twice the length of the multitone waveform. Under these conditions the FFT is still synchronous, but at 16384 samples, the frequency resolution has doubled to 2.93 Hz.

The effect of this is that any tone or product of a tone from the original 8192-sample-long multitone must fall only into alternate bins in the FFT, the “even” bins that are 5.86 Hz apart. The “in-between” or “odd” bins (shown in light gray in Figure 270) contain only noise. The result at each sweep step is twice the rss sum of the noise power in the odd bins between that sweep step and the step below it. A response curve (the dark line in Figure 270) is drawn through these results for display.

Why TWICE the rss sum? To take into account the unmeasured noise power in the skipped “even” bins in each measurement segment.

The 2700 series **Noise** Multitone Measurement selection provides a noise vs. frequency curve as shown in Figure 271.





Figure 271. Typical Multitone **Noise** measurement.

NOTE: In a DUT with no distortion, a Multitone **Distortion** measurement and a **Noise** measurement will provide essentially the same results.

Masking Curve

Figure 272. Example of a multitone masking curve analysis.



In a masking test, the control software determines the correct masking curve (the shapes of which vary with frequency) for every tone to be evaluated, at the levels they are received from the DUT. The dark lines in the upper illustration of Figure 272 are an example of this.

Masking

Masking is a characteristic of human hearing. A loud sound close in frequency to a quieter sound “masks” the quieter sound; under these conditions, we perceive only the louder sound. For example, faint noise or distortion products centered in a range around 7 kHz might be audible in an otherwise quiet signal, but if a louder 7 kHz tone is added to the signal, the noise will be masked.

The effects of masking vary with frequency and level. Curves have been determined which quantify masking effects at different frequencies and levels for the average listener.

It is important to understand and measure masking effects to evaluate under what conditions noise is audible in a dynamic signal. The Multitone Audio Analyzer tests low-bit-rate perceptual coders with multitone signals by summing quantization noise and distortion and comparing it to an embedded psychoacoustic model of the frequency masking effect.

A composite curve is created which represents the total masking which would be in effect for the tones selected. You can then append to this curve the

original data in a spectrum or distortion view to produce a graph like the lower illustration in Figure 272.

You can also save the masking curve data as a limit file and attach it to other tests.

Crosstalk

Figure 273. Example of multitone crosstalk response.



Crosstalk depends on the presence of at least two unique tones in each channel, tones that are not present in the multitone waveform for the opposite channel.

In our example, F9 and F11 exist only on the A channel, and F10 and F12 exist only on B. To measure crosstalk from B to A, the Multitone Analyzer rejects all bins but the ones at F10 and F12. In the same way, crosstalk from A to B is measured by rejecting all bins but the ones at F9 and F11. The only signal in these bins will be crosstalk from the opposite channel. A response curve (the dark line in the illustrations above) is drawn through these amplitudes on each channel for display.

To characterize crosstalk across a range of frequencies, use multitone waveforms with a range of unique crosstalk tones.

The 2700 series **Crosstalk** Multitone Measurement automatically determines from the two generator waveform buffers which frequencies are unique to each channel. Then **Crosstalk** measures the amplitude on the opposite (non-driven) channel at each of those unique tones, providing crosstalk response curves as shown in Figure 274.




Figure 274. Typical Multitone **Crosstalk** measurement.


Time Domain View

A time domain view is also available, showing the multitone waveform as an oscilloscope-style trace. The time domain view does not change with measurement mode selection. This view can be useful to observe the peak levels or crest factor of your multitone signal.

Click the **Spectrum/Waveform** toggle button or choose **Fasttest.Time** in the Sweep **Source 1** browser to enable the time domain view. See the table on page 345 for a listing of available and valid Multitone display modes and their results.

Frequency Resolution

Figure 275. The Multitone Freq Resolution field.



The Freq Resolution control has two functions:

- Setting Multitone triggering frequency resolution.
- Setting root-sum-square (rss) summing frequency resolution in **Response** and **Distortion** measurement modes.

Setting Multitone triggering resolution

The Multitone Audio Analyzer has the ability to recognize a specific multitone waveform in the received signal by comparing the signal to the multitone file information passed from the 2700 series generator. When the frequencies in the received signal match the generator frequencies, the analyzer recognizes the incoming multitone and issues a trigger to begin the acquisition and analysis procedure.

If Frequency Resolution has been set to zero and the frequency of the incoming signal has been shifted, Multitone will not recognize the waveform and will not trigger. A setting greater than zero in the Frequency Resolution field broadens the range of acceptance, so that Multitone will recognize and trigger from a frequency-shifted waveform. The maximum value is 13%.

Setting frequency resolution for rss summing

Speed variations such as flutter spread the stimulus tones into close groupings of modulation products (sidebands). For more accurate measurements the energy in these sidebands must be considered.


The Frequency Resolution control sets the range of frequencies that are:

- included in an rss sum at each specified tone in **Response** and **Crosstalk** measurement modes; or
- excluded from the measurement at each specified tone in **Distortion** and **Noise** measurement modes.

A Frequency Resolution setting of **0%** returns the amplitude of the bin at the stimulus tone. Greater Frequency Resolution settings widen the range to allow inclusion or exclusion of the amplitudes of the close-in modulation products. The maximum widening of resolution is 13%.

Multitone FFT Length

Figure 276. Multitone FFT Length selections.



The Multitone FFT Length field value controls the record length used when signal is acquired or a re-transformation is initiated. Longer transform lengths produce greater frequency resolution (more bins) in the resulting FFT, but require longer times to acquire and transform the signal.


Auto is the recommended selection. The **Auto** selection automatically sets the acquisition buffer and transform length to be exactly twice the length of the arbitrary waveform presently loaded into the generator. This condition is essential for the **Noise** measurement function of the Multitone Audio Analyzer, and will also work well with any other Multitone test.

One of the seven fixed FFT lengths can also be selected. For Multitone to provide useful results, a selected fixed FFT length must be an integral multiple

of the multitone waveform length. See Appendix C for more information on transform length for synchronous FFTs.

Processing

Figure 277. Multitone Processing selections.



The Processing choices for the Multitone Audio Analyzer are

- **Synchronous**
- **Freq Corrected**
- **Windowed.**


Synchronous is the normal selection. **Synchronous** processing uses no window function and assumes that the generator tones are synchronous with the FFT length.

Freq Corrected is also a synchronous selection, but, similar to the **None, move to bin center** selection in the FFT Analyzer, this choice first corrects the frequency of the received signal by up to $\pm 4\%$ in an attempt to make the generator tones and the FFT length synchronous. This process takes more time than the **Synchronous** selection, and should be used only if the received signal has passed through a device that has slightly shifted its frequency.

Windowed applies a Hann window to the signal before transformation. This choice offers poorer selectivity than the two synchronous selections, and should only be used in situations where frequency shifting of the multitone signal has occurred and the use of the **Freq Corrected** mode offers insufficient frequency-shifting range or is otherwise undesirable.

Triggering

Figure 278. Multitone Triggering selections.



The Multitone Audio Analyzer has seven triggering modes.

Off

Off results in untriggered or free-running operation. Acquisition and processing begin as soon as the **Go** button pushed.

DGen and AGen

The 2700 series generators issue a trigger when the first sample of the Multitone waveform is generated. When **DGen** or **AGen** is selected, the Multitone Analyzer triggers from that source. **DGen** and **AGen** triggers provide consistent, stable operation and are the recommended triggering modes for locally-generated multitones.

The generator triggering modes are the only triggering modes that will return a correct result in a **Ch. 2** phase measurement.

Tight, Normal and Loose

Tight, **Normal** and **Loose** triggering are for use when receiving a multitone waveform that is not currently being output from an the 2700 series generator—a waveform from an audio recording or a distant transmitter, for example. As mentioned before, the same multitone waveform that is being received must be loaded into the generator. The Multitone Analyzer compares the incoming signal with the multitone waveform in memory to decide when to begin its acquisition.

Normal is the recommended setting for receiving an external multitone. If the signal is degraded and will not trigger properly, **Loose** relaxes the triggering criteria and may provide more consistent triggering. **Tight** enforces the criteria more strictly, and will provide better triggering when the multitone burst is very short, or when program material on the line might cause false triggering.

External

The **External** triggering selection responds to a trigger event at the EXT TRIGGER IN connector on the instrument rear panel.

Trigger Delay


Audio processors (compressors, limiters, etc.) require time to stabilize following any change of level, such as between the multitone burst and the preceding program material.

If you need to allow processors in an audio chain to stabilize before measurement, a delay can be inserted between recognition and acquisition of the signal. The **Trigger Delay** field controls the interval between initial recognition of the incoming multitone signal and capture of the portion of signal which will be analyzed.

If you set a **Trigger Delay**, be sure that the duration of the multitone burst transmitted is increased by the same amount over the normal minimum burst duration; see **Multitone Minimum Duration Requirements** on page 343.

Phase Measurements

Figure 279. Multitone Ch. 2 Phase selections.



By default, Multitone results are displayed as amplitude vs. frequency plots. To measure phase, select **Fasttest.Ch.1 Phase** or **Fasttest.Ch.2 Phase** (or both) as a Sweep **Data** instrument.

Most multitone waveforms (and all of the multitone samples provided with the 2700 series) have had the phase of each tone shifted randomly to reduce the crest factor of the waveform. In the 2700 series this process is called “phase randomization.” Waveforms that have had this process applied will not return valid phase results, with one exception mentioned below in **Channel 2 Phase**.

You can create your own multitone waveforms for phase tests without randomizing the phase by unchecking the “Minimize Crest Factor” checkbox on the Multitone Creation Utility dialog box. Such waveforms will have a high crest factor. See **Creating Multitone Waveform Files** on page 348.

Channel 1 Phase

When **Fasttest.Ch.1 Phase** is selected for Sweep **Data** in a Multitone test, the readings are of the absolute phase of the acquired Channel 1 multitone rel-

ative to the corresponding tones at the 2700 series generator. The multitone signal must originate from a local generator in the instrument, and the Multitone Analyzer must be set to trigger from that generator. The tones must not have had their phases randomized.

Channel 2 Phase

When Fasttest.Ch.2 Phase is selected for Sweep **Data** in a Multitone test, you can select one of two phase measurements from the Ch. 2 Phase field:

- **Ch. 2**

This selection measures the absolute phase of the acquired Channel 2 multitones relative to the corresponding tones at the instrument generator. The multitone signal must originate from the 2700 series generator, and the Multitone Analyzer must be set to trigger from that generator. The tones must not have had their phases randomized.

- **Ch. 2 – Ch. 1**

This “2 minus 1” selection measures the phase of the Channel 2 multitone signal tones relative to the corresponding tones in the Channel 1 signal. For this to be meaningful, the waveforms for both Channel 1 and Channel 2 must be identical. Use a mono multitone waveform, filename extension .agm.

*NOTE: Since a mono waveform has identical tones on each channel, it is permissible to have used the “**Minimize Crest Factor**” feature in the creation of this file. The phase randomization introduced will be the same on both channels, and the relative phase measurement will be valid.*

References

Analog and digital amplitude and frequency references for the Multitone Audio Analyzer are the same as for other Digital Analyzer tools. See **Digital Analyzer References** on page 151.

Other Considerations

Multitone Minimum Duration Requirements

The minimum duration of multitone signal which must be present to guarantee analyzer triggering depends primarily upon the generator record length used to create the multitone signal. The required signal duration also varies inversely with the sample rate at which the signal was generated (and, in the case of digital inputs, will be received). Small variations in required duration are also a function of whether the signal is acquired from an analog or the

AES3 serial digital source, and whether or not the frequency correction function of the **Processing** field is in use.

Generator Record Length	Minimum Burst Duration	Lowest Freq. & Minimum Freq. Spacing
16384	2.1 s	2.92 Hz
8192	1.05 s	5.86 Hz
4096	520 ms	11.7 Hz
2048	260 ms	23.4 Hz
1024	135 ms	46.9 Hz
512	70 ms	93.7 Hz
256	40 ms	187.5 Hz

*Table 1. Generator record length versus attributes. Conditions are 48 kHz sample rate and use of **Freq Corrected**.*

Table 1 shows the minimum multitone signal duration as a function of generator record length in samples, assuming a 48 kHz sample rate and the use of **Freq Corrected**. Multiply the values shown by 0.5 for a 96 kHz sample rate, by 1.088 for a 44.1 kHz sample rate, and by 1.50 for a 32 kHz sample rate.

If a Trigger Delay is set, the amount of the delay must be added to the minimum multitone signal duration.

Invalid Multitone Readings

When data are not available for graphing or tabular display for the selected combination of Multitone Analyzer display mode and Sweep **Source** browser instrument, the reading will be invalid. The following chart lists the readings available for each combination:

Available Multitone Readings by Measurement and Sweep Type				
	Normal Sweep		Table Sweep	
	Amplitude	Phase	Amplitude	Phase
Spectrum	Peak-picked bin magnitudes	Nearest bin phase	Nearest bin magnitude	<i>Same as Normal Sweep</i>
Response	Interpolated rss magnitude	Interpolated phase	<i>Same as Normal Sweep</i>	<i>Same as Normal Sweep</i>
Distortion	rss from previous sweep freq	Invalid	<i>Same as Normal Sweep</i>	<i>Same as Normal Sweep</i>
Noise	rss from previous sweep freq	Invalid	<i>Same as Normal Sweep</i>	<i>Same as Normal Sweep</i>
Masking Curve	Interpolated masking curve	Invalid	<i>Same as Normal Sweep</i>	<i>Same as Normal Sweep</i>
Crosstalk	Interpolated rss magnitude	Invalid	Nearest rss magnitude	<i>Same as Normal Sweep</i>

Table 2. Available Multitone Readings by Measurement, Amplitude and Phase results, and by Normal Sweep or Table Sweep operation.


Acquired Waveform Files

As with other the 2700 series tests, you can save the setup and results of any Multitone Audio Analyzer tests as an .at27 test file. The acquired waveform in the Multitone acquisition buffer, however, is not saved as part of a test. If you want to keep the acquired data record for further analysis, you must save it as an .aam (acquisition, mono) or .aas (acquisition, stereo) acquired waveform file.

Single-channel “mono” waveforms saved at different times can later be individually loaded into the two channels of the Multitone acquisition buffer to become “stereo” acquisitions for comparison in the time or frequency domains.

Saving Acquired Waveforms

Figure 280. Multitone Audio Analyzer
Save Stereo Waveform dialog box.



To save an acquisition, select the **File > Save As** menu command, choosing either the **Stereo Waveforms** (.aas) or **Mono Waveforms** (.aam) as the file type.

A stereo acquisition waveform file consists of two waveforms joined together into a single file; a mono acquisition waveform file contains a single waveform. To simultaneously save the waveforms from both acquisition buffer channels 1 and 2, select the stereo choice. To save only one of the channels, select mono.

The left half of the dialog box defines what will be saved into the first section of a waveform file and the right half defines what will go into the second section of a stereo waveform. If the **File > Save As > Mono Waveform** option was selected, the right half of the dialog will be gray.

You can save the entire acquisition record or just the portion currently designated for transformation from either the channel 1 or channel 2 acquisition data. If the transform length is shorter than the acquisition record length, the waveform file will be correspondingly smaller.

Opening Acquired Waveforms

Figure 281. Multitone Audio Analyzer
Open Stereo Waveform dialog box.



To open an acquired waveform file, select the **File > Open** menu command, choosing either the **Stereo Waveforms** (.aas) or **Mono Waveforms** (.aam) as the file type.

You can load one waveform or simultaneously load both waveforms into memory from a stereo file, and you can choose to assign the waveform to either channel and to the acquisition or the transform buffers. A mono file only contains one waveform, but you have the same flexibility to load it into either channel or either buffer. When opening a mono waveform file, the right half of the dialog box will be gray.

NOTE: If acquisition in a file to be opened is greater than the length of the specified buffer, an error warning will be displayed and the file will not be opened. If the acquisition length in the file is shorter than the buffer size, erroneous analysis may result.

Combining Mono to Stereo

To compare two single-channel acquisitions made at different times or under different conditions, open the file containing the first acquisition data. Assign the waveform to channel 1 or 2 and load the data. Then open the second waveform file and do the same, this time loading the data into the opposite channel.

The resulting two-channel acquisition can be transformed, processed and viewed, and can be saved as a new stereo waveform file.

Compatibility of Acquired Waveform Files

The waveform files used by both the Spectrum Analyzer and the Multitone Audio Analyzer have the same format, and with certain restrictions on length, can be used by either Digital Analyzer tool.

The Spectrum Analyzer has a larger acquisition buffer, and can open waveform files up to 4M samples in length. Multitone is limited to opening files with acquisitions of 32k or fewer samples.

Also, although any multitone waveform can be analyzed by the Spectrum Analyzer, only properly-formatted waveform files are useful in Multitone. See Chapter 12 for more information about the Spectrum Analyzer.

Creating Multitone Waveform Files

Many multitone waveforms are available for download on the Audio Precision Web site at ap.com. You can also make your own custom multitone waveforms using the Audio Precision Multitone Creation utility. On the Main Menu, choose **Utilities > Multitone Creation**.

Multitone Creation Utility opening dialog box




Figure 282. Multitone Creation Utility opening dialog box.

Figure 282 shows the opening dialog box for the Multitone Creation Utility. The key options are:

- **Waveform Name**

This is the filename you choose for your multitone waveform and for all the associated files created by the utility. The filename extension(s) will be chosen according to the file options you choose in other dialogs.

- **Sample Rate**

Set the sample rate of your multitone waveform to any valid sample rate that is appropriate for your instrument and testing application. Multitone files for analog testing must not exceed the sample rate limitations for the DAC or ADC that may be used in conversions.

- **Margin Headroom**

Margin Headroom specifies in decibels the difference between the highest peak in the multitone waveform and digital full scale.

- **Multitone Waveform Length**

Choose from this list the length of one period of your multitone wave-

form. **8192** samples is a typical choice. The **Multitone Waveform Length** cannot be longer than the **Record Length**, below.

■ **Record Length**

Choose from this list the total file length (for one channel, if a stereo waveform) for your multitone. **8192** is a typical choice. The file may contain multiple periods of the multitone waveform.

On the left of the panel are four checkboxes:

■ **Create Sweep Table File**

This option generates a sweep table file, with entries corresponding to each of the tones in the multitone file.

■ **Create MS_RIFF (.wav) File**

In addition to any Audio Precision generator waveform files, this option generates a Microsoft .wav sound file containing the same multitone waveform as the .agm or .ags source file.

■ **Minimize Crest Factor**

A complex waveform such as a multitone can have a high crest factor, making a low rms level necessary to prevent overload. Changing phase relationships among the component tones can reduce the crest factor. The **Minimize Crest Factor** command enables an automatic feature which randomizes the phase relationships of the component tones repeatedly, then chooses the result with the lowest crest factor. In the small entry field to the right you can set the number of times to repeat the phase randomization before selection of the best candidate.

NOTE: Since the phases of the tones are randomly changed during this process, the resulting multitone waveform will provide meaningful results only in interchannel (Ch.2–Ch.1) phase measurements.

■ **Create Stereo Waveform**

By default, the Multitone Creation Utility generates a mono Audio Precision generator waveform file, with the filename extension .agm. If this box is checked, a stereo waveform file is generated, with the filename extension .ags. When **Create Stereo Waveform** is checked, two option buttons appear below the checkbox:

- **Stereo Waveform Amplitude: Make both equal**

Channels 1 and 2 of a waveform, unless identical, will have different crest factors. This choice optimizes the level of the channel with the higher peak amplitude at the selected **Headroom** setting, then modifies the amplitude of the other channel by the same factor.

- **Stereo Waveform Amplitude: Optimize individually for Headroom**

This choice optimizes the peak level of each channel individually with respect to the Headroom setting. Since the channels will likely have different crest factors, the level of the fundamental tones in the two channels will likely be different after optimization.

At the bottom of the panel, there are four buttons:

- **Use existing file data**

This command begins the file creation process, using the data from a test or data file for tone frequency, level and phase settings. See **Use existing file data**, below.

- **OK**

Like **Use existing file data**, this command begins the file creation process, but uses the settings you make on the Frequencies Menu for tone frequency, level and phase settings. See **Frequencies Menu**, below.

- **Cancel**

This command exits the Multitone Creation Utility, making no changes in your current test or files on disk.

- **File options**

This command opens the Supporting File Creation Options dialog box. See below.

When you have made the settings you want from this panel, click **OK** to create a waveform from the Frequencies Panel, or **Use existing file data** to create a waveform from existing data.


As you initiate the file creation process (by clicking **OK** or **Use existing file data**), the Multitone Creation Utility will save your current 2700 series test as a temporary file named “Makewave.tmp”. This frees up the workspace and memory buffers for file creation tasks.

When the Multitone Creation Utility is finished, the file Makewave.tmp is reloaded into the control software. If you want to do further work with this test, you should save it under its original filename or under a new filename of your choice.

Using Existing File Data


This command begins the file creation process by using the data in memory or in a data file for tone frequency, level and phase settings. To create a new list of frequencies in Multitone Creation Utility, click **OK** instead.

First the current test is saved as “Makewave.tmp”. Then you are presented with the following dialog box:

Figure 283. Multitone Open File dialog box.

Choose **File > Open** from the Main menu and select the test or data file which has the information you want in it, and then click **Continue Macro**. Go to **Editing the Frequency list**, below.

File Options

Figure 284. Multitone Creation Utility Supporting File Creation Options dialog box.

The File Options button opens the Supporting File Creation Options dialog box, which offers the following options:

- **Data File(s), containing Frequency, Amplitude and Phase Information (.ada)**

In addition to the .agm or .ags generator files and sweep table files, this option specifies the creation of an Audio Precision data file.

- **ASCII Data file(s) containing Frequency, Amplitude and Phase Information (.adx)**

This is an ASCII text file containing the same information as the data file in a text table.

- **ASCII Waveform statistics file(s) (.wfs)**

This is a text listing of statistics concerning the waveform files created.

- **ASCII Sweep Table statistics file(s) (.sts)**


This is a text listing of statistics concerning the sweep table file created.

- **Retain (.agm) files when making Stereo files**

When making a stereo generator waveform file, this option enables you to also generate two mono files, each containing the waveform information for one channel.

Frequencies Menu

Figure 285. Multitone Creation Utility Frequencies Menu dialog box.



First, define the range of your multitone signal. Enter the lowest frequency in the **Start Frequency** field, and the highest in the **Stop Frequency** field. Select **Log** or **Linear Frequency Spacing**, and set the **Number of Frequencies** by entering a positive integer in the field.

Editing the Frequency List

Click **OK** when you have made your settings. The Multitone Creation Utility will open the Data Editor, displaying the frequencies you have defined, and also the Edit Waveform Definition Menu, as shown in Figure 286.

The first three buttons on the Edit Definition Menu affect all the frequency selections in the Data Editor.




Figure 286. Multitone Creation Utility Edit Waveform Definition Menu dialog box.

■ Randomize Phase values

To help minimize the waveform crest factor, this command randomizes phase values. This is the same as one iteration of the **Minimize Crest Factor** function.

■ Set Phase values to 0.0 deg

This sets all phase values to 0.0 degrees.

■ Set all Magnitude values to 0.0 dBV

This sets all tone amplitudes to 0.0 dBV.

■ Edit Data Values

This command gives you access to the Data Editor, where you can edit the waveform data, adding or deleting rows, and changing frequencies, amplitudes and phase values.

NOTE: If you add new frequencies using Edit Data Values, be sure that the frequencies you choose are synchronous. See Appendix C for a discussion of synchronous FFTs.

When you are done editing the data, click **OK**.

Sweep Table Definition

If you have requested a sweep table, a dialog box will open to enable you to define the frequencies listed in the sweep table. Your options are as follows:

■ Fundamental Frequencies

This will list all of the fundamental frequencies in your waveform in the sweep table.

■ Harmonics

If you select **Harmonics**, the Multitone Creation Utility will calculate the harmonics you specify for each of the fundamental tones, and will list these frequencies in the sweep table. You can specify the range of harmonics you desire and the utility will generate them up to the limit of $F_s/2$. You can optionally select to list only the odd harmonics.

■ IM Products


If you select **IM Products**, the Multitone Creation Utility will calculate the intermodulation sum and difference products to the order you specify for each combination of fundamental tones, and will list these frequencies in the sweep table. You can specify a listing of **IM Products** up to the order you desire, and the utility will generate them up to $F_s/2$.

You must choose at least one of these selections for a valid sweep table definition. If you want only a subset of these frequencies, you can delete rows from the sweep table using the Data Editor or the Attached File Editor.

Creating an MS RIFF (.wav) File

If you have requested a .wav file, the following dialog box will open:




Figure 287. Multitone Creation Utility MS RIFF Creation dialog box.



You can specify the length of the file, the resolution in bits, and the type of dither to be used. See page 120 for more information about dither.

Final Options

A final series of dialog boxes will open, with some examples shown here.



You may reply **Yes** or **No** to any of these boxes. At this point in the process, all the files you have requested have been created and saved, so replying **No** will not change or abort multitone creation. The **Yes** options enable you to continue directly with your testing or to immediately view the statistics files.

Chapter 15

The MLS Analyzer

The Quasi-Anechoic Acoustical Tester (also called the MLS Analyzer) is a DSP analysis tool selection on the Digital Analyzer panel that can be used with either analog or digital inputs to test audio devices, loudspeakers and acoustical spaces. It is named “**MLS**” on instrument browser lists and in OLE references. This chapter examines the **MLS Analyzer** in detail.




Figure 288. Loudspeaker testing with the 2700 series MLS Analyzer.

MLS Overview

MLS is an acronym for *maximum length sequence*, the name for a set of noise-like but deterministic audio testing waveforms. MLS signals, properly processed and analyzed, are useful for measurement of any linear system but are most widely used for loudspeaker and acoustic space analysis. An MLS signal passed through a system can be cross-correlated with the stimulus signal in


an MLS analyzer, producing the impulse response of the system. A system's impulse response can be displayed as a waveform in the time domain, or as amplitude and phase plots in the frequency domain. See **Impulse Response** on page 374.

Unlike random noise signals and some impulse sources, MLS signals have flat frequency content with equal energy across the spectrum. The noise-like MLS signal delivers more energy to the system than an impulse signal, providing superior signal-to-noise performance compared to impulse sources. When combined with time delay information, MLS measurements can be processed to display the loudspeaker response only (no reflections) or the response only of the reflections (no loudspeaker); for this reason MLS analysis is termed “quasi-anechoic.”

MLS analysis is generally not useful for measurements of non-linear systems.

Generating an MLS signal

Figure 289. Generating an MLS signal in the Analog Generator.



The MLS Analyzer requires a compatible, synchronous MLS stimulus signal for operation. This signal can be produced by either the Analog Generator by selecting **Wfm: MLS (D/A)** or the Digital Generator by selecting **Wfm: MLS**. For more information, see Chapter 6 for the Analog Generator and Chapter 7 for the Digital Generator.

Pink and White MLS Sequences

MLS waveforms can be generated with either a white or pink spectral balance. See the sidebar on white and pink noise on page 87.

Sequence Variations: 1, 2, 3 or 4?

Four different maximum length sequences can be generated for both white and pink spectral balance MLS signals. Each of the signals will produce the same test results; four are provided to allow the MLS Analyzer to discriminate between interfering test signals when more than one MLS test is in progress in the same acoustic space, as on some production lines. Each sequence type provides about 45 dB of isolation from any of the other three sequences. The MLS Analyzer automatically cross-correlates to the sequence selected on the generator that is set as the **Trigger Source** on the MLS Analyzer panel.


Sequence Lengths

The two generator sequence lengths (**32k** or **128k**) enable you to set a shorter sequence for faster operation or a longer sequence as may be necessary in spaces with longer reverberation times, or in tests at higher sample rates.

Sample Rate	MLS Sequence Duration	
	32k	128k
44.1 kHz	0.73 s	2.94 s
48 kHz	0.68 s	2.7 s
96 kHz	0.34 s	1.35 s
192 kHz	0.17 s	0.68 s

Loading the MLS Analyzer

Figure 290. Loading the MLS Analyzer






To use the MLS Analyzer, first open the Digital Analyzer panel. The Digital Analyzer panel is a command selection on the Panels menu, and is also available by the keyboard shortcut **Ctrl+Y**, or by clicking the **Digital Analyzer** button on the Toolbar.

Now select Quasi-anechoic acoustical tester (mls) from the list on the Digital Analyzer panel. This loads the MLS Analyzer program into DSP.


The MLS Analyzer panel

Figure 291. The MLS Analyzer panel



Signal Inputs

Figure 292. MLS Analyzer signal input selections.



The Input field enables you to choose the digital input or the analog inputs (converted to digital) as the signal applied to the MLS Analyzer. The selections are:

- **Digital @ISR**
- **HiRes A/D @65536**
- **HiBW A/D @131072**
- **HiBW A/D @262144**
- **HiRes A/D @SSR**
- **HiBW A/D @2xSSR**

The digital input and converter choices are the same for all five of the DSP audio analysis tools (DSP Audio Analyzer, Spectrum Analyzer, Multitone Analyzer, MLS Analyzer and Harmonic Distortion Analyzer). Go to **Signal Inputs** on page 228 in the **DSP Audio Analyzer** chapter for detailed information about the Digital Analyzer Inputs.

The distortion performance of either the high resolution or the high bandwidth converter is more than sufficient for MLS analysis.

Match the Sample Rates!

You can mix domains for MLS, but the SR or converter sample rate for the generator must match the ISR or converter sample rate for the Analyzer.

Source Selection

The Source selection choices depend on the Input selected; the lists are different for the **Digital @ISR** input and for the analog (**A/D**) inputs.

Digital @ISR Sources




Figure 293. MLS Analyzer digital sources.

When **Digital @ISR** is the analyzer input, the source selections for each analyzer channel are:

- **A**
The embedded channel A audio is routed to the analyzer channel.
- **B**
The embedded channel B audio is routed to the analyzer channel.
- **None**
Acquisition is disabled for the analyzer channel, preserving any signal previously in the acquisition buffer. This permits acquisition of signals into the Ch 1 and Ch 2 buffers at two different times for comparison of different devices or of the same device under different conditions.

Analog (A/D) Sources




Figure 294. MLS Analyzer analog sources.

When one of the analog-to-digital converters is selected as Input, the Source choices list the same set of analyzer analog source options available for the Spectrum Analyzer, which are each discussed beginning on page 264. How-

ever, only the **Anlr A**, **Anlr B** and **None** sources are likely to be used with the MLS Analyzer.

The **Anlr A** and **Anlr B** sources are routed from the Analog Analyzer at circuit points following all input ranging and balanced-to-unbalanced conversion, but prior to any filtering. These are essentially the same points as appear at the Channel A and B Analyzer SIGNAL MONITOR front panel BNCs. When one of the ADCs is the analyzer input, the source selections for each analyzer channel are:

- **Anlr-A**

The Channel A analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL A output, which appears on the front panel on a BNC connector.

- **Anlr-B**

The Channel B analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL B output, which appears on the front panel on a BNC connector.

- **None**

Acquisition is disabled for the analyzer channel, preserving any signal previously in the acquisition buffer. This permits acquisition of signals into the Ch 1 and Ch 2 buffers at two different times for comparison of different devices or of the same device under different conditions.

Peak Level Monitors

Figure 295. MLS Analyzer Peak level monitors.




The two **Peak Mon** meters on the MLS panel continuously display the peak amplitude of the digital signal as it is presented to the MLS Analyzer. Only digital domain units (**FFS**, **dBFS**, **%FS**, or **bits**) are available for these meters.

The primary purpose of the peak monitors is to avoid overload of the input analog-to-digital converters (ADCs). When signal is being acquired from the analog source and **Auto Range** is in use on the Analog Analyzer panel, ADC

over-range should never be a problem. If any of the Analog Analyzer range controls is fixed, you must verify that the maximum signal amplitude never exceeds digital full scale.

Time Delay

Figure 296. MLS Analyzer Time Delay.



MLS analysis is generally used for loudspeaker or acoustic space measurements, and in these cases there will be a propagation delay in the received signal. Normally, this delay represents the time required for the sound wave generated by the loudspeaker to be carried through the air to the microphone.


The value entered in the Time Delay field enables the DSP to subtract the propagation time from the phase readings.

You can enter time delay in units of seconds, or you can enter the measured or estimated distance between the transducers in either English or metric units. These units are computed using the constant 1290 feet per second (or 344 meters per second), the nominal speed of sound at sea level.

You can also determine the time delay experimentally using the MLS Analyzer. On an impulse response plot, the x-value of the early high peak is usually the propagation delay. On a phase spectrum graph, the y-value of the phase trace will be constant (a slope of 0) when the time delay value is correctly entered.

Time Domain Display

Figure 297. MLS Analyzer Time Domain Display.



The default Time Domain Display choice for the MLS Analyzer is **Impulse Response**. As an alternative, you can choose the **Energy Time** display.

Energy-Time Curve

When **Energy-Time** is selected as a Time Domain Display, the MLS Analyzer processes the measurement result somewhat differently before display. The impulse response is transformed into the frequency domain where further processing is performed (including the application of a window, if selected,

and a Hilbert Transform). This result is then inverse transformed back to the time domain for display. This result is commonly called the *energy-time curve*, or ETC.


The energy-time curve is useful for determining arrival times and relative energy distribution in time. It may be considered as similar to the envelope of the impulse response, tracing along the top of the impulse response curve but not showing any of the negative excursions.

However, the ETC is only an approximation of the actual energy arriving at the microphone, since this energy can never be known without the simultaneous measurement of both the velocity and the pressure of the sound; the term *energy-time response* is actually a misnomer. A more accurate term sometimes found in technical papers is the *analytic signal magnitude*, but as *energy-time* has become common usage that term is used here.

ETC measurements (especially with the use of the Hann window; see below) can be misleading. The **Energy-Time** choice is included as an MLS Analyzer selection to accommodate comparison of current tests to legacy techniques.

Energy-Time Window

Figure 298. MLS Analyzer
Energy-Time Window.



When **Energy-Time** is selected as the time domain display, a frequency window can be selected in the Energy-Time Window field to reduce aliasing behavior in the transformations applied.

The choices are:

- **No Window**

The **No Window** selection causes the **Energy-Time** function to perform the required transformations with all frequencies of the signal included in the computations. For signals with deviations from a flat response, aliasing behavior will create ripples in the time domain energy response.

- **Half Hann**

The **Half Hann** window reduces the high-frequency energy in the signal but leaves the low-frequency contributions unchanged. Suggested by Lipshitz and Vanderkooy, this window provides more accurate measurements of typical audio signals than the **Hann** window does.

■ Hann

The **Hann** window reduces both high- and low-frequency energy, focusing analysis on signals around one-quarter of the sample rate. This window creates misleading response curves and is not useful for most applications. However, it is commonly the only window provided on many instruments, and is included here for correlation to measurements made on other equipment.

■ <240 Hz >8 kHz


Audio Precision has developed this and the following window for more accurate measurements of typical audio signals. The **<240 Hz >8 kHz** window filters energy below 240 Hz and above 8 kHz, producing equal sensitivity to signals across a 5 octave range.

■ <120 Hz >16 kHz

The **<120 Hz >16 kHz** window filters energy below 120 Hz and above 16 kHz, producing equal sensitivity to signals across a 7 octave range.

Time Window

Figure 299. MLS Analyzer Time Window.



NOTE: The Energy-Time Window discussed in the previous section is a frequency window for use with the Energy-Time function of the MLS Analyzer. It is not to be confused with the Time Window discussed in this section.

The Time Window is an amplitude window function superimposed on the signal (or the section of the signal isolated for analysis) in the time domain (impulse response) view. This window attenuates the amplitude of both the beginning and the end of the impulse response section, smoothly tapering the amplitude at each end to zero.

The Time Window selections eliminate the discontinuity or jump at the splice point that occurs where the impulse response is looped in the transformation when processing for a frequency domain (spectrum) view. Such discontinuities produce ripples in the frequency response plot, and the Time Window choices reduce these ripples in varying degree.

The Time Window is made up of two half-windows. The first half is selected in the Start field, and is used to process the first portion of data beginning at the **Source 1** Start time on the Sweep panel. The second half is selected


in the Stop field, and is used to process the second portion of data ending at the **Source 1** Stop time on the Sweep panel.

Since an impulse response curve often has an asymmetrical shape, independent selection of the time window curve for the beginning and the end of the data enables you to create an asymmetric window to match the shape of the impulse response.

Both the Start and Stop half-windows multiply the impulse response amplitude by a factor of 0 tapering to a factor of 1 (for Start; 1 tapering to 0 for Stop). The choices for each half-window enable you to select the rate of amplitude tapering. The 5% choice, for example, tapers very quickly, and will adjust the amplitude factor from 0 to 1 (or 1 to 0) in 5% of the total time between Sweep Start and Sweep Stop. The 30% choice is more gradual, tapering across 30% of the selected impulse response duration. The windows with a steeper transition will alter the data less but will reduce the frequency response ripples to a lesser degree. The more gradual transitions provide greater ripple reduction but alter the data more.

Trigger Source

Figure 300. MLS Analyzer Trigger Source.



On the MLS Analyzer panel, choose the appropriate generator as the MLS Trigger Source. This not only synchronizes the MLS Analyzer with the Generator but also informs the DSP of your generator choices for sequence length, spectral balance and the particular sequence (**1**, **2**, **3** or **4**) you have selected.

As mentioned previously, the MLS Analyzer must cross-correlate the received MLS signal from the DUT output with the generator signal. Selecting **Analog** or **Digital** for the Trigger Source directs the MLS Analyzer to the generator you have chosen for your measurements.

Frequency Domain Display





Figure 301. A typical MLS Analyzer frequency domain (spectrum) display.

As mentioned, you must initially process the raw MLS acquisition in the time domain (waveform view) to produce an impulse response. Once this is done, toggle the Spectrum/Waveform button to transform the impulse response into the frequency domain (spectrum view).

Several fields on the MLS Analyzer panel affect frequency domain views, including Time Delay, Time Window, Averages and Display Method.

Averages


Figure 302. MLS Analyzer Averages.



When measuring a coherent signal in the presence of uncorrelated noise, synchronous averaging of many measurements will reduce the noise reading and allow the coherent signal to be recovered more effectively. Averaging for the MLS Analyzer is done synchronously in the time domain. To enable averaging, click the arrow by the **Averages** field and select from the list the number of readings to be averaged.

Display processing Methods

Figure 303. MLS Analyzer Display Method selections.



Four display processing methods are available in the MLS Analyzer for all graphing of results in time or frequency domain.

The four selections available in the Method field are:

- **Interpolate**
- **Display Samples**
- **Peak Values**, and
- **Smooth**.

Interpolate

If **Interpolate** is selected the DSP will compute the displayed data value, interpolated from the nearby measured values. This evens out the “stair-step” appearance of frequency response curves at low frequencies with a Log horizontal axis, where the bin width (2.93 Hz at the 48 kHz sample rate) occupies a significant portion of the screen.

Display Samples

If **Display Samples** is selected the DSP will return the closest actual measured value without altering the data. **Display Samples** is the recommended display method for frequency response data with a Linear horizontal axis or with a Log axis above 100 Hz to 300 Hz. In these cases, the jagged lines caused by the FFT bin width are not usually noticeable.

Peak Values


The **Peak Values** method will return the largest value between the last requested sweep point and the current one. **Peak Values** is recommended for the time domain MLS displays, **Impulse Response** and **Energy-Time**. The **Peak Values** method would not normally be used for frequency response displays with MLS, since high values are of no more interest than low values when plotting frequency response.

When **Peak Values** is selected, the DSP searches all sample amplitudes in the acquisition buffer between each pair of X-axis time values plotted, and

sends to the computer for plotting the largest positive or negative value in that span, preserving the sign. Since all sample values are examined, no signal peaks can be missed.

Smooth

Figure 304. MLS Analyzer
Smooth Display Method.



MLS octave smoothing is a Display Method that shows MLS frequency domain results as modified by a smoothing algorithm. Smoothing only operates on frequency-domain displays.

When **Smooth** is chosen as the Display Method, the Smoothing setting field becomes available. In this field you can specify the degree of smoothing by entering values from **0** to **2.64** octaves.




Figure 305. A typical MLS Analyzer spectrum display, smoothed.

Octave smoothing is a common technique in loudspeaker response measurement, useful in revealing trends by smoothing out anomalies in the response curve. The 2700 series implementation uses a hybrid FFT bin averaging and interpolation technique to achieve smooth results even at very low bin densities. Smoothing, which only affects frequency-domain displays, effectively passes the raw response data through multiple constant-Q bandpass filters, one filter centered on each frequency requested from the Sweep panel. The bandwidth of these filters, in octaves, is specified in the Smoothing field.

Using MLS for Loudspeaker Testing

This section will walk you through a typical MLS loudspeaker measurement, with tips for easy operation. For the purposes of this explanation, we will assume analog MLS generation and acquisition through the analog inputs.

Setting up the Equipment

First, connect the 2700 series analog output to a power amplifier, and connect the output of the amplifier to the loudspeaker under test. Place a measurement microphone at a reasonable distance from the loudspeaker, and connect the microphone to a 2700 series analog input via a suitable microphone preamplifier. See Figure 288 for a simplified diagram of this setup.

Calibration

Many acoustic measurements require careful consideration of transducer separation, the proximity of reflective surfaces, component specifications, and calibration of electrical and acoustical levels for desired results. Standards vary, but the following represent typical requirements for loudspeaker testing:

- *The microphone shall be a measurement microphone, having a documented flat response, low self-noise and low distortion.*
- *The electrical amplitude in the analyzer for the nominal testing level shall be calibrated using a certified acoustic microphone calibration source.*
- *The distance from the loudspeaker to the measurement microphone shall be 1 meter (3.28 feet).*
- *The generator output level and power amplifier levels shall be set so that 1 watt is dissipated in the loudspeaker for a 1 kHz sine wave signal at the nominal testing amplitude.*

Our example does not require calibration, so microphone type, levels and transducer separation are not critical.

Generator settings

On the Analog Generator, select **Wfm: MLS (D/A)**. The default waveform will be **Pink #1** with a **Sequence Length** of **32k** and a **D/A Sample Rate** of **65536**. These will be fine for our example.

Set the output Configuration to select the Analog Output you have connected to the power amplifier.

Set the generator **Amplitude** low enough that it will not overpower your amplifier (or your ears). **50 mV rms** is a prudent starting amplitude. Click **ON**,

and you should hear the MLS signal (which sounds like a pulsating noise signal) in the loudspeaker. Now reset the **Amplitude** to the level you want for your test. This should be moderately loud (perhaps 85 dB spl or more) for an acceptable signal-to-noise ratio in the analyzed signal. Now click **OFF**.

That completes your generator setup. Click **Auto On** so that the generator output will be switched by Sweep **Start** and **Stop** commands as you make your measurements.

Analog Analyzer settings

Since the 2700 series Analog Inputs are configured on the Analog Analyzer panel, we must first go to that panel to be sure the correct inputs have been selected.

On the Analog Analyzer panel, select the Channel A **Source** to match the input you have connected to the microphone preamplifier output.

MLS Analyzer settings

Load the MLS Analyzer into the Digital Analyzer. The default **Input** will be **HiRes A/D @65536** and **Trigger Source** will be set to **Analog Gen**, both of which are correct for our setup.

Using the Spectrum/Waveform Button



If you have used the **Spectrum/Waveform Button** in other FFT-based 2700 series analysis tools, you will have realized that it provides an easy shortcut in loading the basic parameters into the Sweep panel. This is true with the MLS Analyzer as well. Once the inputs and outputs are configured, the easiest way to set up an MLS sweep is to click the **Spectrum/Waveform** button.

The first time you click the **Spectrum/Waveform** button with the MLS Analyzer loaded, the Sweep panel will be set up for a time domain MLS sweep. Click it again and the Sweep panel will be set for a frequency domain MLS sweep. Another click, and you're back to time domain.

Measuring the Impulse Response

Click the **Spectrum/Waveform** button as described above so that the Sweep panel is configured for a time-domain sweep. If you have lost track of the “toggle state” of the button, look in the Sweep panel **Source 1** instrument field. If it reads **Mls.MLS Time**, you are ready for a time domain sweep. If it reads **Mls.MLS Freq**, you are configured for a frequency-domain sweep and need to toggle back to time domain.




Figure 306. A typical MLS Analyzer Impulse Response graph.

When you are set for a time-domain sweep, click **GO (F9)**. The generator will be switched **ON** and **OFF**, the analysis will be made and the impulse response of the loudspeaker (and reflections from the acoustical space) will be plotted and displayed. With the default Sweep Start and Stop settings, the impulse response will show the initial room ambient noise, followed by the response of the loudspeaker and then the room reflections, out to about 50 ms. It should look something like the graph in Figure 306.

NOTE: When using the MLS Analyzer, you must always begin with a time-domain sweep. The resultant impulse response data is stored in memory for further analysis. If you attempt a frequency-domain sweep with no impulse response in memory, an error message will appear.

Impulse responses typically show a pattern of nodes at regular time intervals. These patterns indicate the interference of multiple delay paths caused by the reflections from various surfaces in the acoustic environment. The separation of the nodes in the patterns is related to the differences in length (and therefore propagation time) of the different paths. Measure the distances between the major nodes and look around the room you are measuring; you will recognize the reflecting surfaces that correspond to the delay times you are measuring. For an experiment, move the microphone closer or farther from a reflecting surface, make the measurement again and compare your results.

Plotting the Frequency and Phase Spectrum

Now that you have made an initial impulse response measurement, you can cause the data be transformed for viewing in the frequency domain. Remember, as mentioned in the note just above, you must always make an impulse re-

sponse (time domain) measurement before you attempt to make a frequency-domain sweep.

Impulse Response

When a linear system is excited with a narrow pulse, the resultant response is called the impulse response. Impulse method measurements can be performed on any linear system, but are particularly suited to measurements of transducers (such as microphones or loudspeakers) in acoustic spaces.

For loudspeaker testing, of course, the impulse must be generated electronically to move the loudspeaker; but for microphone or acoustic space measurements, other impulse sources (such as gunshots or popping balloons) have been used.

Because the very short duration of an impulse puts little energy into the system, impulse response measurements in noisy systems suffer from poor signal-to-noise ratios. Gunshots push the upper edge of practical impulse magnitude; loudspeakers, unfortunately, are limited by their maximum linear output level.

One answer to the signal-to-noise problem is to repeat the impulse continuously at some minimum interval. When a synchronized analyzer averages a series of these repeated pulses, the signal-to-noise ratio is improved; this improvement is limited, though, because the high peaks of the impulses must be maintained at a low enough level to keep the loudspeaker within its linear range.

An MLS signal, on the other hand, has a much lower crest factor than an impulse. This makes it possible to deliver a much higher average energy to the system, which translates to a superior signal-to-noise ratio. The raw MLS acquisition is cross-correlated with the original generator signal to produce the impulse response of the system. This result is mathematically identical to the response of a pulsed system, but with much lower noise.

When plotted as amplitude versus time, an impulse response shows the initial delay before reception, followed by the high peak of the impulse, and then the decaying reflections and reverberation from the environment, as shown in Figure 306. The frequency and phase colorations caused by the loudspeaker response and the reflective surfaces are all embodied in this waveform, and a Fourier transform of an impulse waveform produces the familiar spectrum views: amplitude vs. frequency and phase vs. frequency.

The impulse response is the basic record in an MLS Analyzer measurement. Although the data in the impulse response can be truncated or transformed for other views, the acquisition of the raw MLS data and the cross-correlation to produce the impulse response must be performed first for any MLS test.




Figure 307. A typical MLS Analyzer spectrum display before Time Delay correction. Notice the steep slope of the phase graph.

Click the **Spectrum/Waveform Button** to reconfigure the Sweep panel for a frequency-domain sweep. You should see **MLS.MLS Freq** in the Sweep panel **Source 1** instrument field. When the sweep is run you will see a graph with two traces: **Data 1** is the frequency response, and **Data 2** is the phase response. Notice that the phase response runs off the graph at a steep angle as shown in Figure 307. This correctly represents the phase response of the system with the propagation delay, the time delay between the stimulus signal and the analyzed signal due to the distance between the loudspeaker and the microphone.



Removing the Propagation Delay

To remove the effects of the propagation delay from the results, enter the value of the delay in the **Time Delay** field. This value is used during the analysis calculations, providing a useful interpretation of the phase spectrum.

To determine the correct value to enter in the **Time Delay** field, you can either measure the distance between the transducers, or measure the difference between zero time and the impulse arrival time on the impulse response graph. The delay value can be entered in the **Time Delay** field in units of time (seconds) or distance (feet or meters).




Figure 308. Cursor marking the propagation delay shown in an MLS Analyzer impulse response graph.

Use the graph cursors to measure the propagation delay on the impulse response display (as shown in Figure 308). Move the cursor back and forth to find the peak of the impulse, then read the time delay from the X-value display box at the bottom of the graph (in Figure 308, 6.849 ms).

When the correct value is entered in the **Time Delay** field, the phase response trace will approach a slope of zero, as shown in Figure 309.




Figure 309. MLS Analyzer spectrum display after Time Delay correction. Notice that the phase plot has been corrected to a zero slope.

Viewing Only the Loudspeaker Response




Figure 310. MLS Analyzer Impulse Response graph, with marquee surrounding loudspeaker portion of response.

The portion of the impulse response record between the beginning of the impulse and the first reflection represents the loudspeaker response. This is the anechoic response of the loudspeaker, since no echoes have yet arrived. This truncated response can be transformed for viewing in the frequency domain, showing the anechoic frequency spectrum and phase spectrum of the loudspeaker.

The time from the beginning of the first impulse to the first significant node is usually the response of the loudspeaker alone, before the interference of the first reflection. If you truncate the impulse response to only this area and then transform the result, the frequency and phase spectra will be that of the loudspeaker alone, as if it were measured in an anechoic room.

Follow these steps:

- Obtain the basic impulse response of the system.
- Enter the correct value for propagation time in the **Time Delay** field.
- Zoom in on the anechoic loudspeaker response area of the impulse response, as shown in Figure 310.

This zooming will produce a low-resolution display of the anechoic loudspeaker impulse response, as shown in Figure 311.




Figure 311. MLS Analyzer Impulse Response graph, zoomed to loudspeaker portion of response.

Transfer the new graph coordinates produced by zooming to the Sweep panel, using the right mouse button command **Copy to Sweep Panel**. This will cause only the truncated area to be displayed and transformed when you next push **F6** or click the **Spectrum/Waveform** toggle button.

Click **F6** or the **Spectrum/Waveform** toggle button. This will produce a display similar to Figure 312.




Figure 312. Loudspeaker portion of impulse response, re-graphed by **F6** key.

The default **Display Method** for the MLS Analyzer is **Interpolate**. If you have zoomed in to a small region of the graph, you may find that **Display Sam-**

ples will make selecting nodes and the impulse peak easier, as shown in Figure 313.




Figure 313. This is the trace from Figure 312, with Display Samples set as the **Display Method**.

You may find it useful to apply **Time Windows** to the truncated impulse response to reduce rippling in the frequency domains views.

Measuring Delay through an Electronic Device

As mentioned before, MLS is a useful analysis tool for any linear system. One valuable application is the measurement of delay through an electronic device.

Converters, including ADCs, DACs and sample-rate converters (SRC), are electronic devices with significant time delay. As an example of a delay test, we will measure the passage of an MLS signal through an ADC using the following steps:

- Set the Analog Generator to the appropriate output configuration and output amplitude for the inputs of the ADC under test. Then, on the DIO panel, set **Input: Format** to the appropriate configuration for the output of the ADC. Connect your 2700 series instrument to your ADC.
- To be sure your levels are set correctly, set the Analog Generator to output a sine wave at a nominal level (the default of 1.000 V is probably fine) and turn it **ON**. Open the DSP Audio Analyzer, set its **Input** to **Digital@ISR** and monitor the Level meter. Adjust the ADC input level control for a reasonable digital output level, perhaps -5 dB FS or so.

- Go back to the Analog Generator panel. Choose **MLS (D/A)** as the waveform. Set the **D/A Sample Rate** to **ISR**.
- Connect the 2700 series instrument to your ADC.
- On the MLS Analyzer, set **Input** to **Digital@ISR** and be sure **Trigger Source** is set to **Analog Gen**.
- Now click the Spectrum/Waveform button, and then click **GO**. You should get a graph similar to the one shown in Figure 314.




Figure 314. MLS impulse response test of time delay through an ADC, showing an impulse arrival at 1.214 ms.

MLS Acquisition Files

The MLS Analyzer makes a waveform acquisition before analysis, as the Spectrum Analyzer and the Multitone Analyzer do. Like the acquisitions for these analyzers, the MLS acquisition record can also be saved as a mono or stereo acquisition file (.aam or .aas filename extension) and can be combined and otherwise configured and manipulated in the same way as an FFT acquisition record.

Two differences set the MLS acquisition file operation apart:

- In the case of ordinary FFT and multitone acquisitions, sampled data representing the actual acquired waveform is the data saved or retrieved in an acquisition file; for MLS, this “raw” waveform data is first cross-correlated with the MLS generator signal, and the result of those calculations, the impulse response, becomes the acquisition record.
- For FFT and multitone, truncated versions of the acquisitions can be stored in DSP and saved in acquisition files. For MLS, the acquisition record is always the entire impulse response, and only the entire impulse


response can be saved or retrieved. Truncated versions for anechoic frequency-domain analysis, for example, are processed for display but do not replace the full impulse response waveform in DSP.

For detailed information on saving, opening and manipulating acquisition files, see the topics beginning on page 291 in the Spectrum Analyzer chapter.

Chapter 16

The Digital Data Analyzer

Figure 315. The Digital Data Analyzer (Bittest) panel.



Introduction

The Digital Data Analyzer (Bittest) is a DSP analysis tool selection on the Digital Analyzer panel. The Digital Data Analyzer enables a bit-by-bit analysis of the data in the digital interface signal received from a DUT. To accomplish this, specific test waveforms with known bit patterns must be embedded in the digital stimulus signal that is applied to the DUT. The Digital Data Analyzer is set to match the stimulus data pattern, and any bit errors detected on reception are noted.

The Digital Data Analyzer is useful for investigating the integrity of digital audio data links and recording systems, and is invaluable for design test of digital interfaces where “stuck bits” or improper switch settings can be problematic.

The Digital Data Analyzer is a real-time (as opposed to batch-mode) analysis tool, displaying both received data values and errors counts as they are measured.

Data values and error counts can be graphed against time in chart recorder fashion, or, for the **Constant** waveform, against Digital Generator amplitude.

Stimulus Waveform Requirements

See Chapter 7 for detailed descriptions and illustrations of the **Special** waveforms (**Bittest Random**, **Walking Ones**, **Walking Zeros** and **Constant Value**) generated in a 2700 series instrument for use with the Digital Data Analyzer.

Stimulus Resolution

There are restrictions on the relationship of the digital resolution of the stimulus signal to the resolution of the analyzer input (DIO) for some of the Digital Data Analyzer measurements, as shown in the following table.

Digital Data Analyzer Measurement	Digital Resolution Restriction
Sine	none
Random	stimulus resolution $\geq$ input resolution
Walking-1	stimulus resolution = input resolution
Walking-0	stimulus resolution = input resolution
Constant	none

Bittest Random, Walking Ones and Walking Zeros

The stimulus waveforms for Random, Walking-1 and Walking-0 must each be generated in accordance with the algorithm used to analyze that waveform in the Digital Data Analyzer. The waveforms must have no dither added.

The **Special: Bittest Random**, **Special: Walking Ones** and **Special: Walking Zeros** waveforms generated by any Audio Precision instrument (including System One, System Two, Cascade and Cascade Plus, Portable One, ATS-1 and ATS-2) are compatible with these analyses.

Constant

The stimulus waveform for Constant is a continuous stream of data samples at the same fixed value (digital dc). The waveform must have no dither added.

The Constant waveform generated by any Audio Precision instrument (including System One, System Two, Cascade and Cascade Plus, Portable One, ATS-1 and ATS-2) is compatible with this analysis.

Sine

The sine stimulus is unique for the Digital Data Analyzer, in that any low-distortion sine wave, dithered or undithered, can be used as a stimulus signal.

Good quality digital domain sine waves from a wide variety of sources are compatible with **Digital Data Analyzer** analysis—waveforms from System Two, System One, Portable One Dual Domain, ATS-2 and even sine waves recorded on test CDs. The sine wave analysis technique used by the **Digital Data Analyzer** will automatically adapt to normal dither levels, so dither may be turned **ON** or **OFF** as necessary.


Recorded or Remote Stimulus

For the Random, Walking-1, Walking-0 and Sine waveforms, no special considerations must be made for pre-recorded or remote stimulus sources.

For the Constant waveform, the local Digital Generator must be set to generate a Constant waveform at precisely the same digital level as the pre-recorded or remote stimulus source, even though the output of the local generator is not used. The Digital Data Analyzer looks to the Digital Generator for the Constant digital level information.

Loading the Digital Data Analyzer

Figure 316. Loading the Digital Data Analyzer.



To use the Digital Data Analyzer, first open the Digital Analyzer panel by choosing **Panels > Digital Analyzer** or by the keyboard shortcut **Ctrl+Y**, or by clicking the **Digital Analyzer** button on the Toolbar.



Now select **Digital data analyzer (bittest)** from the list on the Digital Analyzer panel. This loads the Digital Data Analyzer program into DSP.

Input

The Digital Data Analyzer operates only with a digital domain input.

The Input Resolution control on the Digital Input/Output (DIO) panel sets the number of input bits to be analyzed for all Digital Data Analyzer waveforms.

For the Random waveform, if the stimulus resolution (the word length) is higher than the Input Resolution setting, it will be truncated to that length. If the stimulus resolution is lower than the Input Resolution setting, errors will be displayed in the Digital Data Analyzer.

For the Walking-1 and Walking-0 waveforms, errors will be displayed if the stimulus resolution is not the same as the Input Resolution setting. See the chart on page 384.

Data and Error Readings

Figure 317. Digital Data Analyzer Data and Error Readings.

Channel A	Channel B
64 dec	1024 dec
0 dec	0 dec

Received data are truncated to the word length set in the Input Resolution field on the DIO panel. The level of each sample is displayed on the Channel A and B Data fields at the top of the panel in decimal or hex units.

When an error is detected, the Data display function depends upon the setting of the Freeze Data on Error check box, below.

Error Display

See Figure 317.

Each sample of received data is compared to its known transmitted value. The number of errors in the received data within the measurement interval are counted and displayed independently for each channel.

Two data samples are required before the error analysis synchronizes with the signal, so errors may be indicated during the initial measurement interval even though no error actually exists.

The **Error Display** field selects the error counting mode.

■ Normal

In the **Normal** mode, the number of errors detected during the last measurement interval (1/4 second, 1/8 second, 1/16 second; set with Reading Rate, below) is displayed in the Channel A and B Errors fields.

■ Maximum

In the **Maximum** mode, the largest error count during any one measurement interval will be held in the display. To reset the **Maximum** error display, click on the Error Display field and press the **Enter** key.

■ Totalize

In the Totalize mode, a running total of all errors is accumulated. To reset the **Totalize** error display, click on the Error Display field and press the **Enter** key.

Error Detection Flag

Whenever an error is detected the Digital Data Analyzer will pulse the AUX OUTPUT BNC connector on the rear panel, to enable oscilloscope triggering to observe received data errors. Since the error indication does not occur until after the end of the data word containing the error, we recommend using a digital storage oscilloscope or logic analyzer, set in pre-trigger mode so it will acquire data before the error detection trigger event.

Freeze Data on Error


Figure 318. Digital Data Analyzer Freeze Data checkbox.

A screenshot of a software interface showing a checkbox labeled "Freeze Data on Error". The checkbox is checked, indicated by a small square with a checkmark inside.

If this box is checked, the **Data** fields will display the data level that was received when the first error occurred. If the check box is not checked, the **Data** fields will continue updating at the **Reading Rate**, regardless of any errors detected.

Reading Rate


Figure 319. Digital Data Analyzer Reading Rate settings.

A screenshot of a software interface showing a dropdown menu for "Reading Rate". The menu is open, displaying the following options: "Auto", "4/sec", "8/sec", and "16/sec". The "Auto" option is currently selected.

The rate selected in the Reading Rate field determines the measurement interval. The **Auto** choice provides a **4/sec** reading rate for the Digital Data Analyzer panel, and a **16/sec** reading rate for sweeps.

Waveform Selection

Figure 320. Digital Data Analyzer Waveform selections.



The Digital Data Analyzer can perform bit-error measurements on five different digital domain stimulus waveforms, chosen in the Waveform selection field. Each waveform has a specific testing application.

For correct analysis, the stimulus signals must match the characteristics required by the Waveform selection. As long as the waveforms match properly, they can be delayed through transmission or recording processes, or can be produced by other generators. See **Stimulus Waveform Requirements**, above.

Sine

The Sine waveform selection is unique in the Digital Data Analyzer, in that the analysis will tolerate level changes due to gain or equalization in the DUT.

Since a low-distortion sine wave retains its shape passing through any linear device, given the sine frequency, digital level, resolution and sample rate, it becomes possible to calculate the quantization value for every sampled point on the waveform, enabling bit-by-bit error detection.

Since the Random, Walking-1, Walking-0 and Constant analysis modes cannot tolerate a change in digital level, use the Sine waveform mode to test DUTs that introduce gain or equalization.

Random

The Random waveform analysis mode requires a specific, predictable pseudo-random waveform uniformly distributed between plus and minus full scale, as generated by the **Digital Generator Special: Bittest Random** waveform setting.

This waveform is intended for error-rate testing of communications links, AES3 interfaces, and digital recorders. It provides the most thorough bit error testing of any of the Digital Data Analyzer waveforms.

Walking-1 and Walking-0

There are two walking bit modes, Walking-1 and Walking-0. These each requires a specific, predictable waveform, as generated by the **Digital Generator Special: Walking Ones / Walking Zeros** waveform settings.

Walking-1 mode sets all bits to 0 except one bit, which is set to 1. This single high bit is continuously incremented from the least significant bit (LSB) to the most significant bit (MSB). When it reaches the MSB it wraps around to the LSB of the selected word length.

The Walking-0 mode sets all bits to 1 except one bit, which is set to 0. Like Walking-1, this single low bit is continuously incremented from LSB to MSB and wrapped back to LSB.

The Samples/Step field on the Digital Generator panel determines the walking rate.

The time required for one complete cycle of the walking pattern depends upon several factors: the DIO Output Resolution, DIO output Sample Rate (SR), and the Digital Generator Samples/Step value. For example, with Samples/Step set to 3 and SR set to 48 kHz, each step will last for 3/48,000 of a second. If Output Resolution is set to 22 bits, the total cycle from LSB to MSB will last for 66/48,000 second or 1.375 ms.

*NOTE: The Data and Errors displays are updated at either 4, 8, or 16 readings per second, as selected in the Reading Rate field. When the **Walking-1** or **Walking-0** waveforms are used, it is possible to arrive at a generator bit-pattern period that is an exact sub-multiple of the Digital Data Analyzer's reading rate, with the result is that the Digital Data Analyzer displays the same Data value continuously, making it appear that a device has locked up; this is particularly likely to happen at sample rates of 96 kHz.*

Since the DIO SR and Output Resolution are normally both determined by the requirements of the DUT, the one remaining variable is the number of samples per step. This value is typically not critical to a testing application, so it can be changed to a value that displays the desired normal changing Data values.

Constant

The Constant waveform analysis mode requires a continuous stream of data samples at the same fixed value (digital dc). Constant mode aids in the investigation of data-dependent errors in digital systems.


On the 2700 series Digital Generator panel, the exact data word to be generated is determined by the value entered in the Amplitude field. Hexadecimal

and decimal units are available in the Digital Generator to correspond with the amplitude units on the Digital Data Analyzer panel.

Chapter 17

The Harmonic Distortion Analyzer

Figure 321. The Harmonic Distortion Analyzer panel.



Introduction

The Harmonic Distortion Analyzer is a DSP analysis tool available on the Digital Analyzer panel. The Harmonic Distortion Analyzer permits flexible, highly selective measurement of the amplitude of user-specified harmonic orders. You can choose to measure any individual harmonic or the sum of any arbitrary selection of harmonic distortion products from the 2nd through the 15th.

The Harmonic Distortion Analyzer uses FFT techniques to isolate and measure each harmonic. The FFT bins are very narrow, and measurement of resid-

ual noise is almost entirely excluded. This means that the Harmonic Distortion Analyzer can measure harmonic distortion without noise for any specified set of harmonic products. If all the harmonics are selected, the Harmonic Sum meters read THD (Total Harmonic Distortion) without noise.

Even though it is internally based on FFT technology, the Harmonic Distortion Analyzer effectively operates as a real-time program. The analyzer drives constantly-updating panel meters and its results can be displayed on bargraphs or plotted as traces on a graph. See Appendix C for more information on FFTs.

The Harmonic Distortion Analyzer will accept either digital or analog domain audio input signals, as selected by the Input field at the top of the panel. It is a two-channel analysis tool, capable of performing measurements on both channels of a stereo signal at the same time. For an analog signal, the Harmonic Distortion Analyzer can measure a frequency range from dc to half the converter sample rate ($F_s/2$) selected in the Input field; for digital signals, the Harmonic Distortion Analyzer can measure a frequency range from dc to half the signal sample rate ($F_s/2$).

There are four pairs of meters on the Harmonic Distortion Analyzer which measure the input signal simultaneously:


- The Fundamental Amplitude meters.
These meters display the signal amplitude at the fundamental frequency, displayed in the field below.
- The Fundamental Frequency meters.
These meters display the frequency that the Harmonic Distortion Analyzer has identified as the fundamental for the current analysis. This frequency is determined by the selection made in the Steering Control field, discussed below.
- The Harmonic Sum 1 meters.
These meters display the sum of the amplitudes of the harmonics selected in the Harmonic Sum 1 fields, and
- The Harmonic Sum 2 meters.
These meters display the sum of the amplitudes of the harmonics selected in the Harmonic Sum 2 fields.

As on other 2700 series panels, you can select the units of measurement you prefer for each reading display.

NOTE: The two Harmonic Sum readings will correctly sum and display only the distortion products which are within the bandwidth limitations determined by the sample rate. See page 396 for more information on bandwidth limitations.

Loading the Harmonic Distortion Analyzer

Figure 322. Loading the Harmonic Distortion Analyzer




To use the Harmonic Distortion Analyzer, first open the Analyzer panel by choosing **Panels > Analyzer** or by the keyboard shortcut **Ctrl+Y**, or by clicking the **Digital Analyzer** button on the Toolbar.



Now select **Harmonic Distortion Analyzer** from the list on the Analyzer panel. This loads the Harmonic Distortion Analyzer program into DSP.

Signal Inputs

Figure 323. Harmonic Distortion Analyzer panel inputs.



The Input field enables you to choose the digital input or the analog inputs (converted to digital) as the signal applied to the Harmonic Distortion Analyzer. The selections are:

- **Digital @ISR**
- **HiRes A/D @65536**
- **HiBW A/D @131072**
- **HiBW A/D @262144**
- **HiRes A/D @SSR**
- **HiBW A/D @2xSSR**

The digital input and converter choices are the same for all five of the DSP audio analysis tools (DSP Audio Analyzer, Spectrum Analyzer, Multitone Analyzer, MLS Analyzer and Harmonic Distortion Analyzer). Go to **Signal Inputs**


on page 228 in the **DSP Audio Analyzer** chapter for detailed information about the Digital Analyzer Inputs.

Source Selection

The Source selection choices depend on the Input selected; the lists are different for the **Digital @ISR** input and for the analog (A/D) inputs.

Digital @ISR Sources

Figure 324. Harmonic Distortion Analyzer Source selections with a digital input.




When **Digital @ISR** is the analyzer input, the source selections for each analyzer channel are:

- **A**
The embedded channel A audio is routed to the analyzer channel.
- **B**
The embedded channel B audio is routed to the analyzer channel.

Analog (A/D) Sources

Figure 325. Harmonic Distortion Analyzer Source selections with an analog input.



When one of the ADCs is the analyzer input, the source selections for each analyzer channel are:

- **Anlr-A**
The Channel A analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument

ANALYZER SIGNAL MONITORS CHANNEL A output, which appears on the front panel on a BNC connector.

■ Anlr-B

The Channel B analog input signal after the Analog Analyzer input ranging and balanced-to-unbalanced conversion, but before any filtering; this is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS CHANNEL B output, which appears on the front panel on a BNC connector.

■ Anlr Rdg Ampl

The final analog-processed Analog Analyzer function reading meter signal, just before the detectors. This point follows all highpass, lowpass and option filtering and the bandpass/bandreject filter.

In either THD+N mode, the bandreject filter will reduce the test signal fundamental to a low level, but up to 60 dB gain is added to the broadband signal after the notch filter, with the result that the residual noise and distortion components are passed to the ADCs at levels typically 60 dB higher than normal, resulting in virtually no contribution of distortion from the ADC. This is essentially the same point that is connected to the instrument ANALYZER SIGNAL MONITORS READING output, which appears on the front panel on a BNC connector.

This selection is an amplitude and is expressed in units of absolute amplitude.

The Fundamental Amplitude Meters

Figure 326. Harmonic Distortion Analyzer Fundamental Amplitude and Frequency meters.



Two Fundamental Amplitude meters are located near the top of the Harmonic Distortion Analyzer panel, one for each input channel. These meters display the rms value of the input signal component at the fundamental frequency displayed in the Fundamental Frequency meters.


This amplitude value is used as the reference for all ratio units (% , dB, ppm, X/Y) when the Ratio box is checked for any Harmonic Sum meter.

The Fundamental Frequency Meters

The Fundamental Frequency meters (or *counters*) display the frequency that the Harmonic Distortion Analyzer has identified as the fundamental for the current analysis. This frequency is determined by the selection made in the Steering control field (see page 398); it is typically the stimulus signal frequency generated by the 2700 series analog or digital generator.

Harmonic Distortion Product Amplitude

Figure 327. *Harmonic Distortion Analyzer Product Amplitude Meters.*



Below the Frequency meter displays are panel sections labeled Harmonic Sum 1 and Harmonic Sum 2. Each section contains a meter display and control fields for input channels 1 and 2, for a total of four Harmonic Sum meters. Each meter consists of the digital display, a Ratio unit checkbox, and controls for selecting the harmonic orders that the meter will measure. The meter display has the usual 2700 series choices for amplitude units. When the Ratio units box is checked, the meter will display in units of %, dB, X/Y, or ppm, referenced to the fundamental amplitude.

Harmonic Order Control

The rows of numbers below each Harmonic Sum meter provide the means to select the harmonics the meter reads.

The upper row of numbers selects the even harmonic orders through the fourteenth—2, 4, 6, 8, 10, 12, and 14. The lower row selects the odd harmonic orders through the fifteenth—3, 5, 7, 9, 11, 13, and 15. You can select or deselect any harmonic order by clicking on the number of the order. Clicking the checkbox at the beginning of a row selects or deselects the entire row of harmonic orders.

When only one harmonic order has been selected for a particular meter, the display in the meter is the amplitude of the specific harmonic signal selected. For example, clicking **3** in the lower row causes the associated display to continuously measure the amplitude of the third harmonic only.

Clicking the **2**, **8**, and **10** in the upper row and the **7** and **13** in the lower row of a meter causes a continuous display of the rms sum of the 2nd, 7th, 8th, 10th, and 13th harmonics of the signal. Checking the boxes at the left end of both rows causes a THD (total harmonic distortion, without noise) measurement that includes the effects of the 2nd through the 15th harmonics.

Distortion Product Bandwidth Limitations

Note that only those harmonic components within the measurement bandwidth of the analyzer can be measured, even if all the harmonic orders are selected.

For example, assume that an analog signal is being measured using the **HiRes A/D@65536 Hz** converter selected on the Analog Input panel, which establishes a bandwidth to about 30 kHz.

If the fundamental frequency is 9 kHz, only the 2nd (18 kHz) and 3rd (27 kHz) harmonics fall within the measurement bandwidth. Selecting any harmonic orders above the 3rd will have no effect on the measurement. When the fundamental is below about 2 kHz, all harmonics up to and including the 15th will be measured. When the stimulus signal frequency is swept during a test, higher-order harmonics will be included while the stimulus frequency is low but excluded by the fixed bandwidth when the stimulus frequency is high.

With analog signals, measurement bandwidth may be increased to as high as approximately 120 kHz by choosing the **HiBW A/D@262144 Hz** converter selection.

For digital signals, bandwidth is intrinsically determined by the sample rate of the device or system being measured.




Figure 328. Fundamental (top curve), 2nd harmonic, 3rd harmonic, 4th harmonic, and 5th harmonic amplitudes of a loudspeaker as a function of power.

The four Harmonic Sum meters are completely independent from one another. On a given channel, one may be set for even harmonics and the other for odd harmonics; or, one may measure a single individual harmonic while the other measures an arbitrary group of harmonics that may or may not include the single harmonic selected on the other meter. Each Harmonic Sum reading for each channel may be simultaneously plotted as a separate trace on the graph during a single sweep.

Amplitude Units

If you click on the arrow to the right of any amplitude or Harmonic Sum meter reading field, a list of measurement unit choices will drop down. The units shown on the list depend upon whether **Digital @ISR** or one of the ADC choices is selected in the Input field.

With **Digital @ISR** selected, the units list displays:

- digital domain units: **FFS**, **dBFS**, **%FS** and **Bits**;
- relative units: **dBr A** and **dBr B**; and
- units relative to the analog domain: **V**, **dBu**, and **dBV**.

These analog domain units are calculated using the value you enter in the **V/FS** field in the References area of the panel, and can be helpful in cross domain measurements.

With analog selected via an ADC choice, the units list displays:

- analog domain units: **V**, **dBu**, **dBV**, and **W** (watts).
- relative units: **dBr A**, **dBr B**, **dBg A**, **dBg B**;
- and units relative to the digital domain: **FFS**, **dBFS** and **%FS**.

For an explanation of the units of measurement used in the 2700 series and the references for the relative units, see Appendix A, **Units of Measurement**.


Click the Ratio checkbox of any of the Harmonic Sum meters to select the ratio units **%,dB**, **X/Y**, and **ppm** for that meter. The reference of these ratio units is the Fundamental signal amplitude of that channel.

References

Analog and digital amplitude and frequency references for the Harmonic Distortion Analyzer are the same as for other Digital Analyzer analysis tools. See **Digital Analyzer References** on page 151.

Steering Control

Figure 329. The Harmonic Distortion Analyzer Steering control field.



The Harmonic Distortion Analyzer must identify the fundamental frequency that you have selected for your measurement. The amplitude of the fundamental component is used as the basis of the Ratio measurements, and the precise

frequency of the fundamental must be known to calculate the frequencies of each of the harmonics to be measured.

The Steering control enables you to choose a source of frequency “steering” to determine how the Harmonic Distortion Analyzer identifies the fundamental signal component. The frequency determined by the Steering Control setting is displayed in the Fundamental Frequency displays.

The five selections available in this field are:

- **Counter Tuned**

Counter Tuned uses the measured frequency of the dominant component of the input signal as the fundamental. Choose this mode when making harmonic distortion measurements from an external signal such as playback of a Compact Disc or an audio tape, or a signal received from a remote source.

- **Sweep Track**

With **Sweep Track** selected, the fundamental frequency value tracks the frequency of the generator is selected in the **Source 1** or **Source 2** fields of the Sweep panel.

- **AGen Track**

With **AGen Track** selected, the fundamental frequency will automatically track the frequency of the Analog Generator.

- **DGen Track**

With **DGen Track** selected, the fundamental frequency will automatically track the frequency of the Digital Generator.

- **Fixed**

Fixed sets the fundamental frequency to the value you enter in the field to the right.

High Speed/High Accuracy Control

Figure 330. Harmonic Distortion Analyzer Distortion High Speed / High Accuracy selection.



The **Harmonic Distortion Analyzer** is normally configured to provide accurate results quickly.

When making measurements of distortion products which are lower than -90 dB or -100 dB (lower than 0.003% to 0.001%) relative to the fundamental, you can choose to set the instrument to a mode of even higher accuracy, at the price of some sweep speed.

In the field to the left of the Steering control, choose **High Accuracy** to enable this mode. The default mode is **High Speed**.

THD vs THD+N

Measurements of THD+N (total harmonic distortion plus noise) vs. THD (total harmonic distortion, not including the effects of noise) on the same signal may differ for two reasons—one theoretical, and the other due to the architecture of typical THD+N analyzers.

The theoretical difference between THD and THD+N lies in the “+N” term—the noise. If distortion products are much higher in amplitude than the wide-band noise in a signal, the two techniques should give essentially identical results. In many cases with modern, well-designed audio equipment, actual distortion is very low across most of the normal operating dynamic range and wide-band noise dominates.

A conventional THD+N analyzer operates by removing the fundamental signal with a notch (bandreject) filter, then measuring what remains. The left-over signal, in this case, is the wide-band noise and distortion products.

A THD analyzer, on the other hand, makes highly selective amplitude measurements only at each specific harmonic product frequency. The bandwidth of these selective measurements is so narrow that broadband noise has almost no effect on the result. In a noise-limited case, a THD analyzer (such as Harmonic Distortion Analyzer) may produce a much lower value than a THD+N analyzer (such as the 2700 series THD+N functions in the Analog Analyzer and DSP Audio Analyzer).

Another difference comes about only when Ratio units (% , dB, X/Y, or ppm) are selected. Practical THD+N instruments make a compromise with the actual definition of distortion ratios in the interest of circuit economy. The definition of THD and THD+N ratios computes the amplitude of the distortion or distortion and noise products with reference to the amplitude of the fundamental signal component. However, practical THD+N analyzers use the amplitude of the input signal, including all distortion products, as the reference instead of the fundamental component alone. At total distortion values of 10.0% and lower (–20 dB and below), the difference between these two approaches is negligible. At higher distortion values, the difference may become large.

For example, when the distortion products are at 10.0 %, the difference in amplitude between the fundamental component and the complex signal including distortion is less than 0.5 %, so distortion values stated as a percentage of either value are nearly the same. At 45 %, typical of a square wave, there is a 9.6 % difference between stating distortion ratios relative to the fundamental rather than to the entire, distorted input signal.

The 2700 series Harmonic Distortion Analyzer makes a selective amplitude measurement of the fundamental signal and refers all Ratio units to that value, conforming to definitions. In their THD+N Ratio function, the 2700 series Analog Analyzer and DSP Audio Analyzers, like all other commercially available THD+N analyzers, refer the distortion product measurements to the raw input signal that includes fundamental and harmonics.

Sweeping and Graphing Results

The fundamental and the harmonic products measured by the **Harmonic Distortion Analyzer** can be swept and graphed with the 2700 series.

The **Harmonic Distortion Analyzer** must be selected as the Digital Analyzer analysis tool. Choose **Harmonic** as the instrument in the Sweep **Data** or **Source** browser, and the following **Parameter** selections will be available for sweeps:

- ChA Fund Ampl
- ChA Fund Freq
- ChA Harm Sum1
- ChA Harm Sum2
- ChB Fund Ampl
- ChB Fund Freq
- ChB Harm Sum1
- ChB Harm Sum2

Chapter 18

Sweeps and Sweep Settling

Introduction: Sweeps and Graphs

A “sweep” is a measurement that includes a number of points of data, the result of varying or “sweeping” one (or more) test parameters across a certain range and reporting the value of other test parameters at regular points during the sweep.

NOTE: You can cause a 2700 series instrument to perform a “single-point sweep” for special purposes, but generally the term sweep indicates that a number of data points are included in the measurement.




Figure 331. Graphical display of sweep results.

The results of a sweep can be listed in a table and viewed in the Data Editor; more commonly, the results are plotted on a graph. As you will see, the 2700 series Sweep, Data Editor and Graph functions are closely tied. When the Data Editor and the Graph panel are open next to your Sweep panel, you can watch the data values and the graph coordinates and traces respond to your Sweep panel settings. See **Sweep Display Mode**, page 413; **Graphs**, page 435, or **Editing Data and Setting Limits**, page 459.

Certain aspects of 2700 series sweep functions are named in terms of the graphic display; for example, the **Source** divisions are called “X-axis divisions;” **Data** results are often called “traces” and so on.

The 2700 series Sweep function gives you the following capabilities:

- You can sweep a parameter as an independent variable across a range you define. This can be a 2700 analysis tool parameter, set with the **Source 1** instrument browser, a table of pre-defined values, an external signal tracked as a sweep source, or a time base to generate chart-recorder type plots.
- As many as six other parameters (called **Data 1** through **Data 6**) can be measured during the sweep.
- You can choose from extensive lists of settings or readings for either **Source** or **Data** selections.
- You can set the number of sweep steps (or the distance between the steps) made within your range.
- You can impose pass / fail limits on your results.
- You can specify the units and divisions displayed on your graph.
- You can set sweeps to automatically repeat.
- You can append subsequent sweeps on your graph.
- You can “nest” sweeps to generate curve “families.”



	0 = Gen.Freq	1 = Anlr.Level A	2 = Anlr.Level B
0	20.0000 kHz	9.581 V	9.582 V
1	15.8875 kHz	7.628 V	7.628 V
2	12.6200 kHz	6.093 V	6.092 V
3	10.0225 kHz	4.870 V	4.870 V
4	7.96250 kHz	3.918 V	3.916 V
5	6.32500 kHz	3.172 V	3.173 V
6	5.02500 kHz	2.588 V	2.588 V
7	3.99000 kHz	2.137 V	2.137 V
8	3.17000 kHz	1.798 V	1.798 V

Figure 332. Tabular display of sweep results graphed in Figure 331.

Batch-Mode “Sweeps”

The 2700 series Sweep panel is also used to initiate and display batch mode DSP measurements for the Spectrum Analyzer, Multitone Audio Analyzer, MLS Analyzer and Digital Interface Analyzer tools. Although these are unlike real-time sweeps in that there is not a swept generator signal or discrete channels of resulting data to be graphed, batch-mode measurements are similar from an operational point of view and in their graphical requirements for an X-Y type plot with scaled and calibrated axes.

This chapter focuses on real-time sweeps. For setup and operation of the Sweep panel in batch mode measurements, see the material in **The Spectrum Analyzer**, Chapter 12; **The Digital Interface Analyzer**, Chapter 13; **The Multitone Audio Analyzer**, Chapter 14; and **The MLS Analyzer**, Chapter 15.

Batch mode sweeps are selected by choosing FFT-based analysis tools (instruments) in the Sweep **Source** and **Data** browsers. There are a few Sweep controls (**Transform Data w/o Acquire**, **Reprocess Data** and **Spectrum<=>Waveform**) which *only* affect batch mode measurements. The operation of these controls is briefly mentioned in this chapter and explained in more detail in the specific Analyzer chapters.

Plan Your Sweep

When you begin a sweep, you should ask yourself questions like these:

- What parameter will the test sweep? In other words, what is the independent variable?
- Over what range should this parameter be swept?
- What data results do I want to see? That is, what will the dependent variables be?

- What range do I expect the results to cover?
- How many points of data do I need?
- How close together must they be?
- Would my sweep be more useful on a linear or a logarithmic scale?

With this type of information at hand it will be easy to set up the Sweep panel for your test. We'll start by looking at the 2700 series Sweep panel and its controls and displays.

The Sweep Panel




Figure 333. The 2700 Sweep Panel (expanded display).



The 2700 series Sweep panel is available by selecting **Panels > Sweep** from the Menu bar or by clicking the **Sweep** button on the toolbar; you can also launch the Sweep panel by selecting **Sweep > Show Panel** from the Menu bar or by using the keyboard combination **CTRL+S**.

Normally, the Sweep panel is used to control a Generator and to collect readings from the Analyzer to produce sweeps for graphing. It also sets the parameters for External Sweeps, and sets the parameters to control FFT graphing for batch-mode analysis tools.

The compact display of the 2700 series Sweep panel (which is the left half of the panel shown in Figure 333) allows you to set up a single-**Source** sweep with one or two sets of **Data** results. If you expand the panel as shown above,

you can use two sweep **Sources** and up to four more **Data** result traces, and you have access to additional controls and settings.

Source 1

Every sweep must have at least one sweep **Source** and one set of **Data** results. The **Source 1** area on the Sweep panel is where you will select and define your primary swept parameter, the independent variable deliberately changed during a sweep. In a graph of a sweep, **Source 1** usually defines the X-axis (the horizontal graph axis). **Source 2** is used for nested sweeps, which are discussed on page 416.

Settings or Readings?

Source 1 will typically be an internal 2700 series setting, such as Analog Generator frequency or amplitude. It could just as well be a Digital Generator setting, or a Digital I/O setting such as **Output Sample Rate**, for example.

It is also possible to use an external signal as the swept parameter (the independent variable). In this case **Source 1** is set to a 2700 series reading such as Audio Analyzer frequency or amplitude. A sweep which uses readings for a source is called an External Sweep. External Sweeps are discussed beginning on page 411.

Selecting a Sweep Source

When the 2700 series control software is first loaded, the default sweep source in **Source 1** is the Analog Generator frequency. To select a different source, click on the **Source 1** browser button.




Figure 334. The Sweep **Source 1** browser dialog box.

A dialog box will open that displays the instruments (analysis tools) and parameters available as sweep sources. Click on a instrument and you will see the settings associated with it in the right browser window.

NOTE: For ordinary sweeps be sure that you have selected your source from the instrument Settings list. Instrument readings are used for External Sweeps, page 411. The check boxes on the browser allow you to choose the Settings or Readings lists.

Start and Stop Values

The values entered in the **Source 1 Start** and **Stop** fields set the sweep range and direction, and also become values for the graph X-axis end points.

In a frequency sweep, for example, the default settings are 20 kHz in the **Start** field and 20 Hz in the **Stop** field.

With these settings, the sweep will move downward in frequency from 20 kHz to 20 Hz. If you would like your sweep to move upward from low to high, enter 20 Hz as the **Start** value and 20 kHz as the **Stop** value.

Source 1 Log or Lin Scales

If neither the **Start** nor the **Stop** value is zero or a negative number, you have the option of calibrating the **Source 1** axis on a logarithmic or a linear scale. Click on the **Log** or **Lin** option buttons to change the scale.

If either value is zero or negative, or if decibel units are chosen (these are available for an amplitude source), the **Log** and **Lin** option buttons will not be available and the scale will be set to linear.

The choice of scale affects the way that step size is calculated for the sweep and also the distribution of the vertical divisions on the resultant graph.

Sweep Resolution

The range between the **Start** and **Stop** values will be stepped through in:

- equal-size increments, in **Lin** scale mode, or
- equal-percentage increments, in **Log** scale mode.

The number of steps, the size of each step, the **Log** / **Lin** selection and the range between the **Start** and **Stop** values are all interrelated.

Linear Scale Steps

When using a linear scale, you can set the step size by entering the number of steps in the **Steps** field. Only integer numbers between 1 and 65,000 are accepted. After you have made an entry, the value in **Stepsize** will be recalculated. Alternately, you can enter a value in the **Stepsize** field and the control software will calculate the correct number of steps to produce this step size.

If the value you enter does not result in an integer number of steps, the control software rounds the calculated value of steps to the next lower integer value to maintain the exact step size you have entered, then takes care of the arithmetical remainder by adding a final, smaller step to the **Stop** value.

Logarithmic Scale Steps

When using a logarithmic scale, the field which had been called **Stepsize** in **Lin** mode is renamed **Multiply**. You can set the step size by entering the number of steps in the **Steps** field just like the **Lin** setting. Or, you can enter a value in the **Multiply** field and the control software will calculate the correct number of steps to produce this step-to-step multiplier.

If the value you enter does not result in an integer number of steps, the software rounds the calculated value of steps to the next lower integer value to maintain the exact step-to-step multiplier you have entered, and then takes care of the remainder by adding a final, smaller step to the **Stop** value.

X-Axis Divisions

In **Log** mode, the placement of grid lines for the graph X-axis divisions is pre-determined and the **Div** field and the **Auto** checkbox are not available.

In **Lin** mode if **Auto** is checked, the grid lines are selected automatically based on the **Source 1** settings. If **Auto** is not checked, you can specify a number of grid lines by entering a value into the **Div** field.

Data 1

As mentioned before, every sweep must have at least one sweep **Source** and one set of **Data** results. The **Data 1** area on the Sweep panel is where you will select and define your primary data result, the dependent variable which changes in response to **Source 1**. In graphing a sweep, **Data 1** is shown as a trace or curve whose values are always read on the graph left Y-axis. **Data 2** through **Data 6**, though similar, have enough differences to warrant their own discussions. **Data 2** begins on page 412, and **Data 3 through Data 6** are on page 413.

Selecting the Data 1 Reading

The default reading for **Data 1** is the **Analyzer Level A** amplitude. To select a different reading, click on the **Data 1** browser button.




Figure 335. The Sweep **Data 1** browser dialog box.

A dialog box will open which displays the instruments (analysis tools) and parameters available as data readings. Click on a instrument and you will see the readings associated with it in the right browser window.

Top and Bottom Values

Enter the graph top and bottom values in the **Top** and **Bottom** fields in the **Data 1** section of the Sweep panel. Drop the arrow list to change units of measurement.

Since **Data 1** displays the results of measurements, it is not always possible to predict the range of the values. If you set the **Top** or **Bottom** values too low or high, the data will still be acquired and saved, but the graph trace will not extend beyond the set values. In this case you can re-enter the **Top** or **Bottom** values and the graph will re-draw itself to correctly plot your results.

*NOTE: You can use the **Optimize** function on the Graph panel to reset the Y-axis extents to accommodate your results.*

You can also automatically set the **Top** and **Bottom** values on this panel in response to the **Data 1** readings. Click the **Autoscale** checkbox to enable this function.

Data 1 Log or Lin Scales

If neither the **Top** nor the **Bottom** value is zero or negative, you have the option of calibrating the **Data 1** axis on a logarithmic or a linear scale.

If either value is zero or negative, or if decibel units are chosen, the **Log** and **Lin** option buttons will not be available and the scale will be set to linear.

Y-Axis Divisions

In **Log** mode, the placement of grid lines for the graph Y-axis divisions is pre-determined and the **Div** field and the **Auto** checkbox are not available.

In **Lin** mode if **Auto** is checked, the grid lines are selected automatically based on the **Data 1** settings. If **Auto** is not checked, you can specify a number of grid lines by entering a value into the **Div** field.

These controls affect scaling for real-time data acquisition. The graph can be re-scaled to accommodate the data in the graph buffer memory using the graph **Optimize** function, page 438.

Data Limits

The **Limits** button opens a dialog box enabling you to attach acceptance (pass / fail) limits to a test. See **Setting Limits**, page 462.

Data 2

Data 2 enables you to plot a second trace of data on your graph against its own scale and calibration, on the right-hand graph axis.

Data 2 operates in exactly the same way as **Data 1**, with these exceptions:

- **Data 2** plots against the scale on the graph right Y-axis,
or, if the **X-Y Data2 on X** option button is selected,
- **Data 2** determines the X-axis calibration to enable you to plot two measured values, or readings, as an X-versus-Y graph. See below for an explanation of plotting data X-Y.

When **Data 1** and **Data 2** are plotted together on a graph, the **Data 1 Top** and **Bottom** range settings and intermediate values are displayed on the graph left Y-axis. The **Data 2 Top** and **Bottom** range settings and intermediate values are displayed on the graph right Y-axis.

Plotting Data as X-versus-Y

Sometimes it is useful to plot two measured values against one another under stimulus from a third signal.

In a Data X-versus-Y graph, **Data 1** is still plotted on the left Y-axis. **Source 1** is still the independent variable, stepping through the **Start / Stop** range and driving the test to create the changes in the **Data 1** and **Data 2** dependent variables which will be plotted. However, **Source 1** values and calibration will not be displayed on the graph at all; instead, **Data 2** values are used to calibrate the X-axis.

As an example, you can perform an amplitude sweep (**Source 1**) on a power amplifier and plot the measured percent distortion (**Data 1** on the Y-axis) against the measured power output (**Data 2** on the X-axis). The amplitude sweep itself is never displayed as such; however, the two sets of results are graphed to show their dynamic relationship.

You can switch between the conventional **X-Y** mode and the **X-Y Data2 on X** mode at any time using the option buttons on the expanded Sweep panel.

*NOTE: Limits cannot be graphed and data cannot be compared to limits when the graph is in **X-Y Data2 on X** mode.*

Data 3 through Data 6

*NOTE: If you are viewing the Sweep panel in its compact mode and one or more of the **Data 3** through **Data 6** functions are in use, these will be listed in the Sweep panel title bar between sets of arrows, as shown below.*



Figure 336. The Sweep panel indicating **Data 3** and **Data 4** in use.

Data 3 through **Data 6** enable you to plot up to six variables when used with **Data 1** and **Data 2**. These additional **Data** functions operate in exactly the same way as **Data 1** and **Data 2**, with this exception: to be plotted on the graph, they must share a graph calibration scale (the horizontal scaling lines and the corresponding numerical legend displayed on the left or right Y-axes) with either **Data 1** or **Data 2**. Consequently, the **Data 3** through **Data 6** sections of the Sweep panel have no **Top** and **Bottom** or scaling fields.

To share a calibration scale with **Data 1** or **Data 2**, the measurements must be of the same “measurement domain.” For example, **dBV**, **dBm**, **V** and **W** are all of the same measurement domain, all being based on voltage measurements. Phase measurements or digital data measurements are not of this measurement domain and cannot be plotted against the same calibration scale as voltage.

Of course, all data in a sweep is always available in the Data Editor and can be viewed in a tabular form, regardless of measurement domain. Data that cannot be plotted because of measurement domain conflicts will be displayed in the Data Editor in the base unit for that measurement domain.

Here’s an example: if **Data 1** is percent distortion and **Data 2** is level, it will not be possible to also plot phase on **Data 3**. If, however, you wanted to plot channel A and B level and the phase difference between them, you could assign channel A level to **Data 1**, phase to **Data 2** and channel B level to **Data 3**.

The **Data 3** measurements would be plotted against the left-hand Y-axis calibration set in **Data 1**.

Sweep Display Mode

The results of a sweep can be displayed as a graph, as a table, or both.

Click the **Create Graph** and / or **Create Table** checkboxes on the expanded Sweep panel to choose the sweep display mode. When you run a sweep you will be able to view the data entering your display in real time.



The tabular display is shown in the Data Editor panel (see page 459). If you have made a sweep without **Create Table** set, you can still choose to view the data in the Data Editor, which is opened by clicking the **Data Editor** button or by using the Menu command **Panel > Data Editor**.

When using a graph for display, you are limited to two sets of unit choices (Volts, dBr, etc.) for your data results, since only the left and right Y-axes are available for graph calibration. However, in tabular form this constraint does not exist, and you can specify different units for each of the **Data 1** through **Data 6** columns, if you wish.

NOTE: If you are running sweeps in an automated or manufacturing test situation where speed is most important, you can set both sweep display modes OFF for fastest performance.

Go / Stop / Pause

Once you have your **Source** and **Data** settings made, all that remains is to trigger the sweep. Click the **Go** button on the Sweep panel or the toolbar; you can also start the sweep by selecting **Sweep > Start** from the Menu bar or by pressing function key **F9**.

To stop the sweep, click the **Stop** button on the Sweep panel or the toolbar; you can also stop the sweep by selecting **Sweep > Stop** from the Menu bar or by pressing the **ESC** key.

To pause or unpause a sweep, press function key **F10**.

Repeat

You can set the control software to repeat your sweep indefinitely. Click the **Repeat** check box on the Sweep panel to enter the **Repeat** mode.

Selecting **Sweep > Start with Repeat** from the Menu bar or pressing the key combination **ALT+F9** sets the **Repeat** mode and starts the sweep.

When you need to interrupt repeated batch-mode processing such as FFT or multitone tests, do it by unchecking the **Repeat** box and letting the sweep completely finish. If you use **Stop** you will leave invalid data in the DSP which will result in a meaningless graph.

Append

You can set the software to append your sweeps to the graph, retaining your previous data and appending the new data to the old. Normally, when not using **Append**, the software clears the existing sweep data from the graph and from memory before beginning a sweep.

To enter the **Append** mode, click checkbox on the Sweep panel. Click the box a second time to remove the check and exit the **Append** mode.

Selecting **Sweep > Start with Append** from the Menu bar or pressing the key combination **CTRL+F9** sets the **Append** mode and starts the sweep.

Appending a File

You can also append previously saved data to a current sweep by using the **File > Append** command, which opens a file browser dialog box.

Select a test (.at27) or data (.ada, .adq, .ads or .adl) file to be appended.

The data currently in memory and the file to be appended must be compatible in these ways:

- They must both have compatible **Source 1** selections; for example, both set to frequency or both to amplitude.
- They must both have the same structure of **Data 1** and **Data 2** selections; for example, a data file with data plotted at both **Data 1** and **Data 2** can not be appended to current data in memory which has **Data 2** set to **None**.
- They must both have compatible “measurement domains;” for example, a measurement of distortion shown in percent units, which expresses a ratio, may not be appended to a measurement of level in amplitude units, which does not express a ratio. However, distortion shown in absolute units, such as volts or dBu, can be appended to amplitude data.

Data appended from a file will be graphed in the same color used in the original test or data file. Both the original and the appended data can be viewed in the Data Editor.

Stereo Sweeps

The 2700 series has the ability to sweep two channels of a device simultaneously with the **Stereo Sweep** function. Although you could manually set up two sweep **Data** functions and get the same results, using the **Stereo Sweep** function brings some additional advantages.

- Automatic selection and setup of opposite channel data settings, including **Limit** file selection.
If you have entered only one channel of a reading instrument (in **Data 1**), the control software will set up the opposite channel in **Data 3** to match. Since both of these readings are of the same measurement domain, they will both be plotted against the calibration and scaling on the left-hand Y-axis. This leaves **Data 2** and the right-hand Y-axis available for other uses.
If you also set up a channel from a second reading source (in **Data 2**) during a stereo sweep, the software will automatically set up the opposite channel in **Data 4** to match.
- In stereo sweep crosstalk tests, the control software performs automatic input and output switching and runs two cross-channel measurements in succession. The two passes are plotted as separate data in one graph and saved in one file.

To make a stereo sweep:

- Set up **Source 1** and **Data 1** (and **Data 2**, if you want to plot two different pairs of variables) for your sweep.
- Click the **Stereo Sweep** checkbox on the Sweep panel.

Some reading parameter selections (such as **Phase** or **DCX-127 DMM Volts**) are not stereo signals. If you select such a parameter for **Data 1** or **Data 2**, the stereo sweep function will not be available.

Opposite-channel limit files which have been automatically attached to **Data 3** or **Data 4** in Stereo sweep can be changed or disabled by clicking the **Limits** button for that **Data** function.

Single Point Sweeps

A “single point” sweep is one in which the independent variable, **Source 1**, is held at only one value. The software can then acquire the measurement data for any dependent variables you have set in **Data 1** through **Data 6**.

Single point sweeps are often used in AP Basic macros to “grab” a value or set of values. Single point sweep results differ from meter readings in several ways:

- The single point **Data** result is dependent upon the **Source** value specified.
- The data can be displayed in a tabular format in the Data Editor.
- The data can be saved as an .ada file, and recalled or exported.
- Sweep settling delays and algorithms can be applied. See **Sweep Settling** on page 427.
- The data results can be compared against Limit files.

To make a single point sweep, click the **Single Point** checkbox on the Sweep panel. Then select an instrument setting parameter for **Source 1**. Enter the value at which you want to make your measurement in the **Source 1 Start** field, and set up whatever **Data** functions you want.

Since an X-Y graph cannot be drawn for a single point measurement, the result will only be displayed in a table. Select **Create Table** on the expanded Sweep panel. Click **Go**, and data will be acquired and displayed in the Data Editor table. See **Sweep Display Mode** on page 413 and **Data Editor** on page 459.

Nested Sweeps using Source 2

The sweep function can generate a “family” of curves using **Source 1** and **Source 2** together in what is called a *nested sweep*. A nested sweep controls two different setting parameters in an interrelated manner.

You can use nested sweeps to generate a set of frequency response curves made at a number of different amplitudes, for example; or you can graph overlaid response measurements for a multichannel recorder, using an Audio Precision SWR-2755 series switcher operated by the control software via APIB.

The nested sweep feature is enabled by entering settings into **Source 2**.

In a nested sweep, **Source 1** is still used as the primary independent variable. When the sweep starts, the software looks first to **Source 2** for the initial Start setting, then begins the first **Source 1** sweep. When that is completed, the sweep then increments by one **Source 2** step. Then the **Source 1** sweep is made again. This process is repeated until all the steps defined in **Source 2** have been completed.

The X-axis scaling and calibration are taken from the **Source 1** settings. The **Source 2** parameter values are not directly visible on the graph, but these values are displayed in the **Graph Legend** (see page 445).

The **Source 1** and **Source 2** controls and browser operate identically.

Pre-Sweep Delay

The pre-sweep delay setting enables you to specify a time delay between the **Go** command and the actual beginning of the sweep, to allow for stabilization of the generator or the device under test, if necessary. This can help eliminate transient “glitches” at the start of a sweep. The allowable pre-sweep delay range is 0.000 seconds to 4.000 seconds; the default setting is 200 ms.

The pre-sweep delay is also applied before batch-mode DSP sweeps. Acquisition of signal into any of the Analyzer FFT (batch-mode) programs will not begin until the pre-sweep delay period has passed.

In nested sweeps (using **Source 2**), the pre-sweep delay is applied at the beginning of each nested sweep.

Pre-Sweep Delay and Auto On

The initial transient created when a generator is turned on requires a delay before measurement to allow the generator, DUT, ranging and analyzer circuits to stabilize. When **Auto On** is enabled, the **ON** command is applied to the generator at the moment the sweep starts. To avoid the effects of the switching transient, set the **Pre-Sweep Delay** to a sufficient time, in many cases **.5 sec to 1 sec** or more.

See pages 67 and 101 for more information about **Auto On**.

Table Sweeps

The sweeps we’ve looked at so far step through a range of values set in **Source 1**, controlling the 2700 series instrument settings as the independent variable.

In a table sweep, the points of measurement are read from a table rather than taken from the **Source 1 Start**, **Stop** and **Steps** settings. You must still use the **Source 1** browser to choose the 2700 series instrument parameter that is to be used, but the range, direction, number of steps and the step size are all determined by the values entered in the sweep table.

This allows you to specify exact values and precise step sizes, which do not need to be regularly spaced. The sweep will move in whatever direction the values dictate, including forward or backward.

A sweep table is assigned to a sweep by “attaching” an appropriate AP data file. This is usually a file saved as an AP sweep data file, with the extension **.ads**. Click **Table Sweep** on the Sweep panel to view the file attachment browser. Find the **.ads** file you want to attach to your sweep and select it.

*NOTE: Other AP data file types can also be attached as sweep tables. See **More About Using AP Data Files** on page 466.*

Before you attach the file, you must indicate to 2700 series which column of data in the table will be your independent variable, that is, which values will drive your sweep. Drop the **Column** field list on the browser and choose the column. If you are not sure which column you want, click the **Edit** button on the browser. This opens a panel called the Attached File Editor. You can view the table in the Attached File Editor and decide which column to choose. For more information on using the Data Editor and the Attached File Editor, go to Chapter 21.

NOTE: The Attached File Editor is similar in appearance to the Data Editor, but they have different functions and should not be confused.

When you are ready, click OK. The table will be attached to your sweep. You will notice that the **Steps** and **Stepsize** (or **Multiply**) fields have disappeared from Source 1, since they are no longer needed.

The **Start**, **Stop** and scale controls (**Log**, **Lin**, **Div** and **Auto**) are still available, but they no longer affect the performance of the sweep; they are only used to set the graph calibration and divisions. If you set the graph range in **Start** and **Stop** narrower than the range of the values in the sweep table, there will be points beyond the range which will not be plotted.

If, instead of attaching an existing sweep table you would like to create your own, open the Data Editor panel by clicking the **Data Editor** button or using the Menu command **Panel > Data Editor**. You can enter, edit and delete values in the Data Editor to create your sweep table. Save the contents of the Data Editor as a sweep data file (.ads) using the Menu command **File > Save As > Sweep Tables**.

External Sweeps

Background: Internal and External sweeps

Many of the sweeps performed in the 2700 series involve one of the internal generators, with the sweep following controlled parameters such as frequency or amplitude. The sweep and the generator share the control settings, and there is no ambiguity about sweep direction, or sweep **Start** or **Stop** values, for example.

However, it is often necessary to have the control software track or follow a sweep source that is not under internal control, such as a CD alignment disc, a recorder alignment tape, or a remote sweep generator. This is accomplished in

the external sweep mode. When performing an external sweep, the 2700 series monitors the input signal and extracts sweep controls from the signal itself.

This information is always less certain than the mutually shared settings of an internal sweep, and the control software requires some hints: the range and direction of the sweep, under what conditions to graph a point, when to end the sweep, and so on. With real-world signals, satisfying these criteria can be difficult, and external sweeps can sometimes fail to start or stop, gather too many or too few points, or graph spurious points.

Performing an External Sweep

External sweeps are driven by actual measurements. The **Source 1** field on the Sweep panel must be configured as a meter reading rather than a generator setting, and the reading must satisfy the sweep settling requirements entered in the Settling panel (see page 427) for that meter. For a frequency sweep, the meter will be one of the frequency meters. For amplitude-controlled sweeps a level or amplitude meter is normally used.

Other meters may be selected for special or difficult measurements. For example, the DSP analyzer in Bandpass mode can be used to control an amplitude sweep with Analog Analyzer measurements. The narrow bandpass filter in the DSP analyzer allows measurements with much-reduced sensitivity to noise.

To begin an external sweep, go to the Sweep panel and click the **Source 1** browser button to open the **Source 1** browser. Select the measurement instrument (analysis tool; **Anlr**, for example); on the right-hand side of the browser unclick **Show Settings** and click **Show Readings**. This will populate the panel with a new set of instrument parameters. Select a reading for your external sweep (**Freq A**, for example).




Figure 337. On the left, the Sweep Source 1 browser set to Show Readings for external sweep control; on the right, the Sweep panel in External Sweep mode, showing the External Rules button.

You are now in external sweep mode. When you close the browser, you will notice that a new button labeled **External Rules** has been added to the Sweep panel. Click the **External Rules** button to open the External Sweep panel.

The External Sweep panel




Figure 338. The External Sweep panel.

An external sweep follows (along the x-axis) a measured signal attached to **Source 1**, and plots (against the y-axis) measured signal(s) attached to **Data 1-6**. The sweep will only start, or plot subsequent points, or stop, when at least two (**Source 1** and **Data 1**) or as many as eight (**Source 1, Data 1-2-3-4-5-6** and the **Threshold** meter) signals have satisfied certain criteria you have set.

Consequently, you must plan an external sweep carefully and test it against the external source to optimize its operation. It is quite possible to design an external sweep that will never start, or will never plot a point, or will never stop.

Start, Stop and Start Value

The extent and direction of the sweep are set by the **Start** and **Stop** fields on the Sweep panel. If the value of **Start** is less than **Stop**, the sweep will proceed upward, in the direction of lesser to greater. If **Start** is greater than **Stop**, the sweep will proceed downward. For convenience, the **Start** value is also listed in the **Start Value** field of the External Sweep panel. These fields share the same data. Entering a value into either field will set the same value in both fields.

Start Tolerance

Start Tolerance defines a range around the **Start Value** that the control software can optionally use to determine when to initiate a sweep. **Start Tolerance** can be entered as a percentage of **Start Value** or as an absolute value.

Start Sweep

A “normal” internal sweep is initiated by pressing **F9** or clicking **GO**. Two things happen in response to this: the generator you have selected begins its sweep, and the acquisition of sweep measurements is enabled.

In an external sweep, of course, the control software does not start a generator, but **F9** (or **GO**) enables the acquisition of sweep measurements in the same way. However, the system must wait for the external generator to start its sweep, and no data will be acquired until the external signals satisfy the conditions set by the **Start Sweep** selection. There are three Start Sweep choices that define the circumstances that will initiate the sweep and plot the first data point(s).

■ when within Start Value $\pm$ Tolerance

- a settled reading of the signal attached to **Source 1** must equal **Start Value $\pm$ Tolerance**; and
- the signal attached to the **Threshold** meter must equal or exceed the **Threshold** value; and
- the signal(s) attached to **Data 1-6** must settle; and
- a second settled reading of the signal attached to **Source 1** must still equal **Start Value $\pm$ Tolerance**.

No data are collected until these conditions are met. This choice is the default behavior of external sweeps.

■ when within Start Value $\pm$ Tolerance or beyond

- a settled reading of the signal attached to **Source 1** must equal or exceed **Start Value $\pm$ Tolerance**; and
- the signal attached to the **Threshold** meter must equal or exceed the **Threshold** value; and
- the signal(s) attached to **Data 1-6** must settle; and
- a second settled reading of the signal attached to **Source 1** must still equal or exceed **Start Value $\pm$ Tolerance**.

No data are collected until these conditions are met.

■ Any Setting Reading

- The signal attached to **Source 1** is irrelevant.
- the signal attached to the **Threshold** meter must equal or exceed the **Threshold** value; and

c. the signal(s) attached to **Data 1-6** must settle.

Data collected under this rule can include values above or below the sweep graph limits set in **Start** and **Stop**.

Data Spacing

Once the sweep has begun and the first data point has been collected, **Data Spacing** defines the circumstances that will plot the subsequent data points. For data after the first collected point,

- a. a settled reading of the signal attached to **Source 1** must exceed the **Source 1** value of the previous collected point plus **Data Spacing**; and
- b. the signal attached to the **Threshold** meter must equal or exceed the **Threshold** value; and
- c. the signal(s) attached to **Data 1-6** must settle; and
- d. a second settled reading of the signal attached to **Source 1** must confirm that the **Source 1** value has not changed.

No further data are collected until these conditions are met.

The **Data Spacing** field determines the minimum x-axis step size of the sweep. **Data Spacing** is normally entered as a percentage of the **Source 1** (x-axis) value of the previous collected point; or, it can be entered as a fixed value.

Data Threshold

The value set in the **Data Threshold** field allows you to exclude any measurements below a preset level, as measured by the meter specified in the **Data Threshold Meter** field just below **Data Threshold**.

When the **Threshold Meter** is attached to the same signal as a **Data 1-6** signal, this acts as a “noise gate,” preventing noise or low-level signals from interfering with the process. When the **Threshold Meter** is attached to another signal, that signal can act as a “triggered noise gate,” allowing a cue signal to enable data plotting.

When **Data Threshold** is set very low, all signals will exceed the setting and will be collected; when **Data Threshold** is set very high, no signals will exceed the setting and nothing will be collected.

End

The **End** field enables you to set the conditions under which an external sweep will be terminated by the **Stop Sweep** selection below. Of course, an external sweep test can be manually terminated by pressing the **Esc** key or clicking on the **Stop** icon when it is apparent that the sequence of test tones has ended, but **End** and **Stop Sweep** can be set to terminate the sweep automatically.

End Tolerance

End Tolerance defines a range around the **End Value** that the control software uses to determine when to terminate a sweep. **End Tolerance** can be entered as a percentage of **End Value** or as an absolute value.

Stop Sweep

Stop Sweep automatically ends an external sweep when the **Source 1** reading equals the **End** value (plus or minus **End Tolerance**), subject to the rule selected here.

■ Within End Value $\pm$ Tolerance

- a. a settled reading of the signal attached to **Source 1** must equal **End Value $\pm$ Tolerance**.

The sweep is not terminated until this condition is met. This choice is the default behavior of external sweeps.

The **End** value must be greater than the **Start** value (in the direction of sweep movement) or the sweep will not terminate. **End** may be set to a value greater than **Stop**, enabling you to place an out-of-band cue tone after the swept tones to terminate the sweep.

■ Return to Within End Value $\pm$ Tolerance

The **End** value must be between the **Start** and **Stop** values.

- a. a first settled reading of the signal attached to **Source 1** must equal or exceed **End Value $\pm$ Tolerance**.
- b. at least one point must be plotted whose **Source 1** value exceeds the reading in (a) above.
- c. a second settled reading of the signal attached to **Source 1** must equal **End Value $\pm$ Tolerance**.

The sweep will pass the **End Value** and continues until the sweep reverses and returns to the **End Value**. The sweep will terminate on the second occurrence of the **End Value** (plus or minus **End Tolerance**).

This selection enables you to set **End** to a value in the mid-range of your desired sweep, accommodating a frequency test which sweeps across the desired spectrum and then returns to a mid-spectrum tone. If **End** is set to that mid-spectrum tone, it will note the first occurrence of that tone as the sweep passes through it, and at the return the second occurrence of the tone will terminate the sweep. Many pre-recorded test tapes and CDs are made just this way, with, for example, a 20 Hz to 20 kHz sweep followed by a 1 kHz reference tone. When performing split-site measurements, the remote generator can be set up so that the generator dwells at its Generator panel setting (which can be a mid-band reference frequency) before and after a **Source 1** frequency sweep.

Some Hints for External Sweeps

In a “glide” sweep, the signal is gliding continuously from one value to another and will never settle as it will in a stepped sweep. In an external frequency glide sweep it is essential that the frequency Settling Algorithm be set to **None**.

Also, check your **Threshold** settings. Acting rather like a noise gate, **Threshold** sets an amplitude threshold below which data will not be acquired; this is useful in directing the sweep to ignore the silence between tracks on a test CD, for example. The default meter assigned to make the **Threshold** reading is **Anlr.Level A**, but a browser offers you a selection of sources. Be sure the meter that you have selected is the appropriate meter for your test, that you have considered the effect of any filters you may have attached to the meter, and that the **Threshold** setting is at the correct level.

External Stereo Sweep

External sweeps can also be configured as stereo sweeps by clicking the **Stereo Sweep** checkbox on the Sweep panel. The 2700 series will automatically set the **Data 3** (and **Data 4**, if necessary) settings to match the **Data 1** (and **Data 2**) settings for stereo pairs. See **Stereo Sweeps** on page 416 for a full discussion.

Since the 2700 series is entirely dependent upon the External signal in an External sweep, the automatic switching for the stereo sweep crosstalk feature (page 416) for ordinary sweeps is not available for external sweeps.

External Single Point Sweeps

External sweeps can also be configured as Single Point sweeps by clicking the **Single Point** checkbox on the Sweep panel. See **Single Point Sweeps** on page 416 for a full discussion.

When set up for an External Single Point Sweep, the 2700 series will wait until the input signal satisfies all the criteria you have set, including **MinLvl**, the operative **Start-On Rule**, and **Settling**. When the **Source 1** reading fulfills these requirements, a **Data** reading will be taken.

An external single point sweep is useful to extract a single reading under a specific condition, or to permit an AP Basic macro to continue only at the point that a measured parameter reaches a certain value.

An X-Y graph will not be drawn for a single-point measurement. You can view the result in the Data Editor table.

Time Sweeps

In addition to generator sweeps and external sweeps, 2700 series can graph data against time in a Time Sweep, which produces a “chart recorder” style measurement. Time Sweeps are commonly used to measure instability or drift of audio parameters over time, or to plot moment-to-moment variations such as wow and flutter or phase jitter.

To run a Time Sweep, open the **Source 1** browser and select **Time** as your instrument and **External Sweep Time** as the parameter. Neither the **Show Readings** nor **Show Settings** checkboxes has any effect on your parameter choices, since you are neither setting a generator nor tracking a measured reading.

The time interval starts when you click the Sweep **Go** button. You can view the Time Sweep from the very beginning if you have entered **0.000 sec** as your **Start** value. The sweep will continue until your **Stop** value is reached.

As with generator sweeps, you can enter the number of **Steps** (or step **Multiply**, in **Log** mode) or **Stepsize** as **Source 1** settings. For very closely spaced readings, 2700 series’s ability to make measurements will be limited by other factors, such as Sweep Settling or meter detector reading rates. For example, if your selected reading rate is 8 readings per second, two consecutive readings cannot be closer than 125 ms.

At the very short reading intervals which are necessary to acquire measurements that are close together, the speed of your computer, the number of control software panels open and the windows open in other applications will have a noticeable effect on the speed of acquisition.

Sweep Settling

Most of the measurements in 2700 series are taken continuously, often at rates as high as 32 or 64 readings per second. The real-time numeric meter displays show this “raw” data, and you will notice that the readings jump around when the signal contains transients or other momentary disruptions. We mentally “settle” these measurements as we observe them, ignoring the brief extremes and taking the perceived average or trend as the reading.

If raw readings like this were plotted without some way of excluding the transients, there would often be meaningless points spread across the graph.


The process of sweeping can also add spurious results to the measurement. This is because the Sweep panel is stepping through **Source 1** parameter changes, and with each change both the system generators and typical DUTs need a moment to stabilize.

To address these considerations, the sweep function uses a sweep Settling panel to set a list of criteria that the measured parameter must satisfy before being acquired. These settling values can be adjusted for various measurement conditions and goals, with the result that clear and meaningful graphs (or tables of data) can be obtained.

The 2700 series control software normally obtains settled data by discarding early measurements and plotting only later, repeatable values after both the DUT and the 2700 series generator and analyzer have stabilized. Default settling values are set in place when you launch the control software, but these can be adjusted to optimize different measurements on the Settling panel. Settling values are saved when you save a test file, and are recalled when a test file is loaded.

The settling values only affect real-time sweep measurements, and, in AP Basic procedures, OLE meter readings. 2700 series panel meter readings and batch mode analysis tool readings are not settled.

The Sweep Settling Panel



Analog Analyzer		Tolerance:	Floor	Points	Delay	Algorithm
Amplitude	3.00000 %	100.0 nV	3	30.00 msec	None	
Level A:	1.00000 %	10.00 uV	3	30.00 msec	None	
Level B:	1.00000 %	10.00 uV	3	30.00 msec	None	
Frequency A:	0.50000 %	250.000 uHz	2	20.00 msec	None	
Frequency B:	0.50000 %	250.000 uHz	2	20.00 msec	None	
Phase:		+0.20 deg	2	20.00 msec	Exponential	
DCX						
DCV	0.20000 %	+0.00050 Vdc	3	30.00 msec	Exponential	
Digital In:	0.00000 %	0 dec	3	30.00 msec	Exponential	
DIO						
Sample Rate:	0.50000 %	100.000 mHz	3	30.00 msec	Flat	
Voltage:	3.00000 %	10.00 mVpp	3	30.00 msec	Flat	
Delay, In from Ref In:	0.01000 %	70.00 nsec	3	30.00 msec	Flat	
Delay from Out:	0.01000 %	70.00 nsec	3	30.00 msec	Flat	
Interface Jitter:	3.00000 %	500.0 psec	3	100.0 msec	Flat	
DSP						
DSP Anlr.Level A:	1.00000 %	1.000 uFFS	3	30.00 msec	Average	
DSP Anlr.Level B:	1.00000 %	1.000 uFFS	3	30.00 msec	Average	
DSP Anlr.Freq A:	0.50000 %	10.0000 mHz	1	2.000 msec	Average	
DSP Anlr.Freq B:	0.50000 %	10.0000 mHz	1	2.000 msec	Average	
DSP Anlr.Ampl A:	1.00000 %	1.000 uFFS	3	30.00 msec	Average	
DSP Anlr.Ampl B:	1.00000 %	1.000 uFFS	3	30.00 msec	Average	
Distortion.Ch.2 Harm Sum1	0.50000 %	10.00 mV	1	2.000 msec	Flat	
Distortion.Ch.2 Harm Sum2	0.50000 %	10.00 mV	1	2.000 msec	Flat	
IEC 61937						
Account for encode delay: ☒						

Figure 339. The sweep Settling panel.

The Settling panel is available by selecting **Panels > Settling** from the Menu bar or by clicking the **Settling** button on the toolbar; you can also launch the Settling panel by selecting **Sweep > Show Settling Panel** from the Menu bar.



The Settling panel allows you to set a number of settling parameters for each of the meters available in a 2700 series sweep. The Digital Analyzer meters available on the Settling panel will change with the analysis tool (instrument) you have selected.

Settling Concepts

Since much of the signal disruption occurs at the beginning of a sweep step because of instrument and DUT stabilization, the settling function is designed to:

- Ignore early readings, and
- Calculate when a reading should be considered stable enough for data to be acquired.

The Settling panel offers two independent controls to accomplish this for each 2700 series meter: the Settling Delay time and the Settling Algorithm selection.

Settling Delay Time

The first task in settling is to ignore all early readings. Any measurements that arrive within the period between the beginning of a sweep step and the time set in the Delay field are discarded.

Typical default Delay settings are in the 20 ms to 100 ms range, depending on the analysis tool selected.

The Delay value is independent of the Algorithm choice, and is effective even if the Algorithm selection is **None**. To completely disable the sweep settling delay for a particular analysis tool (instrument), enter **0.00** as the value in the Delay field and set the Algorithm to **None**.

For Time Sweeps where it is desired to make as many measurements per second as possible, the Delay value should be set to **0.00** and the Algorithm selection should be **None**.

All settling functions must be disabled when performing an External Sweep which has a continuously moving independent variable (a glide sweep). See **Some Hints for External Sweeps** on page 426.

Algorithm Selection

In addition to setting a Delay time, you can also select one of three Settling Algorithms (or **None**) to evaluate the stability of your signal.

The three Settling Algorithms are:

- **Exponential**

Exponential usually provides consistent results in the minimum time. Since typical device transients tend to fall off in an exponential fashion, this can be a very useful settling algorithm, especially for analog signals.

■ Flat

Flat provides highly repeatable results, but often requires more settling time than **Exponential**. **Flat** is the default algorithm selection.

■ Average

Average is useful for noise measurements and for other random or aperiodic signals.

The algorithms look to the Settling panel for values to use in making their evaluation of signal settling. **Average** uses only the **Points** value; **Exponential** and **Flat** also look to the values set in the **Tolerance** and **Floor** fields.

As mentioned in **Settling Delay Time**, above, all measurements taken during the initial **Delay** period are discarded before 2700 series begins evaluating the signal with any of the selected algorithms.

Exponential Settling Algorithm

The **Exponential Algorithm** reports a data point after a certain number of readings (the value set in the **Points** field) fall within an exponential settling criteria envelope, an example of which is shown in black in Figure 340. The shape and calibration of this envelope are determined primarily by the value set in the **Tolerance** field. The **Floor** field, which is explained below, keeps the size of the envelope from decreasing to zero as the value being measured becomes very small.




Figure 340. Successfully settled reading using Exponential method, where **Tolerance** is set to 1 % and **Points** is set to 5.

To satisfy the **Exponential** criteria, a measurement N must agree with the immediately preceding measurement $N - 1$, within the **Tolerance** value; and must also agree with measurement $N - 2$, within twice the **Tolerance** value; and with measurement $N - 3$, within four times the **Tolerance** value, and so on. This relationship must hold for the number of consecutive measurements set in the **Points** field. Figure 340 shows a series of points which have fallen within the specified Exponential settling criteria envelope.

Flat Settling Algorithm

The **Flat Algorithm** reports a data point when the signal is so stable that the difference between any two consecutive readings, when expressed as a percentage, is:

- less than the percentage value specified in the **Tolerance** field, and
- that this degree of stability is held through the number of readings specified in the **Points** field.

The settling criteria envelope for the **Flat** algorithm is a pair of horizontal lines at the plus-and-minus tolerance percentage values. The gray lines on Figure 340 illustrate the **Flat** envelope for a 1% **Tolerance** setting.

The **Flat** algorithm guarantees that the signal transients have been settled to the specified **Tolerance** for some time. This tends to take longer than the **Exponential** algorithm.

Average Settling Algorithm

The **Average** settling algorithm simply takes the mathematical average of the number of consecutive measurements entered in the **Points** field and reports the result as a data point. The Average algorithm is particularly useful when the signal is fundamentally noisy and might never settle within a practical tolerance.

Settling Tolerance

Settling Tolerance represents the amount of variability you are willing to accept from test to test. A tolerance of 0.1 % (about 0.01 dB) may be appropriate for frequency response tests on a DUT with excellent characteristics; at the other extreme, tolerances of 10 % to 25 % may be necessary to obtain data under noisy conditions. The default value of 1 % is a good starting place.

Settling Floor

When working near the very bottom of the dynamic range for a particular 2700 series analysis tools, the difference between two adjacent values or quantization levels can be large compared to the criteria in the settling algo-

rithm. At levels greater than a few percent of full scale, the value set in the **Tolerance** field is normally the determining parameter, but close to the bottom of a measurable range another technique is needed to keep the settling from slowing down the sweep or even stopping it entirely.

The **Floor** setting provides this protection. Whenever the value set in the **Floor** field is larger than the product of the measured signal multiplied by the **Tolerance** percentage, the algorithm uses the **Floor** value instead of waiting for the signal to satisfy the **Tolerance** criteria.

For example, with a **Tolerance** of **1%** and a **Floor** setting of **1 μ V**, the **Floor** takes over when the measured signal drops below **100 μ V**.

The default values of **Floor** for each meter are chosen to be approximately the resolution of that meter on its most sensitive range. Since resolution increases as the reading rate slows, it may be appropriate to change the default **Floor** values when the reading rate is fixed at a specific value.

Settling Issues for Specific Analysis Tools

Settling for each meter in 2700 series is independently controlled by its own row of fields on the Settling panel.

Audio Analyzer Reading meter settling values are stored independently for each Audio Analyzer mode. For example, the settling values for **Audio Analyzer Amplitude A** and **B** are independent of the settling values for **Audio Analyzer THD+N Amplitude A** and **B**.

The Audio Analyzer **Phase** mode has no **Tolerance** field. The acceptable variability for this meter should be entered in the **Floor** field in degrees. An entry of **+10.00 deg**, for example, sets a 10-degree-wide window of acceptance for the selected algorithm to use.

Timeout

It is possible with extremely noisy signals that the instability of the measured parameter is consistently greater than the **Tolerance** value entered on the Settling panel, and that it is impossible to satisfy the Settling algorithm and get a settled reading.

The **Timeout** control exists to keep your sweep from running slowly or even locking up under these conditions. If a settled reading cannot be made within the period of time entered in the **Timeout** field, 2700 series will calculate the average value of the last 6 measurements, enter that value as a data point and move on to the next sweep step.

The default **Timeout** value (per step) is **4.000** sec.

“Timed-out” points are marked with a white “T” at the top of the graph, above the plotted point. In the Data table, each timed-out point is indicated with the letter T following the data.

The Log File can also indicate timed-out data with several notices. See **The Log File**, page 522.

Chapter 19

Graphs

The graph is a central feature of the 2700 series test and measurement system. As mentioned in Chapter 18, the functions of the Graph panel and the Sweep panel are closely related.

Graph and Sweep Interaction

To configure and initiate any measurement to be plotted on a graph, you must go first to the analysis tool panel and then to the Sweep panel. Whether you are making real-time Analog Analyzer measurements or batch-mode FFT measurements, the Sweep panel is the control center.

Besides collecting the data for the graph display, the Sweep panel also sets the graph scaling and calibration; that is, the number and spacing of the vertical and horizontal graticule lines, and the X-axis and Y-axis numerical calibration and unit domain. To change these graph parameters you must go to the Sweep panel.

The Graph Panel

This chapter describes the display controls available on the Graph panel.

The 2700 series Graph panel is available by selecting **Panels > Graph** from the Menu bar or by clicking the **Graph** icon on the toolbar.



The Graph panel plots the **Source** and **Data** information provided by the Sweep panel as X-Y relationships and provides a number of controls to modify the display, examine the traces with cursors, and add labels, comments and descriptive legend information both to the graph and to exported and printed versions.




Figure 341. The 2700 series Graph panel.

The Graph panel itself can be resized to any size or aspect ratio you prefer by dragging the borders with the mouse pointer. Similarly, the **Legend** and **Comment** areas within the Graph panel can be adjusted for size.

Zoom




Figure 342. Dragging the mouse pointer across the graph to zoom.

You can zoom in on any area of the graph by dragging the mouse pointer diagonally across the area you would like to magnify. Dragging the mouse pointer will draw a rectangular marquee surrounding the area, as shown in Figure 342. When you release the mouse button the graph will re-size itself to the

rectangle you have drawn. You can perform this operation repeatedly to zoom further and further in.


When you are zooming into graphs of batch-mode FFT measurements, the **Sweep Reprocess Data (Ctrl-F6)** command is normally sent to the Analyzer, requesting new data at the new sizing, so that the zoomed view will have the maximum possible resolution. This automatic reprocessing can be disabled on the Configuration panel by unclicking the **Reprocess FFT data on zoom**.

*NOTE: The **Sweep Reprocess Data** command is only effective if the acquired signal is still in the DSP memory. A test file loaded from disk, for example, will only contain the Graph data of the FFT being viewed when the test was saved, and increasing the resolution during a zoom is not possible.*

The Graph Options Menu

Click the right mouse button anywhere within the graph itself and the Graph Options menu will appear at the mouse pointer. This menu provides a number of graph display and control options, as shown in Figure 343.

Figure 343. Graph Options menu.



Zoomout

Choose **Zoomout** to reverse the last **Zoom** operation and reduce the magnification of the graph. If you have **Zoomed** repeatedly, clicking **Zoomout** repeatedly will back you out of your **Zoom** operations, one at a time.

If you are viewing a batch-mode FFT, the **Zoomout** command will also send the **Sweep Reprocess Data** command, following the same behavior as with the **Zoom** command.

Zoomout to Original

Choose **Zoomout to Original** to return to the original graph sizing and coordinates in one step.

If you are viewing a batch-mode FFT, the **Zoomout to Original** command will also send the **Sweep Reprocess Data** command, following the same behavior as with the **Zoom** and the **Zoomout** commands.

Optimize

The **Optimize** graph option is a method of zooming or magnifying the scale of the graph relative to the signal currently on the graph. An optimized graph will replot with new Y-axis coordinates for a maximum-resolution display of the signal.

Although you can optimize your graph at any time, it is usually most effective to optimize after the conclusion of a sweep. There are four **Optimize** choices:

- **Optimize Individually.**

This option is only available if both Y-axes are in use, displaying data mapped to the **Data 1** or **Data 2** coordinates. **Optimize Individually** sets the left Y-axis calibration for the best display of the **Data 1** set of values, and sets the right Y-axis calibration for the best display of the **Data 2** set of values.

- **Optimize Together.**

This option is only available if both Y-axes are in use displaying data mapped to the **Data 1** or **Data 2** coordinates, and use the same unit domains. **Optimize Together** sets both the left and right Y-axis and calibration for the best display of the entire range of values. This feature provides the ability to graphically compare traces (of the same unit domain) plotted against both left and right Y-axes.

- **Optimize Left Only.**

This option is only available if the left Y-axis (displaying **Data 1** and other data plotted against the **Data 1** axis) is in use. **Optimize Left Only** sets the left Y-axis calibration for the best display of the **Data 1** set of values.

- **Optimize Right Only.**

This option is only available if the right Y-axis (displaying **Data 2** and other data plotted against the **Data 2** axis) is in use. **Optimize Right Only** sets the right Y-axis calibration for the best display of the **Data 2** set of values.

Unlike the **Zoom** features, the **Optimize** options do not issue a **Sweep Reprocess Data** command to the DSP for batch-mode FFT measurements. **Optimize** only operates on the graph display and does not plot new data.

*NOTE: There is no need to reprocess batch-mode measurements after **Optimizing**. Reprocessing is necessary when the X-axis scale is changed; **Optimize** only re-scales the Y-axis.*

To return to your original display, click **Zoomout** or **Zoomout to Original**.

Copy to Sweep Panel

It is often the case that after zooming or optimizing your graph, you decide that you should re-run your sweep with Start, Stop, Top and Bottom settings which correspond to the coordinates on your resized graph. A shortcut to this adjustment is provided with the **Copy to Sweep Panel** selection. **Copy to Sweep Panel** takes the modified graph calibrations provided by **Zoom** or **Optimize** and writes these as settings in the Sweep panel. A new sweep will create a new graph with the X and Y-axis calibrations from the zoomed or optimized graph.

Display Cursors

The 2700 series provides two cursors as aids in interpreting your graph. On the Graph Options menu, click **Display Cursors**. A green vertical line will appear, with two display boxes at the top and the bottom of the graph, adjacent to the cursor position.

The green line is actually two cursor lines on top of each other. The value in the bottom display box on the graph is the X-axis position of the cursors. The value in the top display box is the difference between the X-axis positions of the two cursors. Since the cursors begin in the same position, the initial difference is **0.00000**.




Figure 344. Graph Cursors on deselected traces.

You can move the cursors by placing the mouse pointer on the green line and dragging sideways. The mouse pointer changes from the standard arrow to a dragging pointer, which indicates by a number whether you are dragging cursor 1 or cursor 2. When you have dragged the cursors off one another, each cursor is assigned its own X-axis display box.

The cursors are shown as vertical lines whenever no **Data** traces are selected. To select a trace, click on the corresponding row shown in the graph legend; the legend row then appears highlighted to indicate that it is selected. See **Graph Legend** later in this chapter on page 445. The selected trace will be displayed as a thicker line, and the cursors will be assigned to that trace, displayed as crossed circles rather than vertical lines. The crossed circles can be dragged along the trace with the mouse pointer.




Figure 345. Graph Cursors on a selected trace with graph legend highlighted.

To deselect a trace, click the selected row a second time. Click in the **Data** or **Axis** cells for deselection to take effect.

When a trace is selected, the Y-axis values at both cursor intersections are shown in new display boxes at the left side of the graph. A new display box also appears at the top of the graph, showing the difference between the two cursor Y-axis values.

You can also move the cursors on the graph using the keyboard. When the graph window is selected (click anywhere in the graph), the left and right arrows move a cursor horizontally across the trace. To select the other cursor, press an arrow key while holding the **SHIFT** key depressed, then move the cursor as before.

To move the cursors to another trace, press the up or down arrow keys.

One or both cursors can be deselected entirely, or the two cursors can be assigned to different traces. In the **Legend** box, there are two columns labeled **Cursor 1** and **Cursor 2**. The data in these columns are the Y values for that particular cursor position. Two of the cells in the Cursor columns also have an asterisk (*) leading the numeric values. This asterisk indicates the cursor assignment.




Figure 346. Graph Cursors 1 and 2 on different traces.

To reassign one cursor to a different trace, first click the **Cursor 1** or **Cursor 2** column header, which will change to read **Select**. The entire column will be highlighted. Then, in that column, click the cursor cell in the row that corresponds to the trace to which you would like to assign the cursor.

To unassign cursors, select a cursor column as in the previous paragraph and click on the cell displaying the “cursor selected” asterisk. The cursor for that trace will be unassigned.

Cursors may be assigned to different traces only if the two traces have compatible parameters or unit domains.

If the graph is a nested sweep, the **Source 2** value for the selected trace is shown in a display box at the top of the graph.


Scroll Bars

If you have zoomed to a particular graph region and would like to view another region, open the Graph Options menu and click **Scroll Bars**. This provides an easy way to move around a graph which extends beyond the Graph panel window.

If you don't need to scroll, click again on **Scroll Bars**. The scroll bars will disappear and the graph will be displayed slightly enlarged.

Title and Labels

Figure 347. Graph Titles and Labels dialog box.



You can modify or add titles and labels to your graph. On the Graph Options menu, click **Title and Labels**. A dialog box will appear for you to make your entries. The **Company Name** setting has its source in the 2700 series Configuration panel, where you can enter a company name or other information.

Comment

You can optionally enter comments in the **Comment Edit** box, which is displayed on the Graph panel below the **Graph Legend**. On the Graph Options menu, click **Comment** to view the **Comment Edit** box on screen.

Your comments will always print at the bottom of a tabular data printout (**File > Print > Data**). When printing a graph (**File > Print > Graph**), you have the option of printing the comments or not, depending on your selections on the **Page Setup** dialog box, discussed on Page 484.

New Data

To clear the graph and the Data Editor, click **New Data** in the Graph Options menu. This has the same function as the command **File > New > Data**. This command actually removes the data from memory, not just from the display, and cannot be undone.

Graph Buffer

Figure 348. Graph Buffer commands.



The Graph Buffer is a dedicated display memory in which you can store a trace (or set of traces) as a reference, and then recall the reference for comparison to a graph of current data. When you click Graph Buffer a small submenu appears with these choices:

- **Store Trace**

Click **Store Trace** to put the traces currently on the Graph panel into the Graph Buffer memory. You may also use the keyboard combination **ALT+F8**.

- **Recall Trace (Hide Trace)**

This choice toggles between **Recall Trace** and **Hide Trace**. The stored reference trace appears in the color gray on the screen, and can be switched on and off with this command. You may also use the keyboard shortcut **F8** as a toggle.

- **Delete Trace**

Click **Delete Trace** to clear the Graph Buffer memory. You may also use the keyboard combination **CTRL+F8**.

This feature allows you to use a measurement of a specific unit or condition as a visual reference for comparison or adjustment of other units.

Reference traces are retained and properly plotted even if you change graph scaling and calibration, including the use of zooming and optimization. Units of measurement can be changed as long as the unit domain remains the same (volts to watts to dBu, for example).

Reference traces are *NOT* retained through changes between analog and digital domains, or when plots are changed from absolute units to ratio units.

Graph Legend

Sweep	Trace	Color	Line Style	Thick	Data	Axis	Comment	Cursor1	Cursor2
X 1	1	Magenta	Dot	2	DSP Anlr.Level A Left		10.60 FFS	10.60 FFS	
X 1	2	Yellow	Solid	3	DSP Anlr.Level B Right		16.04 FFS	16.04 FFS	
X 2	1	Blue	Dash DotDot	7	DSP Anlr.Level A Left		*12.75 FFS	*12.75 FFS	
X 2	2	Red	Solid	1	DSP Anlr.Level B Right		11.06 FFS	11.06 FFS	
X 3	1	Cyan	Dash Dot	2	DSP Anlr.Level A Left		11.04 FFS	11.04 FFS	
X 3	2	Magenta	Solid	1	DSP Anlr.Level B Right		4.268 FFS	4.268 FFS	

Figure 349. The Graph Legend.

On the Graph panel immediately beneath the graph itself is a display called the Graph Legend. The Legend displays one row for each graph trace in memory, showing information about the display of that trace and providing drop-down lists to modify some of the display parameters. If a limit file has been loaded, the limit traces appear in the Legend as well.

The Legend columns are:

- (No Title)

The leftmost column selects which **Data** rows are plotted on the graph. Selected rows show an “X” in this column. The title box for this column is blue when the Graph Legend is selected and gray otherwise.

- Sweep

When more than one sweep is in memory (in cases of appended sweeps or nested sweeps), this column identifies the trace or traces associated with each sweep. The sweeps are numbered sequentially in the Graph Legend.

- Trace

When more than one set of data are associated with a sweep (in cases where **Data 2** through **Data 6** are used), each data set will produce an additional trace. The traces are numbered sequentially in the Graph Legend for each sweep. The trace numbers correspond with the sweep data numbers.

- Color

The **Color** column shows the color currently assigned to each trace, and offers a drop-down list so that you can change a trace’s color.

- Line Style

The **Line Style** column shows the line style currently assigned to each trace, and offers a drop-down list so that you can change a trace’s line style.

- Thickness

The **Thick** column shows the line thickness currently assigned to each trace, and offers a drop-down list so that you can change a trace’s line thickness. Thicknesses greater than **1** can only be applied to **Solid** line style traces.

■ Data

The **Data** column shows the analysis tool (instrument) and parameter associated with that trace.

■ Axis

The **Axis** column shows whether the trace is calibrated and scaled on the left or right Y-axis.

■ Source 2

If **Source 2** is used (a nested sweep), the 2700 series analysis tool (instrument), parameter and value associated with that trace are shown in this column.

■ Cursor 1

If cursors are enabled, this column shows the value of the associated trace at its intersection with **Cursor 1**. An asterisk in the cell indicates that the cursor is assigned to that trace.


■ Cursor 2

If cursors are enabled, this column shows the value of the associated trace at its intersection with **Cursor 2**. An asterisk in the cell indicates that the cursor is assigned to that trace.

The **Source 2** column and the **Cursor 1** and **Cursor 2** columns will only be displayed if these options are in use.

The Graph Legend box can be resized by dragging its top border with the mouse pointer. If the list of traces in the Legend is too long to display, scroll bars will appear on the Legend box for navigation. Column widths can also be resized by dragging the border between column headings with the mouse pointer.

Figure 350. Graph and Graph Legend showing data trace and upper and lower limit traces.



Graph Legend / Data Editor Linkage

The display of information in the graph Legend is visually linked with the tabular sweep data display shown in the Data Editor. For appended or nested sweeps, this can help in identifying which line shown in the Data Editor is associated with a particular trace.




Figure 351. Graph Legend and Data Editor, showing the linked relationship of the typefaces used in the two displays, for a nested sweep.

This linkage in the displays identifies the correspondence between data and traces in two ways:

- Normal Type or **Bold Type**.

Alternate sets of traces in both the graph Legend and the Data Editor are displayed in alternating **bold** and normal typefaces. A **bold typeface** is used for odd-numbered sets of traces; a normal typeface is used for even-numbered sets of traces.

- Data Editor scrolling.

The Data Editor automatically scrolls so that the set of data corresponding to the trace selected in the Graph Legend is shown at the top of its window.

Trace Colors

2700 series traces are normally displayed in one of six colors:

- cyan
- green
- yellow

- red
- magenta, and
- blue.

These colors can be automatically assigned by the control software according to the type of sweep and the settings made on the Configuration panel. The order of these colors is called the “color cycle,” and when the control software automatically increments colors it always does so following this order. The cycle wraps back from blue to cyan when the end of the cycle is reached.

The color gray is also available and can be manually assigned to any trace. However, gray is not part of the color cycle and is normally reserved as the color for reference traces recalled from the Graph Buffer.

Color Assignment for a New Test

A new test inherits the color assignments of the previously run test, except when the new test is opened immediately after control software launch. In that case, the color cycle is reset and the new test begins with cyan for **Data 1**.

Color Assignment for Multiple-Data-Set Sweeps

In a single sweep with more than one set of **Data** values being plotted, by default the control software assigns the **Data** traces colors according to this pattern:

Data 1	cyan
Data 2	green
Data 3	yellow
Data 4	red
Data 5	magenta
Data 6	blue

If the **Reset color cycle** checkbox in the Configuration panel is **checked**, each new sweep will assign colors to the Data sets in this way, whether or not you have made manual color changes in the Graph Legend.

If the **Reset color cycle** checkbox in the Configuration panel is **unchecked**, the control software will use this assignment of colors initially. If you manually change any color-to-**Data** assignment, the software will maintain your new color assignments throughout subsequent sweeps. See Chapter 28, **Configuration**.

Color Assignment when Opening a Saved Test

When a test file is opened, the first display will be the traces from the loaded test using the colors saved in that file. If a new sweep is run, the colors assigned to the traces depend on a Configuration setting:


- If the **Use Test Colors Only** checkbox on the **Graph** tab of the Configuration panel is **unchecked**, the trace(s) of a new sweep will be assigned colors according to the setting of the **Reset color cycle** checkbox, described above.
- If the **Use Test Colors Only** checkbox is **checked**, each new sweep will maintain the trace colors loaded from the test.

See Chapter 28, **Configuration**.

Color Cycling in Nested and Appended Sweeps

When nested or appended sweeps are made, each **Data** trace in each sweep follows the color cycle pattern, picking up at the place in the pattern where the same **Data** trace of the previous sweep left off. For example, a **Data 1** trace which was green in a particular sweep would be displayed in yellow in the next appended or nested sweep.

Figure 352. Traces automatically sequence through the color cycle for appended data and nested sweeps.



When a test file is opened, the first display will be the traces from the loaded test using the colors saved in that file. If new sweeps are appended to

this test by sweeping with the **Append** box checked, the colors assigned to the appended sweeps traces depend on a Configuration setting:

- If the **Use Test Colors Only** checkbox on the **Graph** tab of the Configuration panel is unchecked, the trace colors will rotate through the color cycle, using the test colors as the starting point.
- If the **Use Test Colors Only** checkbox is checked, color cycling is disabled and each appended trace will maintain the trace color loaded in the test.

See Chapter 28, **Configuration**.

Color Cycling with Appended Files

When a current sweep is appended with sweep data from disk using the **File > Append** command, the colors assigned to the sweep traces from the appended file depend on a Configuration setting:

- If the **Cycle Trace Colors** checkbox on the **Graph** tab of the Configuration panel is **unchecked**, the appended file trace colors will come in without change.
- If the **Cycle Trace Colors** checkbox is **checked**, the colors of the traces appended from disk will move through the color cycle, using the last set of traces currently in memory as the starting point.

See Chapter 28, **Configuration**.

Graph Keyboard Shortcuts

Several graphing and graph-related functions are available as keyboard shortcuts.

Graph Only

These functions only affect the graph display and do not re-transform or re-acquire batch data.

- **Ctrl-F6** (for FFT-based, batch mode analysis tools: Spectrum Analyzer, Digital Interface Analyzer, Multitone Analyzer, MLS Analyzer).
Graphs the transform results currently in DSP memory without performing a new transform.
- **F7**
Graphs the data currently in computer memory, comparing it to limits if limits exist.
- **Alt-F8**
Stores the present trace or traces to the Graph Buffer memory.

- **F8**
Displays the trace or traces currently stored in the Graph Buffer memory.
- **Ctrl-F8**
Deletes any trace or traces in the Graph Buffer memory.

Re-Transform and Graph

This function re-transforms and re-graphs batch data but does not make a new acquisition.

- **F6** (for FFT-based, batch mode analysis tools: Spectrum Analyzer, Digital Interface Analyzer, Multitone Analyzer, MLS Analyzer).
Performs a new transform on the acquired data and graphs the results.

Re-Acquire, Re-Transform and Graph

These functions acquire new data and graph it.

- **F9**
Starts a new Sweep; equivalent of Sweep **Start** or clicking the **Go** button.
- **Ctrl-F9**
Starts a new Sweep while retaining previous data, appending the new sweep to the old; equivalent of clicking **Go** when **Append** box is checked.
- **Alt-F9**
Starts a new Sweep in repeating mode; equivalent of clicking **Go** when **Repeat** box is checked.

Chapter 20

Bar Graphs

Each 2700 series analyzer tool has a number of settings and readings on its control panel; the Analog Generator, for example, has fields to set frequency and amplitude, and the Analog Analyzer has fields to read these parameters.




Figure 353. Typical Bar Graph reading, with optional comment.

Bar Graphs are graphical display panels that can be associated with settings and readings for easier control and observation. Up to 32 Bar Graphs can exist simultaneously, associated with any combination of instrument parameters. Bar Graphs can be set to any size.

NOTE: Bar Graphs are not related to the graphs controlled by the Sweep panel and displayed on the Graph panel.

Creating a Bar Graph

A Bar Graph can be associated with any field that sets or reads a signal parameter.



To create a Bar Graph, click on the setting or reading field to be associated with the Bar Graph, then either click on the **Bar Graph** icon or choose **Panels > Bar Graphs > <new>**. A new Bar Graph will be created and associated with the parameter that you highlighted. If no appropriate field was highlighted, the default new Bar Graph association is with the Analog Analyzer **Amplitude** reading. You can change the association at any time using the Bar Graph Setup panel, discussed below.

Figure 354. Creating a Bar Graph by right-clicking the mouse.




Another way to make a new Bar Graph is to right-click the setting or reading field in which you are interested, and click **Create Bargraph** from the menu which appears.

Bar Graph Setup

Click the **Setup** button to access the Bar Graph Setup panel. The **Setup** button may not be visible if the Bar Graph panel is sized too small.

Figure 355. Bar Graph Setup panel.



At the top of the Bar Graph Setup panel is a Connection browser, similar to the instrument browsers at **Source** and **Data** in the Sweep panel. You can select the measurement panel and setting or reading parameter for this Bar Graph using the Connection browser.

Checkboxes allow you to **Display Digits Only** or toggle the **Comment** display.

Target Range displays a dark bar on the Bar Graph to give a visual indication of a range of interest. You can turn the Target Range display on or off by checking the **Range On** checkbox. Set the extents of the Target Range in the **Lower** and **Upper** fields in this area.

Target Range is enabled only on a Bar Graph configured for readings.

In the Axis area you can set up the range of the Bar Graph display, or click **Autoscale** to let the control software scale the display in response to the signal.

For most parameters you can make the choice between a logarithmic or linear scale by clicking the **Log** or **Lin** option buttons.

The **Increment** field is only available for settings, and enables you to specify the minimum increment by which the setting can be changed.

Using a Bar Graph for Readings

To use a Bar Graph for readings, you must create the bar graph while reading field is highlighted, or you must select an analysis tool reading parameter from the Connection browser in the Bar Graph Setup panel.




Figure 356. Typical Bar Graph for readings, with optional comment.

Bar Graph readings are displayed as green digits and also as a horizontal magenta bar. The bar will respond to the signal reading in real time, simulating an analog meter. You can remove the bar display by selecting **Display Digits Only** on the Setup panel.

When the magenta bar moves to show a changing signal, a narrow gray horizontal bar will appear on the magenta bar to indicate the history of minimum and maximum readings. This can be reset by clicking the **Reset** button or the **Reset Min/Max** button on the Setup panel.

You can also add a Target Range display bar to a readings Bar Graph. Target Range displays a dark bar over the magenta bar to give a visual indication of a range of interest. Refer to the previous **Bar Graph Setup** topic for information on setting a Target Range.

Using a Bar Graph for Settings

To use a Bar Graph for settings, you must create the graph while a setting field is highlighted, or you must select a setting parameter from the Connection browser in the Bar Graph Setup panel.




Figure 357. Typical Bar Graph for settings.

Bar Graph settings are displayed as green digits and also as a horizontal white bar with a slider control. Moving the slider along the bar will adjust the signal setting in real time, simulating an analog control. You can remove the slider bar display by selecting **Display Digits Only** on the Setup panel.

You can move the slider by dragging it with the mouse pointer, or, if the slider has been most recently selected, by using the left and right keyboard arrows.

The minimum setting step can be changed by entering a new value into the **Increment** field on the Bar Graph Setup panel.

When the slider has been moved, a blue horizontal bar will appear on the white bar to indicate the history of minimum and maximum settings. This can be reset by clicking the **Reset** button or the **Reset Min/Max** button on the Setup panel.

Chapter 21

Editing Data and Setting Limits

The Data Editor

Any data collected by the Sweep panel, including stimulus and response data from real-time sweeps, and bin centers and values in batch-mode FFTs, are temporarily stored in memory during a test session. These data can be replaced, deleted, appended to, stored on disk, and so on. Data which have been stored on disk as an .ada file or within a test can be loaded to become the current data in memory.

The Data Editor panel gives you a detailed view of the current data in a table, much like a spreadsheet page. The Graph panel uses these values to draw the traces on the X-Y graph display, and if you change a value in a Data Editor cell the corresponding point on the graph will move to the X-Y coordinate.


Certain data will not graph, including a single point sweep, a sweep which contains reverses of direction in **Source 1** values, or, in graphs where two unit domains already occupy the left and right Y-axes, another data set expressed in a third unit domain.

The Data Editor, however, shows all the data in current memory, even data which cannot be plotted on the graph. If you have accidentally configured a sweep which will not graph, the Data Editor allows you to verify that the sweep has actually executed, and to examine the data to find the error.

The Data Editor is closely tied to both the Sweep and Graph functions, which are discussed in Chapters 18 and 19.

The Data Editor Panel

Figure 358. The Data Editor panel.



	0 = Gen.Freq	1 = Gen.Ampl A	2 = Anlr.Ampl
21	1.00000 kHz	-5.000 dBV	-5.072 dBV
22	861.000 Hz	-5.000 dBV	-5.103 dBV
23	741.250 Hz	-5.000 dBV	-5.174 dBV
24	638.000 Hz	-5.000 dBV	-5.337 dBV
25	549.250 Hz	-5.000 dBV	-5.709 dBV
26	472.750 Hz	-5.000 dBV	-6.516 dBV
27	407.000 Hz	-5.000 dBV	-8.035 dBV
28	350.500 Hz	-5.000 dBV	-10.410 dBV
29	301.750 Hz	-5.000 dBV	-13.514 dBV
30	259.750 Hz	-5.000 dBV	-17.069 dBV
31	223.500 Hz	-5.000 dBV	-20.818 dBV
32	192.500 Hz	-5.000 dBV	-24.682 dBV
33	165.725 Hz	-5.000 dBV	-28.559 dBV
34	142.675 Hz	-5.000 dBV	-32.481 dBV
35	122.825 Hz	-5.000 dBV	-36.388 dBV
36	105.725 Hz	-5.000 dBV	-40.304 dBV
37	91.0250 Hz	-5.000 dBV	-44.214 dBV
38	78.3750 Hz	-5.000 dBV	-48.096 dBV
39	67.4750 Hz	-5.000 dBV	-51.933 dBV
40	58.0750 Hz	-5.000 dBV	-55.783 dBV
41	50.0000 Hz	-5.000 dBV	-59.733 dBV



The 2700 series Data Editor is available by selecting **Panels > Data Editor** from the Menu bar or by clicking the **Data Editor** icon on the toolbar.

Columns

Data Editor columns cannot be edited. You cannot add, delete, move or rename a Data Editor column. These columns correspond to the **Source** and **Data** settings in the Sweep panel; to add or remove a column you must reconfigure the sweep.

The column width can be adjusted by dragging the column header delimiters with the mouse pointer.

Rows

Data editor rows correspond to Sweep measurement points (or, in FFT measurements, bin centers). You may add or remove Data Editor rows. Adding or removing rows changes the data in memory, and the graph and stored data files will reflect your modifications.

Data

The settings and reading values shown in the Data Editor cells can also be edited. Editing the value in a cell changes the data in memory, and the graph and stored data files will reflect your modifications.

The displayed values in the cells can appear in a normal type font, in a bold font, and, under some conditions, in a red font.

The normal and **bold** typefaces alternate between sweeps (or changes in sweep direction) for easy identification of data sets when performing appended or nested sweeps. These normal/**bold** designations also correspond to the normal/**bold** designations in the Graph Legend display. The Data Editor will also scroll to the first data point in a trace when the row for that trace is selected in the Graph Legend. See **Graph Legend / Data Editor Linkage**, page 446.

Data values may also be flagged with letters to indicate special conditions:

- **B** (Bad) indicates invalid data.
- **U** (Upper) indicates that the measurement value has exceeded the Upper limit. This condition is also marked by a red typeface. See **Limits** on page 462.
- **L** (Lower) indicates that the measurement value has passed below the Lower limit. This condition is also marked by a red typeface. See **Limits** on page 462.
- **T** (Timeout) indicates that settling has timed out for this measurement. See **Timeout** on page 433.
- **R** (Regulation) indicates that the attempt to regulate this data reading was unsuccessful. See **Regulation** on page 511.

Graph cursor locations are indicated in the Data Editor by highlighting the cursor cells with a light gray background.

Editing the Current Data in Memory

In the Data Editor window, you can enter or change data in any cell by selecting the cell with the mouse pointer and entering or deleting the value.

For other editing options, right click within the Data Editor window and the Data Editor menu will open and provide the following choices:

- **New Data**
New Data erases all the information in memory and cannot be undone.
- **Insert Row Before**
- **Insert Row After**

- **Add Row to the End** will add one row to an empty data table, or will add one row below the last existing row.
- **Delete Row**
- **Select all rows**
- **Unselect all rows**

Saving 2700 Series Data

The information in the Data Editor is saved on disk, along with other information, with the 2700 series test file (*.at27). When a test is loaded, the test information becomes the current data and is viewable in the Data Editor.

The current data shown in the Data Editor can also be saved in several types of data-only files, which the 2700 series uses for different purposes, as follows:

- **Data (.ada) file.** Data files can be reloaded as current data.
- **Limit (.adl) file.** Limit files can be attached to a sweep to provide upper and lower pass/fail limits against which to compare the current measurements. Limits are discussed below.
- **Sweep (.ads) file.** Sweep files are used to store data for Table Sweeps, which are sweeps that get their **Source** data from a table rather than Sweep panel settings. See **Table Sweeps**, page 418.
- **EQ (.adq) file.** EQ files are used to modify sweep measurements by computing the sweep data against the data in an EQ table. See **Compute Equalize**, page 478.

Setting Limits

You may want to compare a graph of a DUT's performance with an ideal device or with a published standard. Of course, you can always append one graph to another and make a visual comparison, but the 2700 series provides a more powerful technique: setting limits and performing a pass/fail test.

To set limits using the 2700 series, you must attach a limit file to your sweep. See Chapter 18 for a detailed discussion of sweeps.

When a measured sweep value exceeds a set limit value, the measurement is flagged as having failed the limit. This flag can be viewed in the Data Editor or reported in more detail in the Log file. If your pass/fail test is part of an automated AP Basic procedure, the flag can be reported, or it can be used as a trigger for some other command. A limit can also be configured to immediately stop the sweep on failure. See **Actions Upon Failure**, page 466.

Making a Limit File

Any 2700 series data which can be viewed in the Data Editor or saved as a data file can be a Limit File. This enables you to use actual measured data from a test on one DUT as the limits or standards for a test on a different DUT.

Alternatively, you may want to use published standards or arbitrary values as your limits. In these cases you can enter the data manually into the Data Editor, or edit an existing Limit File in the Attached File Editor, or even create limit values in a spreadsheet or text editor program and import the file into the 2700 series control software.

As an example we will create a limit file in the Data Editor.

First set up a new sweep with two data traces. The default sweep starts with only one trace, **Data 1**; to add a second trace go to the **Data 3** browser and set it to **DSP Analyzer Level B**. Click **Single Point** and **Go**; this will inform the Data Editor that you are using two data columns.

Open the Data Editor. The display will have three column headings and one row of data, the single point sweep you just performed. Click the right mouse button to open the Data Editor menu, and add five more rows using the **Add Row to the End** command.

To enter a value just set the cursor in a cell and type. To make a complete trace, you must enter all the **Source** and **Data** values necessary to describe the limit you want. If the Graph panel is open, you can view the trace as you create it

Create a limit trace by entering the values shown in Figure 359.


Figure 359. Creating Limit Data in the Data Editor.



	0 = DGen.Freq	1 = DSP Anlr.Level	2 = DSP Anlr.Level
0	20.0014 Hz	+10.000 dBu	-10.000 dBu
1	199.990 Hz	+10.000 dBu	-10.000 dBu
2	200.000 Hz	+7.000 dBu	-7.000 dBu
3	1.99990 kHz	+7.000 dBu	-7.000 dBu
4	2.00000 kHz	+13.000 dBu	-13.000 dBu
5	20.0000 kHz	+13.000 dBu	-13.000 dBu

This will produce the limit traces shown in Figure 360.

Figure 360. Limit Traces shown on Graph



When you are satisfied with the limits you have created, save the data as an AP limit file using the command **File > Save As > Limit Data**.

When making a limit file, there are some constraints you must remember:

- The **Source 1** column of the limit data must correspond with the **Source 1** parameter of the sweep the file will be attached to. For example, a frequency-sweep test will have generator or FFT frequency as **Source 1**, and any limit files used with this test must also have frequency at **Source 1**.
- There must be a **Data** column heading for each limit.
- The units of measurement for each limit data column must be in the same unit domain as the corresponding data in the sweep the file will be attached to.

You can save upper and lower limits in two separate files; or, you can save upper and lower limits as two different data columns in the same file.


If two measurements are to be compared against exactly the same limits, as is often done in stereo sweeps, the same data column can be used as a limit for multiple measurements. If you have checked the **Stereo Sweep** checkbox on the Sweep panel, the limit attached to **Data 1** will also be attached to **Data 3**. See **Stereo Sweeps**, page 416.

Attaching a Limit File

Limits are attached to specific data traces on a sweep. To attach a limit file, choose the data in your sweep that you would like to compare to a limit (**Data 1**, for example) and click the **Limit** button for that **Data**.

The Limit File Attachment dialog box will appear. Browse to the data file that contains the limit data you would like to use. You can select any type of AP data file, not just an “.adl” Limit file, as the source of your limit values.

Figure 361. Limit File Attachment dialog box.



You can attach upper limits, lower limits, or both. Just select a data file in the appropriate area of the dialog box. Check the box labeled **Upper and Lower Limit are from Same File** if you are using data from a single file for both upper and lower limits.

Once you attach a data file, a list of the available data columns in the file will be displayed in the list box under the file selection field. If there is more than one data column, you must indicate the column you would like to use as limit data for your sweep.

Using the Attached File Editor

Once a file is attached, you have the opportunity to edit the data in the file. Click on the **Edit Upper Limit** or **Edit Lower Limit** button to edit the attached file. The Attached File Editor will open.

Figure 362. The Attached File editor.

	Gen.Freq	**Data 1 upperlimit	Data 1 lowerlimit
0	50.0000 kHz	-30.000 dBV	-35.962 dBV
1	44.1500 kHz	-24.000 dBV	-30.629 dBV
2	39.0000 kHz	-18.000 dBV	-25.319 dBV
3	34.4500 kHz	-14.000 dBV U	-20.080 dBV
4	30.4250 kHz	-9.000 dBV U	-14.935 dBV
5	26.8500 kHz	-5.000 dBV U	-10.045 dBV
6	23.7250 kHz	-1.000 dBV U	-6.036 dBV

The Attached File Editor is very similar in appearance to the Data Editor (page 459), but the two windows have different functions. The Data Editor displays the data in memory, while the Attached File Editor displays the data in the upper or lower attached file. The Attached File Editor is also available from the Table Sweep dialog box (see page 418) and the EQ Curve dialog box (see page 74).

You can view and edit the attached limit data in the Attached File Editor. In the Attached File Editor display, the column corresponding to the limit data you have selected is marked with two asterisks (**).

Changes you make in the attached file values will not be effective until you save the file. To save a file from the Attached File Editor, close the editor window. A dialog box will open and prompt you to save the file. The file is always saved under its current filename, overwriting the previously saved file.

*NOTE: The commands on the File menu (**File > Save > Limit**, etc.) save the data in current memory, not the edited data in an attached file. Close the Attached File Editor to properly save this data.*

Actions Upon Failure

A pass/fail test fails when the measured data exceeds a limit value during a test. Depending upon the system settings and configuration, the 2700 series will indicate a limit failure in several ways:

- **Terminate Sweep**

Normally, the sweep will continue even if limits are exceeded. However, if you click the **Terminate Sweep on Failure** box on the Limit File Attachment dialog box, the sweep will end if a limit is exceeded.

- **Tabular Display Flags**

Any measurement that exceeds a limit will be marked with a **U** (for upper) or an **L** (for lower) in the Data Editor table. See **Data Editor**, page 459.

- **Log File Indicators**

If **Log Errors** is set in the Configuration panel, limit failures will be shown in detail, displaying **Source**, **Data** and **Limit** values and the amount and sign (+ or –) of the error for each limit failure. See **The Log File**, page 522.

More About Using AP Data Files

Data files include the four types listed on page 462. Data saved to any of these file types are maintained in an identical format; the extensions are different as an administrative aid to help you and the control software determine the intended purpose of a particular data file, sort your files meaningfully, and so on.

A consequence of this is that you can use an EQ file (.adq) for a Table Sweep, or a Data file (.ada) for setting limits.

This is particularly useful as it enables you to save all your data, including Sweep data, EQ and Limit data, in one file. You can then attach the file as a

Sweep Table or Limit or EQ file and select the appropriate data column from the list within the file browser.

Exporting Data

AP data files are binary files, and it is not possible to edit the files without using the Data Editor or the Attached File Editor. However, it is possible to export the current data in memory as an ASCII text file or as a Microsoft Excel spreadsheet.

The ASCII file contains AP data file header information and the data in a comma-delimited format. The filename extension for the ASCII file is *.adx. Choose **File > Export > ASCII**.

If you have Microsoft Excel installed on the PC, you can export the current data as an Excel spreadsheet, filename extension *.xls. Choose **File > Export > Excel**.

Importing Data

You can import data from a properly-formatted comma-delimited ASCII text file (filename extension *.adx) into the current test by choosing **File > Import > ASCII**. Importing a data file will overwrite the current data in memory.

The data in the file must be properly formatted, as shown in the example below.




Figure 363. ASCII version of an AP data file.

The Attached Files Viewer

Go to **View > Attached Files** to open the Attached Files viewer. This dialog shows all files attached to the current test in a hierarchical tree view.




Figure 364. The 2700 series Attached File Viewer.

Chapter 22

Performing Computations on Data


Chapters 18, 19 and 21 explain how the 2700 series can gather, display, edit and perform other operations on a set of data. Using the commands on the Compute menu, you can also process the current data in memory with a number of mathematical algorithms.

Use of the Compute algorithms does not change the acquisition of data. Instead, the acquired data points are changed according to the applied algorithms.

*NOTE: The Compute algorithms irrevocably change the data in memory. Save the original data on disk if you wish to keep it. See **Comparing Computed Results with Original Data**, page 481.*

The 2700 series provides 11 different computations which you can apply to your data as selections on the Compute menu, as shown in Figure 365.

Figure 365. Compute menu commands.




Additionally, the menu provides a **Compute Status** command, which opens a dialog box to view and edit the list created by applying the **Apply After Sweep** option to one or more Compute algorithms. At the bottom of the menu is the **Clear All and Reset** command.

These commands are discussed on page 480.

The Compute Dialog Boxes

Although each of the 11 Compute dialog boxes has different features associated with a particular compute algorithm, all the boxes are similar and have the following checkboxes and buttons in common:

Figure 366. Compute dialog box common features.



Each Compute dialog box has a list of six checkboxes labeled **Data 1** through **Data 6**. The Compute algorithms will only operate on the data trace or traces you have selected, leaving the other data untouched.

You can select different combinations of data traces in different Compute algorithm dialog boxes.

Four buttons give you the following commands:

- **Cancel**
Abort the operation.
- **Close**
Keep the settings made and close the dialog box.
- **Compute**
Perform the computation while leaving the dialog box open for further operations.
- **Compute and Close**
Keep the settings, perform the computation and close the dialog box.

It is possible to perform a Compute operation repeatedly, or to perform several different compute operations in sequence. You can do this manually by opening and configuring Compute dialog boxes and clicking the **Compute** button.


It is also possible to construct a series of computations which will be performed on the data automatically at the end of the sweep. Checking the **Apply After Sweep** checkbox in a Compute dialog box and then clicking **Close** will place that computation in a list which will be executed after the sweep is completed. The order in which the computations are listed and executed is determined by the order in which you set and close the various compute functions. This list can be viewed and edited in the Compute Status dialog box, page 480.

Compute: Normalize

Compute: Normalize enables you to move a trace up or down against the Y-axis or “normalize” the data in relation to a new value. For example, you may have made a frequency response sweep at some arbitrary level, but now wish to display the trace in relation to a 0 dBr A reference at the mid-frequencies.

As another example, you could make a sweep of a “golden unit” to get a practical reference response, and then normalize the trace 3 dB above and then again 3 dB below a nominal zero level. These upper and lower traces could be saved in a Limit file as upper and lower limits for subsequent tests of other units.

Figure 367. Compute Normalize Dialog Box.



To normalize a trace, you must select the horizontal (X-axis) value of the data point you want to be the normalized reference, and then enter the Y-axis value you want as a target value. In the case of the “golden unit” to make an upper limit you might choose 1 kHz as the **Horizontal Value** and +3 dB as the **Target Value**.


You may normalize more than one trace to the same **Target Value** by checking the appropriate **Data** checkboxes. However, all the traces selected must be of the same unit domain as the **Target Value**.

Compute: Invert

Compute: Invert turns a curve “upside down.” Specifically, **Compute: Invert** reciprocates data expressed in linear units, and negates data expressed in decibel units.

A typical application is to invert a measured frequency response and save the inverted trace as an EQ file, which can then be attached to a sweep to correct for system response variations.

Figure 368. Compute Invert Dialog Box.




To invert a trace, first decide what the “pivot point” of your inversion should be; that is, which data point you would like to remain constant when the trace is flipped. Enter the X-axis value of that data point in the **Horizontal Value** field. The trace inversion will be performed around this point when the data is computed.

Compute: Smooth

Compute: Smooth “smooths out” a trace by assigning each data point a new value that is the average of that point and the two points on either side of it.

Figure 369. Compute Smooth Dialog Box.



The data can be passed through this process repeatedly, with each pass increasing the smoothing. The default number of passes is **1**; you can specify a greater number of passes by entering a higher number in the **Passes** field. If the **Auto** box is checked, the **Passes** field will not be available for entry and the 2700 series will automatically select a number of passes based on the number of measurement points in the data; specifically, if **Auto** is checked, the

number of passes is the integer nearest $(1/2) \times \sqrt{\text{number of points}}$, but is never fewer than 3.

Smoothing is useful when you suspect some of the more extreme data points are spurious. Loudspeaker measurements, for example, often show large peaks and dips which are often attributed to room reflections rather than speaker response. Smoothing out such a trace may provide a more useful view of the speaker response.


Compute: Linearity

Compute: Linearity graphically displays the variance of each of the measurement data points from a linear response across all the data.

In the first of two mathematical operations, the best straight line is fitted to the data, across a range you can specify. This line is computed using the *least squares* method.

Next, the value of every data point is subtracted from this straight line; the result is a graph of deviation from perfect linearity. This is useful to evaluate input-output amplitude linearity of an ADC or DAC; or of the input-output phase shift of a loudspeaker, for example.

Figure 370. Compute Linearity Dialog Box.



Typically, a DUT will have its greatest nonlinearity at the measurement extremes. To keep this atypical data from affecting the initial straight-line fitting, you can enter values in the **Start Value** and **Stop Value** fields to limit the range of data examined. These values only limit the straight-line computation; after the line is derived, every data point in the trace is subtracted from the line value.


Since the values of the data linearity deviations are often small, you may want to optimize the graph view for better resolution. See **Optimize**, page 438.

Compute: Center

Compute: Center can only be used with data sets that have both upper and lower limit files attached. See **Limits**, page 462.

Compute: Center moves the data trace to center it evenly between the upper and lower limits. This is useful in situations where the shape of the curve and its general agreement with the limits are more important considerations than the absolute amplitude of its data points.

Figure 371. Compute Center Dialog Box.



For example, in comparing microphones an evaluation of the overall microphone response as compared to limits is often more important than any minor level differences which may exist.

To keep data from the measurement extremes from skewing the centering process, you can enter values in the **Start Value** and **Stop Value** fields to limit the range of data examined. These values only limit the centering computation; every data point in the trace is moved together.

When the data is compared to limits for a Pass/Fail test, all the data specified in the data files are used to make the Pass/Fail decisions. See **Limits**, page 462.


Compute: Delta

Compute: Delta calculates the difference, or *delta*, between two sets of data. The 2700 series can do this in two different ways:

- by subtracting the data in a specified data file from the current data in memory; or
- by subtracting the data in one column (data trace) of the current data in memory from another column of the current data in memory.

With **Compute: Delta** you can shift your data by an offset, using a constant saved in a file, for example; or subtract one channel of a stereo signal from the other, to measure interchannel differences. If you first normalize your trace at 0 dBV or 1 V at the pivot point, you can use **Compute: Delta** to apply an EQ curve to your measurement after the fact. See **Compute: Equalize**, below.

Figure 372. Compute Delta Dialog Box.



First select the **Delta Source**; that is, the data to be subtracted from the current data in memory. The list under **Delta Source** initially contains two choices: **None** and **SweepData**.

If you want to perform a **Delta** computation on two data traces of the current data in memory, select **SweepData**.

To use a data file, click the browser button and navigate to the file.

In either case, once you have chosen a **Delta Source**, you must then select which data trace in current memory and which data column from the **Delta Source** you wish to compare.

Compute: 2-Sigma

Figure 373. Compute 2-Sigma Dialog Box



Compute: 2-Sigma is used with a series of wow and flutter measurements versus time (chart recorder style) when it is desired to have a single number representing the wow and flutter performance.

The 2-Sigma value for a series of wow and flutter measurements is defined as the magnitude value that is exceeded exactly five percent of the time.

The name “2-Sigma” is based on the fact that five percent of the values in a Gaussian distribution will exceed the two standard deviations (two sigma) value above the center.


The **Compute: 2-Sigma Start** and **Stop** fields enable you to define the range of time included in the calculation. Particularly in the case of wow and flutter measurements, an initial large transient may exist for several seconds because of the long time constants of wow and flutter detectors. You can set the **Start** and **Stop** fields to exclude such an initial transient.

NOTE: **Compute: 2-Sigma** calculates a single number as a wow and flutter result. Every original measured value is replaced with the computed result, producing a horizontal line on the graph and a series of identical values in the Data Editor.

Compute: Average

Compute: Average calculates the average value for all the data points within the range you specify in the **Start Value** and **Stop Value** fields. All the values for the entire data set will be replaced with this computed average, including data points which may be outside the range you set for calculating the average.


Figure 374. Compute Average Dialog Box.



Compute: Minimum

Compute: Minimum will find the minimum value in a data set, examining all the data points within the range you specify in the **Start Value** and **Stop Value** fields. All the values for the entire data set will be replaced with this minimum value, including data points which may be outside the range you set for examining the data.


Figure 375. Compute Minimum Dialog Box.



Compute: Maximum

Compute: Maximum will find the maximum value in a data set, examining all the data points within the range you specify in the **Start Value** and **Stop Value** fields. All the values for the entire data set will be replaced with this maximum value, including data points which may be outside the range you set for examining the data.


Figure 376. Compute Maximum Dialog Box.



Compute: Equalize

Compute: Equalize shifts the value of each point in the selected data set by the value at the corresponding point in the **EQ Source** data set. This gives a result similar to attaching an EQ file to the Analog or Digital Generator (see **Attaching an EQ Curve**, page 74); however, the **Compute: Equalize** technique allows you to apply an EQ curve to your measurement after the fact, rather than equalizing the swept tone.

Figure 377. Compute Equalize Dialog Box.



Compute: Equalize can use either a data column from an attached EQ file or a data column from the current data in memory as an EQ source.

Select the **EQ Source** using the browser in the **Compute: Equalize** dialog box. The list under **EQ Source** initially contains two choices: **None** and **SweepData**. To use a data file, click the browser button and navigate to the file.

If you want use data from another column of the current data in memory, select **SweepData** from the **EQ Source** list instead.

In either case, once you have chosen a **EQ Source**, you must then select which data trace in current memory and which data column from the **EQ Source** you wish to compare.

Compute: Equalize interpolates between data points in the **EQ Source** data as necessary to produce Y-axis values at the specified X-axis values.

Compute Status

The **Compute Status** command on the Compute menu brings up the Compute after Sweep Status panel, which lists all the Compute operations you have selected to **Apply After Sweep**.

The list shows the order in which the computations will be performed. This initial order is determined by the order in which you have set up and enabled Compute operations and set them to **Apply After Sweep**.




Figure 378. Compute Status Dialog Box.

You can add new Compute operations to the list, change the order of the computations, and clear the entire list.

Note that the Compute After Sweep Status list shows only those Compute operations which have their **Compute After Sweep** checkbox checked.

Adding a Compute operation from within the list sets the checkbox in the specified operation panel. Clicking the **Clear List** button does not clear all your Compute settings, but simply unchecks the **Compute After Sweep** checkbox in every Compute panel.

Click **Add** to put a new Compute operation on the list.

To change the sequence of computations, select a Compute operation on the list and click the up or down arrow to move that operation.

Clear All and Reset

The **Clear All and Reset** command at the bottom of the Compute menu clears all existing settings on every Compute panel.

Computed Results and Original Data

The Compute operations actually change the current data in memory, applying the computations you have selected to the data points you have chosen. If you will need your original data again, be sure to save it before you apply a Compute operation.

Since the data in memory is changed after a Compute operation, a comparison between the original data and the computed result requires that certain steps be taken before the Compute operation is performed.

One easy way to view both the original data and the computed result is to duplicate the original data in a unused data column, for reference purposes. Do this by setting both **Data 1** and **Data 3** to the same analysis tool and channel, for example, before sweeping. When your sweep is completed you will have the same values in two columns in the Data Editor.

Now, if you perform your computation on **Data 1**, you can view it against **Data 3**, which displays the reference duplicate of the original data.

Chapter 23

Printing and Exporting

2700 series graphs can be printed to any Windows-compatible printer in black-and-white or in color. As an option, the underlying data can be also printed as a table.

2700 series graphs can be copied to the Windows Clipboard as well, in either bitmap or vector graphics format. Graphs can also be directly exported in a number of common graphics formats.

2700 series panels can be captured as bitmapped “screen shots” by the **Edit > Copy Panel to Clipboard** command on the Edit menu. Once the panel is on the Windows clipboard, it can be pasted into a word processing program such as Microsoft Word or into one of many “paint” or “draw” graphics programs for editing or printing.

Printing 2700 Series Graphs

When printing a 2700 series graph, the key information shown on the graph panel is carried through unchanged to the printed page. This information includes:

- the parameters to be graphed; and
- X-axis and left and right Y-axis calibrations and scaling.


This information cannot be changed from within the print menus.

However, display aspects of the graph such as trace visibility, color and line style, graph labeling and legend, graticule visibility and so on can be modified at print time. These changes are made on the Page Setup panel.

Page Setup

The Page Setup panel is available by the menu choice **File > Page Setup**. The page settings you make are saved when you save your work as a 2700 series test file, along with the current data and the various panel settings also included in a test file.

Figure 379. Page Setup panel, **Display** tab.



The Page Setup panel has three tabs. On the **Display** tab, shown in Figure 379, you can select the page orientation, the text and labels to be included, and how the graticule lines are to be printed.

Figure 380. Page Setup panel, **Layout** tab.




Figure 380 shows the **Layout** tab, where you can set margins, center the graph on the page or resize the graph to fill the page.


You can set margins either by entering numbers in the margin boxes or by dragging the page margins (shown as dotted lines) on the preview panel with the mouse pointer.

To resize the graph, drag the corner of the graph with the mouse pointer. To move the graph on the page, set the mouse pointer within the graph and drag the graph to a new location.

The **Center** and **Fill Page** checkboxes override any existing or manually set size and position adjustments.

On both the **Display** and **Layout** pages you have the option of saving your settings as new default settings. You can also reset your page settings by restoring these defaults, by loading the settings from the current graph screen display, or by loading the page settings from a previously saved 2700 series test file.

Figure 381. Page Setup panel, **Trace** tab.



The **Trace** tab, shown in Figure 381, enables you to choose which traces will be visible in the printed graph. An “X” on a trace row selects that trace to be visible. You can also specify trace color, line style and thickness.

If you check the **Track Display Changes** checkbox, the trace settings on this page will be unavailable, and instead the printer trace settings will be set to the trace settings on the screen display graph.

Print Setup

Click **File > Print Setup** to change your printer or access your printer’s configuration settings. You can also do this from the **Print** dialog box.

Printing a Graph


Click **File > Print > Graph** to send a graph to the printer. If you have not yet set up your page layout, you should first go to **File > Page Setup** (see page 484).

The Print dialog box will appear. Click **OK** to print the graph, or first set other parameters such as number of pages, page range, printer selection and setup and so on.

Print Preview

Click **File > Print Preview** to view an on-screen preview of your printed page. You can zoom to different magnifications by clicking the Zoom buttons or by clicking the mouse pointer on the preview page.

Figure 382. Print Preview.



Printing Data as a Table

You also have the option of printing the test data in a tabular format. Click **File > Print > Data**. The **Data Editor** will appear, and then the Print dialog box. Click **Print** to print the table, or first set other parameters such as number of pages, page range, printer selection and setup and so on.

Audio Precision

File Name: Untitled1

	DGen Freq		DSP Anlr Level A		DSP Anlr Level A
0	20.0014	Hz	+10.000	dBu	-10.000 dBu
1	199.990	Hz	+10.000	dBu	-10.000 dBu
2	200.000	Hz	+7.000	dBu	-7.000 dBu
3	1.99990	kHz	+7.000	dBu	-7.000 dBu
4	2.00000	kHz	+13.000	dBu	-13.000 dBu
5	20.0000	kHz	+13.000	dBu	-13.000 dBu


COMMENTS:

Figure 383. Printing 2700 series data in a tabular format.

Printing to a File

You have the option of routing your print job to an HPGL or Postscript file rather than to your printer.

Click **Print to File**. A file browser dialog box will open.

Figure 384. Print-to-File Browser.

The type of file which will be created depends on the printer driver software which you have chosen. For example, if you have a Postscript laser printer selected in your Print Setup and then click **Print to File**, the file you create will be a Postscript file.

Postscript and HPGL files can be saved and later directly outputted to a printer. Additionally, many word processing and graphics programs will import HPGL and Postscript print files.


A Postscript file can also be converted to an Adobe Acrobat PDF file using the Adobe utility Acrobat Distiller®.

Exporting a Graph

A 2700 series graph can be exported as in a number of different common graphics formats, which can then be imported by a graphics or word processing program for editing or printing. The 2700 series will export graphics files in these formats:

- Enhanced Metafile (*.emf)
- BMP (*.bmp, *.dib, *.rle)
- JPEG (*.jpg, *.jpeg, *.jpe, *.jfif)
- GIF (*.gif)
- TIFF (*.tif, *.tiff)
- PNG (*.png)

Figure 385. Export Graph Browser.



From the Menu bar, choose **File > Export > Graphics** to export a graph as a metafile.

Copying a Graph to the Clipboard

To copy a graph to the Windows Clipboard, select the graph as the active window and use the command **Edit > Copy Panel to Clipboard**.

This command can copy the graph to the clipboard as either a bitmap or as a metafile vector graphic image. To make this choice, you must first set your preference on the **Graph** tab in the 2700 series Configuration panel at **Utilities > Configuration**, which is discussed in Chapter 28.

The images captured in this way can be viewed and saved using Microsoft Clipboard Viewer, or the contents of the Clipboard can be pasted into word processing or graphics documents and applications.

Copying a Panel or Window to the Clipboard

The command **Edit > Copy Panel to Clipboard** will also copy any active 2700 series panel to the Windows Clipboard as a bitmap.

Additionally, Microsoft Windows provides keyboard shortcuts for copying the entire screen or a selected window to the Windows Clipboard as a bitmap image.

To copy the entire screen to the Clipboard, press **Print Scrn**. To copy the active window to the Clipboard, press **Alt+Print Scrn**. Third-party screen capture programs will enable you to copy other screen areas to the clipboard.

The bitmaps captured in this way can be viewed and saved using Microsoft Clipboard Viewer, or the contents of the Clipboard can be pasted into word processing or graphics documents and applications.

Bitmaps and Vector Graphics

*A bitmap graphics file is a bit-by-bit image of the 2700 series graph. The resolution of a bitmap is set at its creation, and magnifying the image will reveal the individual pixels comprising the image. Bitmap files can be edited with “paint” graphics software. Files with the filename extension *.bmp, *.jpg, *.tif and *.png are bitmap files.*

*A vector graphics file describes the image in programming code, and such an image can be resized with no degradation. The resolution of a printed vector graphics file is dependent only on the resolution of the printer. Vector graphics files are edited with “draw” graphics software, and are usually easier to modify than bitmap files. A 2700 series vector graphics image shows the traces as black and colored lines on a white background. A graphic with the filename extension *.emf (enhanced metafile) is vector graphic file.*

Chapter 24

Monitoring


Headphone/Speaker Monitoring

The 2700 series has an internal speaker and a front-panel headphone jack for audible monitoring of audio signals at different points in the system. The headphone output and the internal speaker share a common volume control, mounted on the front panel next to the headphone jack. The headphone jack is a standard 1/4" tip-ring-sleeve (TRS) stereo headphone jack. When a plug is inserted into the headphone jack, the internal speaker is disconnected.

When the monitor source is two-channel, the internal speaker outputs a monaural sum of the two channels. The headphone jack will provide a monaural or stereo signal, depending upon the Stereo / Mono and Source selections on the panel.

Headphone/Speaker panel

Figure 386. The Headphone/Speaker panel.



The Headphone/Speaker panel is available at **Panels > Headphone/Speaker** or by clicking the **Headphone/Speaker** button on the Panels toolbar.



Stereo / Mono

Clicking the Mono button changes the Source selections from a list of (mostly) stereo sources to a list of mono choices.

Source

The Headphone/Speaker panel Source list offers several audible monitor source choices. The same set of choices is available from both a stereo and a mono list, as selected by the Stereo / Mono button. The Mono choices are described here; stereo choices are combinations of the same sources.

■ **Analog Analyzer Reading**

This is the measured signal displayed on the Function Reading meter. This signal has been processed by the Analyzer according to the function and filtering selected. If the Analog Analyzer Function is set to **Bandpass**, for example, this source will be the output of the bandpass filter. If the Function is **THD+N**, this source will be the noise and distortion product residuals. It is a single-channel signal, and it is applied as a mono signal to both the left and right headphone outputs in both Mono and Stereo.

This is the same signal that appears at the ANALYZER SIGNAL MONITORS: READING BNC connector.

■ **Analog Generator A**

Analog Generator B

These are the Analog Generator outputs signals taken before the final output circuits. The Track A, Invert, Auto On, Outputs ON/OFF, Channel ON/OFF and Amplitude controls do not affect these monitor signals. In Stereo, Channel A is routed to the left and Channel B is routed to the right. These are the same signals that appear at the GENERATOR MONITORS: CHANNEL A and CHANNEL B BNC connectors.

■ **DSP Monitor A**

This is the embedded audio signal applied to the Channel 1 input of the Digital Analyzer tools, as selected by the Source controls on the DSP tool panels. This is the same signal that appears at the DIGITAL SIGNAL MONITORS: CHANNEL 1 BNC connector.

■ **DSP Monitor B**

This is the Reading 1 measurement signal after analysis by the DSP Audio Analyzer tool. The other Digital Analyzer tools have no audible reading outputs available. This is the same signal that appears at the DIGITAL SIGNAL MONITORS: READING 1 BNC connector.

■ Analog Input A

Analog Input B

These are the analog input signals to the Analog Analyzer, taken at the same point in the circuit that is connected to the Level Meter detectors. These signals have been ranged but not filtered. Channel A is routed to the left and Channel B is routed to the right. These are the same signals that appear at the ANALOG ANALYZER MONITORS: CHANNEL A and CHANNEL B BNC connectors.

■ DSP Monitor C

This is the embedded audio signal applied to the Channel 2 input of the Digital Analyzer tools, as selected by the Source controls on the DSP tool panels. This is the same signal that appears at the DIGITAL SIGNAL MONITORS: CHANNEL 2 BNC connector.

■ DSP Monitor D

This is the Reading 2 measurement signal after analysis by the DSP Audio Analyzer tool. The other Digital Analyzer tools have no audible reading outputs available. This is the same signal that appears at the DIGITAL SIGNAL MONITORS: READING 2 BNC connector.

The Monitor Outputs



Figure 387. The monitor output connections.

There are nine monitor outputs available on BNC connectors on the 2700 series front panel. The monitor outputs are intended for external oscilloscope, spectrum analyzer or other monitoring. These outputs are not calibrated and should not be used for measurements.

Refer to the manual *Getting Started with Your 2700 Series Instrument* for detailed input and output specifications. See Chapter 4, **Signal Inputs and Outputs** for more information about the 2700 series main inputs and outputs and the software panels associated with them.

The GENERATOR AUX SIGNALS on this panel are discussed in Chapter 25, **Sync and Auxiliary Connections**.

Analyzer Signal Monitors

These outputs are buffered and unbalanced, with a typical voltage range from 0 Vpp to 3.6 Vpp and a source impedance of 600 Ω . The outputs are designed for monitoring only and are not calibrated for use in measurements.

Channel A

Channel B

These are the analog input signals to the Analog Analyzer, taken at the same point in the circuit that is connected to the Level Meter detectors. These signals have been ranged but not filtered. These are the same signals that appear as the **Analog Input A** and **Analog Input B** Headphone/Speaker selections.

Reading

This is the measured signal displayed on the Function Reading meter. This signal has been processed by the Analyzer according to the function and filtering selected. If the Analog Analyzer Function is set to **Bandpass**, for example, this source will be the output of the narrow bandpass filter. If the Function is **THD+N**, this source will be the noise and distortion product residuals. This is the same signal that appears as the **Analog Analyzer Reading** Headphone/Speaker selection.

Digital Signal Monitors

The digital signal monitors are analog outputs that have been converted via four 24-bit DACs. They have a typical voltage range from 0 Vpp to 1.7 Vpp and a source impedance of 600 Ω .

Channel 1

Channel 2

These are the embedded audio signal applied to the Channel 1 and 2 inputs of the Digital Analyzer tools, as selected by the Source controls on the DSP tool panels. These are the same signals that appear as the **DSP Monitor A** and **DSP Monitor C** Headphone/Speaker selections.

Reading 1

Reading 2

These are the Reading 1 and 2 measurement signals after analysis by the DSP Audio Analyzer tool. The other Digital Analyzer tools have no audible reading outputs available. These are the same signals that appear as the **DSP Monitor B** and **DSP Monitor D** Headphone/Speaker selections.

Chapter 25

Sync/Ref, Trigger and Aux Connections

In addition to the main analog and digital signal connections on the front of the instrument, the 2700 series provides a number of monitor, sync and other utility connections. The monitor outputs are discussed in Chapter 24.

GENERATOR AUX SIGNALS



Figure 388. The GENERATOR AUX SIGNALS connections (lower left on this panel).

The GENERATOR AUX SIGNALS are available on two BNC connectors located on the instrument front panel, next to the monitor outputs.

SYNC OUTPUT

The GENERATOR SYNC OUTPUT signal is an LSTTL-compatible output signal that is intended to be used as a trigger for stable external oscilloscope display. Source impedance is 600 Ω .

The SYNC OUTPUT signal is normally low, and goes high at the trigger event.

TRIG/GATE INPUT

The GENERATOR TRIG/GATE INPUT is an LSTTL-compatible input that will accept positive-going pulses up to 5 Vp.

This input is only functional with the S2-BUR-GEN burst, noise and square wave generator option.

Auxiliary Digital Signals




Figure 389. 2700 series Sync, Reference and Auxiliary subpanel.

The 2700 series Sync, Reference and Auxiliary subpanel is located in the instrument lower-right rear panel. Various auxiliary connections can be made on this subpanel.

VIDEO/TTL REF IN

This input can be selected as a synchronization reference on the Sync/Ref Input/Output panel by choosing one of the following in the Source field:

- Squarewave
- NTSC Video Sync Horiz Rate
- PAL/SECAM Video Sync Horiz Rate

The input will accept baseband NTSC or PAL/SECAM video at the nominal video rates and voltages, or a TTL-compatible square wave across the range of 8 kHz–10 MHz. Input impedance is bridging (high) or 75 Ω , as selected on the Sync/Ref Input/Output panel.

TRIGGER OUT

This output provides a 5 V HCMOS-compatible square wave, coincident with the period of the signal waveform generated by the Digital Generator. This signal is intended to be used as a trigger for stable external oscilloscope display. Source impedance is 50 Ω .

The TRIGGER OUT signal is normally high, and goes low at the trigger event.

AES/EBU REF IN

This input can be selected as a synchronization reference on the Sync/Ref Input/Output panel by choosing **AES Sync Rate** in the Source field. The input also serves as the digital audio input for the Pass Thru selections of the Analog and Digital Generators.

The input will receive an AES3 digital audio interface signal at sample rates from 28 kHz–200 kHz. Input impedance is bridging (high) or 110 Ω , as selected on the Sync/Ref Input/Output panel.

AES/EBU REF OUT

This output provides an AES3 signal at the instrument output sample rate (SR) that can be used as a “house sync” reference for a DUT. This signal also serves as the Ref Out reference for the **Delay, Out from Ref Out** control on the Sync/Ref Input/Output panel and for the **Delay from Ref Out** reading on the DIO panel.

The embedded audio is all zeros (infinity zero).

Channel status bits are set to provide the follow reference signal:

- Professional Grade 2.
- Local Address and Time of Day set to zero, so that the status bits repeat from block to block and the CRCC byte (byte 23) remains in a fixed state.
- Origin code is set to “SYS2.”
- Correct frame rate is flagged if actual SR is near one of the standard sample rates of 32 kHz, 44.1 kHz or 48 kHz.

Any jitter added to the main digital outputs or to the master clock is NOT applied to this signal.

MASTER CLK OUT

This output provides a square wave at $256 \times SSR$ (System Sample Rate). SSR and SR are not always equal; see the table on page 157 for a view of the relationship of SSR to SR.

A jitter impairment (set in the DIO panel Jitter Generation fields) can be added to this signal by checking Jitter Clock Outputs on the Sync/Ref Input/Output panel.

TRANSMIT FRAME SYNC

This output provides a square wave at the instrument (DIO Output) sample rate (SR); in normal polarity the square wave is at its positive value during the A subframe and its negative value during the B subframe. The signal polarity can be inverted by checking **Invert Frame Sync** on the Sync/Ref Input/Output panel, enabling oscilloscope synchronization with either subframe.

A jitter impairment (set in the DIO panel Jitter Generation fields) can be added to this signal by checking Jitter Clock Outputs on the Sync/Ref Input/Output panel.

RECEIVE FRAME SYNC

This output provides a square wave at the received (DIO Input) signal sample rate (ISR). Any jitter added as a signal or clock impairment is NOT applied to this signal.

EXT TRIGGER IN

EXT TRIGGER IN provides an input for triggering data acquisitions in the FFT-based batch-mode Digital Analyzer analysis tools: the Spectrum Analyzer, the Multitone Audio Analyzer, the MLS Analyzer and the Digital Interface Analyzer.

This input will accept standard 3 V or 5 V TTL/CMOS logic signals. 2700 series analysis tools normally trigger on the rising edge of the signal transition, although option switches on the Spectrum Analyzer and the Digital Interface Analyzer panels enable selection of the trigger slope.

AUX OUT

This output is an HCMOS signal that goes low when an error is detected using the Digital Data Analyzer (see Chapter 16).

PARALLEL OUTPUT and INPUT


See Chapter 4, **Signal Inputs and Outputs**, and Chapter 9, the **Digital I/O Panel** for information about using the parallel digital input and output.

APSI

This connector provides the two-way Audio Precision Streaming Interface. APSI is only used with for the OPT-2711 Dolby Digital Generator option, and is only functional with the installation of that option and the licensed activation of the software components. See Chapter 10 for more information about the Dolby Digital Generator.

The Sync/Ref Input/Output panel

Figure 390. The Sync/Ref Input/Output panel.



The Sync/Ref Input/Output panel enables you to synchronize the 2700 series master clock to several types of external reference signals, including the sample rate or the frame rate of an AES3 or IEC 60958 reference signal, the horizontal sync frequency of NTSC, PAL, or SECAM analog video signals, or to a square wave or other periodic signal.

The master clock controls the 2700 series internal sample rate and is the reference for all 2700 series frequency measurements. Synchronizing the master clock to an external reference is often necessary when making measurements in an installation where “house sync” is used.

The Sync/Ref Input/Output panel also provides controls that affect the synchronization characteristics of several instrument outputs.


Reference Input

When synchronizing the 2700 series master clock to an external source, two settings are always necessary:

- You must select the format of the external sync signal in the **Source** field.
- You must enter the exact nominal frequency of the external sync signal in the **Frequency** field.

Source

Figure 391. Sync/Ref Sources.



Select the format of the external synchronization signal from the **Source** list.

- **AES Sync Rate**

This selection will synchronize the 2700 series master clock to the sample rate of a properly formatted AES3 or IEC 60958 signal applied to the rear-panel AES/EBU REF IN XLR jack.

This choice synchronizes the sample rates, but does not ensure that the signal frames are aligned in time. To align the frames, the 2700 series digital output signal must be set to the same sample rate as the reference signal and the **Frame Lock** box on the Sync/Ref Input panel must be checked.

The reference signal applied to the AES/EBU REF IN XLR jack may also be used as a reference to measure the time delay through a DUT. See **Delay, In from Ref In** below.

- **Squarewave**

This selection will synchronize the 2700 series master clock to a TTL square wave signal or other repetitive signal applied to the rear panel VIDEO/TTL IN BNC jack. This signal may be between 8 kHz and 10 MHz.

- **NTSC Video Sync Horiz Rate**

This selection will synchronize the 2700 series master clock to the hori-

zontal sync pulse (nominally 15.7343 kHz) of an NTSC analog video signal applied to the VIDEO/TTL IN jack.

■ PAL/SECAM Video Sync Horiz Rate

This selection will synchronize the 2700 series master clock to the horizontal sync pulse (nominally 15.6250 kHz) of a PAL/SECAM analog video signal applied to the VIDEO/TTL IN jack.

Pass Thru Domain Preference

The AES/EBU REF IN signal is used as the signal source for the Special: Pass Thru generator waveforms. For the Analog Generator, this digital signal is sample-rate converted to SSR (if necessary) and then converted to analog by a dedicated DAC running at SSR. For the Digital Generator, the Pass Thru signal is sample-rate converted (if necessary) to SR.

In some modes of operation (see page 157) $SR=SSR$, and in other modes $SR=2 \times SSR$. The Pass Thru sample-rate converter cannot operate at two different sample rates simultaneously, so you must set your preference here. Do you want the SRC to convert the signal to SSR (for the Analog Generator), or SR (for the Digital Generator)?

In the great majority of tests this is not an issue, and your selection here will not be relevant. In the unlikely circumstance of a test that calls for a sample rate higher than 108 kHz (where $SR=2 \times SSR$) and the test specifies the use of the Special: Pass Thru waveform selection for both the Analog Generator and the Digital Generator at the same time, the control software will be guided by your preference selection. The Pass Thru signal will be correctly sample-rate converted for the domain of your choice, and will be badly distorted in the other domain.

Frame Lock

As mentioned above, synchronization of AES3 or IEC 60958 rates alone does not time-align the interface signal frames. Each AES3 or IEC 60958 frame begins with a preamble pattern, and in time-aligned or frame-locked signals the X, Y and Z preambles start at the same moment.

When using **AES Sync Rate** for synchronization in the 2700 series, checking **Frame Lock** time-aligns the frames as well. The 2700 series digital output signal sample rate (SR) must be set to the same value as the reference input signal sample rate for frame lock.

Input Termination Impedance

When the Reference Input Source is set to **AES Sync Rate**, set the termination impedance to **110 Ω** (*terminated*) if the 2700 series instrument is the only device connected to the reference source, or if it is the last device in a chain of

devices. If the instrument is in a chain of devices but is not the last device in the chain, set the impedance to **HiZ** (*bridging*).

Similarly, when using a square wave or video source, set the termination impedance to **75 Ω** if the 2700 series instrument is the only device connected to the reference source, or if it is the last device in a chain of devices. If the instrument is in a chain of devices but is not the last device in the chain, set the impedance to **HiZ**.

Frequency

Set the exact nominal frequency of the synchronization signal in this field. For an AES3 signal, for example, it might be 44.100 kHz or 48.000 kHz. For a square wave, set **Frequency** to the rate of the external clock.

If the actual reference signal is slightly different (less than 15 PPM) from the value entered here, synchronization will be achieved but all 2700 series sample rates and readings will reflect the difference. If the value entered is more than 15 PPM away from the actual reference signal frequency, the internal crystal oscillator may not lock to the reference.

The 2700 series control software automatically enters the two video sync rates for you. These may be changed to a non-standard video rate by entering a new value, if necessary; however, values very near the standard value will be rounded to the exact standard value.

Input Frequency

When a suitable reference signal is present at the reference input jack for the selected Source format, the Input Frequency field will display that signal's frequency. This display aids in verifying the presence or absence of a sync signal and in determining the nominal frequency before synchronization is achieved.

Once the 2700 series instrument has synchronized to the reference, the Input Frequency field is grayed out, since after synchronization the measured frequency is identical to Frequency setting.

Delay, In from Ref In

This field displays the time delay between a serial digital signal applied to the AES/EBU REF IN jack and the serial digital input signal currently selected on the DIO panel. The signals must be at the same sample rate.

The range of the delay measurement is one frame. If the delay exceeds one frame, the measurement result “wraps” back within the one-frame range. The range extends from -10 % to +90 % of the frame length; in other words, from

$$\begin{aligned} & \text{FrameStart} - (0.1 \times \text{FrameLength}) \\ & \text{to} \\ & \text{FrameStart} + (0.9 \times \text{FrameLength}). \end{aligned}$$

Figure 392 gives an example of the delay measurement range for a frame length of 20.83 μs , the length of an AES3 frame at a sample rate of 48 kHz.




Figure 392. The Delay, In from Ref In measurement range, showing times that correspond to a sample rate of 48 kHz.

Out of Range Indicator

The Out of Range indicator on the Sync/Ref Input/Output panel is lighted if the actual reference signal frequency is outside ± 15 PPM of the value entered in the Frequency field, or if the signal is outside the amplitude range required for reliable operation. The indicator may require several seconds to indicate an out of range condition.

Sync Output controls

Delay, Out from Ref Out

The Delay, Out from Ref Out controls apply a time delay to the main serial digital output relative to the AES/EBU REF OUT signal. Click the ON button to enable the entry field and apply the delay. The range of acceptable delay entries varies with system sample rate (SSR) from -64 UI to 63.5 UI.

NOTE: The serial digital output residual jitter is slightly higher with the output delay feature set ON. For this reason, click the button to OFF for a zero delay setting, rather than leaving the delay feature ON with a zero entry.

Invert Frame Sync

The normal polarity of the TRANSMIT FRAME SYNC signal puts the square wave at its positive value during the A subframe and its negative value during the B subframe. The signal polarity can be inverted by checking the Invert Frame Sync checkbox, enabling oscilloscope synchronization with either subframe.

Jitter Clock Outputs

Check the Jitter Clock Outputs checkbox to apply the jitter impairment set on the DIO panel to the MASTER CLK OUT and TRANSMIT FRAME SYNC signals.

Chapter 26

Automating Tests

Introduction

Almost every 2700 series command and panel setting has a corresponding OLE (Object Linking and Embedding) command. OLE automation can be used by programming languages such as AP Basic to control and automate software functions in independent applications, such as the 2700 series control software, AP2700.

AP Basic is a programming language specifically designed for Audio Precision computer-controlled instruments and is included with your 2700 series control software. If you are familiar with Microsoft Visual Basic you will find many similarities in the languages; you can also use programs written in Visual Basic to control 2700 series instruments.

Using AP Basic, you can write macros (automation programs, also called or *procedures* or *scripts*) that issue 2700 series OLE commands, open files, wait for data readings to satisfy necessary conditions, create reports, save information to disk and communicate with other Windows programs. You can design and use custom user interfaces to simplify and direct macro operation. Using OLE, it is possible to control 2700 series instruments from other software programs. Virtually every function of a 2700 series instrument can be automated with AP Basic.

AP Basic macro files for 2700 series instruments are saved with the file-name extension .apb.

Learn Mode

An experienced programmer with a good knowledge of AP Basic can sit down at a text editor and write a macro to run a 2700 series test. It's much easier, though, to use Learn Mode.

Learn Mode records every appropriate operation of the control software, as assembling an AP Basic macro as you perform your test. It is similar to features in other applications called *macro recorders*. Learn Mode is often the easiest way to create a macro, whether simple or complex.



To enter Learn Mode, click the **Start Learn Mode** button on the Learn Mode toolbar; or, from the Main menu, choose **Macro > Learn Mode** or **Utilities > Learn Mode**. An AP Basic macro will open in the Macro Editor, and each 2700 keystroke and mouse click will be entered into the Macro Editor as a line of AP Basic code, as you set up and run a test.



On the Macro and Utilities menus a checkmark will remain next to the **Learn Mode** choice while the control software is in Learn Mode, and the shape of the mouse pointer will change to that of an audio cassette, indicating that a recording is being made. To prevent a particular mouse click from being entered into the macro, press and hold the keystroke combination **Ctrl-Shift** while clicking. This temporarily suspends Learn Mode.



To exit Learn Mode, click the **Stop Learn Mode** button on the Learn Mode toolbar; or, from the Main menu, choose **Macro > ✓ Learn Mode** or **Utilities > ✓ Learn Mode**. The mouse pointer will return to its normal shape and the checkmark next to the **Learn Mode** menu choice will disappear.

The Macro Editor




Figure 393. The Macro Editor, showing a new macro created in Learn Mode.

The Macro Editor is a text editor with dedicated features for editing AP Basic macros, including macro navigation and debugging tools. You can begin a macro “from scratch” in the Macro Editor, or edit macros created by Learn Mode or opened from disk.

AP Basic Documentation

The *AP Basic Language Manual* is the primary reference for using automation with Audio Precision instruments.

Since each family of instruments has different capabilities, each has a dedicated set of OLE commands called *extensions*. For 2700 series instruments, these are discussed in detail in the *AP Basic Extensions Reference for 2700 Series Instruments*.

Both of these books are provided with each 2700 series instrument, and are included as PDF files on the Audio Precision Resources Disc.

Chapter 27

Regulation

Regulation is a software servo-mechanism which enables you to automatically steer test parameters toward a specific measured value.

Let's say, for example, that you would like to find the point at which a power amplifier produces 1% THD+N at its output. With regulation, the 2700 series control software can adjust a generator output amplitude while monitoring the DUT THD+N, guiding the generator up and down to the level where 1% THD+N is measured. At this point, the DUT output wattage can be measured and noted as the power level at 1% THD+N.

Here's another example: you'd like to find the exact frequency at which the DUT response is 3 dB down from the midband level reference. The 2700 series regulation function can adjust a generator frequency while monitoring the DUT output amplitude, guiding the generator up and down to the precise frequency at which -3 dB is measured.

The Regulation panel

Open the Regulation panel by clicking the Regulation button or choosing **Panels > Regulation**.





Figure 394. The Regulation panel.

The Regulation panel enables you to select:

- a target parameter, displayed in the **Regulate** field.
This is the parameter the control software is monitoring as it is steered toward the target value. Use the target browser to select the target parameter from the 2700 series analysis tool (instrument) readings provided.
- a target value, displayed in the **To** field.
This is the reading from the DUT that you are trying to attain.
- a target value tolerance, displayed in the **within a tolerance of** field.
This is the range around the target value that is acceptable for your test.
- a source parameter, displayed in the **by varying** field.
This is the 2700 series setting which will be varied in an attempt to steer the target parameter toward the desired value. Use the source browser to select the source parameter from the 2700 series panel settings provided.
- source **High** and **Low Bounds**
These are the extremes between which you want to confine the source variations.

Figure 395. The Regulation Source Browser.



There are also several panel settings which affect regulation performance:

■ Operation

Operation sets one of five algorithms which determine how the regulation operation proceeds:

• Linear

The assumption for **Linear** operation is that any change in the regulation source parameter will cause the same change in the regulated target parameter. This is the normal relationship, for example, in the input and output amplitudes of an amplifier: a +2 dB change at the input should make a +2 dB change at the output.

Linear is the best choice and the fastest option for setting DUT outputs to a reference level, or making frequency response

measurements at a constant output level.

In **Linear** operation, the regulation algorithm is directed to jump to the target value in a single step, and the **Stepsize** field is unavailable.

- **+Normal**

The assumption for **+Normal** is that any change in the regulation source parameter will cause a proportional change in the regulated target parameter. This is the normal relationship between generator amplitude and measured THD of an amplifier near its maximum power point, or between generator frequency and measured high-pass filter output amplitude on the attenuation skirt.

- **– Normal**

The assumption for **– Normal** is that any change in the regulation source parameter will cause an inverse proportional change in the regulated target parameter. This is the normal relationship between generator frequency and measured low-pass filter output amplitude on the attenuation skirt, or between generator amplitude and measured THD+N in relative units (dB or %) in the lower, noise-limited range of a DUT.

- **Maximum**

Maximum regulates in search of a maximum or peak value, steering the source parameter to find the peak.

- **Minimum**

Minimum regulates in search of a minimum peak value, steering the source parameter to find the minimum peak.

Figure 396. The Regulation Target Browser.



■ Stepsize

The **Stepsize** field controls the initial size of the increments which will be made to the regulation source parameter. When the regulated parameter reading first passes beyond the target value, the actual step size will be decreased and the direction of change reversed as the algorithm goes

into a binary search mode to determine the final value to regulate the measurement. **Stepsize** may be set in a number of ratio units including **%**, **X/Y**, and **dB**. The optimum value for **Stepsize** depends upon the DUT and the distance to the target value from the initial starting value. Large steps will reach and pass the target rapidly, but more iterations will be required to reduce the step size and bring the measurement into regulation. Smaller steps will take longer to reach the approximate area near the target value but may regulate the measurement more rapidly.

■ Iterations

Iterations determines the maximum number of regulation steps which will be made for each measurement. Regulation is considered successful if the target value is attained within the tolerance without exceeding the number of iterations. If regulation is unsuccessful an “Unregulated” message is issued, and an “R” is entered at the measurement on the Graph, in the Data Editor and in the Log file, if enabled.

For **+Normal**, **– Normal** and **Linear** operations, the **Iterations** field limits the maximum number of steps which the regulation algorithm will make in the search for the target value. **Iterations** should be large enough to permit successful regulation.

In **Maximum** and **Minimum** modes, the **Iterations** field determines the number of times that the measured value passes through the target value before the algorithm halts. A larger **Iterations** value will produce a more precise location of the target, but will take longer to complete. Generally, broad peaks and dips can be located with a smaller **Iterations** value, and sharper peaks or dips require a larger **Iterations** value.

■ Timeout (per step)

The readings used for regulation are first processed through the sweep Settling algorithm. See page 427 for a discussion of Settling. In some circumstances, depending upon the variability of the readings and the Settling settings, Settling cannot be satisfied and no data for that step will be forwarded to the Regulation panel. The **Timeout** field enables you to enter a time interval beyond which regulation will not wait for a settled reading. When a reading times out, the most recent stream of up to 32 readings from the analysis tool will be averaged and used as input to regulation.

Once you have made all your settings, click the **Regulate** button to perform regulation.

Check **Enable during each step of the sweep** to set the automatic option for sweep operation.

Examples of Regulated Sweeps

Here are several applications of regulated sweeps:

- Using regulation to hold power amplifier output distortion constant (at 1.0%, for example) by varying generator amplitude, but plotting amplifier output power versus generator frequency to produce a graph of power bandwidth.
- Using regulation to find a -3 dB point on a DUT, then making a single-point sweep to display the measured frequency at that point.
- Using regulation to hold the modulation percentage (or *deviation*) of a preemphasized broadcast transmitter constant while measuring and plotting THD+N versus frequency.
- Using regulation to hold the modulation percentage (the deviation) of a preemphasized broadcast transmitter constant while measuring and plotting the generator amplitude versus frequency required to obtain that constant modulation value.


This curve is essentially a modulation sensitivity test. Plotting the generator amplitude using normal units will result in a curve that is inverted from the actual preemphasis curve shape of the transmitter. Use **dBrInv** (relative decibels, inverted) for the generator units to invert the trace and produce a preemphasis curve.

Chapter 28

Configuration and the Utilities Menu

The Utilities menu offers access to the system Configuration panel and also to several utility functions and programs. We'll look first at the Configuration panel. Go from the Main menu to **Utilities > Configuration**.

Figure 397. The Utilities Menu.




The Configuration panel

The Configuration panel allows you to set your preferences for 2700 series behavior. There are four tabbed pages on the Configuration panel:

- General
- Configure Filters
- Log
- Graph

General

Figure 398. The Configuration General tab.



The General configuration tab enables you to set a number of general behaviors for the 2700 series control software. These are:

- **Prompt to Save Test when a test is closed**

Several commands (such as **File New Test**, **File Open Test** or **File Open Data**) will close the current test, clearing the test data from memory. If this box is **checked**, a dialog box will open when a test is about to be closed, prompting you to save the test before closing it.

- **Load “LAST.at* ” on startup**

If this box is **checked**, when the control software is launched the program will automatically load the test named “Last.at27” in normal mode, or “Last.at2” in emulation mode.

- **Save “LAST.at* ” on exit**

If this box is **checked**, when the control software is closed the program will automatically save the current test in memory as “Last.at27” in normal mode, or “Last.at2” in emulation mode.

- **Keep all readings active during real-time sweeps**

Normally, the 2700 series meters are constantly updating their readings. If this box is **checked**, all meters on all open panels will continue to update their readings during the progress of real-time sweeps. This enables you to view non-swept parameters during a sweep.

If the box is **unchecked**, only the readings selected as sweep parameters

will update their readings, which enables sweeps to run faster.
This setting does not apply to batch mode sweeps.

- **Display data in graph on test open**

If this box is **checked**, data in a test is automatically graphed (and compared to limits, if any) when the test is opened. If the box is **unchecked**, the data is loaded with the test but is not automatically graphed.

- **Reprocess FFT data on zoom**

If this box is **checked**, each time a Graph zoom is initiated for an FFT plot, the data acquisition is re-processed with an automatic **Sweep Reprocess Data (Ctrl-F6)** command. Although this processing takes more time, it assures that the plotted resolution is always the maximum supported by either the number of points graphed or by the FFT length. See **Retransforming and Reprocessing Data** on page 266 and **Zoom** on page 436.

- **European Broadcast option installed.**

If your instrument has the S2-EURZ option installed, you must be sure this box is **checked** to properly configure the control software for this hardware option. If the option is not installed, the box should be **unchecked**. AP2700 must be restarted to apply a change in this configuration setting.

S2-EURZ changes the Analog Generator output impedances to 40 Ω , 200 Ω or 600 Ω .

- **Do not load panels on Open Test**

Normally, when a test is opened, all the panels, bar graphs and graphs are loaded on each page at the location and size that they were when the test was saved. If this box is **checked**, the control settings, including waveform, amplitude, frequency, Digital Analyzer analysis tool and function, sweep settings and so on, are loaded without changing the current panel and graph size and location.

- **Auto-“Enter” for Numeric Fields**

Normally the control software requires an **Enter** keystroke to apply an entry to a numerical setting field. If this box is checked, the **Enter** keystroke is not necessary, and simply moving the mouse pointer to another field will apply the numeric entry.

- **Set Sample Rate when loading generator waveforms**

Most applications using arbitrary waveforms require that they be played back at the same sample rate at which they were created. Audio Precision waveform files contain information on the design value of the sample rate.

For the Digital Generator, if this box is checked the control software automatically sets the DIO Sample Rate (SR) to the waveform sample rate when a waveform file is loaded.

For the Analog Generator, if this box is checked and the rate in the waveform file is one of the fixed rates (65536 Hz or 131072 Hz), the DAC is set to that sample rate. If the rate is not one of the fixed rates, the D/A Sample Rate source is set to SSR, and SSR is set to the waveform rate. If the rate is not supported (i.e., > 108 kHz), a warning is displayed. See **Arbitrary Waveforms** on page 90 and page 119.


■ **Autoscale on ASCII data import**

When ASCII data are imported into a test, the graph coordinates are normally re-scaled to accommodate the new data. If you do not want the graph coordinates to re-scale, **uncheck** the **Autoscale on ASCII data import** checkbox.

At the bottom of the page is the **Company Name** field, where you can enter the name you would like to appear on graphs. If a name is entered here, you have the option enabling or disabling screen or print display in the Graph Label dialog box or in the Page Setup dialog box.

Configure Filters

Figure 399. The Configure Filters tab.




The Configure Filters tab enables you to specify an option filter for each of the seven hardware filter slots in the 2700 series instrument.

The 2700 series control software automatically detects the option filter type in the filter slots, and under normal operation you will not need to manually configure any filter in this configuration dialog. Simply leave the Auto Detect boxes on this panel **checked**.

In some cases you may need to design a test that requires filters not installed in your current instrument hardware, and the Filter Configuration dialog gives you this capability.

Log

Figure 400. The Log Configuration tab.



The Log File

The log file is an optional record of many important 2700 series operations, including test names, date and time of each running of tests, limits failures, file loading and saving activity and error messages. New information is appended to the log file, so a log file can become a complete record of an entire audio testing process.

The log file is a standard ASCII text file, readable by text editors such as Windows Notepad and other applications. A log file has the extension .alg.




Figure 401. A typical log file, showing test file name and path, date and time, **FAIL** message and a list of the failed point values.

The Log configuration tab enables you to set 2700 series Log file options. These are:

■ **Enable Logging**

Check this box to enable logging. Type the filename and path of the log file. The default is log.alg, with a path of C:\Documents and Settings\username\My Documents\Audio Precision\AP2700 n.nn\.

■ **Include in Log File**

• **Error Messages**

If this box is checked, any Windows or 2700 series error messages that occur during the logging period will be written to the log file.

• **File I/O Activity**

If this box is checked, a text message will be written to the log file for every disk file opened and every file saved to disk. The message includes the name and full path of the file and the date and time at which it was saved or opened.

■ **Sweep Activity**

• **Test Name**

If this box is checked, the filename and full path of the executed test is written to the log file with each sweep.

• **Graph Title, Time and Date**

If this box is checked, the graph title, date and time of the test are written to the log file with each sweep.

• **Pass/Fail Message**

If this box is checked, an error summary message will be written to the log file each time a sweep is run. The message will say **PASS** or **FAIL**, followed by the number of measurements below the lower limit, the number of measurements above the upper limit, and the number of timeouts which occurred.

■ **Sweep Data**

• **None**

If this box is checked, no sweep point values will be written to the log file.

• **All**


If this box is checked, all sweep point values will be written to the log file.

• **Failed Only**

If this box is checked, only those sweep point values that have failed the limits will be written to the log file.

Graph

Figure 402. The Configuration Graph tab.



The Graph configuration tab enables you to set the Graph color assignment and copy options for your 2700 series system. See **Trace Colors** on page 447, **Copying a Graph to the Clipboard** on page 488 and **Bitmaps and Vector Graphics**, page 489.

The Graph **Trace Colors** options are:

- **On Sweep:**

- **Reset color cycle**

If **Reset color cycle** is **checked**, each new sweep will reset the color cycle, so that the first trace of the sweep is cyan.

If the **Reset color cycle** is **unchecked**, each new sweep will use the color cycle, but will not reset it to cyan. The first trace of each new sweep will be the next color in the cycle, referenced to the last trace of the previous sweep. If you manually change any color-to-**Data** assignment, the 2700 series control software will maintain your new color assignments throughout subsequent sweeps.

If a New Test is opened with **Reset color cycle unchecked**, the new test will inherit the colors of the previous test. If there was no previous test since launching the control software, the new test will start at the beginning of the color cycle.

- **Use test colors only**

If **Use test colors only** is **checked**, the trace colors in a test loaded from disk will be maintained, and new and appended sweeps for this test will maintain the test colors.

If **Use test colors only** is **unchecked**, any new and appended sweeps will begin with cyan and move through the color cycle.

■ **On Append file data:**

- **Cycle trace colors**

When you are appending a sweep from disk to a sweep in memory using the **File Append** command and **Cycle trace colors** is **checked**, the appended sweep will start at the next color in the current sweep and move normally through the color cycle.

If **Cycle trace colors** is **unchecked**, the colors of the sweep you are appending from disk will be maintained and not be overridden by the color cycle.

The Graph **Copy to clipboard** options are:

■ **Background Color:**

- **White “As Metafile”**

If **White “As Metafile”** is checked, the **Edit > Copy Panel to Clipboard** command copies the current graph to the Windows clipboard as a vector graphic drawing in the Windows metafile format. The graph is rendered as black and colored lines on a white background.

- **Black “As Bitmap”**

If **Black “As Bitmap”** is checked, the **Edit > Copy Panel to Clipboard** command copies the current graph to the Windows clipboard as a bitmap image in the Microsoft bitmap format. The graph is rendered as white and colored lines on a black background, as it appears in the Graph panel.

Other Utilities Menu Commands

Restore Hardware

If the 2700 series instrument hardware has lost power or its APIB connection, the **Utilities > Restore Hardware** command will set the instrument to the current software settings.

Utilities > Restore Hardware can also be used as a hardware reset if the instrument does not appear to be responding normally.

Hardware Status

Figure 403. The Hardware Status panel.



The **Utilities > Hardware Status** command opens the System Status and Information dialog box, which reports a number of 2700 series software and instrument hardware conditions.

Turn All Outputs OFF / ON

The **Utilities > Turn All Outputs Off** issues the same command as the function key **F12**, the “panic button.” Either of these turns off all generator outputs.

The **Utilities > Turn Outputs Back On** issues the same command as the key combination **Ctrl-F12**. Either of these turns on any generator outputs previously turned off by the panic button.

Clear Log File

This command clears all the information from the log file. It does not delete the file, but leaves it empty. See **The Log File** on page 522.

View Log File

This command opens the log file in the associated text editor (usually Windows Notepad) for viewing or printing. See **The Log File** on page 522.

Learn Mode

Learn Mode records every appropriate operation of the 2700 series control software to an AP Basic macro file. It is similar to features in other applications called *macro recorders*. Learn Mode is often the easiest way to create a macro.

Choose **Utilities > Learn Mode** to enter Learn Mode. An AP Basic macro will open in the Macro Editor, and each control software setting you make is entered in AP Basic in the Macro Editor, as you work.

On the Utilities menu a checkmark will remain next to the **Learn Mode** choice while in Learn Mode, and the shape of the mouse pointer will change to that of an audio cassette, indicating that a recording is being made.



Choose **Utilities > Learn Mode** to exit Learn Mode. The mouse pointer will return to its normal shape, the checkmark next to Learn Mode will disappear and you will be prompted to save the macro.

See Chapter 26 for more information on automating tests with AP Basic.

Multitone Creation

A multitone creation utility has been provided with the 2700 series to facilitate making custom arbitrary waveform files for multitone testing. Choose **Utilities > Multitone Creation** to open the program.

See **Creating Multitone Waveform Files** on page 348.

Software License Management

A new Software License Management feature is available here to view or change the activation status of the OPT-2711 Dolby Digital Generator license, if you have purchased, installed and activated that option. For more information go to OPT-2711 Licensing on page 223.

Appendix A


Units of Measurement

Introduction

Many different units of measurement are used to describe audio signals and audio system components and characteristics. The 2700 series offers a wide choice of units of measurement for both setting and reading values.

- Values can be expressed in absolute terms such as the volt, the watt, the ohm, the hertz and the second.
- Values can also be displayed as the ratio of one value to another with units like the decibel or percent.
- In addition, the 2700 series provides relative units which express the relationship of a value to a user-supplied reference, or to another 2700 setting.

Figure 404. Selecting Units of Measurement for readings and settings.



Depending on the current configuration and the parameter you are setting or observing, different units choices will be available. Any reading display or set-

ting field which has a drop-down arrow offers a list of units of measurement. Click the arrow to display the list and choose the units you prefer. When you request a value in different units, the 2700 series control software does the calculation for you.

The decibel

The decibel or dB, in one form or another, is arguably the most widely-used unit of measurement in the field of audio. The ear's response to both sound amplitude and frequency is usually best examined in logarithmic terms, and the dB, being a logarithmic unit of measurement, is often the right choice.

It is important to remember that the dB is always a ratio of two values, and for a meaningful expression both of the values must be known. While "8 dB" means nothing, "8 dB below the input signal" gives us a reference and is a meaningful statement. Whenever using the simple dB unit, the expression must identify the reference value.

A large collection of units of measurement (we've seen it referred to as "the dB zoo") uses the decibel ratio with the reference stated as part of the definition of the unit. Examples include dBV (decibels in relation to 1 V rms); dBu (decibels in relation to .7746 V rms); dBFS (decibels in relation to digital full scale); dB SPL (decibels of sound pressure in relation to 20 micropascals of pressure) and so on.

The formula for decibels in voltage amplitudes is

$$dB = 20 \log_{10} \left(\frac{V_1}{V_2} \right)$$

where V_1 and V_2 are the two related voltages.

The formula for decibels in power amplitudes is

$$dB = 10 \log_{10} \left(\frac{P_1}{P_2} \right)$$

where P_1 and P_2 are the two related powers.

Analog Amplitude Units

V—volts (unqualified). This unit is used only on the Analog Analyzer, the DSP Audio Analyzer and the Harmonic Distortion Analyzer panels. In all meters and reference fields *except* the Analog Analyzer and the DSP Audio Analyzer Function meters, **V** means volts (rms). Since the Function meters have switchable detectors, the **V** units selection takes a qualification from the detector selection; that is, V (rms), V (Peak), V (quasi-peak) and so on.

Vrms—volts (rms). This unit is used only on the Analog Generator and Digital Generator panels, and this setting accurately calibrates the generator output

in **Vrms** when a sine wave is being generated. When using other waveforms (such as noise, square waves, multitone, IMD test signals, and so on) with **Vrms**, the signal has the same peak-to-peak voltage as a sine wave at that setting, as shown in Figure 405. **Vrms** is an open-circuit value and the actual output voltage will be less with a load.




Figure 405. 2700 series generator output calibrations

Vp—volts (peak). This unit is used on the output setting fields on the Analog Generator and Digital Generator panels and on the DSP Audio Analyzer and Harmonic Distortion Analyzer meters. This calibration assumes a sine wave, and is arithmetically scaled to the **Vrms** value by $\sqrt{2}$, approximately 1.414. Since non-sinusoidal waveforms are calibrated to have the same peak-to-peak value as a sine wave, the **Vp** unit should be correct for most non-sinusoidal waveforms. When used with the Analog Generator, **Vp** is an open-circuit value and the actual output voltage will be less with a load.

Vpp—volts (peak-to-peak). This unit is used on the output setting fields on the Analog Generator and Digital Generator panels, on the DSP Audio Analyzer and Harmonic Distortion Analyzer meters and on the DIO **Input** meter. This calibration assumes a sine wave, and is arithmetically scaled to the **Vrms** value by $2 \cdot \sqrt{2}$, approximately 2.828. Since non-sinusoidal waveforms are calibrated to have the same peak-to-peak value as a sine wave, the **Vpp** unit should be correct for most non-sinusoidal waveforms. When used with the Analog Generator, **Vpp** is an open-circuit value and the actual output voltage will be less with a load.

W—watts. This unit of power is used on the Analog Generator and the Analog Analyzer panel. Watts is calculated based on the $P = V^2/R$ relationship. On the Analog Generator panel, V is the setting in **Vrms**, and R is the combination of the instrument source resistance and the resistance of the external load; for an accurate setting, you must enter the value of the load resistance in the **References: Watts** field on the generator panel. On the Analog Analyzer panel, V is the measured rms voltage and R is the value of the source resistance, which you must enter in the **References: Watts** field on that panel.

dBm—decibels relative to 1 mW. Like **Watts**, the **dBm** is a unit of power used on the Analog Generator and the Analog Analyzer panels. **dBm** is calculated based on the $P = V^2/R$ relationship. On the Analog Generator panel, V is the setting in V_{rms} , and R is the combination of the instrument source resistance and the resistance of the external load; for an accurate setting, you must enter the value of the external (DUT) load resistance in the **References: dBm** field on the generator panel. On the Analog Analyzer panel, V is the measured rms voltage and R is the value of the source resistance, which you must enter in the **References: dBm** field on that panel. You can terminate the source at the Analyzer input by selecting 600 Ω as the input impedance for that channel, at the top of the Analog Analyzer panel. 600 Ω is the most common circuit impedance value for dBm measurements.

*NOTE: dBm is rarely the correct choice of units for audio measurements. dBm units are often mistakenly chosen when dBu units should be used. See the sidebar **dBm versus dBu** on page 533.*

dBu—decibels relative to 0.7746 V rms. This is usually the correct choice of units for audio levels in professional audio equipment and systems. The dBu is a voltage unit and, unlike the dBm, is independent of circuit impedance. When used with the Analog Generator, **dBu** is an open-circuit value and the actual output voltage will be less with a load. See the sidebar **dBm versus dBu** on page 533.

dBm versus dBu

The dBm unit of measurement is a legacy from earlier days of audio technology, when measuring the audio power transferred in impedance-matched circuits was important. The dBm is a unit of power (referenced to 1 mW), and the audio circuits of the day often had an impedance of 600 Ω . The voltage drop across a 600 Ω resistor dissipating 1 mW is 0.7746 V, and this voltage (which reads 0 dBm on a dBm meter across 600 Ω) came to be regarded as “zero level” in professional audio circles.

However, many audio circuits do not have a 600 Ω impedance. Microphone circuits may be 150 Ω , and headphone circuits may be 50 Ω . This is even more true in modern design, where circuit outputs often have very low impedances (from almost zero to a few tens of ohms) and input circuits often are “bridging,” with impedances of 1500, 10,000 or even 50,000 Ω . A milliwatt dissipated in any of these circuits will not read 0.7746 V, and the dBm meter (which is simply a voltmeter calibrated for a 600 Ω circuit) will be in error. The circuit impedance must always be taken into account in power measurements.

Because of this, the dBm can be misleading. It has fallen out of use in the last 20 years (except for specific applications where power transfer is an important consideration and the circuit impedances are known) and its place in professional audio has been taken by the dBu, where the “u” can be taken to mean “unloaded.”

The value of 0 dBu, 0.7746 V rms, is the voltage developed across a 600 Ω resistor when 1 mW is being dissipated in that resistor; the same voltage as 0 dBm in that impedance; in 600 Ω , dBu = dBm. The advantage of the dBu is that it is a valid measurement in audio circuits of any impedance.

Unless you know the circuit impedance and have a clear reason to use the dBm reference, use dBu.

dBV—decibels relative to 1.000 V rms. This is usually the correct choice of units for audio levels in consumer audio equipment and systems. The dBV is a voltage unit and, like the dBu, is independent of circuit impedance. When used with the Analog Generator, **dBV** is an open-circuit value and the actual output voltage will be less with a load.

Digital Amplitude Units

FS: Digital Full Scale

All of the units for digital domain audio amplitudes refer to digital full scale. In pulse-code-modulation (PCM) audio, the amplitude of each audio sample is represented as a number. The maximum and minimum values of these numbers vary with the digital word length, but they are precisely defined. A signal which attempts to exceed these values can drive a digital system into overload; in a popular expression, the signal “runs out of numbers.”

Word Length	Positive Full-Scale Value	Negative Full-Scale Value
16-bit	7FFF Hex	8000 Hex
24-bit	7FFFFFF Hex	800000 Hex

The Audio Engineering Society defines digital full scale in terms of a sine wave whose peaks just reach the maximum positive and negative digital codes. The rms value of this sine wave is the full-scale reference, defined as 1 FFS or 0 dBFS. Note that other waveforms (noise or music, for example) have different crest factors than a sine wave (crest factor is the ratio of a signal’s peak amplitude to its rms amplitude) and will have different rms values at the amplitude at which their peaks just reach the maxima.

A consequence of defining full scale as an rms value is that high-level signals that have a lower crest factor than a sine wave can display rms values greater than 1 FFS or 0 dBFS, even though the digital maximum and minimum codes are not exceeded. For example, a square wave whose top and bottom are at the maximum digital codes will have an rms value of 1.414 FFS or +3.01 dBFS. See Figure 406.

FFS—fraction of full scale, simply the ratio of the rms value of the signal to the full-scale value, expressed as a decimal fraction. A sine wave half the value of full scale would be indicated as 0.5 FFS. The lower levels often encountered in practical audio applications may be displayed as mFFS (milli fractions-of-full-scale, or FFS / 1000) and μ FFS (micro fractions-of-full-scale, or FFS / 1000000).

%FS—percent of full scale. This is the FFS value multiplied by 100. For example, a signal at 0.8 FFS is 80 % FS.

dBFS—decibels relative to full scale. This is a logarithmic measurement defined as $20 \cdot \log_{10}(FFS)$. For example, a signal at 0.1 FFS equals –20 dBFS.

dBFS is probably the most common unit of measurement used for digital audio amplitudes. 0 dBFS is the full-scale reference.




Figure 406. The square wave has a lower crest factor than the sine wave. Since dBFS is defined in rms terms, a square wave with the same peak value as a 0 dBFS sine wave will have a value of 3.01 dB FS.

Bits—“Bits” is another way of discussing the dynamic range of a digital converter, by converting a measured dynamic range value to the equivalent number of bits (the digital word length) that a signal would theoretically require to attain that dynamic range. The calculations take into account the effect of quantizing noise in the LSB by the 1.76 dB offset.

For example, the theoretical dynamic range of a 16-bit system can be calculated to be about 98.1 dB, using this formula:

$$\text{Dynamic Range} = 6.02 \cdot \text{number of bits} + 1.76 \text{ dB}$$

Conversely, a dynamic range of 98.1 dB can be expressed as 16 bits.

Levels can also be expressed in this notation. The 2700 series **bits** unit is computed from dBFS using the following relationship, where *dB* is the level to be expressed, relative to full scale:

$$\text{bits} = \left(\frac{\text{dB} + 1.76}{6.02} \right).$$

For example, a signal at 0.0001 FFS, or –80 dBFS, can also be stated as –12.99 bits.

NOTE: A consequence of the 1.76 dB offset is that a 0 dBFS signal displays a bits value of +0.29. A signal at –1.76 dB reads exactly zero bits.

Digital Data Units

dec, hex—decimal and hexadecimal (or hex). These units express the numerical value of the embedded audio at a sample in either base 10 (decimal) or base 16 (hexadecimal) notation, and are used for Data and Error readings in the Digital Data Analyzer (Bittest). Dec and hex are also available as Digital Generator units, where they are useful in setting levels for the **Sine** and **Special: Constant Value** (digital dc) waveforms analyzed by the Digital Data Analyzer, and for the **Offset** (dc) parameter of the **Sine: Offset** waveform. When used with the ac waveforms of the Digital Generator, the dec and hex values refer to the signal peak value.

Ratio Units

%—percent. The percent unit expresses the ratio of two numbers multiplied by 100. For example, a ratio of 0.7 is expressed as 70%.

dB—decibel. The decibel is always a ratio of two amplitudes, expressed logarithmically. For voltage amplitudes, decibels are computed by

$$dB = 20 \log_{10} \left(\frac{V_1}{V_2} \right).$$

See the sidebar on decibels, page 530.

PPM—parts per million. Parts per million expresses the ratio of two numbers, multiplied by 1,000,000. For example, a ratio of 0.00005 equals 50 PPM.

X/Y—The X/Y unit is the simple ratio between two numbers.

NOTE: Specific ratio units, such as dBu or %Hz, are discussed in more detail in the relevant sections on amplitude or frequency units.

Relative Units

dBg—decibels relative to the Analog Generator amplitude setting.

dBr—decibels relative to a user-defined reference. The generators and the analyzer have separate, independent **dBr** or **dBr A/dBr B** fields in the **References** area of their respective panels. You can manually enter **dBr** values from the keyboard, or you can capture current values for certain **Reference** fields as follows:

- Analog Generator dBr: Function Key **F3** or Edit Menu command **Set Generator dBr Ref.**

- Analyzer dBr: Function Key **F4** or Edit Menu command **Set Analyzer dBr Ref.**

dBrInv—decibels relative to a user-defined reference, inverted. This is exactly as described under **dBr** just above, but plotted upside down so that smaller or negative values are at the top of the graph, and larger or positive values are at the bottom.

The **dBrInv** units are commonly used in conjunction with Regulation mode, such as when measuring frequency response of a pre-emphasized broadcast transmitter. Inverted plotting of the generator levels required to produce constant modulation percentages produces the expected shape of the transmitter frequency response.

Frequency Units

Hz—hertz. This is the basic frequency unit, expressing the number of cycles of a signal in one second.

*NOTE: Except for hertz, the frequency units used in 2700 series measurements are relative units, expressing the relationship of the measured frequency to a reference frequency you have entered into the **References > Freq:** fields in the generator and analyzer panels.*

F/R—This is a frequency ratio unit, obtained by dividing the measured frequency F by the reference frequency R .

dHz—delta hertz. dHz is the difference in frequency between the measured frequency and the reference frequency:

$$dHz = F - R.$$

%Hz—percent hertz. %Hz is obtained by dividing the measured frequency by the reference frequency and multiplying the result by 100:

$$\%Hz = 100 \cdot (F/R).$$

For example, a measured frequency of 950 Hz would be expressed as 95.0 %Hz of a reference frequency of 1 kHz.

cent—the cent unit is 1/100 of a musical half-tone interval, which in turn is the 12th root of 2:

$$cent = \frac{\sqrt[12]{2}}{100} \text{ Hz}.$$

octs—octaves. An octave is a frequency ratio of 2:1. For example, with a reference frequency of 1 kHz, a 2 kHz tone is expressed as +1.0 octave and a 500 Hz tone is expressed as -1.0 octave.

decs—decades. A decade is a frequency ratio of 10:1. For example, with a reference frequency of 500 Hz, a 5 kHz tone is expressed as +1.0 decade and a tone of 50 Hz is –1.0 decade.

d%—delta percent. d% is 100 times the ratio of dHz (or $F - R$) to the reference frequency R :

$$d\% = 100 \cdot \left(\frac{F - R}{R} \right).$$

For example, with a reference frequency of 1 kHz and a measured frequency of 950 Hz, the d% value is –5 %.

dPPM—delta parts per million. The dPPM unit is 1,000,000 times the ratio of dHz (or $F - R$) to the reference frequency R :

$$dPPM = 1,000,000 \cdot \left(\frac{F - R}{R} \right).$$

For example, with a reference frequency of 1 kHz and a measured frequency of 1,001 Hz, the dPPM value equals 1,000 dPPM.

Phase Unit

deg—degree. The degree is the basic unit of phase measurement, representing 1/360 of a complete revolution of phase.

Time Units

s, or **sec**—seconds. Seconds are the basic time unit, abbreviated s. At values common in audio, the display may be in ms (milliseconds), μ s (microseconds) or ns (nanoseconds).

UI—unit interval. The unit interval is a convenient unit when examining digital interface signal timing, because by definition the UI is relative to the signal being measured; it scales with the interface data rate. The UI is defined as the *shortest nominal time interval in the coding scheme*. For an AES3 or IEC 60958 signal there are 2 subframes of 32 bits per frame, giving 64 bits per frame; after bi-phase mark encoding the pulse rate is nominally 128 pulses per frame. This interval, 1/128 of a frame, is the unit interval for AES3 and IEC 60958 signals.

For a 44.1 kHz sampling rate, $1\text{ UI} / (128 \times 44100) = 177.2\text{ ns}$;

For a 48 kHz sampling rate, $1\text{ UI} / (128 \times 48000) = 162.8\text{ ns}$;

For a 96 kHz sampling rate, $1\text{ UI} / (128 \times 96000) = 81.4\text{ ns}$.

dBUI—decibels relative to 1 unit interval. The dBUI provides a logarithmic time unit scaled to the interface signal and is primarily used for FFT plots of jitter amplitude.

DCX-127 Units

The DCX-127 Multifunction Module brings additional measurement capabilities to the 2700 series, and with these features come additional units of measurement. See the *DCX-127 User's Manual* for more information.

DCX-127 Amplitude Units

Vdc—volts, dc. This is the basic unit of direct current (dc) electromotive force.

f(V)—“f of V ” is a value which is a function of voltage. f(V) is computed from

$$f(V) = (V + offset) \times scale.$$

DCX-127 Resistance Units

Ohms—ohms. This the basic unit of electrical resistance, also shown by the symbol Ω .

f(O)—“f of O ” is a value which is a function of resistance. f(O) is computed from

$$f(O) = (ohms + offset) \times scale.$$

DCX-127 Digital Input and Output Units

dec—decimal. The decimal (dec) unit converts the DCX-127 digital input and output between binary and decimal representation.

hex—hexadecimal. The hexadecimal (hex) unit converts the DCX-127 digital input and output between binary and hexadecimal representation.

oct—octal. The octal unit converts the DCX-127 digital input and output between binary and octal representation.

g(x)—(input). Like the scaled voltage and resistance units, g(x) enables you to scale digital input units. The g(x) unit is computed from

$$g(x) = x \cdot scale.$$

h(x)—(output). Like the scaled voltage and resistance units, h(x) enables you to scale digital output units. The h(x) unit is computed from

$$h(x) = \frac{x}{scale}.$$

Appendix B

The Digital Audio Signal

This is a brief introduction to the most common digital audio formats, defined in AES3 and IEC 60958. For more detailed information, standards and other informative documents are available from these organizations at their Web sites at www.aes.org and www.iec.ch.


For an in-depth look at digital signal analysis, we recommend *Digital Audio Measurement Techniques* by Julian Dunn. This book is published by Audio Precision and is available on our Web site at ap.com or from an Audio Precision sales representative.

Introduction

Almost all digital audio signals are a form of pulse code modulation (PCM). When an analog signal is digitized, the waveform is sampled at a regular rate (the sample rate) and the amplitude of the waveform at each sampling instant is acquired. Each value is encoded as a binary number, and each number is called a digital word. Placed end-to-end, the words form a string of pulses representing the binary numbers at each sampling instant.

PCM audio can be characterized in a number of ways, chief among them the sampling rate used and the degree of resolution of the numbering system. The sample rate can be low, such as the 8 kHz rate used in telecommunications; or high, such as the 192 kHz sometimes used for high-performance mu-

Figure 407. A 3 kHz sine wave sampled at 48 kHz.



sic recordings. Common sample rates are the 44.1 kHz rate used in Compact Disc (CD) recording, or the 48 kHz rate used in most broadcast and professional audio recording. A key consideration in sample rate selection is signal bandwidth, which is always limited to one-half the sample rate, referred to as $F_s/2$ or the Nyquist frequency.

The numerical resolution of the signal depends on the number of bits assigned to encode the signal value. This is called the *word length*. Word length (or resolution) also varies between different systems, from perhaps 8 bits (256 discrete levels) to as high as 24 bits (16,777,216 discrete levels).

The Serial Digital Interface Signal

For reliable transmission and reception the PCM audio is encoded into an *interface signal* according to one of several international standards. The interface signal adds channel and synchronization identification, status information, and error correction, and embeds the clock signal into the data stream.




Figure 408. The AES3 serial interface signal data pattern.

The AES3 and IEC 60958 standards define the digital audio interface signal for both professional and consumer use. There are several variations set out in the standards that are, for the most part, compatible.

The professional format is most often referred to as AES3, but is also called AES/EBU or IEC 60958-4. There are also other variations of the professional format, such as AES3id and SMPTE 276M. These have the same data pattern but different electrical characteristics.

The consumer format is defined by IEC 60958-3, and is also called SPDIF or EIAJ. The consumer format differs from the professional in electrical characteristics and in the interpretation of Status Bits.

The standards specify not only the pattern and encoding of the PCM audio and other data, but also the electrical and mechanical aspects of the interface. The 2700 series balanced digital connectors conform to AES3, and the unbalanced connectors (including the SYNC/REF BNC on the rear panel) satisfy AES3id. All 2700 series digital inputs and outputs will work with the data patterns of either the AES3/IEC 60958-4 professional format or the IEC 60958-3 consumer format. Output format is selectable in software.

We will use the AES3 professional standard as a model for this discussion. For the purposes here, only the Status Bits interpretation is different for the consumer format.

Bi-phase Mark Encoding

To carry a consistent clock and provide for a robust transmission signal, the interface data is processed by bi-phase mark encoding. This scheme provides a transition at the beginning of every data bit, and a second transition in the center of the bit if the bit is a data “1.” Bi-phase mark encoding ensures that there is at least one transition for each data bit, no matter what the state of the bit is.

The bi-phase mark pattern is broken for the three types of preambles, as a means of identifying the frame, subframe and block beginnings.

The Frame and Subframe

Figure 408 shows the AES3 data pattern. The *frame* is the basic subunit, and is comprised of two *subframes*, called *subframe A* and *subframe B*. The frame rate is normally the same as the sample rate: a signal sampled at 44.1 kHz will normally be carried on an interface signal running at 44,100 frames per second.

Each subframe carries one word of audio. Normally subframe A will carry a word of audio A, nominally the left channel; subframe B usually carries audio B, the right channel. Other assignments may be made, though, and in dual connector operation both subframes A and B may be subsequent words of the same audio channel, with the second channel carried on the second connector. In multitrack applications, subframes A and B may carry audio channels 7 and 8, for example. Each subframe has the following structure:



Figure 409. The AES3 frame.

First there is a *preamble*, which has a length of 4 data bits. The preambles are used for identification and synchronization of the frames and subframes. The X preamble indicates the subframe A beginning, the Y preamble indicates subframe B, and the Z preamble indicates subframe A and the beginning of the Channel Status and User blocks.

Following the preamble are 24 bits reserved for the audio word; with shorter audio words the remaining bits are unused, although bits 4–7 can be re-assigned as *auxiliary bits*. The audio word is arranged with the least significant bit (LSB) first.

After the audio word are four administrative bits, the V bit (Validity), the U bit (User), the C bit (Channel Status) and the P bit (Parity).

The V bit and the P bit carry data which apply only to their particular subframe. If the V bit is 1, the audio data in that subframe is marked as invalid. The P bit is set to give even parity for the subframe.

The C and U bits do not carry information about one particular subframe; instead, these bits are gathered together in blocks of 192 bits. The block beginnings are identified by the Z preamble.

The C bits and the U bits are gathered separately into the Channel Status block and the User block. Although Status and User blocks built by subframes A and B usually contain the same information, it is possible to carry different Status or User data in the A and B subframes.

The 2700 series reads and sets all Channel Status conditions, but does not display or set User bits.

Channel Status

The Channel Status information differs substantially between the professional and the consumer formats. The first bit in the block indicates professional format by a 0 and consumer format by 1.

The following tables show the channel status fields and their interpretations for both the professional and consumer formats.

Consumer format channel status field interpretations																																											
Bits	label	interpretation																																									
0	pro/con	0: consumer; 1: professional format																																									
1	non-audio	0: suitable for conversion to analog audio using linear PCM 1: not suitable																																									
2	copyright	0: asserted; 1: not asserted																																									
3–5	emphasis	000: Emphasis not indicated 100: emphasis—CD-type																																									
6–7	channel status mode	00: mode zero; other values reserved																																									
8–15	category code	The category code depends on the equipment type. For most codes the MSB of the category code carries information about generation status of the material (refer to SCMS), and is called the L-bit. The following are common codes: <table><tr><td></td><td>LSB</td><td>MSB</td></tr><tr><td>General</td><td>0000</td><td>000L</td></tr><tr><td>Laser-Optical</td><td>100x</td><td>xxxL</td></tr><tr><td>D/D Converter</td><td>010x</td><td>xxxL</td></tr><tr><td>Magnetic</td><td>110x</td><td>xxxL</td></tr><tr><td>Digital Broadcast</td><td>001x</td><td>xxxL</td></tr><tr><td>and</td><td>0111</td><td>xxxL</td></tr><tr><td>Musical Instrument</td><td>101x</td><td>xxxL</td></tr><tr><td>DVD</td><td>1001</td><td>100L</td></tr><tr><td>Present A/D Converter</td><td>0110</td><td>0xxL</td></tr><tr><td>Future A/D Converter</td><td>0110</td><td>1xxL</td></tr><tr><td>Solid State Memory</td><td>0001</td><td>xxxL</td></tr><tr><td>Experimental</td><td>0000</td><td>001L</td></tr></table>				LSB	MSB	General	0000	000L	Laser-Optical	100x	xxxL	D/D Converter	010x	xxxL	Magnetic	110x	xxxL	Digital Broadcast	001x	xxxL	and	0111	xxxL	Musical Instrument	101x	xxxL	DVD	1001	100L	Present A/D Converter	0110	0xxL	Future A/D Converter	0110	1xxL	Solid State Memory	0001	xxxL	Experimental	0000	001L
	LSB	MSB																																									
General	0000	000L																																									
Laser-Optical	100x	xxxL																																									
D/D Converter	010x	xxxL																																									
Magnetic	110x	xxxL																																									
Digital Broadcast	001x	xxxL																																									
and	0111	xxxL																																									
Musical Instrument	101x	xxxL																																									
DVD	1001	100L																																									
Present A/D Converter	0110	0xxL																																									
Future A/D Converter	0110	1xxL																																									
Solid State Memory	0001	xxxL																																									
Experimental	0000	001L																																									
16–19	source number	(bit 16 is LSB)																																									
20–23	channel number	(bit 20 is LSB)																																									
24–27	sampling frequency	0000: 44.1 kHz 0100: 48 kHz 1100: 32 kHz xxxx: 24 kHz xxxx: 22.05 kHz xxxx: 192 kHz xxxx: 176.4 kHz xxxx: 96 kHz xxxx: 88.2 kHz																																									
28–29	clock accuracy	10: Level I, ±50 ppm 00: Level II, ±1000 ppm 01: Level III, variable pitch shifted																																									
30–31	reserved																																										
32	word length (field size)	0: Maximum length 20 bits 1: Maximum length 24 bits																																									
33–35	word length	<table><tr><td>000:</td><td>if bit 32 = 1</td><td>if bit 32 = 0</td></tr><tr><td>101:</td><td>not indicated</td><td>not indicated</td></tr><tr><td>001:</td><td>24 bits</td><td>20 bits</td></tr><tr><td>010:</td><td>23 bits</td><td>19 bits</td></tr><tr><td>010:</td><td>22 bits</td><td>18 bits</td></tr><tr><td>011:</td><td>21 bits</td><td>17 bits</td></tr><tr><td>100:</td><td>20 bits</td><td>16 bits</td></tr></table>	000:	if bit 32 = 1	if bit 32 = 0	101:	not indicated	not indicated	001:	24 bits	20 bits	010:	23 bits	19 bits	010:	22 bits	18 bits	011:	21 bits	17 bits	100:	20 bits	16 bits																				
000:	if bit 32 = 1	if bit 32 = 0																																									
101:	not indicated	not indicated																																									
001:	24 bits	20 bits																																									
010:	23 bits	19 bits																																									
010:	22 bits	18 bits																																									
011:	21 bits	17 bits																																									
100:	20 bits	16 bits																																									
36–39	reserved																																										
40–191	reserved																																										

Byte	Professional format channel status fields															
0	Pro/con = 1	Non- audio	Emphasis				Lock		Sample frequency							
	0	1	2	3	4	5	6	7								
1	Channel mode						User bit management									
	8	9	0	1	2	3	4	5								
2	Use of auxiliary mode sample bits						Source word length				Alignment level					
	6	7	8	9	0	1	2	3	4	5	6	7	8	9		
3	Channel Identification for multichannel application															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
4	DARS			Sample frequency (fs)										fs scaling		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
5	Reserved															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
6	Alphanumeric channel origin data (first character)													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
7	Alphanumeric channel origin data													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
8	Alphanumeric channel origin data													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
9	Alphanumeric channel origin data (last character)													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
10	Alphanumeric channel destination data (first character)													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
11	Alphanumeric channel destination data													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
12	Alphanumeric channel destination data													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
13	Alphanumeric channel destination data (last character)													= 0		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
14	Local sample address code (32-bit binary, LSW)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
15	Local sample address code (32-bit binary)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
16	Local sample address code (32-bit binary)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
17	Local sample address code (32-bit binary, MSW)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
18	Time of day code (32-bit binary, LSW)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
19	Time of day code (32-bit binary)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
20	Time of day code (32-bit binary)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
21	Time of day code (32-bit binary, MSW)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
22	reserved										Reliability flags					
											bytes 0-5	bytes 6-13	bytes 14-17	bytes 18-21		
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
23	Cyclic redundancy check character (CRCC)															
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15

Professional format channel status field interpretations				
Bits	label	interpretation		
0	pro/con	0: consumer; 1: professional format		
1	non-audio (or, more accurately, "not linear PCM")	0: audio data is linear PCM samples 1: other than linear PCM samples		
2–4	emphasis	000: Emphasis not indicated 100: No emphasis 110: CD-type emphasis 111: J-17 emphasis		
5	lock	0: not indicated 1: unlocked		
6–7	sampling frequency	00: not indicated (or see byte 4) 10: 48 kHz 01: 44.1 kHz 11: 32 kHz		
8–11	Channel mode (SCDSR = single channel double sample rate)	0000: not indicated (default to 2 ch) 0001: 2 channel 0010: 1 channel (monophonic) 0011: primary / secondary 0100: stereo 0101: reserved for user applications 0110: reserved for user applications 0111: SCDSR (see byte 3 for ID) 1000: SCDSR (stereo left) 1001: SCDSR (stereo right) 1111: Multichannel (see byte 3 for ID)		
12–15	user bit management	0000: no indication 0001: 192-bit block as channel status 0010: As defined in AES18 0011: user-defined 0100: As in IEC60958-3 (consumer)		
16–18	use of aux sample word	0000: not defined, audio max 20 bits 0001: used for main audio, max 24 bits 0010: used for <i>coord</i> , audio max 20 bits 0011: user-defined		
19–21	source word length		if max = 20 bits	if max = 24 bits
		000:	not indicated	not indicated
		001:	23 bits	19 bits
		010:	22 bits	18 bits
		011:	21 bits	17 bits
		100:	20 bits	16 bits
		101:	24 bits	20 bits

Professional format channel status field interpretations (Cont.)		
Bits	label	interpretation
22–23	alignment level	00: not indicated 01: –20 dB FS 10: –18.06 dB FS
24–31	channel identification	if bit 31 = 0 then channel number is 1 plus the numeric value of bits 24–30. if bit 31 = 1 then bits 4–6 define a multichannel mode and bits 0–3 give the channel number within that mode.
32–33	digital audio reference signal (DARS)	00: not a DARS 10: DARS grade 2 (+ / –10 ppm) 01: DARS grade 1 (+ / –1 ppm)
35–38	sampling frequency	0000: not indicated 1000: 24 kHz 0100: 96 kHz 1100: 192 kHz 1001: 22.05 kHz 0101: 88.2 kHz 1101: 176.4 kHz 1111: User defined
39	sampling frequency scaling	0: no scaling 1: apply factor of 1 / 1.001 to value
48–79	alphanumeric channel origin	four-character label using 7-bit ASCII with no parity. Bits 55, 63, 71, 79 = 0.
80–111	alphanumeric channel destination	four-character label using 7-bit ASCII with no parity. Bits 87, 95, 103, 111 = 0.
112–143	local sample address code	32-bit binary number representing the sample count of the first sample of the channel status block.
144–175	time of day code	32-bit binary number representing time of source encoding in samples since midnight
176–183	reliability flags	0: data in byte range is reliable 1: data in byte range is unreliable
184–191	CRCC	00000000: not implemented X: error check code for bits 0–183

Byte	Consumer format channel status fields							
0	Pro/con = 0	Non- audio = 0	Copyright	Emphasis			Channel status mode = 00	
	0	1	2	3	4	5	6	7
1	Category code							
	0	9	0	1	2	3	4	5
2	Source number				Channel number			
	0	7	8	9	0	2	2	2
3	Sampling frequency				Clock accuracy			
	0	0	0	2	0	0	0	3
4	Word length				(Future original sampling frequency?)			
	0	3	0	5	6	7	8	9
5–23	Reserved							
	0							

Serial Interface Measurements

The 2700 series provides tools to examine and test both the embedded audio signal and the serial interface signal.

The 2700 series monitors and analyzes the embedded digital audio signal using analysis tools in the Digital Analyzer panel, such as the DSP Audio Analyzer, the Spectrum Analyzer, the Multitone Audio Analyzer the MLS Analyzer and the Harmonic Distortion Analyzer. Many interface-related problems can show up as symptoms in these embedded audio measurements.

The 2700 series can directly monitor the interface signal on the Digital Input/Output (DIO) panel, which provides direct read-out and control of interface configuration, format, voltage, resolution, sample rate, jitter, status bits and more.

A more powerful tool is the Digital Analyzer's Digital Interface Analyzer (Intervu). The Digital Interface Analyzer uses a dedicated 80 MHz ADC that digitizes the interface data stream for DSP analysis and applies special software measurement tools in the analysis. Using the Digital Interface Analyzer, you can measure and display the interface waveform and spectrum, create an eye pattern, show the jitter waveform and spectrum and display histograms of interface amplitude, interface rate, interface bit width and jitter.

Appendix C

FFTs

The Fast Fourier Transform

The Fast Fourier Transform, or FFT, is a mathematical technique that deconstructs a complex waveform into its component sine waves. Presented with a segment of data which represents the amplitude vs. time relationships of a complex waveform, an FFT will derive two sets of results: the amplitude spectrum (amplitude vs. frequency) and the phase spectrum (phase vs. frequency) of the signal. This information is sufficient to describe the relationships of the sine waves which make up the waveform, and with further computation the FFT results can be interpreted for several different types of display.

NOTE: In the 2700 series, the amplitude spectrum results and the phase spectrum results are stored in a memory area called the Transform Buffer. These results are read and recomputed for the various display options.

Much of the signal analysis in the 2700 series is performed using FFT techniques. The Spectrum Analyzer, the Digital Interface Analyzer, the Multitone Analyzer, the MLS Analyzer and the Harmonic Distortion Analyzer all depend on FFTs. The results are usually displayed as frequency-domain spectrum analysis graphs, but with recalculation the same data can be interpreted and displayed in other ways. Also, the acquisition can be displayed in the time domain as “oscilloscope” or “waveform” views.

Real Time vs. Batch Mode

In the 2700 series an FFT does not work in “real time,” with continually updating displays. Instead, a sample of the signal is acquired, then transformed mathematically (the FFT), then processed for display and shown on the screen. In Audio Precision instruments this is called “batch mode,” since the data is acquired and processed in discrete “batches.”

The Spectrum Analyzer analysis tool is the most straightforward and flexible of the FFT-based tools in the 2700 series, and we will use it as the example of FFT processing throughout this discussion.

Acquiring Data

The first step in performing an FFT is to acquire signal data, which consists of recording a sample of the signal to a special area in the instrument memory, called the *acquisition buffer*. SYS-2722 has a 4 M sample acquisition buffer for each of the two audio channels.

You can specify the amount of memory to be used in an acquisition, in steps from 800 samples to 4 M samples; or you can set the control software to have the acquisition buffer length track the FFT *record length*, which is discussed below. The duration of the signal acquired will depend upon the acquisition buffer length and the sample rate of the signal, and can be calculated from this formula:

$$\text{Acquisition Duration} = \frac{\text{Acquisition Length}}{\text{Sample Rate}}$$

At a sample rate of 48 kHz, a 4 M acquisition will have a duration of 87.38 seconds.

The FFT Record

The FFT *record* is the section of signal upon which the FFT processing is actually performed. Its length in samples is called the *record length*, or *FFT length*, or *transform length*. The record length must be smaller than or equal to the length of the acquisition.

FFT Bandwidth

The bandwidth of the signal, the sample rate, the record length and the frequency resolution are all related.

As with any digital signal, the bandwidth is limited by the sample rate in this relationship:

$$\text{Bandwidth} = \frac{\text{Sample Rate}}{2}.$$

FFT Bin Width

The two results of an FFT consist of amplitude and phase values for a number of frequencies. The number of frequencies is half the number of samples in the FFT record length.

An FFT length of 8 samples would divide the range from DC to the sample rate into 4 rather wide bands (which are called *bins*), and provide the amplitude and phase values for each of the bins. For more resolution, a greater FFT length is required. An FFT length of 16,384 samples would result in 8,192 bins across the same frequency range.

The *bin width* (also called *line spacing*) is an expression of the frequency resolution of the FFT, and has this relationship to sample rate and record length:

$$\text{Bin Width} = \frac{\text{Sample Rate}}{\text{Record Length}}.$$

With an FFT length of 16,384 samples at a sample rate of 48 kHz, the bandwidth of the FFT would be

$$\frac{48\text{kHz}}{2} = 24\text{ kHz}.$$

The bin width would be

$$\frac{48\text{kHz}}{16,384} = 2.93\text{ Hz}.$$

If a frequency-domain amplitude graph were plotted, it would span the range from 0 Hz to 24 kHz and have 8,192 bins, each 2.93 Hz wide. The amplitude of the energy falling within each bin would be plotted. A spectrum graph of a 800 Hz square wave made with these settings would look like this:




Figure 410. FFT spectrum of 800 Hz square wave using the Equiripple window.

In this FFT you can see the 800 Hz fundamental followed by the series of odd harmonics which are the components of a square wave.

FFT Record Looping

The mathematics of FFT processing see the record as an endless loop of signal, just as if the end of the record was “spliced” to the beginning of the record.




Figure 411.

Truncation of non-synchronous waveform.

In audio editing, if there is any difference in the value or slope of the signal at the moment of the splice, there will be a discontinuity or jump in the waveform at that point. An audio edit will “pop” or “click” at such a discontinuity. The same thing happens in FFT processing: the discontinuity, like an audio pop, contains a great deal of energy spread widely over the frequency spectrum. This energy swamps all but the largest signal peaks and produces a useless set of results and a characteristic spectrum.

Figure 412 shows an FFT of a 100 Hz sine wave with a discontinuity in the record loop. Without a way to deal with loop discontinuities, almost all FFTs would look something like this:




Figure 412. Non-synchronous FFT with no windowing function, 100 Hz sine wave.

Two techniques have been developed to solve this problem. One is FFT *windowing*; the other is the use of *synchronous* FFTs.

FFT Windowing

Let's return briefly to the audio editing example. The click caused by an abrupt transition can usually be eliminated by making the transition gradual: with a razor blade edit, that means an angled cut; with a computer edit, a brief fade-up or cross-fade is used.

FFT windowing is similar. An amplitude envelope called a *window* is imposed upon the record data before the FFT processing. There are a number of different window shapes with different characteristics, but they all share this feature: they taper at the beginning and end of the record. This means that the two ends of the windowed record data match so that there is no discontinuity and the broadband noise is not introduced.




Figure 413. Application of a Hann window function (raised cosine shape) to a sine wave, viewed in the time domain.

The windows *do* modify the acquired signal, however, which is why there are so many to choose from. Windowing spreads the energy in the acquired signal over several bins, and window functions differ in the shape of the resulting spreading. The Flat-Top window, for example, is optimized for flat response at the top of the main lobe, but has poorer resolution of closely-spaced frequencies than other windows; the Hamming window resolves close tones well, but has greater main lobe amplitude error and high side lobes.




Figure 414. Example of a Blackman-Harris window function viewed in the frequency domain.

See page 269 for illustrations and full descriptions of the FFT windowing functions available with a 2700 series instrument.

Synchronous FFTs

Another solution to the FFT looping discontinuity problem is to choose a signal frequency and FFT length such that an integer number of cycles of the signal will exactly fit the record length. When this is accomplished, the beginning and the end of the record will be at adjacent points in the signal, and there will be no discontinuity.

This can only be done when you have precise control of the signal you are using for analysis, and there are many circumstances when that is not possible. But when synchronous FFTs can be used, they bring this great advantage: because the signal has not been modified by a window function, it is unchanged. Energy does not spread across the spectrum, and tremendous low-level detail can be seen. Look at the following four figures, all FFTs of the same 800 Hz sine wave signal:




Figure 415. FFTs of 800 Hz sine wave, with no window, Flat Top window, Hann window, and, finally, adjusted very slightly in frequency (to 799.805 Hz) to be synchronous.

Graphing FFTs

2700 series FFT results are usually displayed as graphs. In 2700 series operation, the number of samples in the record and the number of points or steps requested for the graph are not necessarily the same. You can set up an FFT length of only 256 samples and a graph of 5000 steps, or an FFT 32,768 samples long displayed on a graph of only 10 steps.

The FFT length is determined by your frequency resolution needs and the time involved in acquisition. 16,384 samples is a typical choice.

Here are some guidelines to selecting the number of graphed points:

- Use the least steps that result in a useful graph. Fewer steps provide faster operation.
- There is no purpose in graphing more points than you have samples; a 256 point FFT graphed at 512 steps will display at least 384 redundant points.
- If your end use is a graph on a screen or printed on paper, there is no purpose in graphing more points than your monitor or printer can display. Selections of 500 to 1000 points typically provide excellent graphs.
- If your end use is a table, you may want to specify more graph steps than mentioned above, if you have a high-resolution FFT and you would like a detailed table of values.

Appendix D

User Downloadable Filters

Creating User Downloadable Filters

A User Downloadable Filter consists of a properly formatted text file containing information defining the characteristics of the filter. The filter must be named with one of these extensions:

- for a low-pass filter, .afl;
- for a high-pass filter, .afh;
- for a weighting filter, .afw.

As long as the file meets the specifications set out below, you can create the filter by any means, including the use of a text editor or third-party software that has digital filter design capabilities.

User Downloadable Filter Design Constraints:

- Each file specifies a single infinite impulse response (IIR) filter at one or more sample rates.

Each IIR filter can be implemented by cascading one or more second-order sections, shown here:

$$H(z) = \frac{b_0 + b_1 z^{-1} + b_2 z^{-2}}{1 + a_1 z^{-1} + a_2 z^{-2}}.$$

First-order sections are not allowed; a first-order section can be implemented with the second-order section by setting b_2 and a_2 to zero.

- A low-pass filter may not have more than 6 poles or 6 zeros; that is, a low-pass filter can have at most three second-order sections.
- A high-pass filter may not have more than 4 poles or 4 zeros; that is, a high-pass filter can have at most two second-order sections.

- A weighting filter may not have more than 8 poles or 8 zeros; that is, a weighting filter can have at most four second-order sections.
- Unstable filters are not allowed. An unstable filter is a filter with poles on or outside the unit circle on the z -plane.
- Filters with a gain of zero are not allowed. Such filters would result in all zero outputs.
- No coefficient may be greater than 2.0 or less than -2.0.

A simple text file format is used for each user-designed filter. The file format is specified by the following rules:

- All lines starting with # are comment lines.
- Blank lines, that is, lines consisting of zero or more spaces and tabs, are ignored.
- The parameters for filters are specified in a line-oriented fashion, with one entity specified per line.
- Each line has three components: a predefined *keyword*, followed by a *colon*, followed by the *keyword-dependent data*. Any white space surrounding these components is ignored. Three keywords are defined: **info**, **sample_rate**, and **biquad**.
- The **info** keyword specifies a text string of printable ASCII characters to be displayed on the User Downloadable Filters panel when the “**Filter Info**” box is clicked. The **info** comment must be fewer than 1024 characters in length. Only the first **info** keyword found is used; any others are ignored.
- A filter at a given sample rate is specified by the **sample_rate** keyword line followed by one or more **biquad** keyword lines.
- The **sample_rate** keyword is followed by a colon and a floating-point number expressing the sample rate in hertz. There is no limit on the number of sample rates. 2700 series built-in filters are provided at these sample rates:

32000 Hz	44100 Hz	48000 Hz	65536 Hz	88200 Hz
96000 Hz	131072 Hz	176400 Hz	192000 Hz	262144 Hz

Table 3. Sample rates for the 2700 series built-in filters.

- The **biquad** keyword is followed by a colon and five floating-point coefficients a_1 , a_2 , b_1 , b_2 , and b_0 in that order, as described in the equation above.

A valid sample file is shown here:

```
info: 100 Hz Butterworth high-pass filter

sample_rate: 32000.0
biquad: -1.9819275 0.9820230 -1.9745094 0.9872547 0.9872547
biquad: -1.9924182 0.9925142 -2.0000000 1.0000000 1.0000000

sample_rate: 48000.0
biquad: -1.9879366 0.9879792 -1.9829700 0.9914850 0.9914850
biquad: -1.9949605 0.9950032 -2.0000000 1.0000000 1.0000000
```

As you can see, a digital filter can be specified by $(5 \cdot N + 1)$ numbers, where N is the number of second-order sections.

User Downloadable Filters can also be created by specialized third-party software such as MATLAB, available from The Mathworks, Inc. See **MATLAB Functions**, below, for four MATLAB functions useful in working with downloadable filters and Audio Precision waveform files.

We also provide a filter creation program from Momentum Data Systems called Filter Design Package for Audio Precision (FDP). The software and documentation for FDP are available for download from our Web site at ap.com.

MATLAB Downloadable Filter Support

MATLAB is a technical computing environment used in DSP design and analysis. MATLAB is a product of The Mathworks, Inc., who can be reached at 508-647-7000 or on the Web at www.mathworks.com.

Two MATLAB functions useful in creating and modifying downloadable filters for use with the 2700 series have been created as an aid to our customers who also use MATLAB. `ap_write_filter` generates filter files from within MATLAB, and `ap_read_filter` imports such files into MATLAB for further manipulation. These functions are provided as MATLAB files (file-name extension “.m”) on the Audio Precision Resources Disc, and are also available on our Web site at ap.com.

ap_write_filter

Syntax

```
size = ap_write_filter(filename, filter_type, info, sample_rate, sos)
size = ap_write_filter(filename, filter_type, info, sample_rate, b, a)
size = ap_write_filter(filename, filter_type, info, sample_rate, z, p, k)
size = ap_write_filter(filename, filter_type, info, sample_rate, a, b, c, d)
```

Description

`ap_write_filter` generates a text file (or files) in the format recognized by the 2700 series downloadable filters feature. Filters in any of the standard MATLAB forms (second-order section, transfer function, zero-pole-gain, and state-space) can be written, along with the sample rate and textual information.

The AP downloadable filter format consists of one or more sample rates, with accompanying filter coefficients in the form of second-order sections. `ap_write_filter` converts the filter into second-order section form before writing it to the file. This conversion will require functions in the MATLAB signal processing toolbox if the filter is not already in second-order section form.

Filename

The filename argument specifies the name of the file, without the extension. An extension is automatically added by `ap_write_filter` according to the specified filter type (see next section). If the filename ends in '+', the file is appended to, or created if no-existent. This is useful for writing coefficients for multiple sample rates to the same file.

Filter Types

The AP hardware allows three types of filter to be downloaded: highpass, weighting, and lowpass. The filename extensions and maximum sizes (in second-order sections) for these filters are shown below.

Filter type	Max size	Extension	Filter_type
Highpass	2	.afh	'h'
Weighting	4	.afw	'w'
Lowpass	3	.afl	'l'

The `filter_type` argument specifies the filter to create. `Filter_type` is a string containing at least one of 'h', 'w', or 'l'. Thus a lowpass filter, with filename extension .afl, is created when `filter_type` is 'l', for instance. Such a filter can have at most three second-order sections (6 poles). `ap_write_filter` will generate an error if the filter is larger than this.

The downloadable filters in the 2700 series hardware are cascaded in the following order: highpass, weighting, lowpass. This allows a filter that is larger than the maximum size for any of the three filter types to be achieved by distributing the second-order sections across more than one filter type. For instance, a 10-pole filter could be realized with 4 poles in the highpass section, and the remaining 6 poles in the weighting section. `ap_write_filter` supports this mode by allowing `filter_type` to be multi-character, e.g. 'hw'. In this case two files are generated (with filename extensions .afh and .afw) if the filter is too large to fit in one file because of restrictions on filter size.

When specifying multiple output files in this manner, `ap_write_filter` operates in the following way:

It first verifies that the filter is not larger than the sum of the sizes of the supplied filter types.

Regardless of the order in which the filters are specified in the `filter_type` string, it creates files in the order 'h', 'w', 'l'. Thus if `filter_type` is 'lhw', it first creates the .afh file, then creates the .afl file.

The first file is filled with second-order sections to the maximum capacity of the filter type. `ap_write_filter` then moves on to the next file and repeats until all sections have been written.

Files are only created if needed. Thus if `filter_type` is 'hwl' and the filter has two second-order sections, only the .afh file will be created.

The same `info` string and `sample_rate` are written to all files.

Info String

info is a character string that can be viewed inside the 2700 series control software by clicking the **Filter Info** button after loading the filter. This provides filter information to the user.

Sample Rate

`sample_rate`, a scalar, is the sample rate in hertz for which the filter was designed. If a vector is supplied, the first sample rate only is used, and a warning is issued. See **Multiple Sample Rates** below for more information.

Filter Coefficients

`ap_write_filter` uses the number of remaining arguments to determine whether the filter is supplied in second-order section form, in transfer function form, in zero-pole-gain form, or in state-space form. The transfer function form is not recommended for large filters because factorization into second-order sections may cause the poles and zeros to move slightly, deforming the filter response.

Return value

The return value of the function is the total number of bytes written to the file or files.

Multiple Sample Rates

A digital filter will have the intended frequency response only at the sample rate for which it was designed. Thus, a unique filter must be designed for each sample rate that will be encountered. If a filter file contains filters for multiple sample rates, the control software chooses the filter coefficients corresponding to the sample rate closest to the current hardware sample rate.

An Audio Precision filter file can contain a filter defined at any number of sample rates. Either a file handle or the file append mode can be used to add filters for other sample rates to an existing file. `ap_write_filter` writes an info string for each sample rate; however, the control software will only report the first of these strings.

Filter Restrictions

See the Filter Types section for restrictions on filter size. The sample rate must be between 6750 Hz and 262144 Hz. All zeros must be on or inside the unit circle, and all poles must be inside the unit circle. All coefficients must be in the range $[-2, 2]$.

Examples

The following example appends two Butterworth 1 kHz lowpass filters to file `'c:\filters\butter1k.af1'`. If this file does not already exist, it is created. Filters at two sample rates are written. No information string is written.

```
for sr = [44100 48000]
    [b, a] = butter(2, 1000 / (sr / 2));
    ap_write_filter('c:\filters\butter1k+', 'l', '', sr, b, a)
end
```

The following example creates a 12th-order 400 Hz elliptic highpass filter with 0.1 dB ripple in the passband and 120 dB stopband attenuation, and saves it across the files 'c:\filters\ellip400.afh' and 'c:\filters\ellip400.afw'. The sample rate is 48000 Hz.

```
[z, p, k] = ellip(12, 0.1, 120, 400/(48000/2), 'high');  
ap_write_filter('c:\filters\ellip400', 'hw', 'Ellip', 48000, z, p, k)
```

ap_read_filter

Syntax

```
[filter_array,info] = ap_read_filter(filename)  
[filter_array,info] = ap_read_filter(fid)
```

Description

`ap_read_filter` imports an Audio Precision downloadable filter text file into MATLAB. It parses the file and returns a structure array of filters, one structure for each sample rate contained in the file. It also returns the **info** comment strings. The file is closed on exit.

The AP downloadable filter format consists of one or more sample rates, with accompanying filter coefficients in the form of second-order sections. `ap_read_filter` creates one structure in the output array for each sample rate in the file. Each structure contains the sample rate and a matrix consisting of the filter in second-order section form. If other forms are required, such as state-space, the signal processing toolbox conversion functions should be used.

Comments in the file are discarded, but **info** strings are concatenated into the returned `info` variable. The **info** strings are used by the 2700 series to provide information to the user when the **Filter Info** button is clicked.

`ap_read_filter` attempts to deal with syntax errors in the file by issuing a warning of the line number of the error.

Example

To read the filter file generated by the first example in `ap_read_filter`:

```
[filters,info] = ap_read_filter('c:\filters\cheby200.afw');
```

This returns a 1×3 structure array. Typing `filters(1)` at the prompt returns

```
ans = sample_rate: 32000  
      sos: [2x6 double]
```

The second-order sections can be examined by typing `filters(1).sos` at the prompt.

Appendix E

AP Waveform File Support

Audio Precision waveform files (.aam, .aas, .agm, .ags) are of proprietary format. These files can be created in the AP2700 environment and saved on disk using the File Menu. Saved files can be opened for insertion in the acquisition buffer, the transform buffer, or either the analog or digital generator arbitrary waveform buffers.

This chapter discusses additional support for working with Audio Precision waveform files. You can export to and import from standard .WAV files, and MATLAB users are provided with functions to write, read and equalize arbitrary waveforms that are in the Audio Precision format.

Exporting to .WAV


The Export WAV File selection provides the capability to export audio data to disk as a Microsoft Windows PCM (.WAV) file, from one of three 2700 Series instrument memory buffers: the Arbitrary Waveform buffer, the Acquisition buffer or the Transform buffer.

Operation

From the Main menu, select **File > Export... > (.wav) File...**

You will be presented with the File Save dialog. Enter a file name and browse to the folder where you would like create the WAV file. Click Save to continue. In a few moments you will be presented with the Export MS (.wav) Waveform dialog.

In the Instrument Source area, select the memory buffer that contains the audio data to be exported. Only memory buffers that contain audio data will be available. If you select the Transform buffer, you can force the length of your exported audio data to match the current record length (set by the FFT length setting) by checking the “User Instrument defaults” checkbox below.



Stereo WAV files contain two audio waveforms, the first for the left channel and the second for the right channel. You can direct the audio data in the buffer channels to either the Left Waveform or the Right Waveform of the WAV file you are creating. If you select None for the Right Waveform, a mono WAV file will be created.

Set your dither preferences in the Dither field. Your choices are None, Triangular dither or Rectangular dither.

Set the resolution (word length) of your exported WAV file in the Bits field. Choose any word length from 8 bits to 24 bits.

Set the length of your exported waveform in the Waveform Length field, in time (seconds) or by number of samples. If the resulting length is less than the record length of the source the waveform is truncated at the end. If the resulting length is longer than the source, the source data is repeated until the specified waveform length is achieved.

Tips and Tricks

When initially acquiring the audio signal, in the FFT Spectrum analyzer panel set Window to “None, move to bin center”. The signal must be a single sine wave.

This selection shifts the frequency of the acquired signal to the nearest FFT bin center frequency, effectively stretching or compressing the signal in time so that the number of waveform cycles in the analyzer transform buffer is an integer. This is called a synchronous waveform, and no windowing function is necessary for useful FFT analysis.

After the acquisition is completed, export the data in the Transform buffer using this Add-In, and selecting the “Transform” Instrument Source selection. The resulting Windows PCM (.wav) file is synchronous and can be imported into the Analog or Digital generators as an Arbitrary waveform.

Importing from .WAV


The Import (.wav) File selection provides the capability to import audio data from a Microsoft Windows PCM (*.wav) file on disk into one of three 2700 Series instrument memory buffers: the Arbitrary Waveform buffer, the Acquisition buffer or the Transform buffer.

Operation

From the Main menu, select **File > Import... > (.wav) File...** You will be presented with the File Open dialog. Browse to the file you would like to import. Click Open to continue. In a few moments you will be presented with the Import MS (.wav) Waveform dialog.

In the Instrument Destination area, select the memory buffer where the audio data will be stored: the Arbitrary Waveform buffer for the Analog or Digital Generator, the Acquisition buffer or the Transform buffer. If there is currently data in the Arbitrary Waveform buffer, the “Update current generator file” checkbox will be available, and you must check the box to overwrite the current data.

Stereo WAV files contain two audio waveforms, the first for the left channel and the second for the right channel. You can direct these waveforms to the buffer memory channels using the buttons in the “From 1st Waveform in File” and “From 2nd Waveform in File” areas. If you are importing a mono WAV file, the “2nd Waveform in File” options are not available.



In some cases, the beginning of a WAV file may contain audio that is undesirable for measurement. In the “Truncate waveform beginning” field, you can enter the length of the initial audio to exclude. Enter the length in time (seconds) or by specifying the number of samples.

Click OK. The audio data will be imported into the selected buffer.

MATLAB support

MATLAB is a technical computing environment used in DSP design and analysis. MATLAB is a product of The Mathworks, Inc., who can be reached at 508-647-7000 or on the Web at www.mathworks.com.

Three MATLAB functions supporting Audio Precision formatted wave files for use with 2700 series control software have been provided as an aid to our customers who also use MATLAB. `ap_write_wave` generates AP wave files from within MATLAB, `ap_read_wave` imports such files into MATLAB for further manipulation, and `ap_eq_wave` enables equalization of wave files. These functions are provided as MATLAB files (filename extension “.m”) on the Audio Precision Resources Disc, and are also available on our Web site at ap.com.

ap_write_wave

Syntax

```
size = ap_write_wave(filename,sample_rate,normalize,data)
size = ap_write_wave(fid,sample_rate,normalize,data)
```

Description

`ap_write_wave` generates a binary waveform file that can be loaded into Audio Precision hardware. Files with extensions .agm (mono generator waveform) and .ags (stereo generator waveform) are supported.

The AP waveform file format consists of a 256-byte header containing sample rate and other information, and a $3n$ -byte payload, where n is the number of samples in the waveform. Each sample is quantized to 24 bits and is in the range $[-1, 1-2^{-23}]$.

`ap_write_wave` accepts both filenames and file handles. If a filename is supplied, any extension is replaced with .agm or .ags, depending on the size of the data matrix. `ap_write_wave` closes the file when the function exits. If a file handle is supplied, `ap_write_wave` appends to the file, leaving it open on exit.

`sample_rate`, a scalar, is the sample rate of the waveform in hertz.

If `normalize` is 1, the data is scaled so that the peak of the waveform reaches full scale. The data is also dithered before reducing the word size to 24 bits. This preserves low-level information and eliminates harmonic distortion due to quantization. This mode is recommended unless multiple waveforms are being generated whose amplitude relative to one another is important.

If `normalize` is 0, the data is written to the file unscaled. If any samples are outside the allowable range, they are clipped and a warning is issued.

`data` is a matrix containing the waveform. If the smaller dimension is 1, a mono waveform file is generated. If it is 2, a stereo waveform file is generated. Any other size will generate an error.

Example

At a sample rate of 40 kHz, create a sine wave of approximately 1 kHz in channel A and noise in channel B. The length is 2048 samples.

```
len=2048;
samp_num=0:len-1;
samp_rate=40000;
ch_A=sin(samp_num/len*2*pi*round(1000/samp_rate*len));
ch_B=randn(1,len);
ap_write_wave('c:\waveforms\sin_noise',40000,1,[ch_A; ch_B])
```

This generates a file `sin_noise.ags`. The actual frequency of the sine wave is 996.094 Hz. This is a frequency that is synchronous with the sample rate and the waveform length. That is, when the waveform is repeated, there are no discontinuities.

ap_read_wave

Syntax

```
waves = ap_read_wave(filename, system)
waves = ap_read_wave(fid, system)
waves = ap_read_wave(filename)
waves = ap_read_wave(fid)
```

Description

`ap_read_wave` imports an Audio Precision waveform file into a MATLAB structure array. One structure is created for each waveform in the file. Files with extensions `.aam` (mono acquired waveform), `.aas` (stereo ac-

quired waveform), .agm (mono generator waveform), and .ags (stereo generator waveform) are supported. The file is closed on exit.

When reading an acquired file (.aam or .aas), the case-insensitive parameter `system` must be supplied to scale the results correctly. Choices for `system` are:

- 'ATS2' for ATS-2.
- 'S1' for System One.
- 'S2' for System Two.
- 'S27' for 2700 series and System Two Cascade and Cascade *Plus* instruments.

If the wrong `system` is supplied, the results will be unpredictable. When reading a generator file (.agm or .ags), `system` is not required.

Each structure consists of a sample rate, a trigger point, a time vector, and the waveform vector. The sample rate and trigger point are determined from the header information in the waveform file.

For acquired waveforms, the trigger point is the sample at which the trigger occurred during acquisition. For generated waveforms (such as arbitrary waveforms created by the Multitone Creation utility), the trigger point is usually zero. The time vector is constructed from the trigger point, the total number of points in the waveform, and the sample rate. The data vector consists of the file payload converted to `double`.

If `ap_read_wave` determines that the file contains data acquired from an analog source, it attempts to scale the data so that the value of a sample represents the analog voltage at that time. Because some gain constants are known only to the hardware on which the waveform was acquired, however, this will only be approximate. Data originally from a digital source is not scaled.

Example

Read the .ags file generated by the `ap_write_wave` example.

```
waves=ap_read_wave('c:\waveforms\sin_noise.ags');
```

This returns a 1×2 structure array. Typing `waves(1)` at the prompt returns

```
ans = sample_rate: 40000  
      trigger_point: 0  
              time: [2048x1 double]  
              data: [2048x1 double]
```

The data can now be examined:

```
figure(1), plot(waves(1).time,waves(1).data)  
figure(2), plot(waves(2).time,waves(2).data)
```

ap_eq_wave

Syntax

```
outwave = ap_eq_wave(inwave, sos)
outwave = ap_eq_wave(inwave, b, a)
outwave = ap_eq_wave(inwave, z, p, k)
outwave = ap_eq_wave(inwave, a, b, c, d)
```

Description

`ap_eq_wave` filters a signal that is assumed to be cyclic so that the filtered output is also cyclic. It permits equalization of arbitrary waveforms before they are downloaded into Audio Precision hardware.

The Audio Precision arbitrary waveform generator uses a stored waveform file, and plays it repeatedly by outputting the entire waveform, and then jumping back to the start of the waveform. To obtain artifact-free results, the waveform must be cyclically continuous, i.e., when the jump is made from the end to the beginning of the waveform, there must be no discontinuity in the waveform.

It is sometimes desirable to pre-equalize an arbitrary waveform by filtering. However, for this to work correctly, the filtered result must itself be cyclically continuous. In general, filtering produces end effects which destroy this continuity. `ap_eq_wave` deals with this problem.

Input Signal

`inwave` is a matrix of input waveforms. `ap_eq_wave` assumes that the shorter dimension of the matrix is the number of channels, and filters each channel individually. Thus a matrix of size 512×2 and a matrix of size 2×512 are both interpreted as two independent signals, each of length 512. `inwave` can be of any size.

Filter

The filter can be specified in second-order section form, in transfer function form, in zero-pole-gain form, or in state-space form. If the filter is not supplied in transfer function form, it is converted to it. This conversion will require functions in the Signal Processing Toolbox.

Output Signal

`outwave` is a matrix of the same size as `inwave`.

Method of Operation

ap_eq_wave uses the MATLAB function filter to perform the filtering. It filters the input signal with the supplied filter, and stores the resulting output. It maintains the output state of the filter, and once again filters the input signal. The new output is compared with the output from the first filtering operation. If the two outputs are similar enough, the output is assumed to have converged, and the function exits. If not, the filter state is again maintained and the input signal filtered until convergence is achieved.

On rare occasions, the function may exit before convergence occurs, and a warning is issued. In such instances, the resulting output should be examined for anomalies before using it. This could occur when using unstable filters, for example.

Examples

Create a random (white) waveform, and highpass filter it with a single pole to provide a 'blue' noise signal.

```
noise = rand(1, 8192) - 0.5;
[b, a] = butter(1, 0.5, 'high');
noiseEQ = ap_eq_wave(noise, b, a);
```

Create a waveform with 30 log-spaced tones, and shape it with an A-weighting filter. Write the resulting waveform out to a file.

```
awt = [0.5815 -1.1630 0.5815 1 -1.9946 0.9946; ...
       1.0000 -2.0000 1.0000 1 -1.8939 0.8952; ...
       1.0000 0.3000 0.0000 1 -0.4050 0.0410];
[b, a] = sos2tf(awt); b = [b 0];
time = 0 : 8191; tonebin = 4; wfm = zeros(size(time));
for tone = 1 : 30
    wfm = wfm + sin(time / 8192 * 2 * pi * floor(tonebin));
    tonebin = tonebin * 1.262;
end
wfmEQ = ap_eq_wave(wfm, b, a);
ap_write_wave('c:\waveforms\multEQ', 48000, 1, wfmEQ)
```


Index

A

- aai file 322
- aam file 293
- aas file 293
- Absolute values, FFT display processing 283
- acmod 197
- Acoustic space analysis 357
- Acquisition waveform file
 - Digital Interface Analyzer 322
 - Multitone & Spectrum Analyzer
 - combining mono to stereo 293, 347
 - compatibility 293, 347
 - opening 293, 347
 - saving 292, 346
- Active bits indicators 177
- ada file 462
- ADC
 - See Analog-to-digital converter
- ADC selection, DSP Audio Analyzer 228
- adconvtyp 207
- Add-In 26
- adl file 462
- adq file 462
- ads file 462
- adx file 467
- AES/EBU 542
- AES/EBU Ref In, rear panel connector 42
- AES/EBU Ref Out, rear panel connector 42
- AES/EBU reference in 499
- AES/EBU reference out 499
- AES17 filter option 34, 125
- AES3 542
- afh 559
- afl 559
- afw 559
- agm file 351
- ags file 351
- A-Law 160, 173
- Algorithm
 - settling 430
- Amplitude control
 - Analog Generator 68
 - Digital Generator 101
- Amplitude measurement function
 - Analog Analyzer 134
 - DSP Audio Analyzer 235
- Amplitude units 68, 101
- Analog amplitude units 530
- Analog Analyzer panel
 - overview 123
- Analog Generator
 - hardware vs. DSP generation 63
 - overview 63
 - panel 66
- Analog Inputs
 - diagram & description 48
 - front panel connectors 39
- Analog Outputs
 - configuring 95
 - diagram & description 46
 - front panel connectors 38
- Analog signal monitors 494
- Analog-to-digital converter
 - for analog inputs 58
- Analysis, overview
 - See Signal analysis, overview
- AP Basic 8, 507
 - documentation 509
 - Extensions Manual 9
 - Language Manual 8
 - overview 507
- apb file 507
- APIB 33
- APIB interface
 - rear-panel connector 41
- Append
 - data saved in file to sweep 415
 - sweep setting 415
- Arbitrary waveform 90, 119
 - shared memory buffers 91, 120

ASCII data file	467
Attached File Editor	465
Attached Files Viewer	468
Audible monitoring	491
Audio format	
digital input	173
digital output	159
Audio Service, Dolby Digital	195
audprodi2e	201
audprodie	200
Auto On.	67, 101
Automating tests	507
Auxiliary bits, digital audio signal	544
Average, Compute algorithm	478
Averaging, Digital Interface Analyzer	315
Averaging, Spectrum Analyzer	275
power (spectrum) averaging	280
synchronous averaging	276

B

B, bad (invalid) data flag	
See Data Editor, invalid data flag	
Bandpass measurement function	
Analog Analyzer	135
DSP Audio Analyzer	243
Bandpass, selecting harmonics	259
Bandpass/bandreject filter	
Analog Analyzer	149
DSP Audio Analyzer	257
Bandreject measurement function	
Analog Analyzer	136
Bandwidth	
Analog Generator	94
D/A waveforms	65
DAC	65
limitations, Harmonic Dist. Analyzer	396
Bandwidth filters	
Analog Analyzer	147
DSP Audio Analyzer	251
Bandwidth, FFT.	552
Bar graph	
connection browser	455
overview	453
to display readings	456
to make settings	456
Basic language	
See AP Basic	
Batch mode measurements	405
Batch mode vs. real-time measurements	59, 551
Bin width, FFT	553
Bi-phase mark encoding	543
Bit error flag	387
Bit indicators	177
Bits	
resolution	159, 173
Bitstream number (IEC 61937)	221
Bitstream number mode (IEC 61937)	221
Bitstream, Dolby Digital.	198

Bittest	
See Digital Data Analyzer	
Blackman-Harris FFT window	
Digital Interface Analyzer.	315
Spectrum Analyzer	271
Block diagram	
system	7
Bottom values, sweep data	411
bsid	203
bsid mode	203
bsmod	197
Buffer, graph	444
BUR option	34, 64
Burst waveforms	
See tone burst waveforms	

C

C bit	544
Cable simulation, digital output impairment	162
Cascade tests	27
CCIF IMD waveforms	82, 109
CCIF/DFD measurement function	
Analog Analyzer	138
Center, Compute algorithm.	475
Changing data with Compute.	469
Channel Lowpass, Dolby Digital	208
Channel selection	
Analog Generator	67
Digital Generator	100
Channel selection, Analog Analyzer Function meter	133
Channel status bit	544
Chart recorder sweep mode	427
Clock jitter measurement.	314
Clock ref in	498
cmixlev	199
CMT, CMTST	
See common mode test	
Coding error indicator	
digital input signal	178
Color	
trace	448
Color cycle	448
Colors	
configuration	524
Comment, graph	443
Common mode	47, 164, 169
Common mode test output	96
Common mode, digital output impairment	164
compr.	211

Compute algorithms		
2-Sigma	477	
Average	478	
Center	475	
comparing with orig. data.	481	
Delta	476	
Equalize	479	
Invert	472	
Linearity	474	
Maximum	479	
Minimum	478	
Normalize	472	
overview	469	
Smooth	473	
Compute Status list	480	
Confidence error indicator		
digital input signal	178	
Configuration		
colors	524	
Filters	521	
General	518	
graph	524	
Log file	522	
overview	517	
trace	524	
Connector		
parallel i/o	51	
Constant Value waveform		
Digital Generator	116	
use in Digital Data Analyzer.	385, 389	
Consumer format status bits	182	
Consumer format, digital interface	543	
Control software measurement software		
panel readings	14	
panel settings	13	
panels, overview	12	
user interface	11	
Copy		
a window, panel or screen to clipboard	489	
graph to clipboard	488	
Copy to Sweep Panel command	439	
copyrightb	200	
Coupling		
Spectrum Analyzer	274	
crc1	212	
crc2	212	
Crosstalk measurement function		
Analog Analyzer	144	
DSP Audio Analyzer	239	
Ctrl F6		
see Sweep Reprocess Data command	437	
Cursors, graph	439	
Custom new test	27	
Data bit indicators	177	
Data Editor		
data file types	462	
data that will not graph	459	
editing the current data	461	
graph legend linkage	446	
invalid data flag	461	
lower limit flag	461, 466	
overview	459	
regulation flag	461	
saving test data	462	
timeout flag	461	
upper limit flag	461, 466	
Data file	462, 466	
Data, test	461	
Data-type (preambles)	219	
Data-type code	220	
Data-type mode	218	
Data-type-dependent info	220	
Data-type-dependent info mode	220	
dBm generator reference	97	
dBr generator reference	97, 122	
DC coupling		
analog inputs	127	
DSP Audio Analyzer	230	
DC Highpass, Dolby Digital	209	
DCX-127	36	
units	539	
Deemphasis, digital audio	174	
Delay measurement with MLS	379	
Delay time		
pre-sweep	418	
settling	430	
Delay, digital signal	175, 504, 505	
Delta, Compute algorithm	476	
Dependent variable	410	
Detector reading rate		
Analog Analyzer	146	
DSP Audio Analyzer	251	
Detector type		
Analog Analyzer	144	
DSP Audio Analyzer	249	
Detectors, general discussion	145	
DFD IMD waveforms	82, 109	
dheadphonmod	207	
dialnorm	198	
dialnorm2	198	
Digital amplitude units	534	
Digital Data Analyzer error signal	500	
Digital data units	536	
Digital Generator		
frequency units	100	
overview	99	
panel	99	
Digital input		
audio format	173	

D

D/A waveforms	64
DAC testing	
monotonicity waveform	114
Data 1	410
Data 3, 4, 5, 6	413

- Digital Input 168
 - connection 49
 - front panel connectors 38
 - jitter measurement 179
 - peak meters 176
 - Sample Rate (ISR) 171
 - voltage 172
- Digital input and output, parallel 51
- Digital Interface Analyzer
 - overview 295
- Digital interface serial formats
 - electrical vs. data characteristics 50
- Digital interface signal amplitude histogram
 - Digital Interface Analyzer 304
- Digital interface signal bit rate histogram
 - Digital Interface Analyzer 306
- Digital interface signal pulse width histogram
 - Digital Interface Analyzer 305
- Digital interface signal spectrum
 - Digital Interface Analyzer 302
- Digital interface signal waveform
 - Digital Interface Analyzer 299
- Digital output
 - audio format 159
- Digital Output 154
 - connection 49
 - front panel connectors 37
 - impairments 162
 - Sample Rate (SR) 157
 - voltage 158
- Digital signal monitors 494
- DIM (TIM) measurement function
 - Analog Analyzer 139
- DIM IMD waveforms 83, 85, 110
- DIN IMD waveforms 81, 109
- Display samples, FFT display processing 283
- Dither 120
- dmixmod 204
- Documentation
 - about this manual 4
 - AP Basic Extensions Manual 9
 - AP Basic Language Manual 8
 - Getting Started Manual 8
 - See Help, online
- Domain preference, Pass Thru 503
- Downloadable filters 255
- DRC, Dolby Digital 209
- DSP
 - parallel input 52
 - parallel output 54
 - parallel port pin assignments 51
- DSP Audio Analyzer panel
 - overview 225
- DSP filters 255
- dsurexmod 206
- dsurmod 199
- Dual connector mode 171
 - status bits 185
- Dual sine waveforms 78, 105
- Dynamic Range Compression, Dolby Digital 209
- dynrng 210
- E**
 - Edit menu 16
 - Editing data
 - See data editor
 - EIAJ 543
 - encinfo 208
 - Energy-Time window, MLS 365
 - EQ file 462
 - EQ sine waveforms 74, 79, 107
 - Equalization
 - generator 74, 79, 107
 - Equalize, Compute algorithm 479
 - Equiripple FFT window
 - Digital Interface Analyzer 316
 - Spectrum Analyzer 272
 - Error display, Digital Data Analyzer 386
 - Error flag (IEC 61937) 220
 - Error indicators
 - digital input signal 178
 - Error signal, Digital Data Analyzer 500
 - Errors, logging 466
 - Export
 - acquisition to WAV file 567
 - graph 488
 - Ext Trigger In, rear panel connector 43
 - Extended bitstream, Dolby Digital 202
 - Extended Bitstream, Dolby Digital 202
 - External sweep
 - end 424
 - single-point 426
 - spacing 424
 - start and stop 422
 - stereo 426
 - External sweeps
 - Source 1 420
 - External trigger in 500
 - External vs. internal sweeps 419
 - Eye pattern
 - Digital Data Analyzer 300
- F**
 - Fast/High Acc. Analog Generator settings 69
 - Fasttest
 - Multitone Audio Analyzer 323
 - FFT acquisition 266, 552
 - FFT acquisition length 269
 - FFT acquisition record 267, 552
 - FFT bandwidth 552
 - FFT bin width 553
 - FFT commands 266
 - FFT display processing 282
 - Digital Interface Analyzer 309
 - Spectrum Analyzer 266
 - FFT graphing 558
 - FFT record looping 554

- FFT Spectrum Analyzer
 - Spectrum Analyzer 261
 - FFT start time. 285
 - FFT transform record. 269
 - FFT transforming 266
 - FFT trigger delay time 288
 - FFT trigger slope 289
 - FFT triggering 286
 - FFT triggering with quasi AC coupling 290
 - FFT triggering with synchronous averaging 289
 - FFT windows 555
 - Digital Interface Analyzer. 315
 - Spectrum Analyzer 269
 - FFT, synchronous 557
 - FFTs overview 551
 - File
 - data 28
 - test. 27
 - File menu 15
 - Filters
 - configuration 521
 - Filters, user. 559
 - Flat-top FFT window
 - Digital Interface Analyzer. 316
 - Spectrum Analyzer 271
 - Floor
 - settling 432
 - Frame lock 503
 - Frame Sync In, rear panel connector 43
 - Frame sync out inversion, transmitter 505
 - Frame Sync Out, rear panel connector 43
 - Frame sync out, receiver 500
 - Frame sync out, transmitter 500
 - Frame, digital audio signal 543
 - Frequency meters
 - Analog Analyzer 129
 - DSP Audio Analyzer 232
 - Frequency steering control, Harmonic Dist. Analyzer 398
 - Frequency units 70, 100, 537
 - Frequency, generator reference 97, 122
 - Frequency/Time domain toggle button 290
 - Frequency-domain view
 - See Spectrum Analyzer
 - frmsizcod 195
 - fscod 196
 - fscod mode 196
 - Function keys 29
 - Function meter
 - Analog Analyzer 132
 - DSP Audio Analyzer 234
 - Fundamental amplitude meters, Harmonic Dist. Analyzer 395
 - Gate input, Analog Generator 498
 - Gaussian FFT window 272
 - Generating test signals 57, 63, 99
 - GenMon 127
 - Go, sweep command. 414
 - Graph
 - "printing" to a file 487
 - buffer 444
 - comment 443
 - configuration 524
 - copy to clipboard 488
 - cursors 439
 - export. 488
 - legend 445
 - options menu 437
 - overview 435
 - printing 483
 - sweep and table relationship 403, 435
 - sweep display mode 414
 - titles and labels. 443
 - zoom 436
 - Graph, bar
 - See Bar graph
 - Graphic aliasing 284
 - Graphing FFTs 558
 - Graphing Harmonic Dist. Analyzer results. 401
- ## H
- Hamming FFT window 272
 - Hann FFT window
 - Digital Interface Analyzer. 316
 - Spectrum Analyzer 271
 - Hardware options 34
 - Analog Analyzer 124
 - Analog Generator 64
 - Hardware status 526
 - Harmonic Distortion Analyzer
 - bandwidth limitations 396
 - overview 391
 - Harmonic sum meters, Harmonic Dist. Analyzer 396
 - Harmonics, selection in Bandpass function 259
 - Headphone monitoring 491
 - Help menu 20
 - Help, online 8
 - High bound, Regulation parameter. 512
 - Highpass filter
 - Analog Analyzer 147
 - DSP Audio Analyzer 252
 - Histogram
 - Digital Interface Analyzer. 304
 - Hot keys
 - See keyboard shortcuts
- ## I
- Idle data-type 214
 - IEC 60958 542
 - IEC 61937
 - DIO selection 160

- IIR filter 559
 - IMD 81, 125, 137, 138, 139, 245
 - IMD measurement functions
 - Analog Analyzer 137
 - DSP Audio Analyzer 245
 - IMD option 34, 64, 125
 - IMD waveforms 81, 108
 - Import
 - acquisition from WAV file 569
 - Impulse Response 374
 - Independent variable 404, 407
 - Infinite impulse response filter 559
 - Input impedance
 - analog inputs 127
 - digital input 170
 - Input selection
 - DSP Audio Analyzer 228
 - Instrument configurations 33
 - Intermodulation Distortion
 - See IMD
 - Internal vs. external sweeps 419
 - Interpolate, FFT display processing 282
 - Intervu
 - See Digital Interface Analyzer
 - Invalid multitone readings 344
 - Invert 68, 101
 - Invert transmitter frame sync out 505
 - Invert, Compute algorithm 472
 - Invert, digital output impairment 162
 - ISR 171
 - Iterations, Regulation setting 514
- J**
- Jitter detection, Digital Interface Analyzer
 - clock (squarewave) signal 314
 - digital interface signal 312
 - Jitter histogram
 - Digital Interface Analyzer 303, 307
 - Jitter impairment
 - applied to clock outputs 506
 - applied to digital output 165
 - generation 165
 - Jitter measurement
 - digital input 179
 - Jitter waveform
 - Digital Interface Analyzer 301
 - J-Test waveform
 - Digital Generator 114
- K**
- Keyboard shortcuts 29
- L**
- L, lower limit flag
 - See Data Editor, lower limit flag
 - Labels, graph 443
- langcod 201
 - langcod2 202
 - langcod2e 202
 - langcode 201
 - Learn mode.
 - enter 526
 - Learn Mode toolbar 25
 - Legend / Data Editor linkage 446
 - Legend, graph 445
 - Length-code 221
 - Length-code mode 221
 - Level meters
 - Analog Analyzer 128
 - DSP Audio Analyzer 231
 - Level monitors, Spectrum Analyzer 266
 - LFE Lowpass, Dolby Digital 209
 - lfeon 197
 - Limit file 462, 463
 - Limits
 - actions upon failure 466
 - Attached File Editor 465
 - attaching a limit file 464
 - making a limit file 463
 - overview 462
 - sweep data limits 411
 - Lin scale
 - sweep Data 411
 - sweep Source 409
 - Lin scale, Source 1 408
 - Line mode compression, Dolby Digital 209
 - Linear, Regulation algorithm 512
 - Linearity, Compute algorithm 474
 - Lock error indicator
 - digital input signal 178
 - Log errors 466
 - Log file
 - clear 526
 - configuration 522
 - view 526
 - Log scale
 - sweep Data 411
 - sweep Source 409
 - Log scale, Source 1 408
 - Looping, FFT record 554
 - lorocmixlev 204
 - lorosurmixlev 205
 - Loudspeaker testing 357, 371
 - Low bound, Regulation parameter 512
 - Lowpass filter
 - Analog Analyzer 148
 - DSP Audio Analyzer 253
 - ltrlcmixlev 205
 - ltrtsurmixlev 206
- M**
- μ-Law 160, 173
 - Macro 507

Macro Editor	509	Noise, digital output impairment	164
Macro toolbar	25	Noise, random and pseudo	86
Mains fusing	40	Noise, white and pink	87
Mains voltage	40	None, move to bin center FFT "window"	273
Makewave		Normalize, Compute algorithm	472
See Multitone Creation Utility		Notch filter	
Masking curve analysis.	336	Analog Analyzer	149
Master Clock Out, rear panel connector	43	DSP Audio Analyzer	257
master clock reference out	500	Null data-burst repetition period	215
MATLAB	570	Null data-bursts.	214
Maximum length sequence.	357		
See MLS		O	
Maximum, Compute algorithm	479	Object linking and embedding	
Maximum, Regulation algorithm	513	See Also OLE	
Minimum, Compute algorithm	478	Octave smoothing FFT display processing.	285
Minimum, Regulation algorithm	513	Offset, Sine+ waveform	106
mixlevel.	200	OLE.	507
mixlevel2	201	Operation, Regulation setting	512
MLS		Optimize, graph	438
setting gen sample rate	91, 118	Option filters	35, 149
waveform	91, 118	configuration	521
MLS Analyzer	357	Options, hardware	
MLS overview	357	Analog Analyzer	124
Modifying data with Compute.	469	Analog Generator	64
Monitor		origbs.	200
audible	491	Oscilloscope view	
connections	39	See Spectrum Analyzer	
headphone	491	Outputs ON-OFF	
outputs	493	Analog Generator	67
speaker.	491	Digital Generator	100
Monotonicity waveform			
Digital Generator	113	P	
Move to bin center FFT "window"	273	P bit.	544
Multitone		Page setup	484
analysis.	330	Panels menu.	18
informing analyzer about waveform	326	Panels toolbar	23
invalid readings.	344	Parallel digital input and output	51
minimum multitone duration	343	Parallel In, rear panel connector.	43
waveform requirements	324	Parallel input	
Multitone Audio Analyzer		DSP	52
capabilities	324	timing	52
introduction	323	Parallel Out, rear panel connector.	43
processing	340	Parallel output	
rss summing resolution.	339	DSP	54
setting record length	339	timing	54
setting the generator	326	Parallel port pin assignments, DSP	51
trigger delay	342	Parity bit	544
triggering modes	341	Parity error indicator	
triggering resolution	338	digital input signal	178
Multitone Creation Utility	348, 527	Parity error, digital output impairment	163
		Pass Thru domain preference	503
N		Pass Thru feature.	92, 117
+Normal, -Normal Regulation algorithms	513	Pause data-burst repetition.	216
Nested sweeps	417	Pause data-burst repetition mode	217
New test	27	Pause data-burst repetition period	217
New test, custom	27	Pause data-type	215
Noise in the presence of signal.	334		
Noise waveforms	86, 89, 112		

Pause, sweep command	414	Reading meter	
PCM	541	See Function meter	
Peak equivalent sinewave	68, 102	Real time vs. batch mode measurements	59
Peak meters		Real-time sweeps	405
digital interface signal	176	Real-time vs. batch mode measurements	551
Peak picking	285	Receive Frame Sync, rear panel connector	43
Peak values, FFT display processing	283	Receive status bits	184
Peaking filter		Rectangular probability distribution function	
Analog Analyzer	149	See dither	
DSP Audio Analyzer	257	Reference signals	
Phase function, DSP Audio Analyzer	247	AES/EBU in	499
Phase meter, Analog Analyzer	131	AES/EBU out	499
Phase Shift, Dolby Digital	209	Analog Gen sync out	497
Phase units	538	Analog Gen trig/gate in	498
Pink noise	87	Digital Data Analyzer error signal	500
Polarity		Digital Gen trigger out	499
test waveform.	115	external trigger in	500
Polarity inversion	68, 101	invert transmitter frame sync out	505
Polarity waveform	92	jitter clock outputs	506
Power entry module		master clock out	500
mains fuse and voltage selection	41	receiver frame sync out	500
mains power cord	41	REF IN, rear panel connector	42
mains voltage indicator	41	transmitter frame sync out	500
Preamble, digital audio signal	544	video/TTL ref in	498
Preambles controls	218, 219, 220, 221	Reference trace	444
Preemphasis, digital audio	161	References	
Preprocessing, Dolby Digital	208	Analog Analyzer	151
Pre-sweep delay	418	Analog Generator	96
Printing		Digital Generator	121
graphs	483	Digital Interface Analyzer	321
page setup	484	DSP Audio Analyzer	259
Procedure		Multitone Audio Analyzer	343
See macro		Regulation	
Professional format status bits	183	algorithms	512
Professional format, digital interface	542	examples of regulated sweeps	514
Propagation delay, MLS	364	overview	511
Pseudo-random noise	86	panel selections	512
PSIA-2722	35	Relative units	536
Pulse code modulation		Repeat, sweep setting	414
See PCM		Reprocess Data	
		See Sweep Reprocess Data command	
		Reserved bits (IEC 61937)	220
		Resolution	
		for Digital Data Analyzer use	384
		Resolution, digital input	173
		Resolution, digital output	159
		Resolution, sweep	409
		RF mode compression, Dolby Digital	211
		Rife-Vincent FFT window	272
		Rise/Fall time adjustment, digital output impairment	
			164
		roomtyp	200
		roomtyp2	201
		RPDF	
		See dither	
		S	
		S/PDIF	543
		S-AES17 option	125

Sample rate		Source 1	407
D/A waveforms	65	in an external sweep	420
DAC	65, 94	scales, log or lin	408
DIO input reading	171	start and stop	408
DIO output setting	157	Source 2	407, 417
DIO Sample Rate Range setting	156	Source selection	
for arbitrary waveform files	90, 119	Analog Analyzer	126
ISR	171	Source, Regulation	512
SR	157	SPDIF	
Saving test data	462	See S/PDIF	
Scale Freq by		Speaker, internal	491
digital input	174	Spectrum Analyzer commands	266
digital output	161	Spectrum FFT display processing	285
setting a scaling reference	176	Spectrum/Waveform toggle button	290
Script		Spectrum Analyzer	261
See macro		Square wave ref in	498
SDI		Squarewave	
See serial digital interface signal		Analog Generator	80
Sequence, MLS		Digital Generator	111
variation	359	SR	157
Serial digital interface signal	542	SSR	157
Setting limits		Standard toolbar	22
See limits		Status bar	21
Settling		Status bits	180
algorithm	430	Stepsize, Regulation setting	513
floor	432	Stereo sine waveforms	77, 105
See sweep settling		Stereo, sweep setting	416
tolerance	432	Stop, sweep command	414
Shaped dither		Subframe, digital audio signal	543
See dither		surmixlev	199
Shortcuts, keyboard	29	Sweep	
Signal analysis, overview	57	overview	404
audio signal analysis	57	Sweep display mode	414
Digital Analyzer analysis tools	59	Sweep file	462
digital signal analysis	59	Sweep panel	406
serial digital interface analysis	58	Sweep planning	405
Sweeps and Graphs	61	Sweep Reprocess Data command	437
Signal inputs and outputs, main		Sweep resolution	409
overview	45	Sweep settling	
Sine Dual waveforms	78, 105	concepts	430
Sine normal waveform	70, 103	delay time	430
Sine stereo waveform	77	panel	429
Sine Stereo waveforms	105	Sweep Settling	
Sine var phase waveform	77	overview	427
Sine Var Phase waveforms	104	Sweep table	
Sine wave		use with a multitone file	354
Analog Generator	70	Sweep, graph and table relationship	403
Digital Generator	103	Sweeps, time	427
use in Digital Data Analyzer	385	Switchers	36
Sine+Offset waveform	106	Sync	
Single channel parallel I/O	54	connections	39
Single-point sweeps	416	Sync output	
external	426	Analog Generator	497
Smooth, Compute algorithm	473	Synchronization	501
SMPTE IMD waveforms	81, 109	Synchronous FFT	557
SMPTE/DIN measurement function		syncword	213
Analog Analyzer	137	syncword mode	213
DSP Audio Analyzer	245		
Software Add-In	26		

System Sample Rate
See SSR

T

2-Ch Ratio measurement function 477
 Analog Analyzer 143
 DSP Audio Analyzer 237
 T, timeout flag
 See Data Editor, timeout flag
 Table sweeps 418, 462
 Table, sweep and graph relationship 403
 Table, sweep display mode. 414
 Target Range, bargraph 455
 Target, Regulation 512
 Terminate sweep on failure. 466
 Test
 data. 461
 THD+N Ampl. measurement function
 Analog Analyzer 136
 DSP Audio Analyzer 242
 THD+N Ratio measurement function
 Analog Analyzer 137
 DSP Audio Analyzer 242
 Time Code, Dolby Digital 208
 Time sweeps 427
 Time units 538
 Time window, MLS 366
 timecod1e 208
 timecod2e 208
 Time-domain view
 See Spectrum Analyzer
 Timeout per step, Regulation setting 514
 Timing
 parallel output 54
 Timing diagram
 parallel input 52
 Titles, graph 443
 Tolerance
 settling 432
 Tolerance, Regulation 512
 Tone burst 71
 Tone burst waveforms. 71, 79, 104, 107
 Toolbars 21
 Top values, sweep data. 411
 TPDF
 See dither
 Trace
 color cycle 448
 colors 447
 configuration 524
 reference 444
 selection for printing 485
 Transmit Frame Sync, rear panel connector. 43
 Transmit status bits. 181
 Triangular probability distribution function
 See dither

Trigger
 connections 39
 Digital Interface Analyzer. 317
 Multitone Audio Analyzer. 341
 Trigger in 500
 Trigger In, rear panel connector 43
 Trigger input, Analog Generator 498
 Trigger out, Digital Generator 499
 Trigger Out, rear panel connector 42
 TTL Ref In, rear panel connector 42
 Tunable filter
 Analog Analyzer 149
 DSP Audio Analyzer 257

U

μ -Law 160, 173
 U bit 544
 U, upper limit flag
 See Data Editor, upper limit flag
 Units of measurement 529
 analog amplitude 530
 DCX-127 539
 digital amplitude 534
 digital data 536
 frequency. 537
 phase. 538
 ratio. 536
 relative 536
 time. 538
 USASI, noise waveform 113
 User bit 544
 User downloadable filters
 designing 559
 overview 559
 User filters. 255, 559

V

V bit. 544
 V/FS generator reference 122
 Validity bit. 544
 Validity bit error, digital output impairment 164
 Variable phase sine waveforms 104
 Video Ref In, rear panel connector 42
 Video/TTL ref in 498
 View menu. 17
 Visual Basic 507
 Voltage, digital input 172
 Voltage, digital output 158

W

.wav file
 creating a multitone .wav file 349, 354
 W&F measurement function 140
 W&F option 34, 125, 140

Walking Ones and Zeros waveform	
use in Digital Data Analyzer.	384, 389
walking rate	389
Walking Ones, Zeros waveform	
Digital Generator	116
Watts generator reference	97
WAV file	
export.	567
import.	569
Waveform file support	570
Waveform selection, Digital Data Analyzer.	388
Waveforms	
Analog Generator	69
Digital Generator	102
Weighting filters	
Analog Analyzer	149
DSP Audio Analyzer	254
White noise	87
Windows, FFT	555
Word length	
resolution	159, 173
Word width	
See word length, resolution	
Word, digital audio signal.	543
Workspace.	12
Wow and flutter.	140
2-Sigma compute algorithm	477
Wow and flutter measurement function	140

X

X vs. Y data plot	412
X-axis graph divisions	409
xbsi1e	204
xbsi2	207
xbsi2e	206

Y

Y-axis graph divisions	411
----------------------------------	-----

Z

Zoom	436
----------------	-----

